
BRIGHAM YOUNG
UNIVERSITY

REMODEL OFFICE - SUITE #1041 AND SUITE #1053
COLLEGE OF HUMANITIES
JOSEPH F. SMITH BUILDING (JFSB) LEVEL #1

SPECIFICATIONS



FACILITIES PLANNING

240 BRWB PROVO, UTAH 84602
PHONE: (801) 422-5504
FAX: (801) 422-0566

DATE OF RECORD: February 29, 2024

BYU WORK ORDER

K8101
M4027

CONSTRUCTION DOCUMENTS

BRIGHAM YOUNG UNIVERSITY
STANDARD CONTRACT REQUIREMENTS

TABLE OF CONTENTS

BRIGHAM YOUNG UNIVERSITY STANDARD CONTRACT REQUIREMENTS

- I. INVITATION TO BID
- II. NOTICE TO BIDDERS
- III. FORM OF PROPOSAL
- IV. INSTRUCTIONS TO BIDDERS
- V. FORM OF CONTRACT
- VI. SALES TAX EXEMPTION CERTIFICATE
- VII. GENERAL CONDITIONS TABLE OF CONTENTS
 - A. GENERAL CONDITIONS
 - B. SUPPLEMENTARY CONDITIONS
- VIII. REQUEST FOR PAYMENT
 - A. SCHEDULE OF VALUES

21 February 2024

(Attached is a list of bidders invited to bid.)

Re: Invitation to Bid – 2024 CNA Remodel Office Suites 1041 & 1053 JFSB
W.O. K8101 & N4027

To Whom It May Concern:

You are invited to bid on the above-referenced project. This project consists of remodeling 5600 SF of existing office space. The completion date for this project is 15 August 2024.

Plans will be available at the mandatory pre-bid which has been scheduled for 7 March 2024 at 9AM in Room 115 BRWB. Bids will be opened and read aloud on 14 March 2024 at 2PM in Room 115 of the Brewster Physical Facilities Building at Brigham Young University. A performance bond and a labor and materials payment bond for 100% of the contract will be required for this project and must be included in your bid.

We hope that you will be able to bid this project.

Sincerely,

Anthony Burdette

ARB/mh
Attachment

NOTICE TO BIDDERS

SECTION 1--PROJECT: 2024 CNA Remodel Office Suites 1041 & 1053 JFSB

WORK ORDER NUMBER: K8101 & N4027

SECTION 2--LOCATION: Brigham Young University

SECTION 3--OWNER: Brigham Young University

SECTION 4--DESIGNER: Brigham Young University

SECTION 5--STANDARD CONTRACT REQUIREMENTS:

The Bidder is directed to the Brigham Young University Standard Contract Requirements (revised October 2017). This volume is an integral part of the contract documents and is hereby made a part of the contract.

SECTION 6--DATES:

A. Start Date: 1 April 2024

B. Completion Date: 15 August 2024

SECTION 7--PREBID CONFERENCE

A. Prebid Conference will be:

Date: 7 March 2024

Time: 9AM

Place: Room 115, Brewster Building

SECTION 8--RECEIPT AND OPENING OF BIDS:

A. Bids will be received:

Date: 14 March 2024

Time: 2PM

Place: Room 115, Brewster Building

By: Ole M. Smith

B. The Owner reserves the exclusive right to release all publicity relating to the proposals and the project.

SECTION 9--DEPOSIT FOR CONTRACT DOCUMENTS:

A. A deposit of \$0.00 will be required for each set of contract documents (plans and specifications) taken.

SECTION 10--GENERAL CONTRACTORS

A. Bidding by General Contractors will be by invitation only.

BRIGHAM YOUNG UNIVERSITY

FORM OF PROPOSAL

NAME OF PROJECT 2024 CNA Remodel Office Suites 1041 & 1053 JFSB

WORK ORDER NUMBER K8101 & N4027

NAME OF CONTRACTOR _____

DATE OF PROPOSAL _____

The undersigned, hereinafter referred to as the Bidder, certifies that the following facts and/or circumstances have occurred or exist relating to the proposed work: 2024 CNA Remodel Office Suites 1041 & 1053 JFSB prepared by _____.

1. That Bidder has received the contract documents for the above entitled project.
2. That Bidder has received Brigham Young University General Conditions Requirements, revised October 26, 2017.
3. That Bidder is familiar with such documents, has examined the site of the proposed work, including availability of access, utilities, and other similar items relating to performance of the work and is thoroughly familiar with all general and local conditions which could in any way affect this work.
4. That no verbal agreements or representations with or by any officer, agent, or employee of the Owner exist or have been made to the Bidder and the Bidder in submitting this proposal is in no way relying thereon.
5. That if this proposal is accepted, Bidder will enter into a contract with the Owner in substantially the form contained in the contract documents, and will provide the bonds, insurance coverage and all other items required by the contract documents.
6. The term "base bid" shall be understood to include all work contained in the contract documents excluding any substitutes or alternates. The Owner will have the right to accept Alternates in any order or combination, and to determine the low Bidder on the basis of the sum of the Base Bid and Alternates accepted.

Bidder hereby proposes to furnish all materials, labor, equipment, tools, transportation, services, licenses and permits necessary for the completion of all the work set forth in the contract documents for the sum of:

Base Bid* _____ (\$ _____)

*Base bid to include the cost of a Performance Bond and a Labor/Materials Payment Bond and Builder's Risk. See General and Supplementary Conditions.

1. The bidder agrees to complete the work on or before 15 August 2024
2. The bidder acknowledges receipt of addenda No.(s) _____
3. The Bidder's Utah contractor's license number is _____
4. Is your bonding capacity adequate for this job? Yes No
5. For verification call _____
6. Telephone number _____

PROPOSED SUBSTITUTE MATERIALS

The total sum of the Bidder's proposal shall include the furnishing and installing of all materials, equipment, and labor as called for in the contract documents as a base bid.

Hereafter give the total amount to be added or deducted for a complete installation of equipment or materials other than those specified and those approved by addendum are submitted for the Owner's consideration. All materials and equipment proposed for substitution shall be listed below and must meet the requirements of the contract documents. During the time of consideration of the proposals, complete information shall be submitted immediately to the Architect and Owner's Representative. The Contractor is referred to Page 3 of the Instructions to Bidders, Section 9, prior approvals and substitutions for requirements relative to proposed substitutions.

Proposed Substitute	Manufacturer and Catalog Numbers	\$ Add	\$ Deduct

TYPE OF BIDDER'S ORGANIZATION:

Official Name of Organization

Corporation, Co-partnership, Individual, or Other

Address

Name of individual Members of Firm:

Name of President of Corporation:

Name of Secretary of Corporation:

Corporation is organized under the laws of the State of:

()
)Seal(
()

Signature _____

Title or Office _____

Legal Address _____

BIDDER'S LIST OF SUBCONTRACT BIDS USED IN PROPOSAL

(LIST OF SUBCONTRACTORS)

PROJECT NAME 2024 CNA Remodel Office Suites 1041 & 1053 JFSB

WORK ORDER NUMBER K8101 & N4027

OWNER'S NAME Brigham Young University

DIVISION	SUBCONTRACT CLASSIFICATIONS	SUBCONTRACTOR USED	AMOUNT

INSTRUCTIONS TO BIDDERS

SECTION 1 -- BIDDING BY INVITATION

- A. Bidding shall be by written invitation only. Those wanting to be considered for such invitation shall apply to:

Assistant Administration Vice President
Physical Facilities
202 Brewster Building
Provo, UT 84602

- B. The Owner reserves the right to accept or reject any or all bids.

SECTION 2 -- CONTRACT DOCUMENTS

- A. The Contract documents may be obtained by contractors from:

Construction Department
Physical Plant
240 Brewster Building
Provo, UT 84602

- B. Subcontractors and suppliers who want to obtain Contract documents (plans and specifications) may do so by requesting the documents and paying the printing costs.
- C. All Contract documents must be returned within ten (10) days after the bid opening, or the deposit will be forfeited. Those documents purchased outright by the Bidders are exempted.
- D. The Contract documents (plans and specifications) may be deposited with local Bid Depositories. Bidders may contact the Invited General Contractors for locations. The Contract documents may be examined free at:

Construction Department
Physical Plant
240 Brewster Building
Provo, UT 84602

SECTION 3 -- CONTRACT METHOD

- A. All work specified is to be done under one general contract. Bids will be accepted by the Owner from prime contractors only.

SECTION 4 -- INTERPRETATION OF CONTRACT DOCUMENTS

- A. If any Bidder doubts the true meaning of any of the Contract documents, or finds errors, discrepancies or omissions, he shall request a clarification from the Architect in writing. Any interpretations or corrections will be made only by written addenda duly issued by the Owner. All addenda will be mailed, faxed or otherwise delivered to each person receiving a set of the Contract documents. Requests for clarifications must be submitted to the Architect at least five (5) days before bid opening. Unwritten instructions or interpretations will have no validity.
- B. Should discrepancies appear in the Contract documents that are not resolved by an addendum, it is expressly understood that the Contractor has used the most expensive method and/or material in the bid.

SECTION 5 -- REQUIREMENTS BEFORE SUBMITTING BIDS

- A. The Contractor shall become thoroughly familiar with the site and structures located there (if any). The Contractor shall thoroughly examine all Contract documents in relation to all conditions that might directly or indirectly affect the contract work. The bid amount shall reflect all such conditions.

SECTION 6 -- PREPARING AND SUBMITTING BIDS

- A. To receive consideration, a bid must be made according to the following instructions:
1. Bids shall be prepared on BYU bid forms.
 2. Bids shall have all items or blanks filled. Numbers shall be stated both in writing and in figures. If there is a discrepancy between the two, the written number shall govern.
 3. Bids shall be without interlineations, alterations or erasures.
 4. Signatures shall be by those authorized to execute the Contract.
 5. The Bidder's legal name, business address and telephone number shall be stated.
 6. Neither oral bids nor modifications shall be considered.
 7. You may email your bid to the Construction Department Secretary, but it is not official until it is printed, inserted into an envelope, and delivered to the designated person opening the bids prior to the appointed bid opening time. It is suggested that the bidder call in advance to make these arrangements. We do not accept responsibility for email, printing, delivery, or other problems.
 8. It is the Bidder's sole responsibility to see that the bid is received at the proper time. Any bid received after the scheduled bid opening time will be returned unopened to the Bidder.
 9. Bidders shall accept proposals from only those subcontractors who are approved by the Owner or those who have shown to the Bidder's satisfaction that they are financially capable of handling the work. Furthermore, subcontractors must have the technical ability, personnel, plant, experience and reputation to carry out their portions of the work. It will be assumed that the question of bonding subcontractors, where considered desirable or necessary by the Contractor, including the cost of such bonds, has been resolved before bids have been submitted.
 10. In order for the bid to be considered valid, two or more Bidders bidding as a "joint venture" must have the written approval of the Owner before submitting a bid. All members of a joint venture shall sign the bid and an official representative of the joint venture shall be designated in the proposal.
 11. The term "base bid" shall be understood to include all work contained in the Contract, excluding any alternates or substitutes. The Owner shall have the right to accept alternates in any order or combination, and to determine the low Bidder based on the sum of the base bid and alternates accepted.
 12. Substitutes or alternates accepted by the Owner may be included in the Contract or added by Change Order. In determining the low Bidder, the Owner will not consider substitutes.
 13. Bids may be withdrawn by the Bidder, either in person or by a written request before bid opening. Once opened, the Bidders will have 24 hours to review and withdraw their bids. After the 24-hour period, the bids may not be withdrawn and must remain fixed as submitted for 45 days after opening. Envelopes must contain nothing but the proposal and bid breakdown forms if required. Envelopes shall be opaque, sealed and bear the Bidder's name.

SECTION 7 -- APPROVAL OF CONTRACTORS AND SUBCONTRACTORS

- A. As soon after the bid opening as is practicable, the Owner will interview the apparent low Bidder and if deemed advisable, the second or third low Bidders. Within two hours of the bid opening, the low Bidder and the second or third low Bidders will provide to the Owner a list of subcontractors and their dollar amounts that were used in formulating their bid. The list of subcontractors will be examined by the Owner as soon as possible. The Owner reserves the right to accept or reject any subcontract proposal.
- B. Provide Unit Prices within 24 hours of Bid Opening if requested in Form of Proposal.
- C. If a Bidder doubts the correctness or acceptability of any subcontract proposal, the Bidder may submit the names and amount of other competing subcontractors for consideration, making sure that he clearly states which one he has used in formulating his proposal.

SECTION 8 -- FACTORS AFFECTING AWARD OR REJECTION OF BID

- A. The Bidder's and subcontractor's past performance, organization, equipment and ability to perform and complete their contract as specified will be vital elements, as well as the amount of their bids, in the award of the Contract.
- B. The Owner reserves the right to reject any or all bids, or to waive any irregularities or informalities in bids received. The

Owner reserves the right to accept the bid that will, in the Owner's opinion, best serve the interests of the Owner.

- C. If a schedule is requested on form of proposal - The Owner reserves the right to reject a bid that provides a date that is past the requested substantial completion. Further, the Owner reserves the right to award the project based on proposed substantial completion regardless of whether such bid is the lowest.

SECTION 9 -- PRIOR APPROVALS AND SUBSTITUTIONS

- A. Several acceptable brands of equipment, manufactured articles or methods of construction may have been identified in the Contract. It is not intended to close the Contract against other brands, articles, or methods that may warrant consideration. However, unspecified materials must have prior approval by the Owner to be considered.
- B. Prior Approvals: Requests for approval of unspecified materials must be made to the Architect at least five days before bid opening. The requests for prior approval shall be considered by the Architect if time permits and if properly documented. The Architect is not bound to consider these items despite their apparent validity.
- C. Fully detailed technical data, references and other information shall be furnished simultaneously with the requests for prior approval items.
- D. Such requests shall be reviewed by the Architect and the Owner. If accepted, the approved requests will be included in an addendum.
- E. The Contractor's "base bid" shall include the furnishing of only those items that are explicitly specified or which have received prior approval by addendum.
- F. Substitutions: Besides the "base bid," any equipment or material supplier and any contractor or subcontractor may, at his option, submit a substitute price and product for any item specified which he feels warrants consideration by the Owner. This proposed substitution is to be listed where indicated on the bid form.
- G. Any proposed substitute submitted by a Bidder shall include the amount by which the "base bid" would be increased or decreased.
- H. The Owner may accept or reject any substitute proposed. In determining the low Bidder, the Owner will not consider substitutes.
- I. If requested, the Contractor shall furnish information or data concerning the substitute. The Owner may request the Contractor, at his own expense, to have the substitute tested by an approved testing laboratory.

SECTION 10 -- FORM OF CONTRACT

- A. Copies of the form of the Contract that the successful Bidder will be required to execute are included in this specification.

SECTION 11 -- ADDENDA

- A. All addenda issued before bid opening shall be included in the bid and shall be a part of the Contract.

SECTION 12 -- REQUIREMENTS IMMEDIATELY AFTER SIGNING THE CONTRACT

- A. Immediately after signing the Contract, the Contractor shall furnish the following to the Owner:
 - 1. Executed performance, labor and material payment bonds, each in an amount equal to 100 percent of the contract sum as specified in the General Conditions.
 - 2. Insurance certificates as specified in the General Conditions.
 - 3. A cost breakdown of the work that may, as approved by the Owner, serve as a basis for making monthly payments to the Contractor.
 - 4. A project schedule as to how he intends to construct the project. This must be, in the opinion of the Owner, a realistic method of analyzing and scheduling each component of the work. It must show when all trades or crafts start and finish their work. This schedule must be reviewed weekly in the OAC meeting and updated as

required. A critical path method of scheduling is preferred. If the Contractor cannot produce and maintain such a schedule, this service must be obtained from an outside consultant. The schedule must be approved by the Owner's Representative before the Contractor submits the first payment request.

- B. The Contractor shall issue subcontracts as mutually agreed between the Owner and the Contractor. A complete list of subcontractors and major suppliers including names, addresses and telephone numbers are required within fourteen (14) days of the Owner's subcontractor review.

SECTION 13 -- DISQUALIFICATION

- A. If the above requirements are not satisfied, the bid may be disqualified at the discretion of the Owner.



CONTRACT

Project Name

AT

BRIGHAM YOUNG UNIVERSITY

LONG FORM CONTRACT NO.

Project No.:

(Work Order No.:)

THIS CONTRACT, made and executed as of the day day of month, year, by and between BRIGHAM YOUNG UNIVERSITY, a non-profit Utah corporation of Provo, Utah (hereinafter referred to as "Owner"), and Contractor Name (hereinafter referred to as "Contractor").

WITNESSETH:

That for and in consideration of the payments hereinafter specified to be paid by the Owner to the Contractor and the covenants and agreement herein contained to be kept and performed by the parties hereto, the Contractor agrees to build and construct the proposed Project Name at Brigham Young University in Provo, Utah (hereinafter referred to as the "Project") and to furnish and deliver all materials, and perform and supervise all services (hereinafter, the "Work") as required herein and by the contract documents hereinafter identified, all of which shall collectively constitute the contract, and shall hereinafter be referred to collectively as the "Contract".

ARTICLE I. THE IDENTIFICATION OF CONTRACT DOCUMENTS

A. The Plans entitled “Name on plans” were prepared by Brigham Young University, reviewed by Richard or Ray or whomever, Title of Reviewer, and approved by Ole Smith, Assistant Administration Vice-President of Brigham Young University, on date.

B. The Specifications entitled “Name on Specs” were prepared by Brigham Young University, reviewed by Richard or Ray or whomever, Title of Reviewer, and approved by Ole Smith, Assistant Administration Vice-President of Brigham Young University, on date.

C. Addendum Number One, dated Month Day, Year.

D. Addendum Number Two, dated .

E. The Brigham Young University General Conditions are a part of this Contract.

ARTICLE II. THE CONTRACT SUM

The Owner agrees to pay to the Contractor, in accordance with the terms hereof, the following:

Base Bid	\$
Total	\$

The Contractor agrees to accept a total of written dollar amount (check instructions for guidelines) Dollars (\$) as full compensation for performing his obligation under the contract.

ARTICLE III. DATE OF COMPLETION

The Contractor agrees to complete the work required by the Contract on or before midnight, date (Month Day, Year). Time is hereby expressly declared to be of the essence of the Contract.

ARTICLE IV. THE CONTRACTOR'S REPRESENTATIVE

The Contractor's Representative is Name of the Contractor.

ARTICLE V. THE OWNER'S REPRESENTATIVE

The Owner's Representative is Ole M. Smith.

IN WITNESS WHEREOF, the Owner has caused this instrument to be signed by its President, attested by its Secretary, and its corporate seal to be hereunto affixed, and the Contractor has hereunto affixed his signature as of the day and year above written.

ACKNOWLEDGED:
BRIGHAM YOUNG UNIVERSITY CONTRACTOR

Ole M. Smith
Assistant Administration Vice President

contractor rep
contractor company

Steve Hafen
Administration Vice President

Date

Shane Reese
President

BRIGHAM YOUNG UNIVERSITY
(Tax Exempt No. 11691946-003-STC)
SALES TAX EXEMPTION CERTIFICATE
In Lieu of Form TC-721

TO: contractor name

Pursuant to Utah State Tax Commission Rule R865-19S-58, Brigham Young University is exempt from sales/use tax on purchases of all Construction Materials (as defined by the above Rule). You and your subcontractors are hereby authorized to purchase Construction Materials free of Utah sales tax for the Project listed below pursuant to the agreement between you and Brigham Young University dated _____.

PROJECT: _____

**OWNER'S
REPRESENTATIVE:**

Assistant Administration Vice-President Date
202 BRWB, Provo, UT 84602-8100
(801) 422-5500

CONTRACTOR'S (OR SUB'S) AFFIDAVIT

TO (Name of Vendor): _____

I certify that the purchases of Construction Materials from the Vendor above are made in behalf of Brigham Young University for the above referenced Project *only*. I further certify that the Construction Materials purchased will be installed or converted into real property owned by Brigham Young University.

NAME OF CONTRACTOR/SUB: _____

Street Address: _____ **Phone:** _____
Address City State/Zip

By: _____ **Title:** _____
Authorized Representative Position or Job Title Date

NOTE: Vendor must keep this certificate on file for audit review. Contractor or Sub must keep a copy of this certificate on file and must notify vendors of cancellation, modification, or limitation of the exemption claimed. Contractor or Sub is liable for sales tax on any Construction Materials purchased which are not used on the Project above or which do not otherwise qualify for exemption.

GENERAL CONDITIONS

SECTION 1 - DEFINITIONS

- A. OWNER - Brigham Young University, Provo, UT, referred to as the "Owner."
- B. OWNER'S REPRESENTATIVE - The Assistant Administration Vice President - Physical Facilities, 202 Brewster Building, Brigham Young University, Provo, UT 84602.
- C. ARCHITECT - The Architect is a licensed architect, engineer, or organization so designated in the Contract. The term "Architect" means the Architect or his authorized representative.
- D. CONTRACTOR - The Contractor is the person or organization identified as such in the Contract and referred to throughout the Contract as if singular in number and masculine in gender. The term "Contractor" means General Contractor or his authorized representative.
- E. SUBCONTRACTOR - The person, firm or corporation supplying direct or indirect labor and/or materials at the site of the Project and under separate contract or agreement with the Contractor.
- F. PROJECT MANAGER - The BYU personnel who acts as liaison between the Owner and the Contractor for the Project. [CITY INSPECTOR ISSUE]
- G. THE WORK - The work includes all labor necessary to produce the construction, demolition, or other delivery of goods and services required by the Contract and all materials and equipment incorporated or to be incorporated in such work.
- H. THE PROJECT - The Project is the total construction designed by the Architect. The Work performed under the Contract may be the whole or a part of the work required to be performed under the Project.
- I. WRITTEN NOTICE - Written notice shall have been duly served if delivered in person to the Project Manager or the Contractor's designated representative. Written notice is also served by a registered or certified mailing to the last known address of the corporation, if delivered to the direction of the Project Manager or the Contractor's designated representative.
- J. CONTRACT - The Contract consists of the Brigham Young University short or long form contract; the Instructions to Bidders; the Supplementary Conditions; the General Conditions; the Drawings; the Specifications; Addenda; and Change Orders describing the Work and signed or acknowledged between the Owner and Contractor.

SECTION 2 - THE CONTRACT DOCUMENTS

- A. The Contract represents the entire agreement between the parties and supersedes all prior negotiations, representations or agreements, either written or oral, including the bidding documents. After written execution of the Contract, the Contract shall be amended or modified only by a Change Order.
- B. Words that have well-known technical or trade meanings are used herein by such recognized meanings.
- C. Within the Contract there shall be the following order of precedence, (1) being the highest precedent:
 - 1. The BYU Short Form or Long Form Contract takes precedence over all other documents.
 - 2. Supplementary General Conditions take precedence over General Conditions.
 - 3. General Conditions take precedence over Drawings and Specifications.
 - 4. Addenda or modifications of any nature, to the Drawings and Specifications, take precedence over the original.

5. Specifications take precedence over Drawings.
6. Within the Working Drawings, the larger scale takes precedence over smaller, figured dimensions over scaled and noted materials over graphic indications.

SECTION 3 - DISCREPANCIES IN THE CONTRACT

- A. Should any question arise regarding the Contract, the Contractor shall request written interpretation and clarification from the Architect before proceeding. Without such request and written authorization, the Contractor proceeds at his own risk.

SECTION 4 - ADDITIONAL DRAWINGS & INSTRUCTIONS

- A. The Architect shall promptly furnish any additional instructions or clarification necessary for proper execution of the Work specified in the Contract.

SECTION 5 - OWNERSHIP AND MAINTENANCE OF DRAWINGS

- A. All drawings and specifications furnished to the Contractor, including electronic file versions, are the property of the Owner. They are not to be used on other work and must be returned to the Owner if so requested. One copy may be retained by the Contractor, but may not be used for any third-party work without the express written consent of the Owner.
- B. The Owner shall furnish, free of charge to the Contractor, all copies of drawings and specifications reasonably necessary for the execution of the Work. The Contractor shall maintain in good order on the Project one copy of drawings, addenda and specifications that shall be readily available to the Architect and the Project Manager.

SECTION 6 - PROGRESS MEETINGS

- A. Contractor shall be required to attend weekly Owner, Architect, and Contractor (OAC) meetings. The agenda and meeting minutes will be prepared by the Architect. The Architect shall distribute meeting minutes within seven days of the meeting. The Contractor shall attend such meetings and shall require subcontractors to attend as necessary. These meetings are to:
 1. Insure that all activities are being coordinated properly on the Project.
 2. Review the schedule.
 3. Check the status of:
 - a. Submittals, including shop drawings and samples.
 - b. Change Orders and Proposal Requests.
 - c. Payment requests.
 - d. Any other matters that may need to be reviewed.

SECTION 7 - PROJECT SCHEDULE

- A. Before the first payment request, the Contractor shall prepare and submit for review an estimated Project schedule for the Work. The Project schedule shall be in sufficient detail to include, but not be limited to:
 1. Significant elements of the Work.
 2. Period for each element of Work with a beginning and ending date.
 3. Percentage of progress of Work completed or to be completed in a monthly period.
 4. Early start anticipated schedule of all Owner Provided/Contractor Installed (OP/CI) mechanical controls.
- B. The Project schedule shall be updated monthly and submitted with each payment request and shall show the original Project schedule or revised Project schedule, one entry for each item of work, as follows:
 1. All Work already completed and paid for by Owner.

2. Work during current period for which payment is being requested.
3. Remaining Work to be done, itemized in the Schedule of Values.

SECTION 8 - EMERGENCIES

- A. In case of an emergency endangering life or threatening the safety of the structure or of adjoining property, the Contractor may, without waiting for specific authorization from the Architect or Owner, act at his own discretion to safeguard life or property. Compensation and time shall be allowed the Contractor for such emergency work. The amount of both shall be decided between the Contractor, the Architect, and the Owner.
- B. The Contractor shall notify the Project Manager immediately and shall make a full written report of such emergency action to the Project Coordinator within seven days of the event.

SECTION 9 - SUBMITTALS, SHOP DRAWINGS, AND SAMPLES

- A. General:
 1. The Contractor shall deliver submittals, shop drawings or samples to the Owner and Architect as indicated below. Furthermore, the Contractor shall accompany each submittal with a transmittal letter indicating the title of the Project, the name of the Contractor, the title of the submittal and the specification section number.
- B. Submittal Schedule:
 1. The Contractor shall, within twenty-one (21) calendar days after receipt of the signed contract, furnish a submittal schedule listing all items that the Contract requires for review. This schedule shall include shop drawings, manufacturers' literature, certificates of compliance, material samples, material colors, guarantees, etc.
 2. The schedule shall show the type of item, the Contract requirement reference, the Contractor's scheduled dates for submitting the items and the projected need dates for review by the Architect. The schedule shall show a minimum of fourteen (14) calendar days for review by the Architect. If resubmittal is required, an additional seven (7) days will be allowed. The Contractor shall revise and update this schedule as appropriate and submit it with each payment request until all items have been submitted and reviewed.
 3. The Contractor shall coordinate the submittal schedule with the Project schedule for all the work. The Contractor shall revise and update the submittal schedule to insure consistency with the Project schedule. The Contractor shall promptly provide such revised submittal schedules to the Owner.
 4. Furnishing of the submittal schedule or subsequent revisions shall not be interpreted as relieving the Contractor of the obligation to comply with all Contract requirements for items on the schedule.
- C. Definitions:
 1. Shop drawings are drawings, diagrams, illustrations, electronic files, schedules, performance charts, brochures and other data prepared by the Contractor or subcontractor, manufacturer, supplier, or distributor. Shop drawings illustrate some portion of the work and confirm dimensions and conformance to the Contract.
 2. Samples are physical examples furnished by the Contractor to illustrate materials, equipment, color, or construction and to help establish standards by which the work will be judged.
- D. Procedure:
 1. The Contractor shall review and stamp his certification that the products and methods meet the requirements specified in the Contract. The Contractor shall submit one (1) electronic copy of shop drawings to the Architect and one (1) electronic copy to the Owner, with reasonable promptness and in orderly sequence. Shop drawings and samples not required by the Contract

but requested by the Contractor, or supplied by those under contract to him, need not be submitted to the Architect and Owner for approval. These shop drawings shall meet all specified shop drawing requirements, except those relating to submission to the Architect and Owner.

2. The Contractor shall reject shop drawings not in conformance with the Contract.
3. Shop drawings shall be complete and detailed. If reviewed by the Architect, each copy of the shop drawings shall be stamped and dated by the Architect. If review "with exception" or "as noted" by the Architect is so identified, stamped and dated, the Contractor shall comply with notations shown. If the Architect requires resubmission of submittals, the Contractor shall make any corrections at the Contractor's expense. The Contractor shall not copy Project drawings and use those drawings as submittals.
 - a. Any shop drawing which does not conform to the Contract shall be explicitly noted on the drawings and in the transmittal letter. This shall not be construed as approval to proceed with performing or providing the changed work until specifically approved by the Owner and a Change Order accordingly issued. If shop drawings show variations from Contract requirements because of standard shop practice, or for any other reason, such variations shall be explicitly noted in the transmittal letter. Shop drawing review shall be general. It shall not relieve the Contractor of responsibility for accuracy of such shop drawings, nor for proper fitting, construction of work, furnishing of materials or work required by Contract and not shown on shop drawings.
 - b. All transmittal of shop drawings may be by email or other electronic means.

E. By approving shop drawings and samples, the Contractor determines and certifies that all field measurements, field construction criteria, materials, catalog numbers and similar data conform to the Contract. The Contractor determines and certifies that he has checked and coordinated each shop drawing and sample with requirements of the Contract.

F. No work requiring a shop drawing or sample submission shall be commenced until submission has been approved in writing by the Architect.

G. Samples:

1. Where specified or required, the Contractor shall submit samples to the Architect with specification material, affidavits, and other documentation as required by the Architect or the Owner.
2. It is the Contractor's specific responsibility to ascertain that samples have been checked and approved before being submitted.
3. Cost of samples, including transportation, delivery and any other costs, shall be paid by the Contractor. Unless specified otherwise, samples shall be submitted in triplicate for the Architect, the Owner and the Contractor. The Contractor shall keep his samples on the jobsite. Where samples are specifically required to be submitted for approval, no work involving the sampled materials shall proceed until written approval has been obtained from the Architect.

H. Review by the Architect and the Owner:

1. Review of shop drawings by the Architect and the Owner shall not be construed as a complete check, but will show only that the general method of construction and detailing is satisfactory. Review of such drawings will not relieve the Contractor of responsibility for any error that may exist in the submittals.

SECTION 10 - ROYALTIES & PATENTS

A. The Contractor shall pay all royalties and license fees. The Contractor shall defend and hold the Owner harmless from all suits or claims for infringement of any patent rights.

SECTION 11 - CONTRACTOR'S LIABILITY INSURANCE AND BONDS

A. Insurance:

1. The Contractor shall not commence work under this Contract until he has obtained the insurance required and evidence of such insurance has been submitted to and approved by the Owner. The submittal of said evidence to the Owner shall not relieve or decrease the liability of the contractor.

a. Workers' Compensation & Employers' Liability Insurance as required by statute.

b. Commercial General Liability Insurance – the current version of ISO Form CG 00 01 or equivalent, Occurrence Policy, with -

(1) Limits of not less than -

(a) General Aggregate	\$ 2,000,000.00
(b) Products - Comp/OPS Aggregate	\$ 2,000,000.00
(c) Personal and Advertising Injury	\$ 1,000,000.00
(d) Each Occurrence	\$ 1,000,000.00
(e) Fire Damage (any one fire)	\$ 50,000.00
(f) Medical Expense (any one person)	\$ 5,000.00

(2) Endorsements attached thereto including the following or their equivalent -

(a) The current version of ISO Form CG 25 03, Amendment of Limits of Insurance (Designated Project or Premises), describing the subject Contract and specifying the limits as shown above.

(b) The current version of ISO Form CG 20 10, Additional Insured -- Owners, Lessees, or Contractors (Form B), naming the Owner as an additional insured and containing the following statement - "This endorsement also constitutes primary coverage in the event of any occurrence, claim, or suit."

c. Automobile Liability Insurance, with -

(1) Limits of not less than \$1,000,000.00 Combined Single Limit per accident.

(2) Coverage applying to any auto.

B. Certificate of Insurance, on the current version of ACORD 25-S Form, or equivalent, filed with the Owner identifying:

1. Owner, as defined in the Construction Contract, as Certificate Holder and Additional Insured.

2. Endorsements, as listed above. (Note: If forms other than ISO forms are used, copies of the non-ISO forms are to be attached to this certificate).

3. Project as defined in the Construction Contract.

4. Cancellation clause of the certificate amended to read, "Should any of the above described policies be canceled before the expiration thereof, the issuing company will mail a notice within thirty (30) days to the certificate holder named."

5. Insurance companies providing coverage - All companies listed must be rated "A-" or better in the Standard and Poor's Solvency Review Guide Property & Casualty (current edition.)

6. The Name, Address, and Telephone Number of The "Producer" - The certificate is to bear an original signature of the Authorized Representative of the Producer. Facsimile or mechanically reproduced signatures will not be accepted.

C. Performance Bond and Labor & Material Payment Bond:

1. The Contractor shall furnish the Owner a performance bond, and a labor and a material payment bond each in an amount equal to 100 percent of the Contract amount as security for all obligations arising under the Contract. Such bonds shall –

a. Be written on Form AIA Document A312. Where the laws of the state in which the project is located mandate a statutory payment bond form, such mandated payment bond form shall be used but is to be accompanied by the AIA Document A312 Performance Bond.

b. Be issued by a surety company or companies licensed in the state in which the Project is located and holding valid certificates of authority under applicable federal insurance law as acceptable sureties or reinsurance companies on federal bonds. The penal sum

obligation assumed by each surety, shall not exceed the maximum amount permitted by law.

- c. Be accompanied by a certified copy of the Power of Attorney stating the authority of the Attorney-in-fact executing the bonds on behalf of the Surety.
- D. The Owner reserves the right to reject any insurance company, policy, endorsement, certificate of insurance, surety company, performance bond, or labor and material payment bond with or without cause.
- E. The cost of such insurance and such bonds as required above shall be the obligation of the Contractor.

SECTION 12 - HOLD HARMLESS AGREEMENT

- A. Besides obtaining insurance coverage as required above, the Contractor shall indemnify and save the Owner, the Architect, and their agents and employees harmless from and against any liability, demands, causes of action or claims thereof, whether well founded or otherwise, including the cost of defending the same, for bodily injury to any person whatsoever (including the employees of the Owner or the Architect) or damage to property of any person during construction because of the negligence of the Contractor, their subcontractors or material suppliers, their agents or employees.
- B. The Contractor shall defend the Owner and Architect in any lawsuit filed by any of their subcontractors or material suppliers. Where liens have been filed against the Owner's property, this shall require the Contractor or his bonding company to obtain lien releases and record them in the appropriate county or local jurisdiction so as to unencumber and provide the Owner with a title free and clear from any liens.
- C. No subcontract shall relieve the Contractor of any of his liability or obligation under the Contract. The Contractor agrees that he is fully responsible to the Owner for acts or omissions of his subcontractors and their material suppliers and of persons either directly or indirectly employed by them.

SECTION 13 - BUILDERS RISK LOSSES

- A. The Owner will provide Builder's Risk Insurance or reimburse the Contractor for losses to the Project, described herein, to the extent to which such losses are or would be covered by the Owner's Policy Form of F.M. Global's "All Risk" insurance policy covering Builders Risk Insurance. 1.
Deductible Clause - All claims for loss or expense arising out of one occurrence shall be adjusted as one claim, and from the amount of such adjusted claim, there shall be deducted the sum of:
 - a. \$2,500.00 on all Projects. The deductible amount is the responsibility of the Contractor or Subcontractor.
 - 2. Loss Reporting Procedure - All losses requiring reimbursement under this Section shall be reported to the Project Coordinator as soon as practical and always before the beginning of repairs so that details of the loss can be obtained and verified to simplify a prompt loss adjustment.
- B. Copies of the insurance forms are available from the Owner at the Brigham Young University Physical Facilities, Construction Section offices.

SECTION 14 - PERMITS, INSPECTIONS, CERTIFICATES, AND REGULATIONS

- A. Permits:
 - 1. The Contractor shall obtain, and the Owner shall pay cost of, permits necessary for completion of this work. "Permits," as used in this paragraph includes any permits necessary for the Contractor to complete the Work, including but not limited to: excavation, footing, and foundation permits; building permits; hot work permits; elevator permits; fire sprinkler permits; boiler permits; demolition permits; specialty permits from the State of Utah or other federal or state

governmental entities, such as Health Department permits; etc. The responsibility for obtaining, and any resulting liability for failing to obtain, such permits shall rest with the Contractor.

2. The Contractor shall schedule and coordinate all necessary inspections and shall notify the Project Manager and the Authority Having Jurisdiction of all inspections. The Contractor shall be responsible for securing a certificate of occupancy that may be required by Authorities Having Jurisdiction over the Work. The Contractor shall deliver these certificates to the Project Manager before execution of the Certificate of Substantial Completion.
3. The Contractor will be required to notify the Utah Division of Air Quality of any demolition projects and obtain all permits required by the State, County, and/or Provo City. The Contractor shall include all demolition permit fees in his bid.
4. The Contractor shall hold harmless, defend, and indemnify Owner from and against any and all claims, demands, allegations, fines, and damages associated with or arising from the Contractor's failure to obtain required permits.

B. Regulations:

1. The Contractor and others working under his jurisdiction, supervision, or control shall do all work according to laws, regulations, and ordinances required by governmental authority or other agencies having jurisdiction over this work.
2. If the Contractor observes that the Contract is in variance with any laws, regulations or ordinances, he shall notify the Project Manager and shall not proceed unless necessary changes required for compliance with said laws, regulations and ordinances have been made as provided in the General Conditions, Section 24. The Contractor shall be fully responsible for any work knowingly done contrary to laws, regulations and ordinances. The Contractor shall fully indemnify the Owner against loss and bear all costs and penalties arising from those violations.
3. The Contractor shall hold harmless, defend, and indemnify Owner from and against any and all claims, demands, allegations, fines, and damages associated with or arising from the Contractor's failure to follow applicable regulations.

SECTION 15 - MEASUREMENTS, SURVEYS, BUILDING LAYOUT & SITE EXAMINATION

A. The Contractor shall be responsible for:

1. Establishing lot lines and bench marks.
2. Laying out the work on the building site.
3. The proper observance of property lines and set back requirements.
4. The location and layout of buildings as noted in the drawings with respect to the position on the property and elevation in relation to the grade.

B. If existing conditions shown in the Contract documents differ materially from those the Contractor encounters in the performance of the work, the Contractor shall immediately notify the Architect and the Owner in writing.

C. The Architect and the Owner shall promptly investigate the reported conditions. If they find that such conditions do materially differ and cause an increase or decrease in the Contractor's cost or the time required for performance of any part of the work, the Owner shall make an equitable adjustment by Change Order.

D. As the work progresses, the Contractor shall lay out on the forms, or floors, the exact locations of all partitions as a guide to all trades. Subcontractors providing work that is to be placed in connection with walls and/or partitions shall check such locations and immediately notify the Contractor of any conflicts in structure or changes necessary to adapt services, utility lines or equipment required by the Contract. Subcontractors and others failing to make such checks and give notice as outlined above shall be required to assume any costs resulting from their failure to do so.

E. Before ordering materials or doing work, the Contractor shall verify all measurements to properly size or fit

the work. No extra charge or compensation will be allowed by the Owner resulting from the Contractor's failure to comply with this requirement.

SECTION 16 - INSPECTION OF WORK

- A. The Architect, Owner, and other inspectors or government officials as appropriate shall always have full access to all phases of the work. The Contractor shall provide adequate means to simplify inspection.
 - 1. The Contractor shall notify the Project Manager and local authorities twenty-four (24) hours before doing work that covers or otherwise makes it difficult to inspect structural, plumbing, mechanical, electrical, or other work.
 - 2. Should any of the work be covered before it is inspected by Project Manager and local authorities, the Contractor shall uncover that work for inspection at his own expense.
 - 3. The Contractor shall schedule the work so an inspection team may inspect the mechanical, electrical, and plumbing work before it is covered up. This inspection team will furnish a list of items that must be completed before the work is concealed.

SECTION 17 - SUPERVISION & CONSTRUCTION PROCEDURES

- A. The Contractor shall be solely responsible for all construction means, methods, techniques, sequences, and procedures and for coordinating all portions of the work under the Contract. The Contractor shall not change project managers or superintendents without the written consent of the Owner.

SECTION 18 - ARCHITECT'S STATUS AND DECISIONS

- A. The Architect shall assist the Project Manager during the construction period.
 - 1. The Architect will make frequent visits to the site to familiarize himself with the progress and quality of the work and to determine if the work is proceeding according to the Contract and schedule. During periodic visits the Architect may condemn work that fails to conform to the Contract.
 - 2. The Architect shall interpret the conditions of the Contract and be the judge of its performance. He shall use his powers under the Contract to enforce its faithful performance by the Contractor. The Architect will review shop drawings and prepare Proposal Requests. The Architect will conduct inspections with the Project Manager to determine the dates of substantial completion and final completion.
 - 3. In general, the Architect shall work with and coordinate with the Project Manager and the Contractor for the accomplishment of the Work. However, in the event that the Architect and Project Manager disagree on how a work should be accomplished, the Contractor shall take final direction from the Project Manager.
 - 4. Neither the Owner nor the Architect will be responsible for construction means, methods, techniques, sequences or procedures, or for safety precautions and programs concerning the Work. Neither the Owner nor the Architect will be responsible for failure of the Contractor, subcontractor, material supplier or their employees to carry out the Work according to the Contract.

SECTION 19 - MATERIAL & EQUIPMENT

- A. DELIVERY, STORAGE, & HANDLING
 - 1. Materials shall be delivered to the site in original packaging with labels and trademarks intact, and such labels and trademarks shall remain intact until used. Structural steel, piping and fittings shall be manufactured in the United States of America.
 - 2. The Contractor shall confine his apparatus, storage of materials, and operations of his workers to limits indicated by law, ordinances and permits. The Contractor shall arrange and maintain storage of materials within contract limit lines in an orderly manner leaving all walks, driveways, roads and entrances unencumbered. The Contractor and the Contractor's employees shall park

- only in the areas designated by Owner.
- 3. All new and existing equipment on the site shall be protected from physical damage and from the elements by measures satisfactory to the Architect and the Project Coordinator. All rotating equipment shall be rotated four turns weekly during construction.
- 4. If any material is found not conforming to the Contract, the Contractor shall remove such nonconforming materials at his expense.

B. PRODUCT OPTIONS & SUBSTITUTIONS

- 1. When several materials are specified in the Contract by name for one use, the Contractor may select any one of those so specified. The mixing of different products specified by name for one use is prohibited.
- 2. Items and material not specified in the Contract shall be removed and replaced by specified items and material at no additional cost to the Owner. No additional time will be added to the Contract for removal or replacement.
- 3. Wherever words "approved by," "satisfactory to," "submitted to," "inspected by," or similar phrases are used in this specification, they shall be understood to mean that the material or item referred to shall be approved by, be satisfactory to, submitted to, or inspected by the Architect and the Project Manager.

SECTION 20 - TEMPORARY CONSTRUCTION FACILITIES

A. TEMPORARY ELECTRICITY

- 1. The Contractor shall arrange with the proper authority (State, County, City, Owner, etc.) for all power required by the Contractor during the construction period until the Certificate of Substantial Completion is issued. If the power is coming from a BYU owned source, it will be paid for by BYU with the exception of the installation cost of equipment, conduit, wire, etc. BYU may provide transformer(s) and meter(s) at their discretion. Contractor to coordinate with BYU Construction Project Manager prior to bid. If no coordination takes place prior to bid, contractor is to provide transformer and meter at no additional cost to the owner after bid. Contractor shall bare the cost of any damages to owner provided equipment due to contractor's negligence. The method of metering, connections, etc., must have the written approval of the authority furnishing the utility to the Contractor. The Contractor shall be responsible for all utilities needed for his use during the entire construction period.
- 2. The Contractor shall provide all temporary wiring, outlets, metering (if the source of power is other than a BYU source), and associated materials. The temporary electrical system shall comply with local codes and the current, adopted version of the National Electrical Code.
- 3. The Contractor shall provide electrical power to distribution centers only.
- 4. If utility service is available from the Owner's permanent utilities, the Contractor may, by arranging with the Owner, use these permanent utilities. The Owner assumes no responsibility for damage caused by the Contractor using any of the Owner's utilities due to interruption of services by the Owner, whatever the cause.
- 5. The contractor may not use BYU provided power for welding equipment or other major equipment without written approval of BYU. Anything needing power other than for small tools, temporary lighting and project start up and function of permanent equipment (for example: elevator and mechanical equipment) shall be approved in writing by the BYU project Manager.

B. TEMPORARY LIGHTING

- 1. The Contractor shall provide wiring, outlets and fixtures for temporary lighting.
- 2. The Contractor shall provide pigtails and other lights for all areas within and around the building, sufficient to meet OSHA regulations, or to provide the following intensities, whichever is greater:
 - a. All working areas 3 foot candles
 - b. Stairs, landings, ramps 5 foot candles
 - c. Outdoor floodlighting within contract limit lines 3 foot candles
 - d. All areas involving finish work 30 foot candles

C. TEMPORARY HEATING, COOLING & VENTILATING

1. All temporary heating and cooling shall be arranged and paid for by the Contractor. Heating and cooling from the central plant will be charged at \$12.00 per million BTUs, if available and payable monthly to the Owner. BYU will provide the meter and contractor will install.
2. New Additions and New Buildings:
 - a. The Contractor shall be responsible for installation and operation of temporary heating, cooling, and ventilating units including fuel, temporary piping, fittings, wiring, and connections in new additions and new buildings as necessary.
 - b. The Contractor shall be responsible for damage to building and contents caused by cold, heat, and dampness.
 - c. The Contractor shall maintain safe conditions for use of temporary heating, cooling, and ventilating systems including, but not limited to, the following:
 - (1) Operate equipment following the manufacturer's instructions.
 - (2) Provide fresh air ventilation required by the equipment manufacturer.
 - (3) Keep temperature of fuel containers stabilized.
 - (4) Secure fuel containers from overturning.
 - (5) Operate equipment away from combustible materials.
 - (6) Provide adequate fire extinguishers.
3. Existing Building:
 - a. Where practicable and unless otherwise specified, existing facilities may be used, at the Owner's expense, to maintain minimum heating and cooling requirements. Normal setback temperature patterns shall not be interfered with except as specifically required to meet construction requirements. The existing system shall be protected by the Contractor from contamination, construction dust and debris. Filters shall be maintained in a clean condition and replaced with new filters at the completion of construction.
4. Specific heating requirements, unless otherwise specified by industry or manufacturer specifications, include but are not limited to:
 - a. Gypsum Plaster – Uniform minimum temperature of 55 deg F for a week before application of plaster, during plastering operations, and until plaster is dry.
 - b. Gypsum Board - 55 degrees F minimum day and night during entire joint treatment operation and until execution of Certificate of Substantial Completion.
 - c. Ceramic Tile - 50 deg F minimum during preparation of mortar bed, laying of the tile, and for 72 hours after completion of the tile work.
 - d. Acoustical Tile - 70 deg F minimum during setting of the tile.
 - e. Resilient Flooring - 70 deg F minimum during application.
 - f. Painting - 55 deg F minimum during painting operations and until dry.
5. When temporary heating, cooling, or ventilating is no longer required, the Contractor shall dismantle the temporary system and remove it at his own expense. The Contractor shall return permanent mechanical equipment to 'like-new' condition for the Substantial Completion Inspection. All warranties will begin at substantial completion regardless of when the equipment was started.

D. TEMPORARY WATER

1. The Owner will allow the Contractor usage of existing water facilities required for construction, at the Contractor's expense. If additional water is needed which cannot be supplied by existing facilities, the Contractor is to pay for installation of all valves, piping and metering, and arrange with the proper authority for connection of the additional water. BYU will provide the meter and contractor will install.

E. TEMPORARY SANITARY FACILITIES

1. The Contractor shall provide and maintain sanitary, temporary toilets.
2. The Contractor shall at all times maintain such facilities clean, neat and sanitary.
3. Temporary outside toilets shall be removed at completion of the job.

F. SCAFFOLDING AND PLATFORMS

1. The Contractor or his subcontractors shall furnish and maintain all equipment such as temporary stairs, ladders, ramps, platforms, scaffolds, hoists, runways, derricks, chutes, elevators, etc., as required for proper execution of the Work.
2. All apparatus, equipment, and construction shall meet all requirements of labor laws, safety regulations and other applicable Federal, State or local laws.
3. Temporary stairs shall be built whenever needed. The Contractor shall provide temporary treads, handrails and shaft protection as needed or as required by governing codes.

H. TREE & PLANT PROTECTION

1. Before commencing site work, the Owner shall build and maintain protective fencing around existing trees and vegetation as identified on the Project drawings.
 - a. Individual trees shall have protective fencing built beyond the drip line and to the satisfaction of the Project Manager.
 - b. Groups of trees and other vegetation shall have protective fencing built around the entire group to the satisfaction of the Project Manager.
 - c. Areas within protective fencing shall remain undisturbed and shall not be used for any purpose.
2. The Contractor shall protect all other trees, shrubs, lawns and all landscape work from damage and shall provide appropriate guards and covering. If normal sprinkling system is disrupted, the Contractor shall coordinate with BYU grounds to make sure the trees are watered by BYU or the Contractor.
3. Vegetation designated on drawings to be protected that has died or has been damaged beyond repair shall be removed and replaced by the Owner and back charged to the Contractor.

I. TEMPORARY ENCLOSURES

1. When walls and roof are in place, the Contractor shall provide temporary, weather tight enclosures for all exterior openings to protect all work. Openings into existing structure shall be made weatherproof.

J. PROTECTION FROM SNOW & ICE

1. The Contractor shall remove all snow and ice as may be required for the proper safety, protection and execution of the Work.

K. BRACING, SHORING, & SHEATHING

1. The Contractor shall design, furnish, install, and maintain all shoring, bracing, and sheathing as required for safety and proper execution of the Work and have the same removed if required when the Work is completed.

L. PROTECTION OF PERSONS

1. The Contractor shall provide, install, and maintain all necessary precautions to protect all persons on the site, including the public. Such measures shall include:
 - a. Posting of appropriate warning signs in hazardous areas.
 - b. Providing guardrails, fencing and barricades of adequate heights around all openings in floors or roofs, and around all excavations. All guardrails shall meet all applicable codes.
 - c. Providing warning lights around obstructions, pits, trenches, or similar areas on-site or in adjacent streets, roads, sidewalks, or in the structure itself.
 - d. When use or storage of hazardous materials or equipment is necessary for the execution of the Work, the Contractor shall exercise the utmost care and shall carry on such activities under the supervision of properly qualified personnel, and shall perform the work in accordance with all applicable codes or regulations.

M. PROTECTION FROM WEATHER

1. The Contractor shall provide protection against weather and protect all work, materials, apparatus, and fixtures. At the end of the day all work that might be damaged shall be covered.

2. If low temperatures or other weather conditions make it impossible to continue operations safely in spite of precautions, the Contractor shall cease work and notify the Project Manager.

N. PROTECTION OF EXISTING WORK

1. The Contractor shall protect all streets, private roads, and sidewalks, including overhead protection where required, and shall make all necessary repairs to damaged Work at his own expense.
2. The Contractor shall provide proper protection of all existing Work, furnishings, and fixtures likely to be damaged. When exterior openings are made in existing Work, they shall be covered with weather tight protection at the end of the day.
3. Before commencing work, the Contractor shall survey the site, and shall photograph and note any damage to existing structures including walks, curbs and utilities and shall provide copies of the photographs to the Project Manager before proceeding with work. Any damage not noted by the Contractor will be repaired or replaced by the Contractor.
4. Any Work damaged by failure to provide protection shall be removed and replaced at Contractor's expense.

O. FIRE PROTECTION

1. The Contractor shall provide at least one approved fire extinguisher in plain sight on each floor at each usable stairway prior to introduction of any combustible materials into the building.
2. Fires shall not be built on the premises.
3. In existing buildings with fire alarm/detection devices, the Contractor shall cover all smoke detectors within the work area each morning before work begins and remove dust covers at the end of the day. Fire detection devices must be functioning in the work area when the Contractor is not on the site.

P. PROTECTION OF ADJACENT PROPERTY

1. The Contractor shall provide all necessary protection and support of adjacent property.

Q. CONSTRUCTION CLEANING

1. The Contractor shall keep premises broom clean during progress of the work.
2. The Contractor shall remove waste materials and rubbish left by employees, subcontractors, and material suppliers. Roads inside and outside the Project shall be cleaned daily when hauling.
3. Before and during painting and varnishing, the Contractor shall clear the area of all debris, rubbish, and building materials that may cause dust. Sweep floors as required and take all possible steps to keep area dust free.

R. SURFACE WATER CONTROL

1. The Contractor shall protect the excavation, trenches and building from water damage by:
 - a. Providing pumps, equipment and enclosures necessary for such protection.
 - b. Constructing and maintaining temporary drainage and pumping as necessary to keep the site free of water.
2. The cost of water control shall be borne by the Contractor. The Owner may, if promptly notified of adverse underground water conditions, negotiate reasonable financial relief for the Contractor where such conditions could not have been learned from the Soils Engineer's Report, the Contract, or by commonly known local conditions.

S. OFFICES

1. The Contractor shall provide and maintain a weather tight office at the construction site. This building is to be located outside of, and detached from the building under construction. Connection of utilities and monthly utility costs shall be paid by the Contractor. This building shall be the property of the Contractor and shall be removed upon completion of the Project.

T. SHEDS AND TRAILERS

The Contractor shall provide and maintain neat, weather-tight storage sheds or trailers for storage of all materials that might be damaged or affected by weather or moisture. These sheds or trailers shall

have wood floors raised above the ground and will be outside of and detached from the building under construction. They shall be property of the Contractor and shall be removed upon completion of the work.

U. CODE OF CONDUCT

Contractor recognizes that BYU is an affiliate of the Church of Jesus Christ of Latter-day Saints, and that students and employees at BYU expect to work and learn in an environment consistent with the principles of the Church. Contractor agrees that all of Contractor's employees will A) Refrain from consuming alcohol, tobacco, or other illegal drugs on BYU campus, except that smoking may be permitted in designated, outdoor, areas; B) Refrain from using profanity; C) Observe modest standards of dress and behavior; D) be courteous and respectful to all members of the BYU campus community. Violations of these expectations may be grounds for terminating the Contractor's engagement or for asking the Contractor to dismiss a particular, offending employee from the Project.

SECTION 21 - TESTING

- A. Testing companies will be selected by the Owner.
- B. The Owner and/or the Architect reserve the right to have tests taken at any time.
- C. Tests not specified as part of a trade section shall be paid by the Owner.
- D. Should tests reveal a failure of the Work to meet Contract requirements, subsequent tests related to the failure shall be paid by the Contractor.
- E. Tests shall be made according to recognized standards by a competent, independent testing laboratory.
- F. Materials found defective or not in conformance with the Contract shall be promptly replaced or repaired at the expense of the Contractor.
- G. Samples required for testing shall be furnished by the Contractor and selected as directed by the Architect or Project Manager.

SECTION 22 - EXISTING UTILITIES

- A. Prior to execution of the Work the Contractor is to locate all existing vaults, manholes, valves, meters, etc. Contractor is to photograph, GPS, measure from existing structures and facilities that are to remain and keep this information readily available at the site/construction trailer. Contractor is also to mark the above utilities by staking and maintaining stakes for fast and accurate locating of all existing utilities in case of emergencies.
- B. BYU will initially provide all on campus blue staking information. It is the Contractor's responsibility to maintain the blue staking locations and information by staking, painting, keeping GPS coordinates or any alternative ways that the Contractor can keep current, accurate information.

SECTION 23 - CUTTING AND PATCHING

- A. The Contractor shall coordinate all cutting, fitting, or patching of the Work (including but not limited to cutting or patching of floorings; ceilings; roofs; walls; mechanical, electrical and plumbing; and all other surfaces and structures) that may be required to make the several parts of the Work come together properly. The Contractor shall coordinate all portions of the Work so as to receive or to be received by other portions of the Work, whether previously existing or newly created. The Contractor shall make proper repair or

closure of the Work as needed or as directed by the Architect or the Project Manager.

- B. The Contractor shall refrain from cutting or digging in a manner that is harmful to the Owner's premises. Contractor agrees that Contractor will not cut or alter any section of the Owner's premises except as indicated on the plans and specifications without prior consent of the Architect and the Project Manager. The Contractor shall give 48-hour Blue Stake notice to the Project Manager and local Blue Stakes location center.
- C. In the event that Contractor shall cause damage to the Owner's premises while cutting or digging, Contractor shall cause the damage to be repaired at the Contractor's expense.
- D. All concrete slabs whether suspended or on-grade shall be scanned by the general contractor and/or verified by BYU before demoing, drilling, coring or cutting. It is the responsibility of the general contractor to repair or replace the slab, it's reinforcements and other parts, utilities in the slab and adjacent surfaces as a result of failure to scan the slab.

SECTION 24 - CONDEMNATION OF WORK

- A. The Owner or the Architect shall have the right to condemn and require removal of the following at the Contractor's expense:
 - 1. Any portions of the Work that do not meet the requirements of the Contract either in substance or installation.
 - 2. Any portions of the work damaged or rendered unsuitable during installation or resulting from the Contractor's failure to properly protect the work.

SECTION 25 - CHANGES IN THE WORK

- A. The Owner may make changes within the general scope of the Contract, including but not limited to changes:
 - 1. In the Contract.
 - 2. In the method or manner of performance of the Work.
 - 3. In the Owner-furnished facilities, equipment, materials, or site.
 - 4. In directing acceleration of the Work.
- B. Any written order from the Owner or Architect which changes the scope of the work shall be a Change Order.
- C. The Architect is authorized to order minor changes during the Work that will not involve significant extra cost or time. The price of such minor changes will be mutually agreed upon between the Project Manager and the Contractor. The Contractor will proceed with the changed work immediately. These minor field changes will subsequently be included in a Change Order.
- D. Proposal Requests may be issued which ask the Contractor to submit a price for proposed changes in the scope of the Work. The Contractor is to promptly provide costs associated with the prospective changes, including credits for deleting any unnecessary Work. Cost breakdowns are to be submitted in sufficient detail to verify that the complete scope of the Work is understood by the Contractor, Architect, and Project Manager.
- E. Change Orders -
 - 1. Except for emergencies as covered in Section 8, and to avoid delays, no changes in the work shall be made without a written Change Order. The Contractor's proposal shall be the basis of negotiation for the Change Order price and/or time adjustments.
 - 2. If the Owner decides it is necessary to proceed with changed work to avoid delay before prices or times have been negotiated, he may order the Contractor to proceed on a time and materials basis or on a mutually agreed not-to-exceed price and time extension. This notice to proceed shall be issued by the Owner's Representative. Upon receipt of such order, the Contractor shall immediately perform the changed work. The Owner and the Contractor will then negotiate the price and/or time when practicable, and a Change Order will be issued.

3. When submitting proposals for Change Orders, the Contractor shall furnish a price breakdown itemizing costs as required by the Owner. Unless otherwise directed, the breakdown shall be in sufficient detail to allow an analysis of all material, labor, equipment, overhead costs and profit, and shall cover all Work involved in the change, whether such Work was deleted or added. Any amount claimed for subcontractors shall be supported by a similar price breakdown. In addition, if the proposal includes a time extension, a justification shall be furnished. The proposal, with the price breakdown and time extension justification, shall be furnished within fourteen (14) days of the date that the first request was made by the Owner's Representative. In such proposals, profit and overhead shall be computed as follows:
 - a. The Subcontractor's profit and overhead shall not exceed 15% of total direct costs.
 - b. The Contractor's profit and overhead on work done by his own crews shall not exceed 15% of total direct costs.
 - c. The Contractor's profit and overhead on work performed by subcontractors shall not exceed 5% of total direct costs or in the case of a CMGC Contract the Contractor's profit and overhead fee on change orders shall not exceed the pre-contract negotiated fee.
 - d. The subcontractor's profit and overhead on work performed by any of his subcontractors shall not exceed 5% of total direct costs. Contractor's profit and overhead will not exceed 5% of total direct costs.
 - e. On credit changes, profit and overhead on the originally estimated work will not have to be returned to the Owner.
 - f. No supervision costs, office managerial costs, or office expenses can be added to Change Orders.
 - g. Upon signing a Change Order, the Contractor releases the Owner from any further claim for money or time because of the changed work.

SECTION 26 - CLAIMS FOR EXTRA COST

- A. If the Contractor intends to assert any additional claim for equitable adjustment of cost or time, he must, within fourteen (14) calendar days of the events or circumstances giving rise to the change, submit to the Architect and the Owner a written statement of the nature and monetary extent of such claim. If a mutually acceptable settlement of the claim cannot be reached within a reasonable time, the parties to the Contract shall handle the matter as a dispute under Section 27 "DISPUTES."

SECTION 27 - DELAYS AND EXTENSION OF TIME

- A. All time limits stated in the Contract are of the essence. Contractor agrees to carry out the Work according to the time durations and limits as specified in the Contract.
- B. If the Contractor is delayed any time during the progress of the work because of labor disputes, abnormal weather, unusual delays in transportation, or any other causes beyond the Contractor's control, the Contractor may be given additional time to complete the work by Change Order.
 1. All requests for time extensions shall be made in writing to the Project Manager.
 - a. Claims for time extension due to abnormal weather shall be made within fourteen (14) days of the abnormal weather.
 - b. Claims made beyond these time limits shall not be considered by the Owner.
 2. Requests for time extensions shall be fully documented by including copies of daily logs, letters, shipping orders, delivery tickets and other supporting information.
 3. In case of a continuing cause of delay only one claim is necessary.

SECTION 28 - DISPUTES

- A. Except as otherwise provided in the Contract, any dispute concerning a question of fact arising under this Contract that is not disposed of by agreement shall be decided by the Owner's Representative (as represented by the Assistant Administration Vice President/Physical Facilities of Brigham Young University). The decision shall be rendered in writing and mailed or otherwise given to the Contractor. If

the decision is not agreeable to the Contractor, the Contractor will, within fourteen (14) days of the decision, mail or otherwise furnish to the Owner's Representative a written appeal addressed to the Owner.

SECTION 29 - CORRECTION & WARRANTY OF WORK

- A. The Contractor shall promptly correct any work that fails to conform to the requirements of the Contract during the progress of the Work. The Contractor shall remedy any defects due to faulty materials, equipment or construction that appear within one year from substantial completion of the Contract or within such longer periods as may be prescribed by law or by the terms of any applicable extended guarantee required by the Contract. The Contractor shall promptly correct all faulty work or pay all costs of correcting the faulty work.

SECTION 30 - OWNER'S RIGHT TO DO WORK

- A. If the Contractor defaults or neglects to carry out the Work according to the Contract or fails to perform any provision of the Contract, the Owner may, upon approval of the Architect, after providing seven days written notice to the Contractor and without prejudice to any other remedy Owner may have, make good such deficiencies. In such case, an appropriate Change Order will be issued deducting the cost of correcting such deficiencies, including the cost of the Architect's additional services made necessary by such default, neglect or failure. If the payments due the Contractor are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner. .

SECTION 31 - CONTRACTOR'S PAY REQUEST

- A. The Contractor shall submit to the Project Manager a monthly payment request based on the estimated value of the work completed and materials on the site as of that date. The payment request shall be on the form provided in this document, or on the then-current AIA G702 Application and Certification for Payment (or equivalent) Form. Such payment request shall be based on the schedule of values submitted by the Contractor. The Contractor warrants that title to all work, materials and equipment covered by the payment request, whether incorporated in the Project or not, will pass to the Owner upon the receipt of such payment by the Contractor, free and clear of all liens, claims, security interests or encumbrances. The Project Manager may audit Contractor payments to subcontractors or suppliers anytime.

SECTION 32 - PAYMENTS TO CONTRACTOR

- A. Upon approval of the Contractor's monthly payment request, the Owner will, within fourteen (14) days after receipt of said certification, mail to the Contractor a sum equal to 95% of the amount requested, less previous payment thereon. The retention that is withheld by the Owner will be placed in an interest-bearing account and paid to the Contractor after the project is completed and accepted by the Owner.
- B. Upon receipt of a payment by the Owner, the Contractor shall pay each subcontractor within fourteen (14) calendar days, the amount allowed to the Contractor for the subcontractor's work.
- C. The Contractor's monthly payment request, which shall show the amount paid under the subcontract, shall be made available to the Project Manager for examination. Full and final payment of the Contract amount shall be made within thirty (30) days of the completion of the following requirements:
 - 1. The Architect's and Owner's written acceptance of the work.
 - 2. Payment of all labor and material bills, and receipt of all final lien waivers or lien releases from all subcontractors, mechanics and suppliers.
 - 3. No payment made under this Contract shall be construed to be an acceptance of defective or improper materials or construction.
- D. A schedule of dollar values shall be submitted to the Architect and the Owner before the Contractor's first

payment request will be processed.

- E. The schedule of values shall be submitted on the Owner's standard payment request form.
 - 1. This breakdown shall follow the trade divisions of the specification. Each item shall include its pro rata part of overhead and profit so that the sum of the items will equal the Contract price.
 - 2. The breakdown will correspond exactly to items of work in the Project schedule including work of subcontractors.
- F. The Contractor shall make arrangements to receive all payments from the Owner by direct deposit.

SECTION 33 - PAYMENTS WITHHELD

- A. Payments may be withheld from the Contractor by the Owner to protect the Owner from loss due to:
 - 1. Defective work not remedied.
 - 2. Liens or claims filed or reasonable evidence of probable filing.
 - 3. The Contractor's failure to promptly pay subcontractors for labor and materials accepted by the Contractor.
 - 4. The Architect's or the Project Manager's reasonable doubt that the Project can be completed for the unpaid balance of the Contract price.
 - 5. Damage to another contractor.
 - 6. Failure to maintain scheduled progress.
- B. Upon satisfactory correction of the above conditions, withheld payments will be made.

SECTION 34 - CONTRACTOR RESPONSIBILITIES

- A. The Contractor is fully responsible for the Project and all materials and work until the Owner has accepted the completed Project in writing. The Contractor shall replace or repair, at his own expense, any materials or work damaged or stolen even if the Contractor has received payment for the work or materials.
- B. By executing the Contract, the Contractor represents that he has visited the site, familiarized himself with the local conditions under which the Work is to be performed, and correlated his observations with the requirements of the Contract.
- C. The Contractor shall employ a competent superintendent satisfactory to the Architect and the Owner. The superintendent shall be present at the Project site during the progress of the Work. This superintendent shall not be changed except with the prior consent of the Project Manager or unless the superintendent ceases to be in the Contractor's employment. The replacement superintendent shall also be subject to these conditions. The superintendent shall represent the Contractor, and all communications given to the superintendent shall be as binding as if given to the Contractor.
- D. The Contractor shall designate a responsible member of his organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated in writing by the Contractor to the Owner and the Architect.
- E. In the event that the Contractor receives purported directions regarding the Work from anyone other than the Project Manager, the Contractor shall forward/direct all communications to the Project Manager.
- F. Unless otherwise directed, the Contractor shall, within two (2) hours after the bid opening, furnish the Architect and the Owner a list of the proposed subcontractors who will be working on the Project. The Owner will notify the Contractor in writing if any of the subcontractors are unacceptable.
- G. The Contractor shall not contract with any subcontractor who has been rejected by the Owner or the Architect. The Contractor will not be required to contract with any subcontractor, person or organization

against whom he has a reasonable objection if such objection is made before the bid opening. The Contractor is not to use or accept any bid from a subcontractor unless the Contractor is willing and able to work with that subcontractor.

- H. If the Owner or the Architect requires a change of any proposed subcontractor or person or organization previously accepted by them, the Contract amount shall be increased or decreased by the difference in cost occasioned by such change and an appropriate Change Order shall be issued.
- I. The Contractor shall not make any substitution of a subcontractor who has been accepted by the Owner and the Architect unless the substitution is accepted in writing by the Owner and the Architect. Any increase in cost shall be paid by the Contractor.
- J. All damage or loss to any property caused in whole or in part by the Contractor, any subcontractor, or by either of their agents, shall be remedied by the Contractor at no cost to the Owner.
- K. The Contractor shall be solely responsible for initiating and supervising all safety programs including, but not limited to:
 - 1. The protection of all persons on the site, including the public.
 - 2. All conditions specified in this contract.
 - 3. All conditions required by codes and/or governmental regulations including OSHA.
 - 4. The protection of all property on the site or affected by the Work.
 - 5. The Contractor shall designate a responsible member of its organization at the site whose duty will be the prevention of accidents. This person will be Contractor's onsite representative unless otherwise designated in writing by Contractor to Owner and Architect.
- L. The Contractor shall be responsible for:
 - 1. Limiting all Work at the site to Monday through Saturday, between the hours of 7:00 A.M. to 10:00 P.M. No Sunday work is to be performed. Any exceptions to the working hours or days must be made by prior written authorization by the Owner.
 - 2. Requiring all personnel on site to be appropriately dressed. This includes protective clothing and equipment as needed. Shirts are to be worn at all times.
 - 3. Limiting all Work at the site according to local noise ordinances or other ordinances.
- M. The Contractor's employees shall not be allowed to use radios, boomboxes, etc., on the site.
- N. Renderings representing the Work are the property of the Owner. All photographs of the Work, whether taken during construction or at completion, are the property of the Owner. The Owner reserves all rights including copyrights to renderings and photographs of the Work. Buildings shall not be photographed, and no renderings or photographs shall be taken, obtained, used, or distributed without the prior written consent of the Owner.
- O. All information regarding the cost of the Project shall be considered confidential and shall not be disclosed by the Contractor to any third party without the prior written consent of the Owner.

SECTION 35 - SUBCONTRACTORS

- A. The Contractor's responsibility for this Project includes the work of all subcontractors and material suppliers, including those recommended or approved by the Owner. The Contractor shall be held responsible to the Owner for proper completion and guarantee of all construction and materials under subcontracts and for the acts and omissions of his subcontractors or their employees. Any warranties required for such work shall be obtained by the Contractor in favor of the Owner and delivered to the Owner. It is expressly agreed that there is no contractual relationship between the Owner and any subcontractor, and under no circumstances shall the Owner be responsible for the nonperformance or financial failure of any subcontractor.

- B. The Contractor shall require each subcontractor to agree:
 - 1. To be bound by terms of the Contract as far as applicable to the subcontractor's work.
 - 2. To assume toward the Contractor the same obligations the Contractor has assumed toward the Owner, including the prompt payment of his employees and material suppliers affected by this work.
 - 3. To submit his applications for payment to the Contractor in time to allow the Contractor to make timely application to the Owner.
 - 4. To execute claim or lien releases or lien waivers as requested by the Contractor for payments made by the Contractor.
 - 5. To make all claims for extra work or for extensions of time to the Contractor in the same manner the Contractor is to make this type of claim to the Owner.

- C. The Contractor agrees in his relationship with the subcontractors:
 - 1. To bind himself to the subcontractors by all the obligations that the Owner assumes to the Contractor.
 - 2. To pay the subcontractors within fourteen (14) calendar days upon receipt of payment from the Owner that portion of the funds received as represents the subcontractor's portion of the Work completed to the Contractor's satisfaction for which payment was made by the Owner.

SECTION 36 - LOCKOUT/TAGOUT, CONFINED SPACE, HAZARD COMMUNICATION PROGRAMS, HOT WORK and EXCAVATION PERMIT PROGRAMS

- A. The Contractor and the subcontractors will have a written "Lockout/Tagout" program. A copy of this program will be submitted to the Project Manager.

- B. The Contractor and subcontractors shall evaluate all work places to determine if any spaces are permit-required confined spaces in accordance with any applicable OSHA regulations. If the workplace contains permit spaces, the Contractor shall inform exposed employees by posting danger signs in compliance with OSHA regulations. If the Contractor decides that its employees will enter permit spaces, the Contractor shall implement a written confined space program. The written program shall be made available to all persons (whether employees of the Contractor or not) and submitted to the Project Manager. The confined space program shall inform the persons that the workplace contains confined spaces that require a permit to enter those spaces. The Contractor shall identify the hazards that may be encountered in the confined space. The Contractor shall specify any precautions or procedures required for the protection of persons in or near confined spaces.

- C. Besides complying with the confined space requirements that apply to all employers, the Contractor shall:
 - 1. Obtain any available information regarding permit space hazards and entry operations.
 - 2. Coordinate entry operations when both contractor and subcontractor personnel will be working in or near permit spaces.

- D. The Contractor shall inform the Project Manager of the methods the Contractor will use to inform all employees on the site of any precautionary measures that need to be taken for protection during the workplace's normal and emergency operating conditions. The Contractor will specify the methods to inform the employees of the labeling system for hazardous materials. The Contractor may rely on an existing hazard communication program to comply with these requirements if it is current with OSHA regulations.

- E. The Contractor shall make the written hazard communication program available to all personnel working on the Project and to the Project Manager.

- H. In addition to the Hot Work permit required under Section 14, above, the Contractor shall have and implement a Hot Work permitting program that complies with all OSHA regulations. This program must be

communicated to all those who might be involved with Hot Work. Copies of this program shall be made available to the Project Manager upon request.

- I. The Contractor shall have and implement a written excavation permitting program that complies with all OSHA regulations. This program must be communicated to all those who might be involved with related work. Pre-task planning and job hazards must be assessed prior to any excavations on the Project. Existing utilities must be identified and procedures put in place to avoid damage or interruptions to existing buildings or operations. Copies of this program shall be made available to the Project Manager upon request.

SECTION 37 - OWNER'S RIGHT TO CANCEL CONTRACT

- A. The Contractor shall give the Owner at least twenty-one (21) days written notice before filing any petition for bankruptcy. The Contractor shall be in material breach of the Contract if the Contractor fails to give this notice.
- B. Should the Contractor make a general assignment for the benefit of his creditors, or if he should persistently refuse or fail to apply enough properly-skilled workers or proper materials to correctly execute the Work, or if he should fail to make prompt payment to the subcontractors or material suppliers for accepted material or labor, or constantly disregard laws, ordinances or instructions of the Architect and the Owner, or otherwise be guilty of substantial violation of any provision of the Contract, then the Owner may, without any prejudice to any other right or remedy and after giving the Contractor seven (7) days written notice, terminate employment of the Contractor and take possession of the premises and all materials, tools and appliances, and finish the Work by whatever method the Owner deems expedient. In such case, the Contractor shall not be entitled to receive any further payment until the Work is finished. If the unpaid balance of the Contract price exceeds the expense of finishing the Work, including compensation for additional administrative services, such excess shall be paid to the Contractor. If such expense shall exceed the unpaid balance, the Contractor shall pay the difference to the Owner.

SECTION 38 - CONTRACTOR'S RIGHT TO STOP WORK OR TERMINATE CONTRACT

- A. If the Work should be stopped under court order, or other public authority for thirty (30) days, or the Owner shall fail to pay the Contractor within thirty (30) days of receipt of a properly prepared and completed payment request, then the Contractor may, on seven (7) days written notice to the Owner and the Architect, terminate this Contract and recover from the Owner the percentage of the Contract price represented by the work completed as of the date of termination with any loss sustained which can be established.

SECTION 39 - SEPARATE CONTRACTS

- A. The Owner reserves the right to award separate contracts concerning other portions of the Project under these or similar conditions of the Contract to other contractors.
- B. The Contractor shall afford separate contractors reasonable opportunity for the introduction and storage of their materials and equipment and the execution of their work, and shall properly connect and coordinate his work with theirs.
- C. If any part of the Contractor's work depends upon the work of another separate contractor, the Contractor shall inspect and promptly report to the Project Manager any apparent discrepancies or defects in such work that render it unsuitable for proper execution and results. Failure of the Contractor to inspect the work is an acceptance of the work of the separate contractor unless defects develop in the other separate contractor's work after the execution of the Contractor's work.

SECTION 40 - ASSIGNMENT

- A. The Contractor shall not assign or sublet this Contract or any part of it or any monies due him without prior written consent of the Owner.

SECTION 41 - LIQUIDATED DAMAGES

- A. For each calendar day that the Work or any portion of the Work remains incomplete after the expiration of the time limit set in the Contract or by Change Order, the amount per calendar day shown in the Supplementary Conditions will be deducted from the money due or to become due to the Contractor. This deduction is not a penalty, but is liquidated damages and may include additional expenses such as administrative and inspection costs.
- B. At the time of substantial completion, and after the meeting to certify substantial completion, the Owner, Architect and Contractor shall agree upon the time that will be allowed for the Contractor to complete the remaining Work on the Project. If the Contractor does not complete the Work within the agreed time, the liquidated damages will continue at a reduced amount as stated in the Supplementary Conditions. The liquidated damages shall be in full force and effect, not as a penalty but as liquidated damages for each additional calendar day it takes to complete the Project. If liquidated damages are required, they shall be accrued and deducted from the money due the Contractor.

SECTION 42 - ACCELERATION OF WORK

- A. If, in the judgment of the Architect or the Owner, it becomes necessary at any time to accelerate the Work or part of it, the Contractor shall deploy the workers in such portions of the Project to enable others to properly engage and carry on their work. If circumstances require that the entire Work or a portion of it be completed at a date earlier than the Contract completion date as adjusted by Change Orders, the Contractor shall increase his forces, equipment, hours of work, or number of shifts, and shall speed delivery of materials to meet the altered completion date or dates ordered or directed. Any increase in cost to the Contractor according to such orders or directives will be adjusted by Change Order.
- B. If the Work is behind schedule and the rate of placement of work is inadequate to regain scheduled progress, the Contractor shall immediately take action to ensure timely completion of the Work.
 1. This shall be accomplished by any one or a combination of the following or other suitable measures:
 - a. An increase in working forces.
 - b. An increase in equipment or tools.
 - c. An increase in hours of work or number of shifts.
 - d. Expediting delivery of materials.
 2. The Contractor shall notify the Project Manager of specific measures taken or planned to increase the rate of progress with an estimate of when scheduled progress will be regained.
 3. Acceleration of work will continue until scheduled progress is regained. Scheduled progress shall be established from the latest revised and approved Project schedule for the job.
 4. Timely completion will be understood as the Contract completion date as revised by all time extensions.
 5. The Contractor shall not be entitled to additional compensation for efforts to regain scheduled progress.

SECTION 43 - CONTRACTOR'S QUALITY CONTROL

A. MATERIAL QUALITY

1. Materials incorporated into the Project shall be new except as otherwise indicated in the specifications. Materials shall be of specified quality and furnished in sufficient quantity to simplify proper and timely execution of the Work.
2. The Contractor shall furnish evidence of the quality of materials incorporated into the Project as required by the Contract or at request of the Architect or the Project Manager.
3. Materials not meeting requirements of the Contract shall be removed from the Project and replaced with materials meeting the Contract requirements by the Contractor at no additional expense to the Owner.

B. ASBESTOS

1. The Contract has been prepared following generally accepted professional architectural and engineering practices. Accordingly, no asbestos or products containing asbestos have been knowingly specified for this Project. The Contractor agrees to notify the Project Manager immediately for instructions if:
 - a. Materials containing asbestos are brought to the site for inclusion in the Work.
 - b. Asbestos materials are encountered in any existing structures upon which work is being done.
2. At the Architect's direction and with the Owner's approval, an independent testing laboratory will perform testing procedures on suspect materials at Owner's expense.
3. The Contractor shall certify, based upon his best knowledge, information, inspection and belief, that no building materials containing asbestos were used in the construction of the Project. The Contractor will submit certification on form provided by the Owner.

SECTION 44 - TEMPORARY OR TRIAL USAGE OF ANY MECHANICAL DEVICES

- A. Temporary or trial usage by the Owner of mechanical devices, machinery, apparatus, elevators, equipment or other work or materials supplied under this Contract before written acceptance by the Owner shall not be construed as evidence of the Owner's acceptance.

SECTION 45 - PROJECT CLOSEOUT

A. FINAL CLEANING

1. Upon completion of the Work, the Contractor shall remove all tools, scaffolding, surplus materials and all rubbish from under and about the building. The Contractor shall leave the building clean and habitable, having thoroughly swept or vacuumed floors, cleaned windows and dusted flat surfaces such as cabinet tops and window sills.
2. Besides general cleaning noted above, the Contractor shall do the following special cleaning for all trades at the completion of the work:
 - a. Remove putty or caulking stains from glass. Wash and polish inside and outside, exercising care not to scratch glass.
 - b. Remove marks, stains, fingerprints, other soil and dirt from painted, decorated and stained work.
 - c. Clean and polish woodwork.
 - d. Clean and polish hardware for all trades. This shall include removal of stains, dust, dirt, paint and other similar materials.
 - e. Remove spots, soil and paint. Wash tile work.
 - f. Clean fixtures and equipment, and remove stains, paint, dirt and dust.
 - g. Remove temporary floor protection and clean floors. Spray and buff resilient flooring.
 - h. Clean exterior and interior metal surfaces, including doors and windows, required to have polished finishes. Remove oils, stains, dust, and dirt. Polish surfaces, leaving them without fingerprints or other blemishes.
3. If the Contractor fails to clean up, the Owner may do so and the cost will be withheld from the Contractor's final payment.

B. PROJECT RECORD DOCUMENTS

The Contractor shall deliver to the Architect before the substantial completion inspection:

1. Accurate Project "record" drawings, including redline drawings.
2. Certificates of occupancy that may be required by Authorities Having Jurisdiction over the work.

C. OPERATING & MAINTENANCE DATA

Before execution of the certificate of substantial completion, the Contractor shall furnish the operating instructions and maintenance manuals as called for in the Contract.

D. WARRANTIES & GUARANTEES

1. When written guarantees beyond one year after substantial completion are required of any section of the Work, the Contractor shall secure such guarantees properly addressed and signed and in favor

of the Owner. These documents shall be delivered to the Project Manager upon substantial completion of the Contractor's work and before execution of the certificate of substantial completion.

2. Delivery of guarantees and warranties shall not relieve the Contractor from any obligation assumed under any other provisions of his Contract.
3. Nothing within the Contract intends or implies that guarantees shall apply to work abused or neglected by the Owner.

E. PRE-SUBSTANTIAL, SUBSTANTIAL, & FINAL COMPLETION INSPECTIONS

1. Pre-Substantial Completion Inspection:
 - a. Upon the Contractor's request and if the request is accompanied by a punch list prepared by the Contractor, the Project Manager and the Architect will make inspections and furnish a list of additional items to be corrected or completed by the Contractor.
 - b. The Contractor shall notify the Project Manager when items have been corrected or completed. Upon the Project Manager's verification of correction, the Project Manager will arrange a substantial completion inspection to include the Owner, Architect, engineers and college representatives.
2. Substantial Completion Inspection:
 - a. At the substantial completion inspection, unless the Work is rejected, the Architect may execute a certificate of substantial completion (to be signed by the Architect, Owner and Contractor) that states the dates for:
 - (1) User occupancy,
 - (2) Commencement of warranties,
 - (3) Final completion inspection,
 - (4) Modifications to the amount assessed for liquidated damages.
 - b. After inspection, the Architect will furnish a final list of items to be corrected.
 - c. The Owner, Architect and Contractor will decide how much time is to be allowed for completion of the items.
3. Final Completion Inspection:
 - a. Final Completion Inspection will ensure that all deficiencies noted at the substantial completion inspection have been corrected.
 - b. When all items have been corrected, the Project Manager will process the final payment and send a final completion letter indicating the final completion date to the Contractor.
 - c. If all items have not been corrected as agreed, the Owner may elect to complete the work under provisions of Section 29 of the General Conditions.
 - d. All lien waivers and releases are to be submitted before final payment can be made.
 - e. A copy of the final payment consent form will be obtained from the surety/bonding company.

SECTION 46 - OWNER-PURCHASED MATERIALS AND EQUIPMENT

- A. The Owner desires to purchase certain materials which will be utilized in the Work. Contractor's duties with respect to Owner-purchased materials are:
 1. Scheduling:
 - a. The Contractor shall furnish the Owner with a schedule of dates on which the Contractor requires delivery of Owner-purchased materials. The Owner will arrange for the materials to be delivered to the construction site on or before the specified dates. If delivery dates are changed, rescheduled, or otherwise varied from the original schedule, the Contractor shall notify the Owner in writing of delivery date rescheduling and the Contractor shall coordinate the delivery of the Owner-purchased materials directly with the supplier.
 2. Pre-Installation Inspection:
 - a. The Contractor shall be responsible for receiving, inspecting and storing all Owner-purchased materials until the materials are needed for installation by the Contractor. Regardless of any inspection performed by the Owner of the Owner-purchased materials, the Contractor shall be responsible for inspecting the Owner-purchased materials to determine suitability, quality and conformance with specifications before installation or at such other

time as the Contractor may desire in order to avoid interruptions and delays in the progress of the Project. The Contractor shall reject any material which does not meet specifications or which appears to have any defect which may make the material unsuitable for use in the Project. The Contractor shall notify the Owner and the manufacturer or supplier of all defects and assist the Owner in arranging for the repair, replacement or correction of the defective condition. The Contractor shall not be entitled to an extension of any deadline or completion date which results from failure to discover defects which the Contractor should have discovered through an inspection.

3. Defective Materials:

- a. The Contractor acknowledges that use of improper or defective material may result in costs and damages to the Owner in excess of the value of the materials; that after use in the Project it may be difficult or impossible to inspect the material to determine the cause of any failure; and that in the event of the failure of material there may be a question as to the cause of the failure. Because the Contractor's employees will be the last to handle and inspect material prior to incorporation into the Project, the Contractor will be liable to the Owner for damages resulting from failure of Owner-purchased materials during the Contractor's warranty period specified herein from any cause whatsoever unless the Contractor provides clear and convincing proof that (1) the entire loss from a failure is covered by a valid manufacturer's or supplier's warranty, or (2) the Contractor could not have prevented the failure by complying with the requirements of this Section concerning Owner-purchased materials.

4. Claims:

- a. The Contractor agrees to assist the Owner to present claims to manufacturers and suppliers for defects in Owner-purchased materials. Where there is any question as to the division of liability between the Contractor and a manufacturer or vendor, the Contractor shall provide all relevant information in the Contractor's possession which may aid the Owner in determining the division of responsibility. The Owner shall have final approval of any proposed adjustment or settlement of warranty claims.

5. Implied Warranties:

The benefit of contractual and implied warranties with respect to Owner-purchased materials shall run to the Owner and not to the Contractor.

6. Unloading:

Except as otherwise provided herein, the Contractor shall be responsible for unloading all Owner-purchased materials and verifying delivery amounts to the Owner.

7. Custody and Security:

The Contractor shall use reasonable care in protecting Owner-purchased materials from loss, deterioration, damage, theft, vandalism or destruction.

8. Reports:

At Owner's request, the Contractor shall furnish reports to the Project Manager demonstrating the Contractor's compliance with this Section.

9. Retained Ownership:

All materials purchased by the Owner which remain after completion of the Project shall be the property of the Owner. If the Owner does not wish to retain or dispose of surplus Owner-purchased materials, the Contractor shall remove and dispose of them.

10. Rights of Ownership:

None of the foregoing duties of the Contractor with respect to Owner-purchased materials shall prevent the Owner from exercising any prerogative of ownership of the materials.

SECTION 47 - OWNER'S SALES TAX EXEMPT STATUS

- A. Contractor and subcontractors are authorized to purchase Construction Materials on behalf of Brigham Young University free of Utah sales tax, as defined by applicable Utah State Tax Rule. The grant of this contractual right is conditioned upon and made subject to the following:
1. The construction materials must be installed or converted into real property owned by Brigham Young University and may not be used for any purpose other than constructing the Project.
 2. All construction materials purchased without sales tax must be clearly identified and segregated at all times between the time of purchase and time of installation into the Project.
 3. Contractor and subcontractors will comply with such instructions and guidance as Brigham Young University may issue from time to time to implement Tax Commission requirements for the sales tax exemption on construction materials.
- B. Brigham Young University will provide the Contractor with the Sales Tax Exemption Certificate.

SECTION 48 – FOREIGN PRODUCTS AND CURRENCY

- A. All foreign product costs shall be negotiated in U.S. dollars. Owner will not assume any risk for currency fluctuations after bidding. Contractor assumes all responsibility for any change in costs due to foreign currency fluctuations if the Contractor chooses to negotiate product costs in a foreign currency.

SUPPLEMENTARY CONDITIONS

SECTION 1--COMMENCEMENT, PROSECUTION & COMPLETION OF THE WORK

- A. The Contractor shall be required to commence work after receipt of the contract from the Owner.
- B. The Contractor shall prosecute the work diligently so as to complete it within the time limit allowed in this document.
- C. The Contractor agrees to complete this work required by the Contract on or before midnight 15 August 2024.
- D. Time is hereby expressly declared to be of the essence of the Contract.

SECTION 2--LIQUIDATED DAMAGES

- A. The amount agreed upon and established as liquidated damages up to substantial completion is \$500 per calendar day.
- B. At the time of substantial completion the Owner and the Contractor will agree on how much time will be allowed for the Contractor to complete the remaining work. If the Contractor exceeds the time allowed, liquidated damages will continue at one third (1/3) of the amount of the original liquidated damages or \$500 per calendar day.

SECTION 3--FIRE/SMOKE ALARMS

- A. The Contractor shall be charged \$1,000.00 for any fire alarm or smoke alarm that is caused by the Contractor and disrupts the building occupants. BYU fire alarm technicians are available to answer any questions concerning the alarm systems. The Contractor is to contact the Project Manager to coordinate alarm technicians.

SECTION 4—EXISTING UTILITIES

- A. Prior to execution of the work the contractor is to locate all existing vaults, manholes, valves, meters, etc. Contractor is to photograph, GPS, measure from existing structures and facilities that are to remain and keep this information readily available at the site/construction trailer. Contractor is also to mark the above utilities by staking and maintaining stakes for fast and accurate locating of all existing utilities in case of emergencies.
- B. BYU will initially provide all on campus blue staking information. It is the contractor's responsibility to maintain the blue staking locations and information by staking, painting, keeping GPS coordinated or any alternative ways that the contractor can keep current, accurate information.

SECTION 5—CONTRACTOR WORKING HOURS

- A. No work will be performed between the hours of 10:00 p.m. and 7 a.m. without prior written authorization or in case of emergency situation approved by BYU Project Manager. No work is allowed on Sunday.

SECTION 6—BUILDER’S RISK INSURANCE

Section 13 of the General Conditions is deleted in its entirety and replaced with the following:

SECTION 13—BUILDERS RISK LOSSES

- A. If the Contract Sum is over \$100,000, prior to performing any work, Contractor will obtain and maintain during the term of this Agreement All-Risk Builders Risk Insurance Policy – ISO Form CP 00 20 (10/12), Builders' Risk Coverage (or equivalent) and ISO Form CP 10 30 (10/12), Causes of Loss Special Form, including coverage for flood, or equivalent insurance forms, with Limits of Insurance in the amount of the Contract Sum. An installation floater may be used, if approved in writing by Owner. The Policy will:*
- a. cover materials stored at temporary storage locations and materials in transit;*
 - b. include Owner and all Subcontractors as additional named insureds;*
 - c. be subject to a deductible payable by Contractor of not less than \$2,500 per occurrence of any loss, which will be the responsibility of Contractor and will not be included in the Cost of the Work or be a reimbursable expense; and*
 - d. provide that such insurance is primary, non-contributory and not excess coverage.*
- B. Contractor will provide evidence of this insurance coverage to Owner by providing, if applicable, a Certificate of Insurance on ACORD 27, Evidence of Property Insurance, for the Builder’s Risk Insurance Policy, identifying the Project as defined in the Contract, submitted to Owner, attaching the endorsement giving evidence that the Owner and all Subcontractors are listed as named insureds on the Builder’s Risk Policy.*

Contact the BYU Construction Department (construction@byu.edu) for an electronic Excel version of this form.



Brigham Young University

Physical Facilities -- Construction Department

MONTHLY PAYMENT REQUEST

Date _____
 Request No. _____
 Period From _____ to _____
 TAX ID# _____

Payable To: _____
 Contractor _____
 Address _____
 City, State, Zip _____

Project Name _____
 Project No. _____

 Contract No. _____
 Contract Date _____

APPLICATION FOR PAYMENT

HOLD FOR PICKUP

1. ORIGINAL CONTRACT AMOUNT	\$	-
2. NET CHANGE BY CHANGE ORDERS	\$	-
3. CONTRACT AMOUNT TO DATE	\$	-
<small>(line 1 plus line 2)</small>		
4. TOTAL EARNED	\$	-
<small>(work completed and materials stored to date)</small>		
5. AMOUNT THIS REQUEST	\$	-
6a. RETAINAGE HELD THIS REQUEST	\$	-
<small>(5% of line 5)</small>		
6b. RETAINAGE RELEASED THIS REQUEST	\$	-
6c. RETAINAGE RELEASED TO DATE	\$	-
<small>(total of line 6b above plus previous pay app line 6c)</small>		
6d. TOTAL HELD RETAINAGE TO DATE	\$	-
<small>(5% of line 4 minus line 6c)</small>		
7. TOTAL EARNED LESS RETAINAGE HELD TO DATE	\$	-
<small>(line 4 minus line 6d)</small>		
8. LESS PREVIOUS PAYMENTS	\$	-
<small>(line 7 from previous pay app)</small>		
9. CURRENT PAYMENT DUE	\$	-
<small>(line 7 minus line 8) (to check take line 5 minus line 6a plus line 6b)</small>		
10. BALANCE TO FINISH,		
Including Retainage	\$	-
<small>(line 3 minus Line 4 plus Line 6d)</small>		

Contractor's Representative _____
 Date _____

Owner's Representative _____
 Date _____

Project Manager _____ Date _____
 Director of Construction _____
 Director of Planning _____
 Accounting _____
 Architect _____

Legend

data input



**SECTION 000103
PROJECT DIRECTORY**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Identification of project team members and their contact information.

1.02 OWNER:

- A. Name: Brigham Young University
 - 1. Address: Provo, Utah 84602
 - 2. Telephone: (801) 422-5406
- B. Primary Contact: All correspondence from the Contractor to the Architect will be through this party, unless alternate arrangements are mutually agreed upon at preconstruction meeting.
 - 1. Name: Keith Austin (Construction Project Manager)
 - 2. Email: keith_austin@byu.edu
 - 3. Telephone: (801) 404-1531

1.03 CONSULTANTS:

- A. Architect: Design Professional of Record. All correspondence from the Contractor regarding construction documents authored by Architect's consultants will be through this party, unless alternate arrangements are mutually agreed upon at preconstruction meeting.
 - 1. Company Name: BYU Facilities Planning
 - 2. Primary Contact: Scott McClellan
 - a. Email: scotty_mcclellan@byu.edu
 - b. Telephone: (385) 241-8592
- B. Interior Designer:
 - 1. Company Name: BYU Facilities Planning
 - 2. Primary Contact: Kosha Hansen
 - a. Email: kosha_hansen@byu.edu
 - b. Telephone: (801) 422-5640
- C. Structural Engineer:
 - 1. Company Name: BYU Facilities Planning
 - 2. Primary Contact: Richard Nelson
 - a. Email: Richard_nelson@byu.edu
 - b. Telephone: (801) 422-5504
- D. Mechanical Engineering:
 - 1. Company Name: BYU Facilities Planning
 - 2. Primary Contact: Chris Reynolds
 - a. Email: chris_reynolds@byu.edu
 - b. Telephone: (801) 422-3449
- E. Electrical Engineering:
 - 1. Company Name: BYU Facilities Planning
 - 2. Primary Contact: Luke Moore
 - a. Email: luke_moore@byu.edu
 - b. Telephone: (801) 422-5438

END OF SECTION



**SECTION 000110
TABLE OF CONTENTS**

PROCUREMENT AND CONTRACTING REQUIREMENTS

DIVISION 00 -- PROCUREMENT AND CONTRACTING REQUIREMENTS

- 000103 - Project Directory
- 000110 - Table of Contents

SPECIFICATIONS

DIVISION 01 -- GENERAL REQUIREMENTS

- 011000 - Summary
- 013000 - Administrative Requirements
- 014000 - Quality Requirements
- 015000 - Temporary Facilities and Controls
- 015713 - Temporary Erosion and Sediment Control
- 016000 - Product Requirements
- 017000 - Execution and Closeout Requirements
- 017419 - Construction Waste Management and Disposal
- 017800 - Closeout Submittals
- 017900 - Demonstration and Training
- 019113 - General Commissioning Requirements

DIVISION 02 -- EXISTING CONDITIONS

- 024100 – Demolition

DIVISION 05 -- METALS

- 055000 - Metal Fabrications

DIVISION 06 -- WOOD, PLASTICS, AND COMPOSITES

- 061000 - Rough Carpentry
- 062000 - Finish Carpentry
- 064100 - Architectural Wood Casework

DIVISION 07 -- THERMAL AND MOISTURE PROTECTION

- 072100 - Thermal Insulation
- 072500 - Weather Barriers
- 079200 - Joint Sealants
- 079513 – Expansion Joint Covers

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



DIVISION 08 -- OPENINGS

- 081113 - Hollow Metal Doors and Frames
- 081416 - Flush Wood Doors
- 087100 - Door Hardware
- 088000 – Glazing

DIVISION 09 -- FINISHES

- 090561 - Common Work Results for Flooring Preparation
- 092116 - Gypsum Board Assemblies
- 095100 - Acoustical Ceilings
- 096813 - Tile Carpeting
- 096900 - Access Flooring
- 099123 - Interior Painting

DIVISION 10 -- SPECIALTIES

- 102233 - Accordion Folding Partitions

DIVISION 12 -- FURNISHINGS

- 123600 - Countertops

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 011000 SUMMARY

PART 1 GENERAL

1.01 PROJECT

- A. Project Name: Miscellaneous Renovation Projects
- B. Owner's Name: Brigham Young University.
- C. Additional Project contact information is specified in Section - 000103 - Project Directory.
- D. The Project consists of the construction of the following:
K8101 – JSFB Remodel Office Suite 1041 and Office Suite 1053

1.02 DESCRIPTION OF ALTERATIONS WORK

- A. Scope of demolition and removal work is indicated on drawings and specified in Section 024100.
- B. Owner will remove the following items before start of work:
- C. Contractor shall remove and deliver the following to Owner prior to start of work:
- D. Contractor shall remove and store the following prior to start of work, for later reinstallation by Contractor:

1.03 WORK BY OWNER

- A. Refer to the drawings for a list of NIC (Not in Contract) work by owner.

1.04 OWNER OCCUPANCY

- A. Owner intends to occupy the Project upon Substantial Completion.
- B. Cooperate with Owner to minimize conflict and to facilitate Owner's operations.
- C. Schedule the Work to accommodate Owner occupancy.

1.05 CONTRACTOR USE OF SITE AND PREMISES

- A. Construction Operations: Limited to areas noted on Drawings.
- B. Arrange use of site and premises to allow:
 - 1. Owner occupancy.
 - 2. Work by Others.
 - 3. Work by Owner.
 - 4. Use of site and premises by the public.
- C. Provide access to and from site as required by law and by Owner:
 - 1. Emergency Building Exits During Construction: Keep all exits required by code open during construction period; provide temporary exit signs if exit routes are temporarily altered.
 - 2. Do not obstruct roadways, sidewalks, or other public ways without permit.
- D. Existing building spaces may not be used for storage.
- E. Utility Outages and Shutdown:
 - 1. Limit disruption of utility services to hours the building is unoccupied unless approved by owner.
 - 2. Do not disrupt or shut down life safety systems, including but not limited to fire sprinklers and fire alarm system, without 7 days notice to Owner and authorities having jurisdiction.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Prevent accidental disruption of utility services to other facilities.

1.06 WORK SEQUENCE

- A. Coordinate construction schedule and operations with Owner.

1.07 CONTRACT NO. ____ - PLUMBING

- A. Specification sections listed above as applicable to all contracts.
- B. Division 22 - Plumbing:
 1. Section _____ - _____: Plumbing fixtures.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 013000
ADMINISTRATIVE REQUIREMENTS**

PART 1 GENERAL

UPDATED 26 MARCH 2021

1.01 SECTION INCLUDES

SEE BOLDED UPDATES

- A. General administrative requirements.
- B. Preconstruction meeting.
- C. Progress meetings.
- D. Construction progress schedule.
- E. Contractor's daily reports.
- F. Progress photographs.
- G. Submittals for review, information, and project closeout.
- H. Number of copies of submittals.
- I. Requests for Interpretation (RFI) procedures.
- J. Submittal procedures.

1.02 RELATED REQUIREMENTS

- A. Section 00 00000 - BYU Standard Contract Requirements
- B. Section 016000 - Product Requirements: General product requirements.

1.03 GENERAL ADMINISTRATIVE REQUIREMENTS

- A. Conform to requirements of Section 017000 - Execution and Closeout Requirements for coordination of execution of administrative tasks with timing of construction activities.
- B. Make the following types of submittals to Architect:
 - 1. Requests for Interpretation (RFI).
 - 2. Requests for substitution.
 - 3. Shop drawings, product data, and samples.
 - 4. Design data.
 - 5. Manufacturer's instructions and field reports.
 - 6. Progress schedules.
 - 7. Coordination drawings.
 - 8. Correction Punch List and Final Correction Punch List for Substantial Completion.
 - 9. Closeout submittals.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PRECONSTRUCTION MEETING

- A. Owner will schedule a meeting after Notice of Award.
- B. Attendance Required:
 - 1. Owner.
 - 2. Architect.
 - 3. Contractor.
- C. Agenda:
 - 1. Execution of Owner-Contractor Agreement.
 - 2. Submission of executed bonds and insurance certificates.
 - 3. Distribution of Contract Documents.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



4. Submission of list of subcontractors, list of products, schedule of values, and progress schedule.
 5. Submission of initial Submittal schedule.
 6. Designation of personnel representing the parties to Contract, _____ and Architect.
 7. Procedures and processing of field decisions, submittals, substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
 8. Scheduling.
 9. Scheduling activities of a Geotechnical Engineer.
- D. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

3.02 PROGRESS MEETINGS

- A. Schedule and administer meetings throughout progress of the work at maximum weekly intervals.
- B. Architect will prepare agenda with copies for participants and will conduct the meeting.
- C. Attendance Required:
 1. Contractor.
 2. Owner.
 3. Architect.
 4. Contractor's superintendent.
 5. Subcontractors by invitation.
- D. Agenda:
 1. Review minutes of previous meetings.
 2. Review overall project schedule. Are we on schedule?
 3. Review project budget and potential change orders.
 4. Review of work progress.
 5. Field observations, problems, and decisions.
 6. Identification of problems that impede, or will impede, planned progress.
 7. Review of submittals schedule and status of submittals.
 8. Review of RFIs log and status of responses.
 9. Review of off-site fabrication and delivery schedules.
 10. Maintenance of progress schedule.
 11. Corrective measures to regain projected schedules.
 12. Review three week rolling schedule.
 13. Maintenance of quality and work standards.
 14. Effect of proposed changes on progress schedule and coordination.
 15. Other business relating to work.
- E. Architect will record meeting minutes and distribute copies to those who attended the meeting within two days following the meeting.

3.03 CONSTRUCTION PROGRESS SCHEDULE

- A. Within 10 days after date of the Agreement, submit preliminary schedule defining planned operations for the first 60 days of work, with a general outline for remainder of work.
- B. If preliminary schedule requires revision after review, submit revised schedule within 10 days.
- C. Within 20 days after review of preliminary schedule, submit draft of proposed complete schedule for review.

3.04 DAILY CONSTRUCTION REPORTS

- A. Include only factual information. Do not include personal remarks or opinions regarding operations and/or personnel.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Prepare a daily construction report recording the following information concerning events at Project site and project progress:
1. Date.
 2. High and low temperatures, and general weather conditions.
 3. List of subcontractors at Project site.
 4. Approximate count of personnel at Project site.
 - a. Include a breakdown for supervisors, laborers, journeymen, equipment operators, and helpers.
 5. Major equipment at Project site.
 6. Material deliveries.
 7. Safety, environmental, or industrial relations incidents.
 8. Meetings and significant decisions.
 9. Unusual events (submit a separate special report).
 10. Stoppages, delays, shortages, and losses. Include comparison between scheduled work activities (in Contractor's most recently updated and published schedule) and actual activities. Explain differences, if any. Note days or periods when no work was in progress and explain the reasons why.
 11. Meter readings and similar recordings.
 12. Emergency procedures.
 13. Directives and requests of Authority(s) Having Jurisdiction (AHJ).
 14. Change Orders received and implemented.
 15. Testing and/or inspections performed.
 16. List of verbal instruction given by Owner and/or Architect.
 17. Signature of Contractor's authorized representative.

3.05 PROGRESS PHOTOGRAPHS

- A. Maintain one set of all photographs at project site for reference.
- B. In addition to periodic, recurring views, take photographs of each of the following events:
1. Completion of site clearing.
 2. Excavations in progress.
 3. Foundations in progress and upon completion.
 4. Structural framing in progress and upon completion.
 5. Enclosure of building, upon completion.
 6. Final completion, minimum of ten (10) photos.

3.06 REQUESTS FOR INTERPRETATION (RFI)

- A. Definition: A request seeking one of the following:
1. An interpretation, amplification, or clarification of some requirement of Contract Documents arising from inability to determine from them the exact material, process, or system to be installed; or when the elements of construction are required to occupy the same space (interference); or when an item of work is described differently at more than one place in the Contract Documents.
 2. A resolution to an issue which has arisen due to field conditions and affects design intent.
- B. Preparation: Prepare an RFI immediately upon discovery of a need for interpretation of the Contract Documents. Failure to submit a RFI in a timely manner is not a legitimate cause for claiming additional costs or delays in execution of the work.
1. Prepare a separate RFI for each specific item.
 - a. Review, coordinate, and comment on requests originating with subcontractors and/or materials suppliers.
 - b. Do not forward requests which solely require internal coordination between subcontractors.
 2. Prepare in a format and with content acceptable to Owner.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Reason for the RFI: Prior to initiation of an RFI, carefully study all Contract Documents to confirm that information sufficient for their interpretation is definitely not included.
 - 1. Include in each request Contractor's signature attesting to good faith effort to determine from the Contract Documents information requiring interpretation.
 - 2. Unacceptable Uses for RFIs: Do not use RFIs to request the following:
 - a. Approval of submittals (use procedures specified elsewhere in this section).
 - b. Approval of substitutions (see Section - 016000 - Product Requirements)
 - c. Changes that entail change in Contract Time and Contract Sum (comply with provisions of the Conditions of the Contract).
 - 3. Improper RFIs: Requests not prepared in conformance to requirements of this section, and/or missing key information required to render an actionable response. They will be returned without a response, with an explanatory notation.
- D. Content: Include identifiers necessary for tracking the status of each RFI, and information necessary to provide an actionable response.
 - 1. Official Project name and number, and any additional required identifiers established in Contract Documents.
 - 2. Owner's, Architect's, and Contractor's names.
 - 3. Discrete and consecutive RFI number, and descriptive subject/title.
 - 4. Issue date, and requested reply date.
 - 5. Reference to particular Contract Document(s) requiring additional information/interpretation. Identify pertinent drawing and detail number and/or specification section number, title, and paragraph(s).
 - 6. Annotations: Field dimensions and/or description of conditions which have engendered the request.
 - 7. Contractor's suggested resolution: A written and/or a graphic solution, to scale, is required in cases where clarification of coordination issues is involved, for example; routing, clearances, and/or specific locations of work shown diagrammatically in Contract Documents. If applicable, state the likely impact of the suggested resolution on Contract Time or the Contract Sum.
- E. Attachments: Include sketches, coordination drawings, descriptions, photos, submittals, and other information necessary to substantiate the reason for the request.
- F. RFI Log: Prepare and maintain a tabular log of RFIs for the duration of the project.
 - 1. Indicate current status of every RFI. Update log promptly and on a regular basis.
 - 2. Note dates of when each request is made, and when a response is received.
 - 3. Highlight items requiring priority or expedited response.
 - 4. Highlight items for which a timely response has not been received to date.
- G. Review Time: Architect will respond and return RFIs to Contractor within seven calendar days of receipt. For the purpose of establishing the start of the mandated response period, RFIs received after 12:00 noon will be considered as having been received on the following regular working day.
 - 1. Response period may be shortened or lengthened for specific items, subject to mutual agreement, and recorded in a timely manner in progress meeting minutes.
- H. Responses: Content of answered RFIs will not constitute in any manner a directive or authorization to perform extra work or delay the project. If in Contractor's belief it is likely to lead to a change to Contract Sum or Contract Time, promptly issue a notice to this effect, and follow up with an appropriate Change Order request to Owner.
 - 1. Response may include a request for additional information, in which case the original RFI will be deemed as having been answered, and an amended one is to be issued forthwith. Identify the amended RFI with an R suffix to the original number.
 - 2. Do not extend applicability of a response to specific item to encompass other similar conditions, unless specifically so noted in the response.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Upon receipt of a response, promptly review and distribute it to all affected parties, and update the RFI Log.
4. Notify Architect within seven calendar days if an additional or corrected response is required by submitting an amended version of the original RFI, identified as specified above.

3.07 SUBMITTAL SCHEDULE

- A. Submit to Architect for review a schedule for submittals in tabular format.
 1. Coordinate with Contractor's construction schedule and schedule of values.
 2. Format schedule to allow tracking of status of submittals throughout duration of construction.
 3. Arrange information to include scheduled date for initial submittal, specification number and title, submittal category (for review or for information), description of item of work covered, and role and name of subcontractor.
 4. Account for time required for preparation, review, manufacturing, fabrication and delivery when establishing submittal delivery and review deadline dates.
 - a. For assemblies, equipment, systems comprised of multiple components and/or requiring detailed coordination with other work, allow for additional time to make corrections or revisions to initial submittals, and time for their review.

3.08 SUBMITTALS FOR REVIEW

- A. When the following are specified in individual sections, submit them for review:
 1. Product data.
 2. Shop drawings.
 3. Samples for selection.
 4. Samples for verification.
- B. Submit to Architect for review for the limited purpose of checking for conformance with information given and the design concept expressed in the contract documents.
- C. Samples will be reviewed for aesthetic, color, or finish selection.
- D. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article below and for record documents purposes described in Section 017800 - Closeout Submittals.

3.09 SUBMITTALS FOR INFORMATION

- A. When the following are specified in individual sections, submit them for information:
 1. Design data.
 2. Certificates.
 3. Test reports.
 4. Inspection reports.
 5. Manufacturer's instructions.
 6. Manufacturer's field reports.
 7. Other types indicated.
- B. Submit for Architect's knowledge as contract administrator or for Owner.

3.10 SUBMITTALS FOR PROJECT CLOSEOUT

- A. Submit Correction Punch List for Substantial Completion.
- B. Submit Final Correction Punch List for Substantial Completion.
- C. When the following are specified in individual sections, submit them at project closeout in conformance to requirements of Section 017800 - Closeout Submittals:
 1. Project record documents.
 2. Operation and maintenance data.
 3. Warranties.
- D. Submit for Owner's benefit during and after project completion.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.11 NUMBER OF COPIES OF SUBMITTALS

- A. Electronic Documents: Submit one electronic copy in PDF format; an electronically-marked up file will be returned. Create PDFs at native size and right-side up; illegible files will be rejected.
- B. Documents for Review:
 - 1. Small Size Sheets, Not Larger Than 11 x 17 inches: Submit one copy; the Contractor shall make his own copies from original returned by the Architect after making his own file copy.
- C. Samples: Submit the number specified in individual specification sections; one of which will be retained by Architect.
 - 1. After review, produce duplicates.
 - 2. Retained samples will not be returned to Contractor unless specifically so stated.

3.12 SUBMITTAL PROCEDURES

3.13 COMPLY WITH BYU STANDARD CONTRACT REQUIREMENTS.

- A. General Requirements:
 - 1. Sequentially identify each item. For revised submittals use original number and a sequential numerical suffix.
 - 2. Identify: Project; Contractor; subcontractor or supplier; pertinent drawing and detail number; and specification section number and article/paragraph, as appropriate on each copy.
 - 3. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of products required, field dimensions, adjacent construction work, and coordination of information is in accordance with the requirements of the work and Contract Documents.
 - a. Submittals from sources other than the Contractor, or without Contractor's stamp will not be acknowledged, reviewed, or returned.
 - 4. Deliver each submittal on date noted in submittal schedule, unless an earlier date has been agreed to by all affected parties, and is of the benefit to the project.
 - a. Send submittals in electronic format via email to Architect.
 - 5. Schedule submittals to expedite the Project, and coordinate submission of related items.
 - a. For each submittal for review, allow 15 days excluding delivery time to and from the Contractor.
 - b. For sequential reviews involving Architect's consultants, Owner, or another affected party, allow an additional 7 days.
 - 6. Provide space for Contractor and Architect review stamps.
 - 7. When revised for resubmission, identify all changes made since previous submission.
 - 8. Distribute reviewed submittals. Instruct parties to promptly report inability to comply with requirements.
- B. Product Data Procedures:
 - 1. Submit only information required by individual specification sections.
 - 2. Collect required information into a single submittal.
 - 3. Do not submit (Material) Safety Data Sheets for materials or products.
- C. Shop Drawing Procedures:
 - 1. Prepare accurate, drawn-to-scale, original shop drawing documentation by interpreting the Contract Documents and coordinating related work.
 - 2. Generic, non-project-specific information submitted as shop drawings do not meet the requirements for shop drawings.
- D. Samples Procedures:
 - 1. Transmit related items together as single package.
 - 2. Identify each item to allow review for applicability in relation to shop drawings showing installation locations.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.14 SUBMITTAL REVIEW

- A. Submittals for Review: Architect will review each submittal, and approve, or take other appropriate action.
- B. Architect's actions will be reflected by marking each returned submittal using virtual stamp on electronic submittals.
- C. Architect's and his consultants' actions on items submitted for review:
 - 1. Authorizing purchasing, fabrication, delivery, and installation:
 - a. "Approved", or language with same legal meaning.
 - b. "Approved as Noted, Resubmission not required", or language with same legal meaning.
 - 1) At Contractor's option, submit corrected item, with review notations acknowledged and incorporated.
 - c. "Approved as Noted, Resubmit for Record", or language with same legal meaning.
 - 1) Resubmit corrected item, with review notations acknowledged and incorporated. Resubmit separately, or as part of project record documents.
 - 2. Not Authorizing fabrication, delivery, and installation:
 - a. "Revise and Resubmit".
 - 1) Resubmit revised item, with review notations acknowledged and incorporated.
 - b. "Rejected".
 - 1) Submit item complying with requirements of Contract Documents.
- D. **No Part of this section relieves the Contractor of the responsibility to comply with the Contract Documents.**
Updated 26 Mar 2021

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 014000
QUALITY REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Submittals.
- B. Quality assurance.
- C. References and standards.
- D. Testing and inspection agencies and services.
- E. Control of installation.
- F. Mock-ups.
- G. Tolerances.
- H. Manufacturers' field services.
- I. Defect Assessment.

1.02 RELATED REQUIREMENTS

- A. Section 013000 - Administrative Requirements: Submittal procedures.
- B. Section 016000 - Product Requirements: Requirements for material and product quality.

1.03 REFERENCE STANDARDS

- A. ASTM C1021 - Standard Practice for Laboratories Engaged in Testing of Building Sealants; 2008 (Reapproved 2014).
- B. ASTM C1077 - Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation; 2017.
- C. ASTM C1093 - Standard Practice for Accreditation of Testing Agencies for Masonry; 2015a, with Editorial Revision (2016).
- D. ASTM D3740 - Standard Practice for Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction; 2012a.
- E. ASTM E329 - Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection; 2014a.
- F. IAS AC89 - Accreditation Criteria for Testing Laboratories; 2017.
- G. Codes and Regulations Adopted by the State of Utah and Local Jurisdiction.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Design Data: Submit for Architect's knowledge for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents, or for Owner's information.
- C. Test Reports: After each test/inspection, promptly submit a digital or one paper copies of report to owner, Architect and to Contractor.
 - 1. Include:
 - a. Date issued.
 - b. Project title and number.
 - c. Name of inspector.
 - d. Identification of product and specifications section.
 - e. Location in the Project.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- f. Type of test/inspection.
 - g. Date of test/inspection.
 - h. Results of test/inspection.
 - i. Conformance with Contract Documents.
2. Test report submittals are for Architect's knowledge as for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents, or for Owner's information.
- D. Certificates: When specified in individual specification sections, submit certification by the manufacturer and Contractor or installation/application subcontractor to Architect, in quantities specified for Product Data.
- 1. Indicate material or product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
- E. Manufacturer's Instructions: When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, for the Owner's information. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.
- F. Erection Drawings: Submit drawings for Architect's benefit or for Owner.
- 1. Submit for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.
 - 2. Data indicating inappropriate or unacceptable Work may be subject to action by Architect or Owner.

1.05 QUALITY ASSURANCE

- A. Testing Agency Qualifications:
- 1. Prior to start of Work, submit agency name, address, and telephone number, and names of full time registered Engineer and responsible officer.
 - 2. Submit copy of report of laboratory facilities inspection made by NIST Construction Materials Reference Laboratory during most recent inspection, with memorandum of remedies of any deficiencies reported by the inspection.
 - 3. Qualification Statement: Provide documentation showing testing laboratory is accredited under IAS AC89.

1.06 REFERENCES AND STANDARDS

- A. For products and workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Conform to reference standard of date of issue current on date of Contract Documents, except where a specific date is established by applicable code.
- C. Obtain copies of standards where required by product specification sections.
- D. Maintain copy at project site during submittals, planning, and progress of the specific work, until Substantial Completion.
- E. Should specified reference standards conflict with Contract Documents, request clarification from Architect before proceeding.
- F. Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of Architect shall be altered from the Contract Documents by mention or inference otherwise in any reference document.

1.07 TESTING AND INSPECTION AGENCIES AND SERVICES

- A. Owner will employ and pay for services of an independent testing agency to perform specified testing.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Employment of agency in no way relieves Contractor of obligation to perform Work in accordance with requirements of Contract Documents.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Architect before proceeding.
- D. Comply with specified standards as minimum quality for the Work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Have Work performed by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, and disfigurement.

3.02 MOCK-UPS

- A. Before installing portions of the Work where mock-ups are required, construct mock-ups in location and size indicated for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work. The purpose of mock-up is to demonstrate the proposed range of aesthetic effects and workmanship.
- B. Accepted mock-ups establish the standard of quality the Architect will use to judge the Work.
- C. Integrated Exterior Mock-ups: construct integrated exterior mock-up as indicated on Drawings. Coordinate installation of exterior envelope materials and products as required in individual Specification Sections. Provide adequate supporting structure for mock-up materials as necessary.
- D. Provide a schedule that describes when mock-ups and "first-install" items are available for owner review.
- E. Notify Architect and owner fifteen (15) working days in advance of dates and times when mock-ups will be constructed.
- F. Provide supervisory personnel who will oversee mock-up construction. Provide workers that will be employed during the construction at Project.
- G. Tests shall be performed under provisions identified in this section and identified in the respective product specification sections.
- H. Assemble and erect specified items with specified attachment and anchorage devices, flashings, seals, and finishes.
- I. Obtain Architect's approval of mock-ups before starting work, fabrication, or construction.
 - 1. Architect will issue written comments within five (5) working days of initial review and each subsequent follow up review of each mock-up.
 - 2. Make corrections as necessary until Architect's approval is issued.
- J. Accepted mock-ups shall be a comparison standard for the remaining Work.
- K. Where mock-up has been accepted by Architect and is specified in product specification sections to be removed, protect mock-up throughout construction, remove mock-up and clear area when directed to do so by Architect.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.03 TOLERANCES

- A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Architect before proceeding.
- C. Adjust products to appropriate dimensions; position before securing products in place.

3.04 TESTING AND INSPECTION

- A. Testing Agency Duties:
 - 1. Test samples of mixes submitted by Contractor.
 - 2. Provide qualified personnel at site. Cooperate with Owner, Architect and Contractor in performance of services.
 - 3. Perform specified sampling and testing of products in accordance with specified standards.
 - 4. Ascertain compliance of materials and mixes with requirements of Contract Documents.
 - 5. Promptly notify Owner, Architect and Contractor of observed irregularities or non-conformance of Work or products.
 - 6. Perform additional tests and inspections required by Architect.
 - 7. Submit reports of all tests/inspections specified.
- B. Limits on Testing/Inspection Agency Authority:
 - 1. Agency may not release, revoke, alter, or enlarge on requirements of Contract Documents.
 - 2. Agency may not approve or accept any portion of the Work.
 - 3. Agency may not assume any duties of Contractor.
 - 4. Agency has no authority to stop the Work.
- C. Contractor Responsibilities:
 - 1. Deliver to agency at designated location, adequate samples of materials proposed to be used that require testing, along with proposed mix designs.
 - 2. Cooperate with laboratory personnel, and provide access to the Work and to manufacturers' facilities.
 - 3. Provide incidental labor and facilities:
 - a. To provide access to Work to be tested/inspected.
 - b. To obtain and handle samples at the site or at source of Products to be tested/inspected.
 - c. To facilitate tests/inspections.
 - d. To provide storage and curing of test samples.
 - 4. Notify Owner, Architect and laboratory 24 hours prior to expected time for operations requiring testing/inspection services.
 - 5. Arrange with Owner's agency and pay for additional samples, tests, and inspections required by Contractor's error beyond specified requirements.
- D. Re-testing required because of non-conformance to specified requirements shall be performed by the same agency on instructions by Architect.
- E. Re-testing required because of non-conformance to specified requirements shall be paid for by Contractor.

3.05 MANUFACTURERS' FIELD SERVICES

- A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust and balance of equipment as applicable, and to initiate instructions when necessary.
- B. Submit qualifications of observer to Owner and Architect 30 days in advance of required observations.
 - 1. Observer subject to approval of Architect.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 2. Observer subject to approval of Owner.
- C. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

3.06 DEFECT ASSESSMENT

- A. Replace Work or portions of the Work not conforming to specified requirements.
- B. If, in the opinion of Owner, it is not practical to remove and replace the Work, Owner will direct an appropriate remedy or adjust payment.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 015000
TEMPORARY FACILITIES AND CONTROLS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Temporary utilities.
- B. Temporary telecommunications services.
- C. Temporary sanitary facilities.
- D. Temporary Controls: Barriers, enclosures, and fencing.
- E. Security requirements.
- F. Vehicular access and parking.
- G. Waste removal facilities and services.
- H. Project identification sign.
- I. Field offices.

1.02 RELATED REQUIREMENTS

- A. Section 015500 - Vehicular Access and Parking.

1.03 TEMPORARY UTILITIES SEE BYU STANDARD CONTRACT REQUIREMENTS

1.04 TELECOMMUNICATIONS SERVICES

- A. Provide and maintain telecommunications services to field office at time of project mobilization. Coordinate installation with the BYU Construction Project Manager.

1.05 TEMPORARY SANITARY FACILITIES SEE BYU STANDARD CONTRACT REQUIREMENTS

- A. Maintain daily in clean and sanitary condition.

1.06 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas, to prevent access to areas that could be hazardous to workers or the public, to allow for owner's use of site and to protect existing facilities and adjacent properties from damage from construction operations and demolition.
- B. Provide barricades and covered walkways required by governing authorities for public rights-of-way and for public access to existing building.
- C. Provide protection for plants designated to remain. Replace damaged plants. Refer to BYU Standard Contract Requirements for more information.
- D. Protect stored materials, site, and structures from damage.

1.07 FENCING

- A. Construction: Commercial grade chain link fence.
- B. Provide 6 foot high fence around construction site; equip with vehicular and pedestrian gates with locks.

1.08 VEHICULAR ACCESS AND PARKING - SEE SECTION 015500

- A. Comply with BYU regulations (www.relaying.com) relating to use of streets and sidewalks, access to emergency facilities, and access for emergency vehicles.
- B. Coordinate access and haul routes with governing authorities and Owner.
- C. Provide and maintain access to fire hydrants and fire lanes free of obstructions.
- D. Provide means of removing mud from vehicle wheels before entering streets.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- E. Designated existing on-site roads may be used for construction traffic.
- F. Existing parking areas located at LaVell Edwards Stadium (LVES) may be used for construction parking.

1.09 WASTE REMOVAL

- A. Provide waste removal facilities and services as required to maintain the site in clean and orderly condition.

1.10 PROJECT IDENTIFICATION

- A. Provide project identification sign of design and construction indicated on Drawings.
- B. Erect on site at location indicated.
- C. No other signs are allowed without Owner permission except those required by law.

1.11 FIELD OFFICES

- A. Office: Weathertight, with lighting, electrical outlets, heating, cooling equipment, and equipped with sturdy furniture, drawing rack, and drawing display table.
- B. Provide space for Project meetings, with table and chairs to accommodate 10 persons as needed.

1.12 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary utilities, equipment, facilities, materials, prior to Date of Substantial Completion inspection.
- B. Remove underground installations. Grade site as indicated.
- C. Clean and repair damage caused by installation or use of temporary work.
- D. Restore existing facilities used during construction to original condition, unless noted otherwise.
- E. Restore new permanent facilities used during construction to specified condition.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 016000 PRODUCT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. General product requirements.
- B. Re-use of existing products.
- C. Transportation, handling, storage and protection.
- D. Product option requirements.
- E. Substitution limitations.
- F. Procedures for Owner-supplied products.
- G. Maintenance materials, including extra materials, spare parts, tools, and software.

1.02 RELATED REQUIREMENTS

- A. Section 011000 - Summary: Identification of Owner-supplied products.
- B. Section 012500 - Substitution Procedures: Substitutions made during and after the Bidding/Negotiation Phase.
- C. Section 014000 - Quality Requirements: Product quality monitoring.
- D. Section 230513 - Common Motor Requirements for HVAC Equipment: Motors for HVAC equipment.

PART 2 PRODUCTS

2.01 EXISTING PRODUCTS

- A. Do not use materials and equipment removed from existing premises unless specifically required or permitted by the Contract Documents.
- B. Unforeseen historic items encountered remain the property of the Owner; notify Owner promptly upon discovery; protect, remove, handle, and store as directed by Owner.
- C. Existing materials and equipment indicated to be removed, but not to be re-used, relocated, reinstalled, delivered to the Owner, or otherwise indicated as to remain the property of the Owner, become the property of the Contractor; remove from site.

2.02 NEW PRODUCTS

- A. Provide new products unless specifically required or permitted by the Contract Documents.
- B. Motors: Refer to Section 230513 - Common Motor Requirements for HVAC Equipment, NEMA MG 1 Type. Specific motor type is specified in individual specification sections.

2.03 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.
- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.

2.04 MAINTENANCE MATERIALS

- A. Furnish extra materials, spare parts, tools, and software of types and in quantities specified in individual specification sections.
- B. Deliver and place in location as directed; obtain receipt prior to final payment.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 3 EXECUTION

3.01 SUBSTITUTION LIMITATIONS

- A. See Section 012500 - Substitution Procedures.

3.02 OWNER-SUPPLIED PRODUCTS

- A. See Section 011000 - Summary for identification of Owner-supplied products.
- B. Owner's Responsibilities:
 - 1. Arrange for and deliver Owner reviewed shop drawings, product data, and samples, to Contractor.
 - 2. Arrange and pay for product delivery to site.
 - 3. On delivery, inspect products jointly with Contractor.
 - 4. Submit claims for transportation damage and replace damaged, defective, or deficient items.
 - 5. Arrange for manufacturers' warranties, inspections, and service.
- C. Contractor's Responsibilities:
 - 1. Review Owner reviewed shop drawings, product data, and samples.
 - 2. Receive and unload products at site; inspect for completeness or damage jointly with Owner.
 - 3. Repair or replace items damaged after receipt.

3.03 TRANSPORTATION AND HANDLING

- A. Package products for shipment in manner to prevent damage; for equipment, package to avoid loss of factory calibration.
- B. If special precautions are required, attach instructions prominently and legibly on outside of packaging.
- C. Coordinate schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials.
- D. Transport and handle products in accordance with manufacturer's instructions.
- E. Transport materials in a legal fashion in covered trucks to prevent contamination of product and littering of surrounding areas.
- F. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.
- G. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage, and to minimize handling.
- H. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

3.04 STORAGE AND PROTECTION

- A. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication.
- B. Store and protect products in accordance with manufacturers' instructions.
- C. Store with seals and labels intact and legible.
- D. Store sensitive products in weather tight, climate controlled, enclosures in an environment favorable to product.
- E. For exterior storage of fabricated products, place on sloped supports above ground.
- F. Provide bonded off-site storage and protection when site does not permit on-site storage or protection.
- G. Protect products from damage or deterioration due to construction operations, weather, precipitation, humidity, temperature, sunlight and ultraviolet light, dirt, dust, and other contaminants.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- H. Comply with manufacturer's warranty conditions, if any.
- I. Do not store products directly on the ground.
- J. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- K. Store loose granular materials on solid flat surfaces in a well-drained area. Prevent mixing with foreign matter.
- L. Prevent contact with material that may cause corrosion, discoloration, or staining.
- M. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- N. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 017000
EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Examination, preparation, and general installation procedures.
- B. Requirements for alterations work, including selective demolition, except removal, disposal, and/or remediation of hazardous materials and toxic substances.
- C. Pre-installation meetings.
- D. Cutting and patching.
- E. Surveying for laying out the work.
- F. Cleaning and protection.
- G. Starting of systems and equipment.
- H. Demonstration and instruction of Owner personnel.
- I. Closeout procedures, including Contractor's Correction Punch List, except payment procedures.
- J. General requirements for maintenance service.

1.02 RELATED REQUIREMENTS

- A. Section 011000 - Summary: Limitations on working in existing building; continued occupancy; work sequence; identification of salvaged and relocated materials.
- B. Section 013000 - Administrative Requirements: Submittals procedures.
- C. Section 014000 - Quality Requirements: Testing and inspection procedures.
- D. Section 015000 - Temporary Facilities and Controls: Temporary exterior enclosures.
- E. Section 015000 - Temporary Facilities and Controls: Temporary interior partitions.
- F. Section 015100 - Temporary Utilities: Temporary heating, cooling, and ventilating facilities.
- G. Section 015713 - Temporary Erosion and Sediment Control: Additional erosion and sedimentation control requirements.
- H. Section 017800 - Closeout Submittals: Project record documents, operation and maintenance data, warranties and bonds.
- I. Section 017900 - Demonstration and Training: Demonstration of products and systems to be commissioned and where indicated in specific specification sections
- J. Section 019113 - General Commissioning Requirements: Contractor's responsibilities in regard to commissioning.
- K. Section 024100 - Demolition: Demolition of whole structures and parts thereof; site utility demolition.
- L. Standard Contract Requirements - General Conditions
- M. Section 078400 - Firestopping.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Survey work: Submit name, address, and telephone number of Surveyor before starting survey work.
 - 1. On request, submit documentation verifying accuracy of survey work.
- C. Cutting and Patching: Refer to BYU Standard Contract Requirements
- D. Project Record Documents: Accurately record actual locations of capped and active utilities.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.04 QUALIFICATIONS

- A. For demolition work, employ a firm specializing in the type of work required.
 - 1. Minimum of Three years of documented experience.
- B. For design of temporary shoring and bracing, employ a Professional Civil Engineer or a Professional Structural Engineer experienced in design of this type of work and licensed in Utah.

1.05 PROJECT CONDITIONS

- A. Use of explosives is not permitted.
- B. Grade site to drain. Maintain excavations free of water. Provide, operate, and maintain pumping equipment.
- C. Perform dewatering activities, as required, for the duration of the project.
- D. Ventilate enclosed areas to assist cure of materials, to dissipate humidity, and to prevent accumulation of dust, fumes, vapors, or gases.
- E. Dust Control: Execute work by methods to minimize raising dust from construction operations. Provide positive means to prevent air-borne dust from dispersing into atmosphere and over adjacent property.
 - 1. Provide dust-proof barriers between construction areas and areas continuing to be occupied by Owner.
- F. Erosion and Sediment Control: Provide SWPPP plan and execute work by methods to control surface drainage from cuts and fills, from borrow and waste disposal areas. Prevent erosion and sedimentation.
 - 1. Provide temporary measures such as berms, dikes, and drains, to prevent water flow.
 - 2. Construct fill and waste areas by selective placement to avoid erosive surface silts or clays.
 - 3. Periodically inspect earthwork to detect evidence of erosion and sedimentation; promptly apply corrective measures.
- G. Noise Control: Provide methods, means, and facilities to minimize noise produced by construction operations to the limits established by the agency having jurisdiction.
- H. Pollution Control: Provide methods, means, and facilities to prevent contamination of soil, water, and atmosphere from discharge of noxious, toxic substances, and pollutants produced by construction operations. Comply with federal, state, and local regulations.

1.06 COORDINATION

- A. See Section 011000 for occupancy-related requirements.
- B. Coordinate scheduling, submittals, and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements, with provisions for accommodating items installed later.
- C. Notify affected utility companies and comply with their requirements.
- D. Verify that utility requirements and characteristics of new operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to, and placing in service, such equipment.
- E. Coordinate space requirements, supports, and installation of mechanical and electrical work that are indicated diagrammatically on drawings. Follow routing indicated for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- F. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within the construction. Coordinate locations of fixtures and outlets with finish elements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- G. Coordinate completion and clean-up of work of separate sections.
- H. After Owner occupancy of premises, coordinate access to site for correction of warranty work, to minimize disruption of Owner's activities.

PART 2 PRODUCTS

2.01 PATCHING MATERIALS

- A. New Materials: As specified in product sections; match existing products and work for patching and extending work.
- B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.
- C. Product Substitution: For any proposed change in materials, submit request for substitution described in Section 016000 - Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
- E. Verify that utility services are available, of the correct characteristics, and in the correct locations.
- F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions. Refer also to the BYU Standard Contract Requirements.

3.02 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

3.03 PREINSTALLATION MEETINGS

- A. When required in individual specification sections, convene a preinstallation meeting at the site prior to commencing work of the section.
- B. Require attendance of parties directly affecting, or affected by, work of the specific section.
- C. Notify Owner and Architect four days in advance of meeting date.
- D. Prepare agenda and preside at meeting:
 - 1. Review conditions of examination, preparation and installation procedures.
 - 2. Review coordination with related work.
- E. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

3.04 LAYING OUT THE WORK

- A. Verify locations of survey control points prior to starting work.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Promptly notify Owner and Architect of any discrepancies discovered.
- C. Contractor shall locate and protect survey control and reference points.
- D. Control datum for survey is that indicated on drawings.
- E. Protect survey control points prior to starting site work; preserve permanent reference points during construction.
- F. Promptly report to Owner and Architect the loss or destruction of any reference point or relocation required because of changes in grades or other reasons.
- G. Replace dislocated survey control points based on original survey control. Make no changes without prior written notice to Owner and Architect.
- H. Utilize recognized engineering survey practices.
- I. Establish elevations, lines and levels. Locate and lay out by instrumentation and similar appropriate means:
 - 1. Site improvements including pavements; stakes for grading, fill and topsoil placement; utility locations, slopes, and invert elevations.
 - 2. Grid or axis for structures.
 - 3. Building foundation, column locations, ground floor elevations.
- J. Periodically verify layouts by same means.
- K. Maintain a complete and accurate log of control and survey work as it progresses.

3.05 GENERAL INSTALLATION REQUIREMENTS

- A. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.
- B. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.
- C. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.
- D. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.
- E. Make neat transitions between different surfaces, maintaining texture and appearance.

3.06 ALTERATIONS

- A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
 - 1. Verify that construction and utility arrangements are as indicated.
 - 2. Report discrepancies to Owner and Architect before disturbing existing installation.
 - 3. Beginning of alterations work constitutes acceptance of existing conditions.
- B. Keep areas in which alterations are being conducted separated from other areas that are still occupied.
 - 1. Provide, erect, and maintain temporary dustproof partitions of construction indicated on drawings in locations indicated on drawings.
- C. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; prevent water and humidity damage.
 - 1. Where openings in exterior enclosure exist, provide construction to make exterior enclosure weatherproof.
 - 2. Insulate existing ducts or pipes that are exposed to outdoor ambient temperatures by alterations work.
- D. Remove existing work as indicated and as required to accomplish new work.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Remove rotted wood, corroded metals, and deteriorated masonry and concrete; replace with new construction specified.
 2. Remove items indicated on drawings.
 3. Relocate items indicated on drawings.
 4. Where new surface finishes are to be applied to existing work, perform removals, patch, and prepare existing surfaces as required to receive new finish; remove existing finish if necessary for successful application of new finish.
 5. Where new surface finishes are not specified or indicated, patch holes and damaged surfaces to match adjacent finished surfaces as closely as possible.
- E. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications): Remove, relocate, and extend existing systems to accommodate new construction as described in documents or directed by Owner.
1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components; if necessary, modify installation to allow access or provide access panel.
 2. Where existing systems or equipment are not active and Contract Documents require reactivation, put back into operational condition; repair supply, distribution, and equipment as required by Owner.
 3. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
 - a. Disable existing systems only to make switchovers and connections; minimize duration of outages.
 - b. See Section 011000 for other limitations on outages and required notifications.
 - c. Provide temporary connections as required to maintain existing systems in service.
 4. Verify that abandoned services serve only abandoned facilities.
 5. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification; patch holes left by removal using materials specified for new construction.
- F. Protect existing work to remain.
1. Prevent movement of structure; provide shoring and bracing if necessary.
 2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
 3. Repair adjacent construction and finishes damaged during removal work.
- G. Adapt existing work to fit new work: Make as neat and smooth transition as possible.
1. When existing finished surfaces are cut so that a smooth transition with new work is not possible, terminate existing surface along a straight line at a natural line of division and make recommendation to Owner and Architect.
 2. Where removal of partitions or walls results in adjacent spaces becoming one, rework floors, walls, and ceilings to a smooth plane without breaks, steps, or bulkheads.
 3. Where a change of plane of 1/4 inch or more occurs in existing work, submit recommendation for providing a smooth transition for Owner and Architect review and request instructions.
 4. Trim existing wood doors as necessary to clear new floor finish. Refinish trim as required.
- H. Patching: Where the existing surface is not indicated to be refinished, patch to match the surface finish that existed prior to cutting. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
- I. Refinish existing surfaces as indicated:
1. Where rooms or spaces are indicated to be refinished, refinish all visible existing surfaces to remain to the specified condition for each material, with a neat transition to adjacent finishes.
 2. If mechanical or electrical work is exposed accidentally during the work, re-cover and refinish to match.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- J. Clean existing systems and equipment.
- K. Remove demolition debris and abandoned items from alterations areas and dispose of off-site; do not burn or bury.

3.07 CUTTING AND PATCHING - REFER ALSO TO BYU STANDARD CONTRACT REQUIREMENTS

- A. Whenever possible, execute the work by methods that avoid cutting or patching.
- B. See Alterations article above for additional requirements.
- C. Perform whatever cutting and patching is necessary to:
 - 1. Complete the work.
 - 2. Fit products together to integrate with other work.
 - 3. Provide openings for penetration of mechanical, electrical, and other services.
 - 4. Match work that has been cut to adjacent work.
 - 5. Repair new work damaged by subsequent work.
 - 6. Remove samples of installed work for testing when requested.
 - 7. Remove and replace defective and non-conforming work.
- D. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.
- E. Employ skilled and experienced installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.
- F. Cut rigid materials using masonry saw or core drill. Pneumatic tools not allowed without prior approval.
- G. Restore work with new products in accordance with requirements of Contract Documents.
- H. Fit work air tight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- I. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material in accordance with Section 078400, to full thickness of the penetrated element.
- J. Patching:
 - 1. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
 - 2. Match color, texture, and appearance.
 - 3. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

3.08 PROGRESS CLEANING

- A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces, and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing, and continue cleaning to eliminate dust.
- D. Collect and remove waste materials, debris, and trash/rubbish from site periodically and dispose off-site; do not burn or bury.

3.09 PROTECTION OF INSTALLED WORK - REFER ALSO TO BYU STANDARD CONTRACT REQUIREMENTS

- A. Protect installed work from damage by construction operations.
- B. Provide special protection where specified in individual specification sections.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.
- D. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.
- E. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.
- F. Protect work from spilled liquids. If work is exposed to spilled liquids, immediately remove protective coverings, dry out work, and replace protective coverings.
- G. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- H. Prohibit traffic from landscaped areas.
- I. Remove protective coverings when no longer needed; reuse or recycle coverings if possible.

3.10 SYSTEM STARTUP

- A. Coordinate with requirements of Section 019113 - General Commissioning Requirements_____.
- B. Coordinate schedule for start-up of various equipment and systems.
- C. Notify Owner and Architect and owner seven days prior to start-up of each item.
- D. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions that may cause damage.
- E. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.
- F. Verify that wiring and support components for equipment are complete and tested.
- G. Execute start-up under supervision of applicable Contractor personnel and manufacturer's representative in accordance with manufacturers' instructions.
- H. When specified in individual specification Sections, require manufacturer to provide authorized representative to be present at site to inspect, check, and approve equipment or system installation prior to start-up, and to supervise placing equipment or system in operation.
- I. Submit a written report that equipment or system has been properly installed and is functioning correctly.

3.11 DEMONSTRATION AND INSTRUCTION

- A. See Section 017900 - Demonstration and Training.

3.12 ADJUSTING

- A. Adjust operating products and equipment to ensure smooth and unhindered operation.
- B. Testing, adjusting, and balancing HVAC systems: See Section 230593 - Testing, Adjusting, and Balancing for HVAC.

3.13 FINAL CLEANING

- A. Execute final cleaning prior to Substantial Completion.
 - 1. Clean areas to be occupied by Owner prior to final completion before Owner occupancy.
- B. Use cleaning materials that are nonhazardous.
- C. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, and others impacted surfaces.
- D. Remove all labels that are not permanent. Do not paint or otherwise cover fire test labels or nameplates on mechanical and electrical equipment.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- E. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned, and approved by the Owner.
- F. Clean filters of operating equipment.
- G. Clean debris from roofs, gutters, downspouts, scuppers, overflow drains, area drains, and drainage systems.
- H. Clean site; sweep paved areas, rake clean landscaped surfaces.
- I. Remove waste, surplus materials, trash/rubbish, and construction facilities from the site; dispose of in legal manner; do not burn or bury.

3.14 CLOSEOUT PROCEDURES

- A. Make submittals that are required by governing or other authorities.
 - 1. Provide copies to Architect and Owner.
- B. Refer to BYU standard contract requirements for punch list procedures.

3.15 MAINTENANCE

- A. Provide service and maintenance of components indicated in specification sections and coordinate with Owner.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 017419
CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 GENERAL

1.01 WASTE MANAGEMENT REQUIREMENTS

- A. Owner requires that this project generate the least amount of trash and waste possible.
- B. Employ processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors.
- C. Minimize trash/waste disposal in landfills; reuse, salvage, or recycle as much waste as economically feasible.
- D. Methods of trash/waste disposal that are not acceptable are:
 - 1. Burning on the project site.
 - 2. Burying on the project site.
 - 3. Dumping or burying on other property, public or private.
 - 4. Other illegal dumping or burying.
- E. Regulatory Requirements: Contractor is responsible for knowing and complying with regulatory requirements, including but not limited to Federal, state and local requirements, pertaining to legal disposal of all construction and demolition waste materials.

1.02 DEFINITIONS

- A. Clean: Untreated and unpainted; not contaminated with oils, solvents, caulk, or the like.
- B. Construction and Demolition Waste: Solid wastes typically including building materials, packaging, trash, debris, and rubble resulting from construction, remodeling, repair and demolition operations.
- C. Hazardous: Exhibiting the characteristics of hazardous substances, i.e., ignitibility, corrosivity, toxicity or reactivity.
- D. Nonhazardous: Exhibiting none of the characteristics of hazardous substances, i.e., ignitibility, corrosivity, toxicity, or reactivity.
- E. Nontoxic: Neither immediately poisonous to humans nor poisonous after a long period of exposure.
- F. Recyclable: The ability of a product or material to be recovered at the end of its life cycle and remanufactured into a new product for reuse by others.
- G. Recycle: To remove a waste material from the project site to another site for remanufacture into a new product for reuse by others.
- H. Recycling: The process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for the purpose of using the altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- I. Return: To give back reusable items or unused products to vendors for credit.
- J. Reuse: To reuse a construction waste material in some manner on the project site.
- K. Salvage: To remove a waste material from the project site to another site for resale or reuse by others.
- L. Sediment: Soil and other debris that has been eroded and transported by storm or well production run-off water.
- M. Source Separation: The act of keeping different types of waste materials separate beginning from the first time they become waste.
- N. Toxic: Poisonous to humans either immediately or after a long period of exposure.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- O. Trash: Any product or material unable to be reused, returned, recycled, or salvaged.
- P. Waste: Extra material or material that has reached the end of its useful life in its intended use. Waste includes salvageable, returnable, recyclable, and reusable material.

PART 3 EXECUTION

2.01 WASTE MANAGEMENT PROCEDURES

- A. See Section 013000 for additional requirements for project meetings, reports, submittal procedures, and project documentation.
- B. See Section 015000 for additional requirements related to trash/waste collection and removal facilities and services.
- C. See Section 016000 for waste prevention requirements related to delivery, storage, and handling.
- D. See Section 017000 for trash/waste prevention procedures related to demolition, cutting and patching, installation, protection, and cleaning.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 017800
CLOSEOUT SUBMITTALS**

PART 1 GENERAL

UPDATED 26 MARCH 2021

1.01 SECTION INCLUDES

SEE BOLDED UPDATES

- A. Project Record Documents.
- B. Operation and Maintenance Data.
- C. Warranties.

1.02 RELATED REQUIREMENTS

- A. Section 013000 - Administrative Requirements: Submittals procedures, shop drawings, product data, and samples.
- B. Section 017000 - Execution and Closeout Requirements: Contract closeout procedures.
- C. Individual Product Sections: Specific requirements for operation and maintenance data.
- D. Individual Product Sections: Warranties required for specific products or Work.

1.03 SUBMITTALS

- A. Project Record Documents: Submit documents to Architect who will transfer them to the owner. Provide one hard copy and one electronic copy in pdf and rvt format.
- B. Operation and Maintenance Data:
 - 1. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Architect will review draft and return one copy with comments.
 - 2. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within ten days after acceptance.
 - 3. Submit one copy of completed documents 15 days prior to final inspection. This copy will be reviewed and returned after final inspection, with Owner and Architect comments. Revise content of all document sets as required prior to final submission.
 - 4. **Submit one hard copy and one electronic copy in pdf format sets of revised final documents in final form within 10 days after final inspection. Updated 26 March 2021**
- C. Warranties:
 - 1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 10 days after acceptance.
 - 2. Make other submittals within 10 days after Date of Substantial Completion, prior to final Application for Payment.
 - 3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 10 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PROJECT RECORD DOCUMENTS

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 - 1. Drawings.
 - 2. Specifications.
 - 3. Addenda.
 - 4. Change Orders.
 - 5. Reviewed shop drawings, product data, and samples.
 - 6. Manufacturer's instruction for assembly, installation, and adjusting.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



7. Owner's Project Requirements document.
 8. Commissioning Plan.
- B. Ensure entries are complete and accurate, enabling future reference by Owner.
 - C. Store record documents separate from documents used for construction.
 - D. Record information concurrent with construction progress.
 - E. Specifications: Legibly mark and record at each product section description of actual products installed, including the following:
 1. Manufacturer's name and product model and number.
 2. Product substitutions or alternates utilized.
 3. Changes made by Addenda and modifications.
 - F. Record Drawings and Shop Drawings: Legibly mark any change from design to record actual construction including:
 1. Measured depths of foundations in relation to finish first floor datum.
 2. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 3. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 4. Field changes of dimension and detail.
 5. Details not on original Contract drawings.

3.02 OPERATION AND MAINTENANCE DATA

- A. Source Data: For each product or system, list names, addresses and telephone numbers of Subcontractors and suppliers, including local source of supplies and replacement parts.
- B. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.
- C. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams. Do not use Project Record Documents as maintenance drawings.
- D. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.03 OPERATION AND MAINTENANCE DATA FOR MATERIALS AND FINISHES

- A. For Each Product, Applied Material, and Finish:
 1. Product data, with catalog number, size, composition, and color and texture designations.
 2. Information for re-ordering custom manufactured products.
- B. Instructions for Care and Maintenance: Manufacturer's recommendations for cleaning agents and methods, precautions against detrimental cleaning agents and methods, and recommended schedule for cleaning and maintenance.
- C. Moisture protection and weather-exposed products: Include product data listing applicable reference standards, chemical composition, and details of installation. Provide recommendations for inspections, maintenance, and repair.
- D. Additional information as specified in individual product specification sections.
- E. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.

3.04 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

- A. For Each Item of Equipment and Each System:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Description of unit or system, and component parts.
 2. Identify function, normal operating characteristics, and limiting conditions.
 3. Include performance curves, with engineering data and tests.
 4. Complete nomenclature and model number of replaceable parts.
- B. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
- C. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed.
- D. Include color coded wiring diagrams as installed.
- E. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
- F. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and troubleshooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- G. Provide servicing and lubrication schedule, and list of lubricants required.
- H. Include manufacturer's printed operation and maintenance instructions.
- I. Include sequence of operation by controls manufacturer.
- J. Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- K. Provide control diagrams by controls manufacturer as installed.
- L. Provide Contractor's coordination drawings, with color coded piping diagrams as installed.
- M. Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- N. Include test and balancing reports.
- O. Additional Requirements: As specified in individual product specification sections.

3.05 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

- A. Assemble operation and maintenance data into durable manuals for Owner's personnel use, with data arranged in the same sequence as, and identified by, the specification sections, unless otherwise directed in individual product specification sections.
- B. Where systems involve more than one specification section, provide separate tabbed divider for each system.
- C. Binders: Commercial quality, 8-1/2 by 11 inch three D side ring binders with durable plastic covers; 4 inch maximum ring size. When multiple binders are used, correlate data into related consistent groupings.
- D. Cover: Identify each binder with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.
- E. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Architect, Consultants, Contractor and subcontractors, with names of responsible parties.
- F. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- G. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
- H. Text: Manufacturer's printed data, or typewritten data on 20 pound paper.
- I. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
- J. Arrangement of Contents: Organize each volume in parts as follows:
 - 1. Project Directory.
 - 2. Table of Contents, of all volumes, and of this volume.
 - 3. Operation and Maintenance Data: Arranged by system, then by product category.
 - a. Source data.
 - b. Product data, shop drawings, and other submittals.
 - c. Operation and maintenance data.
 - d. Field quality control data.
 - e. Photocopies of warranties.
 - 4. Design Data: To allow for addition of design data furnished by Architect or others, provide a tab labeled "Design Data" and provide a binder large enough to allow for insertion of at least 20 pages of typed text.

3.06 WARRANTIES

- A. Obtain warranties, executed in duplicate by responsible subcontractors, suppliers, and manufacturers, within 10 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until date of substantial completion is determined.
- B. Verify that documents are in proper form, contain full information.
- C. Co-execute submittals when required.
- D. Retain warranties until time specified for submittal.
- E. Include photocopies of each in operation and maintenance manuals, indexed separately on Table of Contents.
- F. Manual: Bind in commercial quality 8-1/2 by 11 inch three D side ring binders with durable plastic covers.
- G. Cover: Identify each binder with typed or printed title WARRANTIES, with title of Project; name, address and telephone number of Contractor and equipment supplier; and name of responsible company principal.
- H. Table of Contents: Neatly typed, in the sequence of the Table of Contents of the Project Manual, with each item identified with the number and title of the specification section in which specified, and the name of product or work item.
- I. Separate each warranty with index tab sheets keyed to the Table of Contents listing. Provide full information, using separate typed sheets as necessary. List Subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 017900
DEMONSTRATION AND TRAINING

PART 1 GENERAL

1.01 SUMMARY

- A. Demonstration of products and systems to be commissioned and where indicated in specific specification sections.
- B. Training of Owner personnel in operation and maintenance is required for:
 - 1. All software-operated systems.
 - 2. HVAC systems and equipment.
 - 3. Plumbing equipment.
 - 4. Electrical systems and equipment.
 - 5. Conveying systems.
 - 6. Items specified in individual product Sections.
- C. Training of Owner personnel in care, cleaning, maintenance, and repair is required for:
 - 1. Roofing, waterproofing, and other weather-exposed or moisture protection products.
 - 2. Finishes, including flooring, wall finishes, ceiling finishes.
 - 3. Fixtures and fittings.
 - 4. Items specified in individual product Sections.

1.02 RELATED REQUIREMENTS

- A. Section 017800 - Closeout Submittals: Operation and maintenance manuals.
- B. Section 019113 - General Commissioning Requirements: Additional requirements applicable to demonstration and training.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures; except:
 - 1. Make all submittals specified in this section, and elsewhere where indicated for commissioning purposes, directly to the Commissioning Authority.
 - 2. Submit one copy to the Commissioning Authority, not to be returned.
 - 3. Make commissioning submittals on time schedule specified by Commissioning Authority.
 - 4. Submittals indicated as "Draft" are intended for the use of the Commissioning Authority in preparation of overall Training Plan; submit in editable electronic format, Microsoft Word 2003 preferred.
- B. Draft Training Plans: Owner will designate personnel to be trained; tailor training to needs and skill-level of attendees.
 - 1. Submit to Commissioning Authority for review and inclusion in overall training plan.
 - 2. Submit not less than four weeks prior to start of training.
 - 3. Revise and resubmit until acceptable.
 - 4. Provide an overall schedule showing all training sessions.
 - 5. Include at least the following for each training session:
 - a. Identification, date, time, and duration.
 - b. Description of products and/or systems to be covered.
 - c. Name of firm and person conducting training; include qualifications.
 - d. Intended audience, such as job description.
 - e. Objectives of training and suggested methods of ensuring adequate training.
 - f. Methods to be used, such as classroom lecture, live demonstrations, hands-on, etc.
 - g. Media to be used, such as slides, hand-outs, etc.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- h. Training equipment required, such as projector, projection screen, etc., to be provided by Contractor.
- C. Training Manuals: Provide training manual for each attendee; allow for minimum of two attendees per training session.
 - 1. Include applicable portion of O&M manuals.
 - 2. Include copies of all hand-outs, slides, overheads, video presentations, etc., that are not included in O&M manuals.
 - 3. Provide one extra copy of each training manual to be included with operation and maintenance data.
- D. Training Reports:
 - 1. Identification of each training session, date, time, and duration.
 - 2. Sign-in sheet showing names and job titles of attendees.
 - 3. List of attendee questions and written answers given, including copies of and references to supporting documentation required for clarification; include answers to questions that could not be answered in original training session.
 - 4. Include Commissioning Authority's formal acceptance of training session.

1.04 QUALITY ASSURANCE

- A. Instructor Qualifications: Familiar with design, operation, maintenance and troubleshooting of the relevant products and systems.
 - 1. Provide as instructors the most qualified trainer of those contractors and/or installers who actually supplied and installed the systems and equipment.
 - 2. Where a single person is not familiar with all aspects, provide specialists with necessary qualifications.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 DEMONSTRATION - GENERAL

- A. Demonstrations conducted during system start-up do not qualify as demonstrations for the purposes of this section, unless approved in advance by Owner.
- B. Demonstrations conducted during Functional Testing need not be repeated unless Owner personnel training is specified.
- C. Demonstration may be combined with Owner personnel training if applicable.
- D. Operating Equipment and Systems: Demonstrate operation in all modes, including start-up, shut-down, seasonal changeover, emergency conditions, and troubleshooting, and maintenance procedures, including scheduled and preventive maintenance.
 - 1. Perform demonstrations not less than two weeks prior to Substantial Completion.
 - 2. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
- E. Non-Operating Products: Demonstrate cleaning, scheduled and preventive maintenance, and repair procedures.
 - 1. Perform demonstrations not less than two weeks prior to Substantial Completion.

3.02 TRAINING - GENERAL

- A. Commissioning Authority will prepare the Training Plan based on draft plans submitted.
- B. Conduct training on-site unless otherwise indicated.
- C. Owner will provide classroom and seating at no cost to Contractor.
- D. Do not start training until Functional Testing is complete, unless otherwise specified or approved by the Commissioning Authority.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- E. Provide training in minimum two hour segments.
- F. The Commissioning Authority is responsible for determining that the training was satisfactorily completed and will provide approval forms.
- G. Training schedule will be subject to availability of Owner's personnel to be trained; re-schedule training sessions as required by Owner; once schedule has been approved by Owner failure to conduct sessions according to schedule will be cause for Owner to charge Contractor for personnel "show-up" time.
- H. Review of Facility Policy on Operation and Maintenance Data: During training discuss:
 - 1. The location of the O&M manuals and procedures for use and preservation; backup copies.
 - 2. Typical contents and organization of all manuals, including explanatory information, system narratives, and product specific information.
 - 3. Typical uses of the O&M manuals.
- I. Product- and System-Specific Training:
 - 1. Review the applicable O&M manuals.
 - 2. For systems, provide an overview of system operation, design parameters and constraints, and operational strategies.
 - 3. Review instructions for proper operation in all modes, including start-up, shut-down, seasonal changeover and emergency procedures, and for maintenance, including preventative maintenance.
 - 4. Provide hands-on training on all operational modes possible and preventive maintenance.
 - 5. Emphasize safe and proper operating requirements; discuss relevant health and safety issues and emergency procedures.
 - 6. Discuss common troubleshooting problems and solutions.
 - 7. Discuss any peculiarities of equipment installation or operation.
 - 8. Discuss warranties and guarantees, including procedures necessary to avoid voiding coverage.
 - 9. Review recommended tools and spare parts inventory suggestions of manufacturers.
 - 10. Review spare parts and tools required to be furnished by Contractor.
 - 11. Review spare parts suppliers and sources and procurement procedures.
- J. Be prepared to answer questions raised by training attendees; if unable to answer during training session, provide written response within three days.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 019113
GENERAL COMMISSIONING REQUIREMENTS**

PART 1 GENERAL

1.01 SUMMARY

- A. Commissioning is intended to achieve the following specific objectives; this section specifies the Contractor's responsibilities for commissioning:
 - 1. Verify that the work is installed in accordance with the Contract Documents and the manufacturer's recommendations and instructions, and that it receives adequate operational checkout prior to startup: Startup reports and Prefunctional Checklists executed by Contractor are utilized to achieve this.
 - 2. Verify and document that functional performance is in accordance with the Contract Documents: Functional Tests executed by Contractor and witnessed by the Commissioning Authority are utilized to achieve this.
 - 3. Verify that operation and maintenance manuals submitted to Owner are complete: Detailed operation and maintenance (O&M) data submittals by Contractor are utilized to achieve this.
 - 4. Verify that the Owner's operating personnel are adequately trained: Formal training conducted by Contractor is utilized to achieve this.
- B. Commissioning, including Functional Tests, O&M documentation review, and training, is to occur after startup and initial checkout and be completed before Functional Completion with penalty for non-completion as defined in the Conditions of the Contract.
- C. The Commissioning Authority directs and coordinates all commissioning activities; this section describes some but not all of the Commissioning Authority's responsibilities.
- D. The Commissioning Authority is employed by Owner.

1.02 SCOPE OF COMMISSIONING

- A. The following are to be commissioned:
- B. Building envelope.
 - 1. Thermal and moisture integrity.
 - 2. Air tightness.
- C. Elevating and conveying systems.
- D. Fire Protection Systems.
- E. Plumbing Systems:
 - 1. Water heaters.
 - 2. Booster pumps.
 - 3. Laboratory gas systems.
- F. HVAC System, including:
 - 1. Major and minor equipment items.
 - 2. Piping systems and equipment.
 - 3. Ductwork and accessories.
 - 4. Terminal units.
 - 5. Control system.
 - 6. Sound control devices.
 - 7. Vibration control devices.
 - 8. Variable frequency drives.
- G. Special Ventilation:
 - 1. Fume hoods.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Laboratory pressurization.
 3. Specialty fans.
 4. Egress pressurization.
- H. Electrical Systems:
1. Power quality.
 2. Emergency power systems.
 3. Uninterruptible power systems.
 4. Lighting controls other than manual switches.
- I. Electronic Safety and Security:
1. Security system, including doors and hardware.
 2. Fire and smoke alarms.
- J. Other equipment and systems explicitly identified elsewhere in Contract Documents as requiring commissioning.
- K. Sound Transmission Class-rated interior partitions.

1.03 RELATED REQUIREMENTS

- A. Section 017800 - Closeout Submittals: Scope and procedures for operation and maintenance manuals and project record documents.
- B. Section 017900 - Demonstration and Training: Scope and procedures for Owner personnel training.
- C. Section 019114 - Commissioning Authority Responsibilities.
- D. Section 230800 - Commissioning of HVAC: HVAC control system testing; other requirements.

1.04 REFERENCE STANDARDS

- A. ASHRAE Std 202 - Commissioning Process for Buildings and Systems; 2013 (2017a).
- B. ASTM E336 - Standard Test Method for Measurement of Airborne Sound Attenuation between Rooms in Buildings; 2017.
- C. ASTM E779 - Standard Test Method for Determining Air Leakage Rate by Fan Pressurization; 2010.
- D. ASTM E1827 - Standard Test Methods for Determining Airtightness of Buildings Using an Orifice Blower Door; 2011 (Reapproved 2017).
- E. NEBB S110 - Whole Building Technical Commissioning Of New Construction; 2018.
- F. PECL (Samples) - Sample Forms for Prefunctional Checklists and Functional Performance Tests; current edition.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures; except:
 1. Make all submittals specified in this section, and elsewhere where indicated for commissioning purposes, directly to the Commissioning Authority, unless they require review by Architect; in that case, submit to Architect first.
 2. Submit one copy to the Commissioning Authority, not to be returned.
 3. Make commissioning submittals on time schedule specified by Commissioning Authority.
 4. Submittals indicated as "Draft" are intended for the use of the Commissioning Authority in preparation of Prefunctional Checklists or Functional Test requirements; submit in editable electronic format, Microsoft Word 2010 preferred.
 5. As soon as possible after submittals made to Architect are approved, submit copy of approved submittal to the Commissioning Authority.
- B. Product Data: If submittals to Architect do not include the following, submit copies as soon as possible:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Manufacturer's product data, cut sheets, and shop drawings.
 2. Manufacturer's installation instructions.
 3. Startup, operating, and troubleshooting procedures.
 4. Fan and pump curves.
 5. Factory test reports.
 6. Warranty information, including details of Owner's responsibilities in regard to keeping warranties in force.
- C. Manufacturers' Instructions: Submit copies of all manufacturer-provided instructions that are shipped with the equipment as soon as the equipment is delivered.
- D. Startup Plans and Reports.
- E. Completed Prefunctional Checklists.
- F. Commissioning Issues Log:
1. Construction observations.
 2. Supporting photographs.

1.06 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Independent firm specializing in performing testing and inspections of the type specified in this section.

PART 2 PRODUCTS

2.01 TEST EQUIPMENT

- A. Provide all standard testing equipment required to perform startup and initial checkout and required Functional Testing; unless otherwise noted such testing equipment will NOT become the property of Owner.
- B. Calibration Tolerances: Provide testing equipment of sufficient quality and accuracy to test and/or measure system performance with the tolerances specified. If not otherwise noted, the following minimum requirements apply:
1. Temperature Sensors and Digital Thermometers: Certified calibration within past year to accuracy of 0.5 degree F and resolution of plus/minus 0.1 degree F.
 2. Pressure Sensors: Accuracy of plus/minus 2.0 percent of the value range being measured (not full range of meter), calibrated within the last year.
 3. Calibration: According to the manufacturer's recommended intervals and when dropped or damaged; affix calibration tags or keep certificates readily available for inspection.
- C. Equipment-Specific Tools: Where special testing equipment, tools and instruments are specific to a piece of equipment, are only available from the vendor, and are required in order to accomplish startup or Functional Testing, provide such equipment, tools, and instruments as part of the work at no extra cost to Owner; such equipment, tools, and instruments are to become the property of Owner.
- D. Dataloggers: Independent equipment and software for monitoring flows, currents, status, pressures, etc. of equipment.
1. Dataloggers required to for Functional Tests will be provided by the Commissioning Authority and will not become the property of Owner.

PART 3 EXECUTION

3.01 COMMISSIONING PLAN

- A. Commissioning Authority has prepared the Commissioning Plan.
1. Attend meetings called by the Commissioning Authority for purposes of completing the commissioning plan.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Require attendance and participation of relevant subcontractors, installers, suppliers, and manufacturer representatives.
- B. Contractor is responsible for compliance with the Commissioning Plan.
- C. Commissioning Plan: The commissioning schedule, procedures, and coordination requirements for all parties in the commissioning process.
- D. Basis of Design Documentation (BOD): Detailed documentation of the functional requirements of the project; descriptions of the systems, components, and methods chosen to meet the design intent; assumptions underlying the design intent.
 1. Basis of Design Documentation is to be prepared by Design-Builder.
- E. Commissioning Schedule:
 1. Submit anticipated dates of startup of each item of equipment and system to Commissioning Authority within 60 days after award of Contract.
 2. Re-submit anticipated startup dates monthly, but not less than 4 weeks prior to startup.
 3. Prefunctional Checklists and Functional Tests are to be performed in sequence from components, to subsystems, to systems.
 4. Provide sufficient notice to Commissioning Authority for delivery of relevant Checklists and Functional Test procedures, to avoid delay.

3.02 STARTUP PLANS AND REPORTS

- A. Startup Plans: For each item of equipment and system for which the manufacturer provides a startup plan, submit the plan not less than 8 weeks prior to startup.
- B. Startup Reports: For each item of equipment and system for which the manufacturer provides a startup checklist (or startup plan or field checkout sheet), document compliance by submitting the completed startup checklist prior to startup, signed and dated by responsible entity.
- C. Submit directly to the Commissioning Authority.

3.03 PREFUNCTIONAL CHECKLISTS

- A. A Prefunctional Checklist is required to be filled out for each item of equipment or other assembly specified to be commissioned.
 1. No sampling of identical or near-identical items is allowed.
 2. These checklists do not replace manufacturers' recommended startup checklists, regardless of apparent redundancy.
 3. Prefunctional Checklist forms will not be complete until after award of the contract; the following types of information will be gathered via the completed Checklist forms:
 - a. Certification by installing contractor that the unit is properly installed, started up, and operating and ready for Functional Testing.
 - b. Confirmation of receipt of each shop drawing and commissioning submittal specified, itemized by unit.
 - c. Manufacturer, model number, and relevant capacity information; list information "as specified," "as submitted," and "as installed."
 - d. Serial number of installed unit.
 - e. List of inspections to be conducted to document proper installation prior to startup and Functional Testing; these will be primarily static inspections and procedures; for equipment and systems may include normal manufacturer's start-up checklist items and minor testing.
 - f. Sensor and actuator calibration information.
 4. PECl (Samples) found at <http://www.peci.org/library/mcpgs.htm> indicate anticipated level of detail for Prefunctional Checklists.
- B. Contractor is responsible for filling out Prefunctional Checklists, after completion of installation and before startup; witnessing by the Commissioning Authority is not required unless otherwise specified.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Each line item without deficiency is to be witnessed, initialed, and dated by the actual witness; checklists are not complete until all line items are initialed and dated complete without deficiencies.
 2. Checklists with incomplete items may be submitted for approval provided the Contractor attests that incomplete items do not preclude the performance of safe and reliable Functional Testing; re-submission of the Checklist is required upon completion of remaining items.
 3. Individual Checklists may contain line items that are the responsibility of more than one installer; Contractor shall assign responsibility to appropriate installers or subcontractors, with identification recorded on the form.
 4. If any Checklist line item is not relevant, record reasons on the form.
 5. Contractor may independently perform startup inspections and/or tests, at his option.
 6. Regardless of these reporting requirements, Contractor is responsible for correct startup and operation.
 7. Submit completed Checklists to Commissioning Authority within two days of completion.
- C. Commissioning Authority is responsible for furnishing the Prefunctional Checklists to Contractor.
1. Initial Drafts: Contractor is responsible for initial draft of Prefunctional Checklist where so indicated in the Contract Documents.
 2. Provide all additional information requested by Commissioning Authority to aid in preparation of checklists, such as shop drawing submittals, manufacturers' startup checklists, and O&M data.
 3. Commissioning Authority may add any relevant items deemed necessary regardless of whether they are explicitly mentioned in the Contract Documents or not.
 4. When asked to review the proposed Checklists, do so in a timely manner.
- D. Commissioning Authority Witnessing: Required for:
1. Each piece of primary equipment, unless sampling of multiple similar units is allowed by the commissioning plan.
 2. A sampling of non-primary equipment, as allowed by the commissioning plan.
- E. Deficiencies: Correct deficiencies and re-inspect or re-test, as applicable, at no extra cost to Owner.
1. If difficulty in correction would delay progress, report deficiency to the Commissioning Authority immediately.

3.04 FUNCTIONAL TESTS

- A. A Functional Test is required for each item of equipment, system, or other assembly specified to be commissioned, unless sampling of multiple identical or near-identical units is allowed by the final test procedures.
- B. Contractor is responsible for execution of required Functional Tests, after completion of Prefunctional Checklist and before closeout.
- C. Commissioning Authority is responsible for witnessing and reporting results of Functional Tests, including preparation and completion of forms for that purpose.
- D. Contractor is responsible for correction of deficiencies and re-testing at no extra cost to Owner; if a deficiency is not corrected and re-tested immediately, the Commissioning Authority will document the deficiency and the Contractor's stated intentions regarding correction.
 1. Deficiencies are any condition in the installation or function of a component, piece of equipment or system that is not in compliance with the Contract Documents or does not perform properly.
 2. When the deficiency has been corrected, the Contractor completes the form certifying that the item is ready to be re-tested and returns the form to the Commissioning Authority; the Commissioning Authority will reschedule the test and the Contractor shall re-test.
 3. Identical or Near-Identical Items: If 10 percent, or three, whichever is greater, of identical or near-identical items fail to perform due to material or manufacturing defect, all items will be

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



considered defective; provide a proposal for correction within 2 weeks after notification of defect, including provision for testing sample installations prior to replacement of all items.

- 4. Contractor shall bear the cost of Owner and Commissioning Authority personnel time witnessing re-testing.
- 5. Contractor shall bear the cost of Owner and Commissioning Authority personnel time witnessing re-testing if the test failed due to failure to execute the relevant Prefunctional Checklist correctly; if the test failed for reasons that would not have been identified in the Prefunctional Checklist process, Contractor shall bear the cost of the second and subsequent re-tests.

E. Functional Test Procedures:

- 1. Some test procedures are included in the Contract Documents; where Functional Test procedures are not included in the Contract Documents, test procedures will be determined by the Commissioning Authority with input by and coordination with Contractor.
- 2. Examples of Functional Testing:
 - a. Test the dynamic function and operation of equipment and systems (rather than just components) using manual (direct observation) or monitoring methods under full operation (e.g., the chiller pump is tested interactively with the chiller functions to see if the pump ramps up and down to maintain the differential pressure setpoint).
 - b. Systems are tested under various modes, such as during low cooling or heating loads, high loads, component failures, unoccupied, varying outside air temperatures, fire alarm, power failure, etc.
 - c. Systems are run through all the HVAC control system's sequences of operation and components are verified to be responding as the sequence's state.
 - d. Traditional air or water test and balancing (TAB) is not Functional Testing; spot checking of TAB by demonstration to the Commissioning Authority is Functional Testing.
- 3. PECCI (Samples) found at <http://www.peci.org/library/mcpgs.htm> indicated anticipated level of detail for Functional Tests.

F. Deferred Functional Tests: Some tests may need to be performed later, after substantial completion, due to partial occupancy, equipment, seasonal requirements, design or other site conditions; performance of these tests remains the Contractor's responsibility regardless of timing.

3.05 SENSOR AND ACTUATOR CALIBRATION

- A. Calibrate all field-installed temperature, relative humidity, carbon monoxide, carbon dioxide, and pressure sensors and gages, and all actuators (dampers and valves) on this piece of equipment shall be calibrated. Sensors installed in the unit at the factory with calibration certification provided need not be field calibrated.
- B. Calibrate using the methods described below; alternate methods may be used, if approved by Commissioning Authority and Owner beforehand. See PART 2 for test instrument requirements. Record methods used on the relevant Prefunctional Checklist or other suitable forms, documenting initial, intermediate and final results.
- C. All Sensors:
 - 1. Verify that sensor location is appropriate and away from potential causes of erratic operation.
 - 2. Verify that sensors with shielded cable are grounded only at one end.
 - 3. For sensor pairs that are used to determine a temperature or pressure difference, for temperature make sure they are reading within 0.2 degree F of each other, and for pressure, within tolerance equal to 2 percent of the reading, of each other.
 - 4. Tolerances for critical applications may be tighter.
- D. Sensors Without Transmitters - Standard Application:
 - 1. Make a reading with a calibrated test instrument within 6 inches of the site sensor.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Verify that the sensor reading, via the permanent thermostat, gage or building automation system, is within the tolerances in the table below of the instrument-measured value.
 3. If not, install offset, calibrate or replace sensor.
- E. Sensors With Transmitters - Standard Application.
1. Disconnect sensor.
 2. Connect a signal generator in place of sensor.
 3. Connect ammeter in series between transmitter and building automation system control panel.
 4. Using manufacturer's resistance-temperature data, simulate minimum desired temperature.
 5. Adjust transmitter potentiometer zero until 4 mA is read by the ammeter.
 6. Repeat for the maximum temperature matching 20 mA to the potentiometer span or maximum and verify at the building automation system.
 7. Record all values and recalibrate controller as necessary to conform with specified control ramps, reset schedules, proportional relationship, reset relationship and P/I reaction.
 8. Reconnect sensor.
 9. Make a reading with a calibrated test instrument within 6 inches of the site sensor.
 10. Verify that the sensor reading, via the permanent thermostat, gage or building automation system, is within the tolerances in the table below of the instrument-measured value.
 11. If not, replace sensor and repeat.
 12. For pressure sensors, perform a similar process with a suitable signal generator.
- F. Sensor Tolerances for Standard Applications: Plus/minus the following maximums:
1. Watthour, Voltage, Amperage: 1 percent of design.
 2. Pressure, Air, Water, Gas: 3 percent of design.
 3. Air Temperatures (Outside Air, Space Air, Duct Air): 0.4 degrees F.
 4. Relative Humidity: 4 percent of design.
 5. Barometric Pressure: 0.1 inch of Hg.
 6. Flow Rate, Air: 10 percent of design.
 7. Flow Rate, Water: 4 percent of design.
 8. AHU Wet Bulb and Dew Point: 2.0 degrees F.
- G. Critical Applications: For some applications more rigorous calibration techniques may be required for selected sensors. Describe any such methods used on an attached sheet.
- H. Valve/Damper Stroke Setup and Check:
1. For all valve/damper actuator positions checked, verify the actual position against the control system readout.
 2. Set pump/fan to normal operating mode.
 3. Command valve/damper closed; visually verify that valve/damper is closed and adjust output zero signal as required.
 4. Command valve/damper to open; verify position is full open and adjust output signal as required.
 5. Command valve/damper to a few intermediate positions.
 6. If actual valve/damper position does not reasonably correspond, replace actuator or add pilot positioner (for pneumatics).
- I. Isolation Valve or System Valve Leak Check: For valves not associated with coils.
1. With full pressure in the system, command valve closed.
 2. Use an ultra-sonic flow meter to detect flow or leakage.

3.06 TEST PROCEDURES - GENERAL

- A. Provide skilled technicians to execute starting of equipment and to execute the Functional Tests. Ensure that they are available and present during the agreed upon schedules and for sufficient duration to complete the necessary tests, adjustments and problem-solving.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Provide all necessary materials and system modifications required to produce the flows, pressures, temperatures, and conditions necessary to execute the test according to the specified conditions. At completion of the test, return all affected equipment and systems to their pre-test condition.
- C. Sampling: Where Functional Testing of fewer than the total number of multiple identical or near-identical items is explicitly permitted, perform sampling as follows:
 - 1. Identical Units: Defined as units with same application and sequence of operation; only minor size or capacity difference.
 - 2. Sampling is not allowed for:
 - a. Major equipment.
 - b. Life-safety-critical equipment.
 - c. Prefunctional Checklist execution.
 - 3. XX = the percent of the group of identical equipment to be included in each sample; defined for specific type of equipment.
 - 4. YY = the percent of the sample that if failed will require another sample to be tested; defined for specific type of equipment.
 - 5. Randomly test at least XX percent of each group of identical equipment, but not less than three units. This constitutes the "first sample."
 - 6. If YY percent of the units in the first sample fail, test another XX percent of the remaining identical units.
 - 7. If YY percent of the units in the second sample fail, test all remaining identical units.
 - 8. If frequent failures occur, resulting in more troubleshooting than testing, the Commissioning Authority may stop the testing and require Contractor to perform and document a checkout of the remaining units prior to continuing testing.
- D. Manual Testing: Use hand-held instruments, immediate control system readouts, or direct observation to verify performance (contrasted to analyzing monitored data taken over time to make the "observation").
- E. Simulating Conditions: Artificially create the necessary condition for the purpose of testing the response of a system; for example apply hot air to a space sensor using a hair dryer to see the response in a VAV box.
- F. Simulating Signals: Disconnect the sensor and use a signal generator to send an amperage, resistance or pressure to the transducer and control system to simulate the sensor value.
- G. Over-Writing Values: Change the sensor value known to the control system in the control system to see the response of the system; for example, change the outside air temperature value from 50 degrees F to 75 degrees F to verify economizer operation.
- H. Indirect Indicators: Remote indicators of a response or condition, such as a reading from a control system screen reporting a damper to be 100 percent closed, are considered indirect indicators.
- I. Monitoring: Record parameters (flow, current, status, pressure, etc.) of equipment operation using dataloggers or the trending capabilities of the relevant control systems; where monitoring of specific points is called for in Functional Test Procedures:
 - 1. All points that are monitored by the relevant control system shall be trended by Contractor; at the Commissioning Authority's request, Contractor shall trend up to 20 percent more points than specified at no extra charge.
 - 2. Other points will be monitored by the Commissioning Authority using dataloggers.
 - 3. At the option of the Commissioning Authority, some control system monitoring may be replaced with datalogger monitoring.
 - 4. Provide hard copies of monitored data in columnar format with time down left column and at least 5 columns of point values on same page.
 - 5. Graphical output is desirable and is required for all output if the system can produce it.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



6. Monitoring may be used to augment manual testing.

3.07 BUILDING ENVELOPE COMMISSIONING

- A. General: Conform to the following procedural requirements:
 - 1. NEBB S110 Whole Building Technical Commissioning of New Construction.
 - 2. ASTM E779 Standard Test Method for Determining Air Leakage Rate by Fan Pressurization.
 - 3. ASTM E1827 Standard Test Methods for Determining Airtightness of Buildings Using an Orifice Blower Door.
- B. Verify that the building envelope has been sufficiently completed for testing to commence.
- C. Conduct ongoing inspections as construction progresses to document satisfactory installation conditions. related to thermal and moisture integrity of the building envelope that become concealed upon completion of construction.
- D. Submit a detailed narrative of proposed pressure test procedures prior to the test. Include a plan view showing proposed installation locations (personnel doors or other similar openings) for blower doors (or flexible ducts for trailer-mounted fans, if used).
- E. Avoid testing on days forecast to experience high winds, rain, or snow.
- F. Test the completed building and demonstrate that the air leakage rate of the building envelope does not exceed the specified requirements.
 - 1. Use equipment and methods necessary to produce indoor/outdoor pressure differential of 0.2 inches w.g..
- G. Determine location and nature of undesirable air leakage pathways using methods specified in ASTM E1186-17 Standard Practices for Air Leakage Site Detection in Building Envelopes and Air Barrier Systems.
- H. Deficiencies: Correct deficiencies and re-inspect or re-test, as applicable, at no extra cost to Owner.
 - 1. If difficulty in correction would delay progress, report deficiency to the Commissioning Authority immediately.

3.08 FIELD TESTING AND COMMISSIONING OF PARTITIONS FOR NOISE ISOLATION

- A. Conduct testing of partitions requiring a specific STC class indicated on drawings and/or in various specifications sections. Conform to ASTM E336 for testing methods, including requirements of Annex A1 for reduction of flanking sound transmission.
- B. Confirm that the FSTC values are not less than 67 percent of design STC values.
- C. Deficiencies: Correct deficiencies and re-inspect or re-test, as applicable, at no extra cost to Owner.
 - 1. If difficulty in correction would delay progress, report deficiency to the Commissioning Authority immediately.

3.09 OPERATION AND MAINTENANCE MANUALS

- A. See Section 017800 - Closeout Submittals for additional requirements.
- B. Add design intent documentation furnished by Architect to manuals prior to submission to Owner.
- C. Submit manuals related to items that were commissioned to Commissioning Authority for review; make changes recommended by Commissioning Authority.
- D. Commissioning Authority will add commissioning records to manuals after submission to Owner.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 024100
DEMOLITION**

UPDATED OCT 2022

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. **Building demolition including removal of select hazardous materials and toxic substances.**
- B. Selective demolition of built site elements.
- C. Selective demolition of building elements for alteration purposes.
- D. Abandonment and removal of existing utilities and utility structures.

1.02 RELATED REQUIREMENTS

- A. Section 003100 - Available Project Information: Existing building survey conducted by Owner; information about known hazardous materials.
- B. Section 015000 - Temporary Facilities and Controls: Site fences, security, protective barriers, and waste removal.
- C. Section 015713 - Temporary Erosion and Sediment Control.
- D. Section 016000 - Product Requirements: Handling and storage of items removed for salvage and relocation.
- E. **Section 260505 - Selective Demolition for Electrical.**
- F. Section 311000 - Site Clearing: Vegetation and existing debris removal.

1.03 REFERENCE STANDARDS

- A. 29 CFR 1926 - U.S. Occupational Safety and Health Standards; current edition.
- B. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations; 2013.

1.04 SUBMITTALS

- A. See Section 9 of General Conditions 013000 - Administrative Requirements for submittal procedures.
- B. Site Plan: Showing:
 - 1. Vegetation to be protected.
 - 2. Areas for temporary construction and field offices.
 - 3. Areas for temporary and permanent placement of removed materials.
- C. Demolition Plan: Submit demolition plan as specified by OSHA and local authorities.
 - 1. Indicate extent of demolition, removal sequence, bracing and shoring, and location and construction of barricades and fences.
 - 2. Identify demolition firm and submit qualifications.
 - 3. Include a summary of safety procedures.
- D. Project Record Documents: Accurately record actual locations of capped and active utilities and subsurface construction.

1.05 QUALITY ASSURANCE

- A. Demolition Firm Qualifications: Company specializing in the type of work required.
 - 1. Minimum of 5 years of experience.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 2 PRODUCTS -- NOT USED

PART 3 EXECUTION

3.01 SCOPE

- A. Remove paving and curbs as required to accomplish new work.
- B. Remove and legally dispose of all materials, being demolished, indicated on plans.
 - 1. **Removal and dispose all asbestos containing material (ACM) under 1.49% following all Federal, State and Local requirements. ACM above 1.49% will be abated by Owner.**
 - 2. **Remove all light fixture ballasts (PCB's) and lamp tubes. Place in Owner-provided collection bins. Place filled bins in dock area or other accessible outdoor location as reviewed with Owner. Owner will remove bins and dispose of contents.**
 - 3. **Remove and dispose all lead following all Federal, State and Local requirements.**
- C. Remove other items indicated, for salvage, relocation, and reinstallation.

3.02 GENERAL PROCEDURES AND PROJECT CONDITIONS

- A. Comply with applicable codes and regulations for demolition operations and safety of adjacent structures and the public.
 - 1. Obtain required permits.
 - 2. Comply with applicable requirements of NFPA 241.
 - 3. Use of explosives is not permitted.
 - 4. Provide, erect, and maintain temporary barriers and security devices.
 - 5. Use physical barriers to prevent access to areas that could be hazardous to workers or the public.
 - 6. Conduct operations to minimize effects on and interference with adjacent structures and occupants.
 - 7. Conduct operations to minimize obstruction of public and private entrances and exits; do not obstruct required exits at any time; protect persons using entrances and exits from removal operations.
 - 8. Obtain written permission from owners of adjacent properties when demolition equipment will traverse, infringe upon or limit access to their property.
- B. Do not begin removal until receipt of notification to proceed from Owner.
- C. Do not begin removal until built elements to be salvaged or relocated have been removed.
- D. Do not begin removal until vegetation to be relocated has been removed and specified measures have been taken to protect vegetation to remain.
- E. Protect existing elements that are not to be removed.
 - 1. Provide bracing and shoring.
 - 2. Prevent movement or settlement of adjacent structures.
 - 3. Stop work immediately if adjacent structures appear to be in danger.
- F. Minimize production of dust due to demolition operations; do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.
- G. If hazardous materials are discovered during removal operations, stop work and notify Architect and Owner; hazardous materials include regulated asbestos containing materials, and mercury.
- H. Partial Removal of Paving and Curbs: Neatly saw cut at right angle to surface.

3.03 EXISTING UTILITIES

- A. Coordinate work with utility companies; notify before starting work and comply with their requirements; obtain required permits.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Protect existing utilities to remain from damage.
- C. Do not disrupt public utilities without permit from authority having jurisdiction.
- D. Do not close, shut off, or disrupt existing life safety systems that are in use without at least 7 days prior written notification to Owner.
- E. Do not close, shut off, or disrupt existing utility branches or take-offs that are in use without at least 3 days prior written notification to Owner.
- F. Locate and mark utilities to remain; mark using highly visible tags or flags, with identification of utility type; protect from damage due to subsequent construction, using substantial barricades if necessary.
- G. Use concrete to plug and cap all open ends of abandoned underground utilities which are to remain in place. Some pipelines and conduits will require flowable fill to be placed in pipe see plans for specific areas. Provo City Standards apply to Provo City Utilities review City requirements and permit for specific direction.
- H. Remove exposed piping, valves, meters, equipment, supports, and foundations of disconnected and abandoned utilities.
- I. Prepare demolition areas by disconnecting and capping utilities outside the demolition zone; identify and mark utilities to be subsequently reconnected, in same manner as other utilities to remain.

3.04 ABANDONED UTILITIES

- A. GPS/Survey of Abandoned and New Utilities.
 - 1. Coordinate with BYU Construction Project Manager to request BYU Civil Engineer to GPS/Survey abandoned and new utilities that have been installed, capped/plugged and/or abandoned in place before burying the utility.
 - 2. Provide at least a 24-hour notice.
 - 3. Utilities include but are not limited to the following: Water, storm & sewer pipelines, valves, hydrants, manholes, catch basins, clean outs, conduits, duct banks, etc.
 - 4. Contractor will be responsible at their expense to uncover abandoned utilities that have not been properly GPS or surveyed by BYU.
- B. Abandoning Pipelines
 - 1. Abandon utility pipes shown in the plans or designated by the OWNER by emptying the pipeline contents and plugging the ends with grout or flowable fill.
 - 2. Fill or remove the following abandoned utility pipes:
 - a. Fill abandoned pipe with grout or flowable fill. Prepare grout or flowable fill to a consistency that will flow and be vibrated in order for the mix to flow uniformly into the pipe to be filled.
 - b. Pipe larger than 24".
 - c. Pipe located within the foot print of an existing building, the roadway typical section or the project slope stake line and one of the following:
 - 1) Pipe 12" to 24" diameter located less than 20 ft below finished grade.
 - 2) Pipe 6" to 12" diameter located less than 12 ft below finished grade and not made of ductile iron, HDPE or PVC.
 - 3) Located below groundwater table that could become a conduit for water movement.
- C. Remove existing Utility Pipes
 - 1. Excavate, remove and dispose of properly any abandoned pipe to be removed when so designated in the plans or as directed. When an existing pipe is encountered that is not shown in the plans, do not remove until the Engineer is notified of its presence and has directed its removal.
 - 2. Remove any abandoned utility pipe exposed by grading operations to a minimum depth of 12" below subgrade elevation of the proposed roadbed or grading plan.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Backfill the resulting trench and properly compact using local excavated material or select backfill as required.
4. Salvaged pipe is the property of the Contractor unless otherwise indicated by the plans.
5. Plug all abandoned utility pipes. Use grout to plug all abandoned utility pipes at the entrance to all manholes whether the manhole is to be abandoned or not. Use grout to plug all abandoned water mains after new mains are placed in service.
6. Discharge flowable fill material directly from the truck into the space to be filled or by other approved methods. The mix may be placed full depth or in lifts as site conditions warrant.
7. Pipeline abandonment or disconnection to Provo City Utilities shall be as per Provo City Standards.

3.05 SELECTIVE DEMOLITION FOR ALTERATIONS

- A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
 1. Verify that construction and utility arrangements are as indicated.
 2. Report discrepancies to Architect and BYU Construction Project Manager before disturbing existing installation.
 3. Beginning of demolition work constitutes acceptance of existing conditions that would be apparent upon examination prior to starting demolition.
- B. Separate areas in which demolition is being conducted from other areas that are still occupied.
 1. Provide, erect, and maintain temporary dustproof partitions of construction indicated on drawings in locations indicated on drawings.
- C. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; take care to prevent water and humidity damage.
- D. Remove existing work as indicated and as required to accomplish new work.
 1. Remove items indicated on drawings.
- E. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, Telecommunications, and _____): Remove existing systems and equipment as indicated.
 1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components.
 2. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
 3. Verify that abandoned services serve only abandoned facilities before removal.
 4. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification.
- F. Protect existing work to remain.
 1. Prevent movement of structure; provide shoring and bracing if necessary.
 2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
 3. Repair adjacent construction and finishes damaged during removal work.
 4. Patch as specified for patching new work.

3.06 DEBRIS AND WASTE REMOVAL

- A. Remove debris, junk, and trash from site.
- B. Remove from site all materials not to be reused on site; dispose of these materials in a lawful manner.
- C. Leave site in clean condition, ready for subsequent work.
- D. Clean up spillage and wind-blown debris from public and private lands.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 055000
METAL FABRICATIONS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Shop fabricated steel and aluminum items.

1.02 RELATED REQUIREMENTS

- A. Section 051200 - Structural Steel Framing: Structural steel column anchor bolts.
- B. Section 052100 - Steel Joist Framing: Structural joist bearing plates, including anchorage.
- C. Section 053100 - Steel Decking: Bearing plates for metal deck bearing, including anchorage.
- D. Section 055100 - Metal Stairs.
- E. Section 055213 - Pipe and Tube Railings.

1.03 REFERENCE STANDARDS

- A. AAMA 611 - Voluntary Specification for Anodized Architectural Aluminum; 2014 (2015 Errata).
- B. ANSI A14.3 - American National Standard for Ladders -- Fixed -- Safety Requirements; 2008.
- C. ASTM A36/A36M - Standard Specification for Carbon Structural Steel; 2014.
- D. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2012.
- E. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- F. ASTM A283/A283M - Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates; 2013.
- G. ASTM A307 - Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength; 2014 (Editorial 2017).
- H. ASTM A501/A501M - Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing; 2014.
- I. ASTM B209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2014.
- J. ASTM B209M - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric); 2014.
- K. ASTM B210 - Standard Specification for Aluminum and Aluminum-Alloy Drawn Seamless Tubes; 2012.
- L. ASTM B210M - Standard Specification for Aluminum and Aluminum-Alloy Drawn Seamless Tubes (Metric); 2012.
- M. ASTM B221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2014.
- N. ASTM B221M - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2013.
- O. ASTM F3125/F3125M - Standard Specification for High Strength Structural Bolts, Steel and Alloy Steel, Heat Treated, 120 ksi (830 MPa) and 150 ksi (1040 MPa) Minimum Tensile Strength, Inch and Metric Dimensions; 2015a.
- P. AWS A2.4 - Standard Symbols for Welding, Brazing, and Nondestructive Examination; 2012.
- Q. AWS D1.1/D1.1M - Structural Welding Code - Steel; 2015 (with March 2016 Errata).

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- R. AWS D1.2/D1.2M - Structural Welding Code - Aluminum; 2014, with Errata.
- S. SSPC-Paint 15 - Steel Joist Shop Primer/Metal Building Primer; 1999 (Ed. 2004).
- T. SSPC-Paint 20 - Zinc-Rich Primers (Type I, "Inorganic," and Type II, "Organic"); 2002 (Ed. 2004).
- U. SSPC-SP 2 - Hand Tool Cleaning; 1982 (Ed. 2004).

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories. Include erection drawings, elevations, and details where applicable.
 - 1. Indicate welded connections using standard AWS A2.4 welding symbols. Indicate net weld lengths.
- C. Welders' Certificates: Submit certification for welders employed on the project, verifying AWS qualification within the previous 12 months.

PART 2 PRODUCTS

2.01 MATERIALS - STEEL

- A. Steel Sections: ASTM A36/A36M.
- B. Steel Tubing: ASTM A501/A501M hot-formed structural tubing.
- C. Plates: ASTM A283/A283M.
- D. Pipe: ASTM A53/A53M, Grade B Schedule 40, black finish.
- E. Bolts, Nuts, and Washers: ASTM A307, Grade A, plain.
- F. Bolts, Nuts, and Washers: ASTM F3125/F3125M, Type 1, plain.
- G. Welding Materials: AWS D1.1/D1.1M; type required for materials being welded.
- H. Shop and Touch-Up Primer: SSPC-Paint 15, complying with VOC limitations of authorities having jurisdiction.
- I. Touch-Up Primer for Galvanized Surfaces: SSPC-Paint 20, Type I - Inorganic, complying with VOC limitations of authorities having jurisdiction.

2.02 MATERIALS - ALUMINUM

- A. Extruded Aluminum: ASTM B221 (ASTM B221M), 6063 alloy, T6 temper.
- B. Sheet Aluminum: ASTM B209 (ASTM B209M), 5052 alloy, H32 or H22 temper.
- C. Aluminum-Alloy Drawn Seamless Tubes: ASTM B210 (ASTM B210M), 6063 alloy, T6 temper.
- D. Bolts, Nuts, and Washers: Stainless steel.
- E. Welding Materials: AWS D1.2/D1.2M; type required for materials being welded.

2.03 FABRICATION

- A. Fit and shop assemble items in largest practical sections, for delivery to site.
- B. Fabricate items with joints tightly fitted and secured.
- C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
- D. Supply components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.04 FABRICATED ITEMS

- A. Ladders: Steel; in compliance with ANSI A14.3; with mounting brackets and attachments; prime paint finish.
 - 1. Side Rails: 3/8 x 2 inches members spaced at 20 inches.
 - 2. Rungs: one inch diameter solid round bar spaced 12 inches on center.
 - 3. Space rungs 7 inches from wall surface.
- B. Ledge Angles, Shelf Angles, Channels, and Plates Not Attached to Structural Framing: For support of metal decking; prime paint finish.
- C. Lintels: As detailed; prime paint finish.
- D. Door Frames for Overhead Door Openings and Wall Openings: Channel and Angle sections; prime paint finish.
- E. Recessed Mat Frames : As detailed; steel, galvanized finish.
- F. Elevator Hoistway Divider Beams: Beam sections; prime paint finish.
- G. Toilet Partition Suspension Members: Steel channel sections; prime paint finish.

2.05 FINISHES - STEEL

- A. Prime paint steel items.
 - 1. Exceptions: Galvanize items to be embedded in concrete, items to be embedded in masonry, and items specified for galvanized finish.
 - 2. Exceptions: Do not prime surfaces in direct contact with concrete, where field welding is required, and items to be covered with sprayed fireproofing.
- B. Prepare surfaces to be primed in accordance with SSPC-SP2.
- C. Clean surfaces of rust, scale, grease, and foreign matter prior to finishing.
- D. Prime Painting: One coat.
- E. Galvanizing of Structural Steel Members: Galvanize after fabrication to ASTM A123/A123M requirements. Provide minimum 1.7 oz/sq ft galvanized coating.
- F. Galvanizing of Non-structural Items: Galvanize after fabrication to ASTM A123/A123M requirements.

2.06 FINISHES - ALUMINUM

- A. Exterior Aluminum Surfaces: Class I color anodized.
- B. Interior Aluminum Surfaces: Class I natural anodized.
- C. Class I Natural Anodized Finish: AAMA 611 AA-M12C22A41 Clear anodic coating not less than 0.7 mils thick.

2.07 FABRICATION TOLERANCES

- A. Squareness: 1/8 inch maximum difference in diagonal measurements.
- B. Maximum Offset Between Faces: 1/16 inch.
- C. Maximum Misalignment of Adjacent Members: 1/16 inch.
- D. Maximum Bow: 1/8 inch in 48 inches.
- E. Maximum Deviation From Plane: 1/16 inch in 48 inches.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field conditions are acceptable and are ready to receive work.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.02 PREPARATION

- A. Clean and strip primed steel items to bare metal where site welding is required.
- B. Supply setting templates to the appropriate entities for steel items required to be cast into concrete or embedded in masonry.

3.03 INSTALLATION

- A. Install items plumb and level, accurately fitted, free from distortion or defects.
- B. Provide for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Field weld components as indicated on drawings.
- D. Perform field welding in accordance with AWS D1.1/D1.1M.
- E. Obtain approval prior to site cutting or making adjustments not scheduled.
- F. After erection, prime welds, abrasions, and surfaces not shop primed, except surfaces to be in contact with concrete.

3.04 TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch per story, non-cumulative.
- B. Maximum Offset From True Alignment: 1/4 inch.
- C. Maximum Out-of-Position: 1/4 inch.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 061000 ROUGH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Roofing nailers.
- B. Roofing cant strips.
- C. Preservative treated wood materials.
- D. Fire retardant treated wood materials.
- E. Communications and electrical room mounting boards.
- F. Concealed wood blocking, nailers, and supports.
- G. Miscellaneous wood nailers, furring, and grounds.

1.02 RELATED REQUIREMENTS

- A. Section 076200 - Sheet Metal Flashing and Trim: Sill flashings.
- B. Section 077200 - Roof Accessories: Prefabricated roof curbs.
- C. Section 092116 - Gypsum Board Assemblies: Gypsum-based sheathing.

1.03 REFERENCE STANDARDS

- A. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2016a.
- B. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- C. AWPA U1 - Use Category System: User Specification for Treated Wood; 2017.
- D. PS 1 - Structural Plywood; 2009.
- E. PS 20 - American Softwood Lumber Standard; 2015.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide technical data on wood preservative materials and application instructions.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. General: Cover wood products to protect against moisture. Support stacked products to prevent deformation and to allow air circulation.
- B. Fire Retardant Treated Wood: Prevent exposure to precipitation during shipping, storage, or installation.

PART 2 PRODUCTS

2.01 GENERAL REQUIREMENTS

- A. Dimension Lumber: Comply with PS 20 and requirements of specified grading agencies.
 - 1. Species: Douglas Fir, #2, unless otherwise indicated.
 - 2. Grading Agency: Any grading agency whose rules are approved by the Board of Review, American Lumber Standard Committee (www.alsc.org) and who provides grading service for the species and grade specified; provide lumber stamped with grade mark unless otherwise indicated.
 - 3. Lumber of other species or grades is acceptable provided structural and appearance characteristics are equivalent to or better than products specified.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.02 DIMENSION LUMBER FOR CONCEALED APPLICATIONS

- A. Sizes: Nominal sizes as indicated on drawings, S4S.
- B. Moisture Content: S-dry or MC19.
- C. Miscellaneous Framing, Blocking, Nailers, Grounds, and Furring:
 - 1. Lumber: S4S, No. 2 or Standard Grade.
 - 2. Boards: Standard or No. 3.

2.03 CONSTRUCTION PANELS

- A. Communications and Electrical Room Mounting Boards: PS 1 A-D plywood, or medium density fiberboard; 0.5 inch thick; flame spread index of 25 or less, smoke developed index of 450 or less, when tested in accordance with ASTM E84.
- B. Other Applications:
 - 1. Plywood Concealed From View But Located Within Exterior Enclosure: PS 1, C-C Plugged or better, Exterior grade.
 - 2. Other Locations: PS 1, C-D Plugged or better.
 - 3. Wood structural panels when used in non-combustible type construction shall be fire rated and installed in accordance with the adopted IBC code.

2.04 ACCESSORIES

- A. Fasteners and Anchors:
 - 1. Metal and Finish: Hot-dipped galvanized steel complying with ASTM A153/A153M for high humidity and preservative-treated wood locations, unfinished steel elsewhere.
 - 2. Drywall Screws: Bugle head, hardened steel, power driven type, length to achieve full penetration of sheathing substrate.

2.05 FACTORY WOOD TREATMENT

- A. Treated Lumber and Plywood: Comply with requirements of AWPA U1 - Use Category System for wood treatments determined by use categories, expected service conditions, and specific applications.
 - 1. Fire-Retardant Treated Wood: Mark each piece of wood with producer's stamp indicating compliance with specified requirements.
 - 2. Preservative-Treated Wood: Provide lumber and plywood marked or stamped by an ALSC-accredited testing agency, certifying level and type of treatment in accordance with AWPA standards.
- B. Fire Retardant Treatment:
 - 1. Interior Type A: AWPA U1, Use Category UCFA, Commodity Specification H, low temperature (low hygroscopic) type, chemically treated and pressure impregnated; capable of providing a maximum flame spread index of 25 when tested in accordance with ASTM E84, with no evidence of significant combustion when test is extended for an additional 20 minutes.
 - a. Kiln dry wood after treatment to a maximum moisture content of 19 percent for lumber and 15 percent for plywood.
 - b. Treat rough carpentry items as indicated .
 - c. Do not use treated wood in applications exposed to weather or where the wood may become wet.
- C. Preservative Treatment:
 - 1. Preservative Pressure Treatment of Lumber Above Grade: AWPA U1, Use Category UC3B, Commodity Specification A using waterborne preservative.
 - a. Kiln dry lumber after treatment to maximum moisture content of 19 percent.
 - b. Treat lumber in contact with roofing, flashing, or waterproofing.
 - c. Treat lumber in contact with masonry or concrete.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 3 EXECUTION

3.01 INSTALLATION - GENERAL

- A. Select material sizes to minimize waste.
- B. Reuse scrap to the greatest extent possible; clearly separate scrap for use on site as accessory components, including: shims, bracing, and blocking.
- C. Where treated wood is used on interior, provide temporary ventilation during and immediately after installation sufficient to remove indoor air contaminants.

3.02 BLOCKING, NAILERS, AND SUPPORTS

- A. Provide framing and blocking members as indicated or as required to support finishes, fixtures, specialty items, and trim.
- B. In framed assemblies that have concealed spaces, provide solid wood fire blocking as required by applicable local code, to close concealed draft openings between floors and between top story and roof/attic space; other material acceptable to code authorities may be used in lieu of solid wood blocking.
- C. In metal stud walls, provide continuous blocking around door and window openings for anchorage of frames, securely attached to stud framing.
- D. In walls, provide blocking attached to studs as backing and support for wall-mounted items, unless item can be securely fastened to two or more studs or other method of support is explicitly indicated.
- E. Where ceiling-mounting is indicated, provide blocking and supplementary supports above ceiling, unless other method of support is explicitly indicated.
- F. Provide the following specific non-structural framing and blocking:
 - 1. Cabinets and shelf supports.
 - 2. Wall brackets.
 - 3. Handrails.
 - 4. Grab bars.
 - 5. Towel and bath accessories.
 - 6. Wall-mounted door stops.
 - 7. Chalkboards and marker boards.
 - 8. Wall paneling and trim.
 - 9. Joints of rigid wall coverings that occur between studs.
 - 10. Flat-panel displays, and media projectors..
 - 11. Communications and electrical room mounting boards.

3.03 ROOF-RELATED CARPENTRY

- A. Coordinate installation of roofing carpentry with deck construction, framing of roof openings, and roofing assembly installation.
- B. Provide wood curb at all roof openings except where prefabricated curbs are specified and where specifically indicated otherwise. Form corners by alternating lapping side members.

3.04 INSTALLATION OF CONSTRUCTION PANELS

- A. Communications and Electrical Room Mounting Boards: Secure with screws to studs with edges over firm bearing; space fasteners at maximum 24 inches on center on all edges and into studs in field of board.
 - 1. At fire-rated walls, install board over wall board indicated as part of the fire-rated assembly.
 - 2. Where boards are indicated as full floor-to-ceiling height, install with long edge of board parallel to studs.
 - 3. Install adjacent boards without gaps.
 - 4. Size: 48 by 96 inches, installed horizontally at ceiling height.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.05 TOLERANCES

- A. Framing Members: 1/4 inch from true position, maximum.
- B. Surface Flatness of Floor: 1/8 inch in 10 feet maximum, and 1/4 inch in 30 feet maximum.
- C. Variation from Plane (Other than Floors): 1/4 inch in 10 feet maximum, and 1/4 inch in 30 feet maximum.

3.06 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Leave carpentry wood work of this section open and accessible for required inspections before covering. The inspections will be executed by the BYU Construction PM.

3.07 CLEANING

- A. Waste Disposal: Comply with the requirements of Section 017419 - Construction Waste Management and Disposal.
 - 1. Comply with applicable regulations.
 - 2. Do not burn scrap on project site.
 - 3. Do not burn scraps that have been pressure treated.
 - 4. Do not send materials treated with pentachlorophenol, CCA, or ACA to co-generation facilities or "waste-to-energy" facilities.
- B. Do not leave any wood, shavings, sawdust, etc. on the ground, buried in fill, or in interstitial building spaces.
- C. Prevent sawdust and wood shavings from entering the storm drainage system.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 062000 FINISH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Finish carpentry items.
- B. Wood door frames, glazed frames.
- C. Wood casings and moldings.
- D. Hardware and attachment accessories.

1.02 RELATED REQUIREMENTS

- A. Section 061000 - Rough Carpentry: Support framing, grounds, and concealed blocking.
- B. Section 064100 - Architectural Wood Casework: Shop fabricated custom cabinet work.
- C. Section 064216 - Wood-Veneer Paneling: Shop fabricated custom paneling.
- D. Section 081416 - Flush Wood Doors.
- E. Section 099123 - Interior Painting: Painting and finishing of finish carpentry items.
- F. Section 099300 - Staining and Transparent Finishing: Staining and transparent finishing of finish carpentry items.

1.03 REFERENCE STANDARDS

- A. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2016a.
- B. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- C. AWI (QCP) - Quality Certification Program; current edition at www.awiqcp.org.
- D. AWI/AWMAC/WI (AWS) - Architectural Woodwork Standards; 2014, with Errata (2016).
- E. AWMAC/WI (NAAWS) - North American Architectural Woodwork Standards, U.S. Version 3.1; 2016, with Errata (2017).
- F. AWPA U1 - Use Category System: User Specification for Treated Wood; 2017.
- G. BHMA A156.9 - American National Standard for Cabinet Hardware; 2015.
- H. HPVA HP-1 - American National Standard for Hardwood and Decorative Plywood; 2016.
- I. PS 1 - Structural Plywood; 2009.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate the work with plumbing rough-in, electrical rough-in, and installation of associated and adjacent components.
- B. Sequence installation to ensure utility connections are achieved in an orderly and expeditious manner.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data:
 - 1. Provide data on fire retardant treatment materials and application instructions.
 - 2. Provide instructions for attachment hardware and finish hardware.
- C. Shop Drawings: Indicate materials, component profiles, fastening methods, jointing details, and accessories.
 - 1. Provide the information required by AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS).

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 2. Include certification program label.
- D. Samples: Submit three samples of finish plywood, 12 by 12 inch in size illustrating wood grain and specified finish.
- E. Samples: Submit three samples of wood trim 12 inch long.
- F. Certificate: Submit labels and certificates required by quality assurance and quality control programs.

1.06 QUALITY ASSURANCE

- A. Fabricator Qualifications: Company specializing in fabricating the products specified in this section with minimum five years of documented experience.
 - 1. Accredited participant in the specified certification program prior to the commencement of fabrication and throughout the duration of the project.
 - 2. Single Source Responsibility: Provide and install this work from single fabricator.
- B. Quality Certification:
 - 1. Comply with AWI (QCP) woodwork association quality certification service/program in accordance with requirements for work specified in this section: www.awiqcp.org
 - 2. Provide labels or certificates indicating that the work complies with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS) requirements for grade or grades specified.
 - 3. Provide designated labels on shop drawings as required by certification program.
 - 4. Provide designated labels on installed products as required by certification program.
 - 5. Submit certifications upon completion of installation that verifies this work is in compliance with specified requirements.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Deliver factory-fabricated units to project site in original packages, containers or bundles bearing brand name and identification.
- B. Store finish carpentry items under cover, elevated above grade, and in a dry, well-ventilated area not exposed to heat or sunlight.
- C. Protect work from moisture damage.
- D. Handle materials and products to prevent damage to edges, ends, or surfaces.

PART 2 PRODUCTS

2.01 FINISH CARPENTRY ITEMS

- A. Quality Standard: Custom Grade, in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), unless noted otherwise.
- B. Surface Burning Characteristics: Provide materials having fire and smoke properties as required by applicable code.
- C. Interior Woodwork Items:
 - 1. Moldings, Bases, Casings, chair rails, and Miscellaneous Trim: As indicated on drawings.
 - 2. Valance Work: Clear fir; prepare for paint finish.

2.02 LUMBER MATERIALS

- A. Hardwood Lumber: red oak, cherry, maple, walnut species as shown on drawings, Sawn as indicated on drawings, maximum moisture content of 6 percent; with vertical grain, of quality suitable for transparent finish.

2.03 SHEET MATERIALS

- A. Softwood Plywood, Not Exposed to View: Any face species, medium density fiberboard core; PS 1 Grade A-B, glue type as recommended for application.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Softwood Plywood, Exposed to View: Face species as indicated, plain sawn, medium density fiberboard core; PS 1 Grade A-B, glue type as recommended for application.
- C. Hardwood Plywood: Face species as indicated, plain sawn, book matched, medium density fiberboard core; HPVA HP-1, Front Face Grade AA, Back Face Grade 1, glue type as recommended for application.

2.04 FASTENINGS

- A. Adhesive for Purposes Other Than Laminate Installation: Suitable for the purpose; not containing formaldehyde or other volatile organic compounds.
- B. Adhesive for factory-fabricated units: Manufacturer's recommended adhesive for application.
- C. Fasteners of size and type to suit application.
- D. Fasteners for Exterior Applications: Hot-dipped galvanized steel complying with ASTM A153/A153M; length required to penetrate wood substrate 1-1/2 inch minimum.
- E. Concealed Joint Fasteners: Threaded steel.

2.05 ACCESSORIES

- A. Lumber for Shimming and Blocking: Softwood lumber of Douglas Fir species.
- B. Primer: As specified in Section 099000.
- C. Wood Filler: Water base, tinted to match surface finish color.

2.06 HARDWARE

- A. Hardware: Comply with BHMA A156.9.
- B. Shelf Standards: KV 85 Series style, Anochrome finish; Double Slotted Standards manufactured by Knappe and Vogt, KV.
- C. Shelf Brackets: KV 185 style, Anochrome finish; Extra Duty Bracket manufactured by Knappe and Vogt, KV.

2.07 FABRICATION

- A. Shop assemble work for delivery to site, permitting passage through building openings.
- B. When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide trim for scribing and site cutting.

2.08 SHOP FINISHING

- A. Sand work smooth and set exposed nails and screws.
- B. Apply wood filler in exposed nail and screw indentations.
- C. On items to receive transparent finishes, use wood filler that matches surrounding surfaces and is of type recommended for the applicable finish.
- D. Finish work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), Section 5 - Finishing for grade specified and as follows:
 - 1. Transparent:
 - a. System - 1, Lacquer, Nitrocellulose.
 - b. Stain: As selected by Architect.
 - c. Sheen: Satin.
- E. Back prime woodwork items to be field finished, prior to installation.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify adequacy of backing and support framing.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Verify mechanical, electrical, and building items affecting work of this section are placed and ready to receive this work.
- C. See Section 061000 for installation of recessed wood blocking.

3.02 INSTALLATION

- A. Install work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS) requirements for grade indicated.
- B. Set and secure materials and components in place, plumb and level.
- C. Carefully scribe work abutting other components, with maximum gaps of 1/32 inch. Do not use additional overlay trim to conceal larger gaps.

3.03 TOLERANCES

- A. Maximum Variation from True Position: 1/16 inch.
- B. Maximum Offset from True Alignment with Abutting Materials: 1/32 inch.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 064100
ARCHITECTURAL WOOD CASEWORK

PART 1 GENERAL

**UPDATED 2/21, FEB 23, JULY 12, NOV
2021, DEC 2023**

1.01 SECTION INCLUDES

SEE CHANGES IN BOLD

- A. Specially fabricated cabinet units.
- B. Cabinet hardware.
- C. Factory finishing.
- D. Preparation for installing utilities.

1.02 RELATED REQUIREMENTS

- A. Section 061000 - Rough Carpentry: Support framing, grounds, and concealed blocking.
- B. Section 088000 - Glazing: Glass for casework.
- C. Section 123600 - Countertops.

1.03 REFERENCE STANDARDS

- A. AWI/AWMA/WI (AWS) - Architectural Woodwork Standards; 2014, with Errata (2016).
- B. AWI (QCP) - Quality Certification Program; current edition at www.awiqcp.org.
- C. AWI/AWMA/WI (AWS) - Architectural Woodwork Standards; 2014, with Errata (2016).
- D. AWMA/WI (NAAWS) - North American Architectural Woodwork Standards, U.S. Version 3.1; 2016, with Errata (2017).
- E. BHMA A156.9 - American National Standard for Cabinet Hardware; 2015.
- F. HPVA HP-1 - American National Standard for Hardwood and Decorative Plywood; 2016.
- G. NEMA LD 3 - High-Pressure Decorative Laminates; 2005.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene a preinstallation meeting not less than one week before starting work of this section; require attendance by all affected installers.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate materials, component profiles, fastening methods, jointing details, and accessories.
 - 1. Provide the information required by AWI/AWMA/WI (AWS) or AWMA/WI (NAAWS).
 - 2. Include certification program label.
- C. Product Data: Provide data for hardware accessories.
- D. Samples: Submit actual samples of architectural cabinet construction, minimum 12 inches square, illustrating proposed cabinet, countertop, and shelf unit substrate and finish.
- E. Samples: Submit actual sample items of proposed pulls, hinges, shelf standards, and locksets, demonstrating hardware design, quality, and finish.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



- F. Certificate: Submit labels and certificates required by quality assurance and quality control programs.

1.06 QUALITY ASSURANCE

- A. Fabricator Qualifications: Company specializing in fabricating the products specified in this section with minimum five years of documented experience.
 - 1. Company with at least one project in the past 5 years with value of woodwork within 20 percent of cost of woodwork for this Project.
 - 2. Accredited participant in the specified certification program prior to the commencement of fabrication and throughout the duration of the project.
 - 3. Single Source Responsibility: Provide and install this work from single fabricator.
- B. Quality Certification:
 - 1. Comply with AWI (QCP) woodwork association quality certification service/program in accordance with requirements for work specified in this section: www.awiqcp.org/#sle.
 - 2. Provide labels or certificates indicating that the installed work complies with AWI/AWMAC/WI (AWS) requirements for grade or grades specified.
 - 3. Provide designated labels on shop drawings as required by certification program.
 - 4. Provide designated labels on installed products as required by certification program.
 - 5. Submit certifications upon completion of installation that verifies this work is in compliance with specified requirements.
 - 6. Replace, repair, or rework all work for which certification is refused.

1.07 MOCK-UP

- A. Provide mock-up of typical base cabinet, wall cabinet, and countertop, including hardware, finishes, and plumbing accessories.
- B. See Section 014000 - Quality Requirements for additional requirements.
- C. Locate where directed.
- D. Mock-up may remain as part of the Work.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Protect units from moisture damage.

1.09 FIELD CONDITIONS

- A. During and after installation of custom cabinets, maintain temperature and humidity conditions in building spaces at same levels planned for occupancy.

PART 2 PRODUCTS

2.01 CABINETS

- A. Quality Standard: Custom Grade, in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), unless noted otherwise.
- B. Wood Veneer Faced Cabinet:
 - 1. Exposed Surfaces: HPVA HP-1 Grade A, Red Oak, Walnut, Maple, or Cherry, Architect to confirm cut type with BYU, Architect to confirm matching type with BYU.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



2. Semi-Exposed Surfaces: HPVA HP-1 Grade A, Red Oak, Cherry, Maple, Walnut, Poplar, Pine, Architect to confirm cut type with BYU, Architect to confirm matching type with BYU.
 3. Concealed Surfaces: Manufacturer's option using plywood materials, not particle board or MDF.
 4. All cabinet material shall be a minimum of 3/4" thick.
 5. No particle board or MDF is allowed in the cabinet construction.
- C. Plastic Laminate Faced Cabinets: Not allowed, unless specifically requested by BYU.
- D. Cabinets:
1. Finish - Exposed Exterior Surfaces: Wood.
 2. Finish - Exposed Interior Surfaces: Wood.
 3. Finish - Semi-Exposed Surfaces: Wood
 4. Finish - Concealed Surfaces: Manufacturer's option using plywood materials, not particle board or MDF.
 5. Door and Drawer Front Edge Profiles: Square edge with thin applied band.
 6. Grained Face Layout for Cabinet and Door Fronts: Flush panel.
 - a. Custom Grade: Doors, drawer fronts and false fronts wood grain to run and match vertically within each cabinet unit.
 7. Cabinet Design Series: As indicated on drawings.
 8. Adjustable Shelf Loading: 50 lbs. per sq. ft.
 - a. Deflection: L/144.
 9. Cabinet Doors and Drawer Fronts: As indicated.
 10. Drawer Side Construction: Multiple-dovetailed.
 11. Drawer Construction Technique: Dovetail joints.

2.02 LAMINATE MATERIALS

- A. Manufacturers:
1. Formica Corporation; ____: www.formica.com/#sle.
 2. Panolam Industries International, Inc; Nevamar; ____: www.nevamar.com/#sle.
 3. Wilsonart; ____: www.wilsonart.com/#sle.
- B. Thermally Fused Laminate (TFL): Melamine resin, NEMA LD 3, Type VGL laminate panels.
1. Manufacturers:
 - a. Wilsonart; ____: www.wilsonart.com/#sle.
- C. High Pressure Decorative Laminate (HPDL): NEMA LD 3, types as recommended for specific applications.
- D. Provide specific types as follows:
1. Horizontal Surfaces: HGS, 0.048 inch nominal thickness, through color, color as selected, finish as indicated.
 2. Vertical Surfaces: VGS, 0.028 inch nominal thickness, through color, ____ color, finish as indicated.

2.03 COUNTERTOPS

- A. Countertops are specified in Section 123600.

2.04 ACCESSORIES

- A. Adhesive: Type recommended by AWI/AWMAC to suit application.
- B. Plastic Edge Banding: Extruded PVC, flat shaped; smooth finish; self locking serrated tongue; of width to match component thickness.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



1. Color: As selected by Architect from manufacturer's standard range.
2. Use at all exposed plywood edges.
3. Use at all exposed shelf edges.
4. **Min. 3mm edge band thickness.**

Updated July 12, 2021

- C. Glass: Type A as specified in Section 088000.
- D. Fasteners: Size and type to suit application.
- E. Concealed Joint Fasteners: Threaded steel.
- F. Grommets: Standard plastic, painted metal, or rubber grommets for cut-outs, in color to match adjacent surface.

2.05 HARDWARE

- A. Hardware: BHMA A156.9, types as indicated for quality grade specified.
- B. Adjustable Shelf Supports: Standard back-mounted system using surface mounted metal shelf standards and coordinated cantilevered shelf brackets, satin chrome (Anochrome) finish, for nominal 1 inch spacing adjustments. Maximum spacing between standards shall not exceed 32-inches. Attachment of standard shall be into studs or solid backing. The brackets shall be seismically - anchored to the wall standard. The shelves shall be seismically-anchored to the brackets.
1. Product: KV #85, double-slot standard; KV #185 double-slot bracket manufactured by Knappe and Vogt (KV).
- C. Drawer and Door Pulls: "U" shaped wire pull, steel with satin finish, 4 inch centers.
- D. Sliding Door Pulls: Circular shape for recessed installation, steel with satin finish.
- E. Cabinet Locks: Keyed cylinder, two keys per lock, master keyed, **steel with chrome finish, with manufacturer's lock number stamped on lock face.** **Updated 2/21.**
1. **Use Deadbolt Style. CompX National Lock C8703-MKKD-14A Updated July 12, 2021**
- F. Catches: Magnetic.
- G. Drawer Slides:
1. Type: Full extension.
 2. Static Load Capacity: medium-duty (150-lbs or less), heavy-duty (more than 150-lbs).
 3. Mounting: side-mounting; a screw in each screw hole..
 4. Stops: Integral type.
 5. Manufacturers:
 - a. Accuride International, Inc; Web Address: www accuride.com/#sle.
 - b. Knappe & Vogt Manufacturing Company; Heavy-Duty Drawer Slides: www.knappeandvogt.com/#sle.
 - c. Substitutions: See Section 016000 - Product Requirements.
- H. Hinges: European style concealed self-closing type, steel with satin finish.
1. Manufacturers:
 - a. Hettich America, LP; Web Address: www.hettich.com/#sle.
 - b. Blum, Inc; Web Address: www.blum.com/#sle.
 - c. No more than 24-inches between hinges..
- I. Soft Close Adapter: Concealed, frame-mounted, screw-adjustable damper ; steel with brushed nickel finish.
- J. Sliding Door Track Assemblies: Upper and lower track of satin anodized aluminum, with matching shoe equipped with nylon rollers.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



2.06 FABRICATION

- A. Assembly: Shop assemble cabinets for delivery to site in units easily handled and to permit passage through building openings.
- B. Edging: Fit shelves, doors, and exposed edges with specified edging. Do not use more than one piece for any single length.
- C. Fitting: When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide matching trim for scribing and site cutting.
- D. Plastic Laminate: Apply plastic laminate finish in full uninterrupted sheets consistent with manufactured sizes. Fit corners and joints hairline; secure with concealed fasteners.
 - 1. Cap exposed plastic laminate finish edges with material of same finish and pattern.
- E. Matching Wood Grain: Comply with requirements of quality standard for specified Grade and as follows:
 - 1. Provide center matched panels at each elevation.
 - 2. Provide sequence matching across each elevation.
- F. Mechanically fasten back splash to countertops as recommended by laminate manufacturer at 16 inches on center.
- G. Provide cutouts for plumbing fixtures, inserts, appliances, outlet boxes, and fixtures and fittings. Verify locations of cutouts from on-site dimensions. Prime paint cut edges.

2.07 SHOP FINISHING

- A. Sand work smooth and set exposed nails and screws.
- B. For opaque finishes, apply wood filler in exposed nail and screw indentations and sand smooth.
- C. On items to receive transparent finishes, use wood filler matching or blending with surrounding surfaces and of types recommended for applied finishes.
- D. Finish work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), Section 5 - Finishing for grade specified and as follows:
 - 1. Transparent:
 - a. **System - 5, Varnish, Conversion** **Updated Nov 2021**
 - b. **Stain: As selected by Architect.**
 - c. **Sheen: Semigloss. AWI Sheen Level 50 - 70.**
 - d. **Products:**
 - 1) **MEGAVAR, Water White Conversion Varnish 1M.430X (1A.622 Catalyst) by Lenmar Coatings, www.lenmar-coatings.com. _____.**
 - (a) **Application:**
 - (1) **Two Coats.**
 - (2) **Apply in strict compliance with manufacturer's technical data sheet.**
 - 2) **Substitutions: Section 016000 - Product Requirements.**

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify adequacy of backing and support framing.
- B. Verify location and sizes of utility rough-in associated with work of this section.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



3.02 INSTALLATION

- A. Install work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS) requirements for grade indicated.
- B. Set and secure custom cabinets in place, assuring that they are rigid, plumb, and level.
- C. Use fixture attachments in concealed locations for wall mounted components.
- D. Use concealed joint fasteners to align and secure adjoining cabinet units.
- E. Carefully scribe casework abutting other components, with maximum gaps of 1/32 inch. Do not use additional overlay trim for this purpose.
- F. Countersink anchorage devices at exposed locations. Conceal with solid wood plugs of species to match surrounding wood; finish flush with surrounding surfaces.
- G. Site glaze glass materials using the Interior Dry method specified in Section 088000.

3.03 ADJUSTING

- A. Adjust installed work.
- B. Adjust moving or operating parts to function smoothly and correctly.

3.04 CLEANING

- A. Clean casework, counters, shelves, hardware, fittings, and fixtures.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



**SECTION 072100
THERMAL INSULATION**

PART 1 GENERAL

UPDATED OCTOBER 2021

1.01 SECTION INCLUDES

LOOK FOR CHANGES IN BOLD

- A. Board insulation at cavity wall construction, perimeter foundation wall, underside of floor slabs, over roof deck, over roof sheathing, and exterior wall behind exterior wall finish.
- B. Sound attenuation batt insulation in interior wall construction and above ceilings where indicated on drawings.
- C. Low-density spray foam insulation for filling perimeter window and door shim spaces and crevices in exterior wall and roof.

1.02 RELATED REQUIREMENTS

- A. Section 016116 - Volatile Organic Compound (VOC) Content Restrictions.
- B. Section 031119 - Insulating Concrete Forming: Polystyrene insulation used for forms.
- C. Section 042723 - Cavity Wall Unit Masonry: Masonry walls enclosing insulation.
- D. Section 072119 - Foamed-In-Place Insulation: Plastic foam insulation other than boards.
- E. Section 072123 - Loose Fill Insulation: Granular and bead insulation.
- F. Section 072126 - Blown Insulation: Blown-in, gravity-held fibrous insulation.
- G. Section 072129 - Sprayed Insulation: Sprayed-on, adhered fibrous insulation.
- H. Section 072500 - Weather Barriers: Separate air barrier and vapor retarder materials.
- I. Section 075300 - Elastomeric Membrane Roofing: Installation requirements for board insulation over low slope roof deck specified in this section.
- J. Section 075400 - Thermoplastic Membrane Roofing: Installation requirements for board insulation over low slope roof deck specified in this section.
- K. Section 078400 - Firestopping: Insulation as part of fire-rated through-penetration assemblies.
- L. Section 092116 - Gypsum Board Assemblies: Acoustic insulation inside walls and partitions.

1.03 REFERENCE STANDARDS

- A. ASTM C578 - Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation; 2016.
- B. ASTM C665 - Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing; 2012.
- C. ASTM C1289 - Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board; 2016.
- D. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- E. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2016.
- F. ASTM E136 - Standard Test Method for Behavior of Materials in a Vertical Tube Furnace At 750 Degrees C; 2016a.
- G. ASTM E2357 - Standard Test Method for Determining Air Leakage of Air Barrier Assemblies; 2017.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on product characteristics, performance criteria, and product limitations.
- C. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- D. Manufacturer's Installation Instructions: Include information on special environmental conditions required for installation and installation techniques.

1.05 QUALITY ASSURANCE

- A. Quality Assurance Requirements:
 1. Installer Qualification: Use licensed contractor and installers with minimum of 5 years experience.
 2. Manufacturer Qualification: Use evaluated materials from a single manufacturer regularly engaged in air barrier material manufacture. Use secondary materials approved in writing by primary material manufacturer.
 3. Provide a five year warranty covering materials.

1.06 FIELD CONDITIONS

- A. Do not install insulation adhesives when temperature or weather conditions are detrimental to successful installation.

PART 2 PRODUCTS

2.01 APPLICATIONS

- A. Insulation Under Concrete Slabs: Extruded polystyrene (XPS) board.
- B. Insulation at Perimeter of Foundation: Extruded polystyrene (XPS) board.
- C. Insulation Inside Masonry Cavity Walls: Extruded polystyrene (XPS) board.
- D. Insulation Inside Prefabricated Wall Panels: Polyisocyanurate board.
- E. Insulation Over Metal Stud Framed Walls, Continuous: Extruded polystyrene (XPS) or mineral fiber board.
- F. Insulation in gaps and crevices of exterior wall components, door frames, and widow frames: [Low-density spray polyurethane foam].
- G. Insulation in Metal Framed Walls: Sound attenuation batt insulation with no vapor retarder.
- H. Insulation Above Lay-In Acoustical Ceilings: Batt insulation with no vapor retarder. At locations shown on drawings.
- I. Insulation Over Roof Deck: Polyisocyanurate board.

2.02 FOAM BOARD INSULATION MATERIALS

UPDATED OCT 2021

- A. Expanded Polystyrene (EPS) Board Insulation: **Tapered** insulation. Complies with ASTM C578.
 1. Flame Spread Index (FSI): Class A - 0 to 25, when tested in accordance with ASTM E84.
 2. Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
 3. Board Size: 48 inch by 96 inch.
 4. Board Thickness: Tapered inch.
 5. Board Edges: Square.
 6. Type and Compressive Resistance: Type XI, 5 psi (35 kPa), minimum.
 7. Type and Water Absorption: Type XI, 4.0 percent by volume, maximum, by total immersion.
 8. Type and Thermal Resistance, R-value: Type XI, 3.1 (0.55) per 1 inch thickness at 75 degrees F mean temperature.
 9. Manufacturers:
 - a. AFM Corp; _____: www.r-control.com/#sle.
 - b. Diversifoam Products; _____: www.diversifoam.com
 - c. InsulFoam LLC; InsulFoam _____: www.insulfoam.com
 - d. InsulFoam LLC; R-Tech _____: www.insulfoam.com
 - e. InsulFoam LLC; InsulFoam Below Grade Insulation _____: www.insulfoam.com
 - f. Mar-flex Waterproofing & Building Products; ArmorFoam 25: www.mar-flex.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Extruded Polystyrene (XPS) Board Insulation: Complies with ASTM C578 with natural skin surfaces.
 - 1. Type and Compressive Resistance: Type IV, 25 psi (173 kPa), minimum.
 - 2. Flame Spread Index (FSI): Class A - 0 to 25, when tested in accordance with ASTM E84.
 - 3. Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
 - 4. Type and Thermal Resistance, R-value: Type IV, 5.0 (0.88) per 1 inch thickness at 75 degrees F mean temperature.
 - 5. Board Edges: Square.
 - 6. Type and Water Absorption: Type IV, 0.3 percent by volume, maximum, by total immersion.
 - 7. Manufacturers:
 - a. Dow Chemical Company; STYROFOAM HIGHLOAD 40: www.dowbuildingsolutions.com
 - b. Kingspan Insulation LLC; GreenGuard XPS Type IV, 25 psi: www.kingspan.com
 - c. Owens Corning Corporation; FOAMULAR Extruded Polystyrene (XPS) Insulation: www.ocbuildingspec.com
 - d. Amoco Foam Products
- C. Polyisocyanurate (ISO) Board Insulation: Rigid cellular foam, complying with ASTM C1289.
 - 1. Classifications:
 - a. Type II:
 - 1) Class 1 - Faced with glass fiber reinforced cellulosic felt facers on both major surfaces of core foam.
 - 2) Compressive Strength: Classes 1-2-3, Grade 1 - 16 psi (110 kPa), minimum.
 - 3) Thermal Resistance, R-value: At 1-1/2 inch thick; Class 1, Grades 1-2-3 - 8.4 (1.48) at 75 degrees F.
 - 2. Flame Spread Index (FSI): Class A - 0 to 25, when tested in accordance with ASTM E84.
 - 3. Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
 - 4. Water Vapor Permeance: 1.2 perm, maximum, at 1 inch thickness, and when tested in accordance with ASTM E96/E96M, desiccant method.
 - 5. Board Size: 48 inch by 96 inch.
 - 6. Board Thickness: As Indicated on drawings inch.
 - 7. Board Edges: Square.
 - 8. Manufacturers:
 - a. Carlisle Coatings & Waterproofing, Inc; R2+ Matte: www.carlisleccw.com
 - b. Dow Chemical Company; THERMAX Brand ____: www.dowbuildingsolutions.com
 - c. Hunter Panels; Xci CG: www.hunterpanels.com
 - d. Johns Manville; CI Max: www.jm.com
- D. Glass-Fiber-Reinforced Polyisocyanurate (ISO) Board Insulation with Facers Both Sides and Providing Interior Finish System: Rigid cellular foam, complying with ASTM C1289.
 - 1. Compressive Strength: 16 psi, minimum.
 - 2. Thermal Resistance, R-value: Type I, Class 2, at 1-1/2 inch thick; 9.0 at 75 degrees F.
 - 3. Flame Spread Index (FSI): Class A - 0 to 25, when tested in accordance with ASTM E84.
 - 4. Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
 - 5. Board Size: 48 inch by 96 inch.
 - 6. Board Thickness: As indicated on drawings inch.
 - 7. Board Edges: Square.
 - 8. Manufacturers:
 - a. Dow Chemical Company; THERMAX Heavy Duty: www.dowbuildingsolutions.com.
- E. Polyisocyanurate Board Insulation with Facers Both Sides: Rigid cellular foam, complying with ASTM C1289.
 - 1. Classifications:
 - a. Type II:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 1) Class 1 - Faced with glass fiber reinforced cellulosic felt facers on both major surfaces of core foam.
- 2) Compressive Strength: Classes 1-2-3, Grade 1 - 16 psi (110 kPa), minimum.
- 3) Thermal Resistance, R-value: At 1-1/2 inch thick; Class 1, Grades 1-2-3 - 8.4 (1.48) at 75 degrees F.
2. Flame Spread Index (FSI): Class A - 0 to 25, when tested in accordance with ASTM E84.
3. Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
4. Board Size: 48 inch by 96 inch.
5. Board Thickness: As indicated on drawings inch.
6. Board Edges: Square.
7. Manufacturers:
 - a. Carlisle Coatings & Waterproofing, Inc; R2+ Matte: www.carlisleccw.com
 - b. Dow Chemical Company; THERMAX Brand _____: www.dowbuildingsolutions.com
 - c. GAF; EnergyGuard Polyiso Insulation: www.gaf.com/#sle.
 - d. Hunter Panels; Xci Foil (Class A): www.hunterpanels.com
 - e. Johns Manville; AP Foil-Faced: www.jm.com

2.03 BATT INSULATION MATERIALS

- A. Where batt insulation is indicated, either glass fiber or mineral fiber batt insulation may be used, at Contractor's option.
- B. **Glass Fiber Batt Insulation: Flexible preformed batt or blanket, complying with ASTM C665; friction fit. Update 10/21**
 1. Flame Spread Index: 75 or less, when tested in accordance with ASTM E84.
 2. Smoke Developed Index: 450 or less, when tested in accordance with ASTM E84.
 3. Combustibility: Non-combustible, when tested in accordance with ASTM E136, except for facing, if any.
 4. Formaldehyde Content: Zero.
 5. Thickness: As Indicated on Drawings.
 6. Manufacturers:
 - a. CertainTeed Corporation; _____: www.certainteed.com
 - b. Johns Manville; _____: www.jm.com
 - c. Owens Corning Corporation; EcoTouch PINK FIBERGLAS Insulation: www.ocbuildingspec.com
- C. **Mineral Fiber Batt Insulation: Flexible preformed batt or blanket, complying with ASTM C665; friction fit; unfaced flame spread index of 0 (zero) when tested in accordance with ASTM E84. Updated 10/21**
 1. Flame Spread Index: 25 or less, when tested in accordance with ASTM E84.
 2. Smoke Developed Index: 0 (zero), when tested in accordance with ASTM E84.
 3. Thickness: As Indicated on Drawings.
 4. Manufacturers:
 - a. Johns Manville; MinWool Sound Attenuation Fire Batts: www.jm.com
 - b. Knauf Insulation; EcoBatt Insulation: www.knaufinsulation.com
 - c. ROCKWOOL (ROXUL, Inc); COMFORTBATT: www.rockwool.com
 - d. ROCKWOOL (ROXUL, Inc); AFB: www.rockwool.com
 - e. ROCKWOOL (ROXUL, Inc); AFB evo™: www.rockwool.com
 - f. Thermafiber, Inc; SAFB: www.thermafiber.com
 - g. Thermafiber, Inc; SAFB FF: www.thermafiber.com

2.04 ACCESSORIES

- A. **Insulation Fasteners: Appropriate for purpose intended and approved by roofing manufacturer. Updated 10/21**

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Length as required for thickness of insulation material and penetration of deck substrate.
- B. **Adhesively Attached, Spindle-Type Anchors:**
 1. **Description:** Plate welded to projecting spindle; capable of holding insulation of thickness indicated securely in position indicated with self-locking washer in place; and complying with the following requirements:
 - a. **Plate:** Perforated galvanized carbon-steel sheet, 0.030 in (0.75mm) thick by 2 in (50mm) square.
 - b. **Spindle:** Copper-coated, low carbon steel; fully annealed; 0.105 in (2.62 mm) in diameter; length to suit depth of insulation indicated.
 2. **Manufacturers and Products:**
 - a. **AGM Industries, Inc.:** Perforated TACTOO Insulation Hangers.
 - b. **Gemco;** Spindle Type Perforated Base Insulation Hangers.
- C. **Insulation Retaining Washers:**
 1. **Description:** Self Locking washers formed from 0.016 in (0.4mm) thick galvanized steel sheet with beveled edge for increased stiffness, sized as required to hold insulation securely in place, but not less than 1-1/2 in (38mm) square or in diameter.
 2. **Manufacturers and Products:**
 - a. **AGM Industries, Inc;** RC150
 - b. **AGM Industries, Inc;** SC150
 - c. **Gemco;** R-150.
 - d. **Gemco;** S-150.
- D. **Insulation Standoff:**
 1. **Description:** Spacer fabricated from galvanized mild-steel for fitting over spindle of insulation anchor to maintain air space of 1 in (25 mm) between face of insulation and substrate to which anchor is attached.
 2. **Basis of Design Manufacturer and Product:** Gemco; Clutch Clip.
- E. **Anchor Adhesive:**
 1. **Description:** Product with demonstrated capability to bond insulation anchors securely to substrates indicated without damaging insulation, fasteners, and substrates.
 2. **Manufacturers and Products:**
 - a. **AGM Industries, Inc.;** TACTOO GPA72 Adhesive.
 - b. **Gemco;** Tuff-Bond Hanger Adhesive.
- F. **Polyethylene Vapor-Retarder Membrane:**
 1. **Description:** Fire-retardant reinforced polyethylene vapor-retarder membrane comprised of two outer layers of polyethylene film laminated to an inner reinforcing layer consisting of either a non-woven grid of nylon cord or polyester scrim.
 - a. **Physical Properties:**
 - (1) **Vapor Permeance:** Maximum 0.13 perm (7.4 ng/Pa x s x sq. m); ASTM E 96/E 96M.
 2. **Surface Burning Characteristics:**
 - a. **Flame Spread:** 25 or less.
 - b. **Smoke Developed:** 450 or less.
 3. **Manufacturers and Products:**
 - a. **Raven Industries;** Dura-Skrim 2FR.
 - b. **Reef Industries, Inc.,** Griffolyn Type T-55 FR.
 4. **Accessories:**
 - a. **Sealing Tape:** Asphalt based tape with double-sided adhesive and release liner provided by vapor-retarder manufacturer.
 - (1) **Manufacturers and Products:**

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- (a) Raven Industries; Butyl Seal Tape (TP2BR).
- (b) Reef Industries, Inc., Griffolyn Division; Fab Tape.
- b. Seaming Tape: Pressure-sensitive tape for seaming and bonding joints and penetrations in vapor-retarder membrane provided by vapor-retarder manufacturer.
 - (1) Manufacturers and Products:
 - (a) Raven Industries; Vapor Bond Tape (TVB4).
 - (b) Reef Industries, Inc., Griffolyn Division; Pressure Sensitive Tape.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that substrate, adjacent materials, and insulation materials are dry and that substrates are ready to receive insulation.
- B. Verify substrate surfaces are flat, free of honeycomb, fins, irregularities, or materials or substances that may impede adhesive bond.

3.02 BOARD INSTALLATION AT FOUNDATION PERIMETER

- A. Apply adhesive to back of boards:
 - 1. Three continuous beads per board length.
 - 2. Full bed 1/8 inch thick.
- B. Install boards horizontally on foundation perimeter.
 - 1. Place boards to maximize adhesive contact.
 - 2. Install in running bond pattern.
 - 3. Butt edges and ends tightly to adjacent boards and to protrusions.
- C. Extend boards over expansion joints, unbonded to foundation on one side of joint.
- D. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.
- E. Immediately following application of board insulation, place protective boards over exposed insulation surfaces.
 - 1. Install boards horizontal or vertical from base of foundation to top of insulation.
 - 2. Butt boards tightly, with joints staggered from insulation joints.

3.03 BOARD INSTALLATION AT EXTERIOR WALLS

- A. Apply adhesive to back of boards:
 - 1. Three continuous beads per board length.
 - 2. Full bed 1/8 inch thick.
- B. Install rigid insulation directly to steel studs or exterior grade sheathing at 16 inches on center with manufacturer recommended mechanical fasteners, and tape joints with manufacturer's minimum 4 inch wide sealant tape; comply with ASTM E2357.
- C. Install boards horizontal or vertical on walls.
 - 1. Install in running bond pattern.
 - 2. Butt edges and ends tightly to adjacent boards and to protrusions.
- D. Extend boards over expansion joints, unbonded to wall on one side of joint.
- E. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.

3.04 BOARD INSTALLATION AT CAVITY WALLS

- A. Apply adhesive to back of boards:
 - 1. Three continuous beads per board length.
 - 2. Full bed 1/8 inch thick.
- B. Install boards to fit snugly between wall ties.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Place membrane surface against adhesive.
 2. Place membrane surface facing out, and tape seal board joints.
- C. Install boards horizontal or vertical on walls.
1. Place boards to maximize adhesive contact.
 2. Install in running bond pattern.
 3. Butt edges and ends tightly to adjacent boards and to protrusions.
- D. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.

3.05 BOARD INSTALLATION UNDER CONCRETE SLABS

- A. Place insulation under slabs on grade after base for slab has been compacted.
- B. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.
- C. Prevent insulation from being displaced or damaged while placing vapor retarder and placing slab.

3.06 BOARD INSTALLATION OVER LOW SLOPE ROOF DECK

- A. Board Installation Over Roof Deck, General:
1. See applicable roofing specification section for specific board installation requirements.
 2. Ensure vapor retarder is clean and dry, continuous, and ready for application of roofing system.
 3. Fasten insulation to deck in accordance with roofing manufacturer's written instructions.
 4. Do not apply more insulation than can be covered with roofing in same day.

3.07 BATT INSTALLATION

- A. Install insulation and vapor retarder in accordance with manufacturer's instructions.
- B. Install in exterior wall and roof spaces without gaps or voids. Do not compress insulation.
- C. Trim insulation neatly to fit spaces. Insulate miscellaneous gaps and voids.
- D. Fit insulation tightly in cavities and tightly to exterior side of mechanical and electrical services within the plane of the insulation.

3.08 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Coordination of Tests and Inspections:
 1. Testing and inspection by owner.
 2. Notify owner in writing of schedule for testing and inspection.
 3. Cooperate with owners testing agency.
 4. Allow access to insulation work areas and staging.
 5. Do not cover air barrier and insulation work until tested, inspected, and accepted.

3.09 PROTECTION

- A. Do not permit installed insulation to be damaged prior to its concealment.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 072126
BLOWN INSULATION**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Ceiling and Attic: Blown insulation pneumatically placed into joist cavities.

1.02 RELATED REQUIREMENTS

1.03 REFERENCE STANDARDS

- A. ASTM C764 - Standard Specification for Mineral Fiber Loose-Fill Thermal Insulation; 2017.
- B. ASTM C1015 - Standard Practice for Installation of Cellulosic and Mineral Fiber Loose-Fill Thermal Insulation; 2017.

1.04 SYSTEM DESCRIPTION

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on product characteristics, performance criteria, and limitations.
- C. Certificates: Certify that products of this section meet or exceed specified requirements.
- D. Manufacturer's Installation Instructions: Indicate procedure for preparation and installation.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Blown Insulation:
 - 1. CertainTeed Corporation; _____: www.certainteed.com
 - 2. GreenFiber; _____: www.greenfiber.com
 - 3. Johns Manville; _____: www.jm.com
 - 4. Thermafiber, Inc; _____: www.thermafiber.com

2.02 MATERIALS

- A. Applications: Provide blown insulation in attic and ceiling as indicated on drawings.
- B. Blown Insulation: ASTM C764, fiberglass type, nodulated for pour and bulk for pneumatic placement.
 - 1. Installed Thickness: As indicated on drawings.
- C. Ventilation Baffles: Formed plastic.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that substrate and adjacent materials are dry and ready to receive insulation.
- B. Verify that light fixtures have thermal cut-out device to restrict over-heating in soffit or ceiling spaces.
- C. Verify spaces are unobstructed to allow for proper placement of insulation.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.02 INSTALLATION

- A. Install insulation and ventilation baffle in accordance with ASTM C1015 and manufacturer's instructions.
- B. Place insulation against baffles, and do not impede natural attic ventilation to soffit.
- C. Place against and behind mechanical and electrical services within the plane of insulation.
- D. Completely fill intended spaces leaving no gaps or voids.
- E. Repair and reseal insulation access ports, and refinish to match adjacent work.

3.03 CLEANING

- A. Remove loose insulation residue.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 079200 JOINT SEALANTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Nonsag gunnable joint sealants.
- B. Self-leveling pourable joint sealants.
- C. Joint backings and accessories.
- D. Owner-provided field quality control.

1.02 RELATED REQUIREMENTS

- A. Section 016116 - Volatile Organic Compound (VOC) Content Restrictions: Additional requirements for sealants and primers.
- B. Section 071300 - Sheet Waterproofing: Sealing cracks and joints in waterproofing substrate surfaces using materials specified in this section.
- C. Section 072500 - Weather Barriers: Sealants required in conjunction with air barriers and vapor retarders.
- D. Section 078400 - Firestopping: Firestopping sealants.
- E. Section 079513 - Expansion Joint Cover Assemblies: Sealants forming part of expansion joint cover assemblies.
- F. Section 087100 - Door Hardware: Setting exterior door thresholds in sealant.
- G. Section 092116 - Gypsum Board Assemblies: Sealing acoustical and sound-rated walls and ceilings.
- H. Section 092216 - Non-Structural Metal Framing: Sealing between framing and adjacent construction in acoustical and sound-rated walls and ceilings.
- I. Section 093000 - Tiling: Sealant between tile and plumbing fixtures and at junctions with other materials and changes in plane.
- J. Section 233100 - HVAC Ducts and Casings: Duct sealants.

1.03 REFERENCE STANDARDS

- A. ASTM C661 - Standard Test Method for Indentation Hardness of Elastomeric-Type Sealants by Means of a Durometer; 2015.
- B. ASTM C834 - Standard Specification for Latex Sealants; 2014.
- C. ASTM C919 - Standard Practice for Use of Sealants in Acoustical Applications; 2012.
- D. ASTM C920 - Standard Specification for Elastomeric Joint Sealants; 2014a.
- E. ASTM C1193 - Standard Guide for Use of Joint Sealants; 2016.
- F. ASTM C1248 - Standard Test Method for Staining of Porous Substrate by Joint Sealants; 2008 (Reapproved 2012).
- G. ASTM C1311 - Standard Specification for Solvent Release Sealants; 2014.
- H. ASTM C1521 - Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints; 2013.
- I. ASTM D2240 - Standard Test Method for Rubber Property--Durometer Hardness; 2015.
- J. SWRI (VAL) - SWR Institute Validated Products Directory; Current Listings at www.swrionline.org.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data for Sealants: Submit manufacturer's technical data sheets for each product to be used, that includes the following.
 - 1. Physical characteristics, including movement capability, VOC content, hardness, cure time, and color availability.
 - 2. List of backing materials approved for use with the specific product.
 - 3. Substrates that product is known to satisfactorily adhere to and with which it is compatible.
 - 4. Substrates the product should not be used on.
 - 5. Substrates for which use of primer is required.
 - 6. Installation instructions, including precautions, limitations, and recommended backing materials and tools.
 - 7. Sample product warranty.
 - 8. Certification by manufacturer indicating that product complies with specification requirements.
 - 9. SWRI Validation: Provide currently available sealant product validations as listed by SWRI (VAL) for specified sealants.
- C. Product Data for Accessory Products: Submit manufacturer's technical data sheet for each product to be used, including physical characteristics, installation instructions, and recommended tools.
- D. Color Cards for Selection: Where sealant color is not specified, submit manufacturer's color cards showing standard colors available for selection.
- E. Samples for Verification: Where custom sealant color is specified, obtain directions from Owner and Architect and submit at least two physical samples for verification of color of each required sealant.
- F. Installation Plan: Submit at least four weeks prior to start of installation.
- G. Field Quality Control Plan: Submit at least two weeks prior to start of installation.
- H. Installation Log: Submit filled out log for each length or instance of sealant installed.
- I. Field Quality Control Log: Submit filled out log for each length or instance of sealant installed, within 10 days after completion of inspections/tests; include bagged test samples and photographic records, if any.

1.05 QUALITY ASSURANCE

- A. Maintain one copy of each referenced document covering installation requirements on site.
- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- C. Installer Qualifications: Company specializing in performing the work of this section and with at least three years of documented experience.
- D. Installation Plan: Include schedule of sealed joints, including the following.
 - 1. Approximate date of installation, for evaluation of thermal movement influence.
- E. Field Quality Control Plan:
 - 1. Visual inspection of entire length of sealant joints.
 - 2. Destructive field adhesion testing of sealant joints, except interior sealant joints.
 - a. For each different sealant and substrate combination, allow for one test every 100 feet in the first 1000 linear feet, and one test per 1000 linear feet thereafter, or once per floor on each elevation.
 - b. If any failures occur in the first 1000 linear feet, continue testing at frequency of one test per 500 linear feet at no extra cost to Owner.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.06 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Correct defective work within a five year period after Date of Substantial Completion.
- C. Warranty: Include coverage for installed sealants and accessories that fail to achieve watertight seal, exhibit loss of adhesion or cohesion, or do not cure.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Non-Sag Sealants: Permits application in joints on vertical surfaces without sagging or slumping.
 - 1. Dow Chemical Company; _____: consumer.dow.com/en-us/industry/ind-building-construction.html
 - 2. Sika Corporation; _____: www.usa-sika.com
 - 3. Tremco Commercial Sealants & Waterproofing; _____: www.tremcosealants.com
- B. Self-Leveling Sealants: Pourable or self-leveling sealant that has sufficient flow to form a smooth, level surface when applied in a horizontal joint.
 - 1. Dow Chemical Company; _____: consumer.dow.com/en-us/industry/ind-building-construction.html
 - 2. Sika Corporation; _____: www.usa-sika.com
 - 3. Tremco Commercial Sealants & Waterproofing; _____: www.tremcosealants.com

2.02 JOINT SEALANT APPLICATIONS

- A. Scope:
 - 1. Exterior Joints: Seal open joints, whether or not the joint is indicated on drawings, unless specifically indicated not to be sealed. Exterior joints to be sealed include, but are not limited to, the following items.
 - a. Wall expansion and control joints.
 - b. Joints between door, window, and other frames and adjacent construction.
 - c. Joints between different exposed materials.
 - d. Openings below ledge angles in masonry.
 - e. Other joints indicated below.
 - 2. Interior Joints: Do not seal interior joints unless specifically indicated to be sealed. Interior joints to be sealed include, but are not limited to, the following items.
 - a. Joints between door, window, and other frames and adjacent construction.
 - b. In sound-rated wall and ceiling assemblies, gaps at electrical outlets, wiring devices, piping, and other openings; between wall/ceiling and other construction; and other flanking sound paths.
 - 1) Exception: Such gaps and openings in gypsum board and plaster finished stud walls and suspended ceilings.
 - 2) Exception: Open-, membrane-, and through-penetrations in sound-rated assemblies that are also fire-rated assemblies.
 - c. Other joints indicated below.
 - 3. Do not seal the following types of joints.
 - a. Intentional weepholes in masonry.
 - b. Joints indicated to be treated with manufactured expansion joint cover or some other type of sealing device.
 - c. Joints where sealant is specified to be provided by manufacturer of product to be sealed.
 - d. Joints where installation of sealant is specified in another section.
 - e. Joints between suspended panel ceilings/grid and walls.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Exterior Joints: Use non-sag non-staining silicone sealant, unless otherwise indicated.
- C. Interior Joints: Use non-sag polyurethane sealant, paintable, unless otherwise indicated.

2.03 JOINT SEALANTS - GENERAL

- A. Sealants and Primers: Provide products with levels of volatile organic compound (VOC) content as indicated in Section 016116.
- B. Colors: As indicated on drawings.

2.04 NONSAG JOINT SEALANTS

- A. Non-Staining Silicone Sealant: ASTM C920, Grade NS, Uses M and A; not expected to withstand continuous water immersion or traffic.
 - 1. Color: To be selected by Architect from manufacturer's standard range.
 - 2. Manufacturers:
 - a. Dow Chemical Company; 790 Silicone Building Sealant: consumer.dow.com/en-us/industry/ind-building-construction.html
 - b. Dow Chemical Company; 795 Silicone Building Sealant: consumer.dow.com/en-us/industry/ind-building-construction.html
 - c. Sika Corporation; Sikasil WS-290: www.usa-sika.com
 - d. Sika Corporation; Sikasil WS-295: www.usa-sika.com
 - e. Tremco Commercial Sealants & Waterproofing; Spectrem 1: www.tremcosealants.com
 - f. Tremco Commercial Sealants & Waterproofing; Spectrem 2: www.tremcosealants.com
 - g. Substitutions: See Section 016000 - Product Requirements.
- B. Type ____ - Hybrid Urethane Sealant: ASTM C920, Grade NS, Uses M and A; single component; not expected to withstand continuous water immersion or traffic.
 - 1. Movement Capability: Plus and minus 35 percent, minimum.
 - 2. Color: To be selected by Architect from manufacturer's standard range.
 - 3. Manufacturers:
 - a. Substitutions: See Section 016000 - Product Requirements.
- C. Polyurethane Sealant: ASTM C920, Grade NS, Uses M and A; single or multi-component; not expected to withstand continuous water immersion or traffic.
 - 1. Movement Capability: Plus and minus 25 percent, minimum.
 - 2. Hardness Range: 20 to 35, Shore A, when tested in accordance with ASTM C661.
 - 3. Color: To be selected by Architect from manufacturer's standard range.
 - 4. Manufacturers:
 - a. Sherwin-Williams Company; Stampede-1/-TX Polyurethane Sealant: www.sherwin-williams.com
 - b. Tremco Commercial Sealants & Waterproofing; Dymeric 240 FC: www.tremcosealants.com

2.05 SELF-LEVELING SEALANTS

- A. Self-Leveling Silicone Sealant: ASTM C920, Grade P, Uses M and A; single-component, explicitly approved by manufacturer for traffic exposure when recessed below traffic surface; not expected to withstand continuous water immersion.
 - 1. Movement Capability: Plus 100 percent, minus 50 percent, minimum.
 - 2. Hardness Range: 0 to 15, Shore A, when tested in accordance with ASTM C661.
 - 3. Color: To be selected by Architect from manufacturer's standard range.
 - 4. Service Temperature Range: Minus 40 to 180 degrees F.
 - 5. Manufacturers:
 - a. Sika Corporation; Sikasil 728SL: www.usa-sika.com
 - b. Tremco Commercial Sealants & Waterproofing; Spectrem 900SL: www.tremcosealants.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.06 ACCESSORIES

- A. Backer Rod: Cylindrical open cellular foam rod compatible with specific sealant used, and recommended by backing and sealant manufacturers for specific application.
 - 1. Open Cell: 40 to 50 percent larger in diameter than joint width.
- B. Backing Tape: Self-adhesive polyethylene tape with surface that sealant will not adhere to and recommended by tape and sealant manufacturers for specific application.
- C. Masking Tape: Self-adhesive, nonabsorbent, non-staining, removable without adhesive residue, and compatible with surfaces adjacent to joints and sealants.
- D. Joint Cleaner: Non-corrosive and non-staining type, type recommended by sealant manufacturer; compatible with joint forming materials.
- E. Primers: Type recommended by sealant manufacturer to suit application; non-staining.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joints are ready to receive work.
- B. Verify that backing materials are compatible with sealants.
- C. Verify that backer rods are of the correct size.

3.02 PREPARATION

- A. Remove loose materials and foreign matter that could impair adhesion of sealant.
- B. Clean joints, and prime as necessary, in accordance with manufacturer's instructions.
- C. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.
- D. Mask elements and surfaces adjacent to joints from damage and disfigurement due to sealant work; be aware that sealant drips and smears may not be completely removable.
- E. Concrete Floor Joints That Will Be Exposed in Completed Work: Test joint filler in inconspicuous area to verify that it does not stain or discolor slab.

3.03 INSTALLATION

- A. Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
- B. Perform installation in accordance with ASTM C1193.
- C. Perform acoustical sealant application work in accordance with ASTM C919.
- D. Measure joint dimensions and size joint backers to achieve width-to-depth ratio, neck dimension, and surface bond area as recommended by manufacturer, except where specific dimensions are indicated.
- E. Install sealant free of air pockets, foreign embedded matter, ridges, and sags, and without getting sealant on adjacent surfaces.
- F. Do not install sealant when ambient temperature is outside manufacturer's recommended temperature range, or will be outside that range during the entire curing period, unless manufacturer's approval is obtained and instructions are followed.
- G. Nonsag Sealants: Tool surface concave, unless otherwise indicated; remove masking tape immediately after tooling sealant surface.
- H. Concrete Floor Joint Filler: After full cure, shave joint filler flush with top of concrete slab.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements for additional requirements.
- B. Perform field quality control inspection/testing as specified in PART 1 under QUALITY ASSURANCE article.
- C. Non-Destructive Adhesion Testing: If there are any failures in first 100 linear feet, notify Architect immediately.
- D. Destructive Adhesion Testing: If there are any failures in first 1000 linear feet, notify Architect immediately.
- E. Remove and replace failed portions of sealants using same materials and procedures as indicated for original installation.
- F. Repair destructive test location damage immediately after evaluation and recording of results.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____

SECTION 079513
EXPANSION JOINT COVER ASSEMBLIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Expansion joint cover assemblies for floor, wall, ceiling, soffit, and roof surfaces.

1.02 RELATED REQUIREMENTS

- A. Section 03 1000 - Concrete Forming and Accessories: Placement of joint cover assembly frames in formwork.
- B. Section 04 2000 - Unit Masonry: Placement of joint cover assembly frames in masonry.
- C. Section 04 2613 - Masonry Veneer: Placement of joint cover assembly frames in masonry.
- D. Section 05 5000 - Metal Fabrications: Custom fabricated metal expansion and control joint devices.
- E. Section 07 6200 - Sheet Metal Flashing and Trim: Roof expansion and control joint covers.
- F. Section 07 7100 - Roof Specialties: Roof expansion and control joint covers.
- G. Section 07 9100 - Preformed Joint Seals: Sealing expansion and control joints using preformed joint seals.
- H. Section 07 9200 - Joint Sealants: Sealing expansion and control joints using gunnable and pourable sealants.
- I. Section 09 2116 - Gypsum Board Assemblies: Gypsum board control joint trim.
- J. Section 09 2116 - Gypsum Board Assemblies: Placement of expansion joint assemblies in gypsum board walls and ceilings.
- K. Section 09 5100 - Acoustical Ceilings: Expansion joint assemblies in suspended ceiling grids.

1.03 REFERENCE STANDARDS

- A. ASTM B221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2020.
- B. ASTM B221M - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2013.
- C. ASTM B308/B308M - Standard Specification for Aluminum-Alloy 6061-T6 Standard Structural Profiles; 2020.
- D. ASTM B455/B455M - Standard Specification for Copper-Zinc-Lead Alloy (Leaded-Brass) Extruded Shapes; 2020.
- E. ASTM E1966 - Standard Test Method for Fire-Resistive Joint Systems; 2015 (Reapproved 2019).
- F. ITS (DIR) - Directory of Listed Products; current edition.
- G. UL (DIR) - Online Certifications Directory; Current Edition.
- H. UL 2079 - Standard for Tests for Fire Resistance of Building Joint Systems; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Installation Templates: For frames and anchors to be embedded in concrete or masonry, furnish templates to relevant installers; include installation instructions and tolerances.

1.05 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide joint assembly profiles, profile dimensions, anchorage devices, available colors and finish, and _____.
- C. Shop Drawings: Indicate joint and splice locations, miters, layout of the work, affected adjacent construction, anchorage locations, and _____.
- D. Samples: Submit two samples 3" inch (____ mm) long, illustrating profile, dimension, color, and finish selected.
- E. Manufacturer's Installation Instructions: Indicate rough-in sizes and required tolerances for item placement.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 01 6000 for additional provisions.
 - 2. Extra Resilient Joint Filler: ____ ft (____ mm) length and any special tools required for installation.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Expansion Joint Cover Assemblies:
 - 1. Architectural Art Mfg, Inc; _____: www.archart.com/#sle.
 - 2. Construction Specialties, Inc; _____: www.c-sgroup.com/#sle.
 - 3. EMSEAL Joint Systems, Ltd; _____: www.emseal.com/#sle.
 - 4. Inpro; _____: www.inprocorp.com/#sle.
 - 5. MM Systems Corp; _____: www.mmsystemscorp.com/#sle.
 - 6. Nystrom, Inc; _____: www.nystrom.com/#sle.
 - 7. Pecora Corporation; _____: www.pecora.com/#sle.
 - 8. SITURA Inc; _____: www.situra.com/#sle.
 - 9. Watson Bowman Acme Corporation; _____: www.watsonbowmanacme.com/#sle.
 - 10. Substitutions: See Section 01 6000 - Product Requirements.

2.02 EXPANSION JOINT COVER ASSEMBLY APPLICATIONS

- A. Interior Floor Joints Subject to Seismic Movement:
 - 1. Manufacturers:
 - a. Balco, Inc; HDTH Heavy-Duty Twin Hinge Floor Cover: www.balcousa.com/#sle.
 - b. Construction Specialties, Inc; Allway Seismic Metal Floor Covers: www.c-sgroup.com/#sle.
 - c. Watson Bowman Acme Corporation; Wabo Allure: www.watsonbowmanacme.com/#sle.
 - d. _____.
 - e. Substitutions: See Section 01 6000 - Product Requirements.
- B. Interior Wall/Ceiling Joints Subject to Thermal Movement:
 - 1. Manufacturers:
 - a. Balco, Inc; WD Wall and Ceiling Snap-On Joint Cover: www.balcousa.com/#sle.
 - b. Construction Specialties, Inc; Allway Standard Wall and Ceiling Covers: www.c-sgroup.com/#sle.
 - c. Substitutions: See Section 01 6000 - Product Requirements.

- C. Interior Non-Fire-Rated Wall/Ceiling Joints Subject to Seismic Movement:
 - 1. Manufacturers:
 - a. Balco, Inc; CM Wall Expansion Joint Cover: www.balcousa.com/#sle.
 - b. Construction Specialties, Inc; Flush Seismic Wall and Ceiling Covers: www.c-sgroup.com/#sle.
 - c. Substitutions: See Section 01 6000 - Product Requirements.

- D. Interior Fire-Rated Wall/Ceiling/Floor Joints Subject to Thermal Movement:
 - 1. Manufacturers:
 - a. Construction Specialties, Inc; Fire Barriers: www.c-sgroup.com/#sle.
 - b. Substitutions: See Section 01 6000 - Product Requirements.

- E. Interior/Exterior Fire-Rated Wall Joints Subject to Thermal Movement:
 - 1. Manufacturers:
 - a. EMSEAL Joint Systems, Ltd; Emshield WFR2 System: www.emseal.com/#sle.
 - b. Substitutions: See Section 01 6000 - Product Requirements.

- F. Exterior Wall Joints Subject to Thermal Movement:
 - 1. Manufacturers:
 - a. Balco, Inc; Exterior Wall, Elastomeric Face Seal System (FCWW): www.balcousa.com/#sle.
 - b. Construction Specialties, Inc; Exterior Wall Covers: www.c-sgroup.com/#sle.
 - c. EMSEAL Joint Systems, Ltd; BG System: www.emseal.com/#sle.
 - d. SITURA Inc; RedLINE Waterproof Expansion Joint Systems: www.situra.com/#sle.
 - e. Substitutions: See Section 01 6000 - Product Requirements.

- G. Exterior Wall Joints Subject to Seismic Movement:
 - 1. Manufacturers:
 - a. Balco, Inc; CMX Wall Cover: www.balcousa.com/#sle.
 - b. SITURA Inc; RedLINE Waterproof Expansion Joint Systems: www.situra.com/#sle.
 - c. Substitutions: See Section 01 6000 - Product Requirements.

- H. Exterior Roof Bellows with Metal Flange Expansion Joint Covers:
 - 1. Manufacturers:
 - a. Balco, Inc; Roof Bellows, Aluminum Flanges (BRBA): www.balcousa.com/#sle.
 - b. _____.
 - c. Substitutions: See Section 01 6000 - Product Requirements.

- I. Exterior Roof Expansion Joint Covers:
 - 1. Manufacturers:
 - a. Balco, Inc; Roof Metal Plate System, with Canted Curb (LPR): www.balcousa.com/#sle.
 - b. SITURA Inc; RedLINE Waterproof Expansion Joint Systems: www.situra.com/#sle.
 - c. _____.
 - d. Substitutions: See Section 01 6000 - Product Requirements.

- J. Below Grade, Blind-Side and Positive-Side, and Under-Slab Joints:
 - 1. Manufacturers:
 - a. EMSEAL Joint Systems, Ltd; BG System: www.emseal.com/#sle.
 - b. SITURA Inc; RedLINE Waterproof Expansion Joint Systems: www.situra.com/#sle.
 - c. _____.
 - d. Substitutions: See Section 01 6000 - Product Requirements.

2.03 EXPANSION JOINT COVER ASSEMBLIES

- A. Expansion Joint Cover Assemblies - General: Factory-fabricated and assembled; designed to completely fill joint openings, sealed to prevent passage of air, dust, water, smoke; suitable for traffic expected.
 - 1. Joint Dimensions and Configurations: As indicated on drawings.
 - 2. Joint Cover Sizes: Selected to suit joint width and configuration, based on manufacturer's published recommendations and limitations.
 - 3. Joint Cover Styles: As indicated on drawings.
 - 4. Joint Movement Capability: If not indicated, provide minimum plus/minus 25 percent joint movement capability.
 - 5. Lengths: Provide covers in full lengths required; avoid splicing wherever possible.
 - 6. Anchors, Fasteners, and Fittings: Provided by cover manufacturer.
- B. Floor Joint Covers: Coordinate with indicated floor coverings.
 - 1. If floor covering is not indicated, obtain instructions from Architect before proceeding.
 - 2. If style is not indicated, provide extruded aluminum frame both sides, resilient seals, and minimize exposed metal.
- C. Resilient Seal Type Covers: Having flat exposed surface without crevices that could collect dirt; designed to withstand expected movement without extrusion of seal from joint assembly; for floors, provide style that is flush with top of floor covering; for exterior joints, weathertight.
- D. Sliding Cover Plate Type Covers: Provide plate with beveled edges and neat fit that does not collect dirt.
- E. Covers in Gypsum Board Assemblies: Provide style with anchoring wings that can be completely covered by joint compound.
- F. Covers in Fire Rated Assemblies: Provide cover assembly having fire rating equivalent to that of assembly into which it is installed.
 - 1. Acceptable Evaluation Agencies: UL (DIR) and ITS (DIR).

2.04 MATERIALS

- A. Extruded Aluminum: ASTM B221 (ASTM B221M), 6063 alloy, T6 temper; or ASTM B308/B308M, 6061 alloy, T6 temper.
 - 1. Exposed Finish Outdoors: Natural anodized.
 - 2. Exposed Finish at Floors: Mill finish or natural anodized.
 - 3. Exposed Finish at Walls and Ceilings: Natural anodized.
- B. Extruded Bronze: ASTM B455/B455M, UNS C38500 architectural bronze.
 - 1. Exposed Finish Outdoors: _____.
 - 2. Exposed Finish at Floors: _____.
 - 3. Exposed Finish at Walls and Ceilings: _____.
- C. Resilient Seals:
 - 1. For Ceilings: Any resilient material, flush, pleated, or hollow gasket.
 - 2. For Pedestrian Traffic Applications: EPDM rubber, Neoprene, or Santoprene; no PVC; Shore A hardness of 40 to 50 Durometer.
 - 3. For Vehicular Traffic Applications: EPDM rubber, Neoprene, or Santoprene; no PVC; Shore A hardness of 40 to 50 Durometer.
 - 4. Color: Gray.
- D. Anchors and Fasteners: As recommended by cover manufacturer.
- E. Ferrous Metal Anchors: Galvanized where embedded in concrete or in contact with cementitious materials.
- F. Threaded Fasteners: Aluminum.
- G. Backing Paint for Aluminum Components in Contact with Cementitious Materials: Asphaltic type.

2.05 ACCESSORIES

- A. Resilient Fire Barrier: For use with metal expansion joint covers and elastomeric seals without use of mechanical fasteners, with fire rating in accordance with surrounding construction performance capabilities.
 - 1. Application: Floor.
 - 2. Fire Resistance Rating: 2-hour, in accordance with ASTM E1966 and UL 2079.
 - 3. Joint Opening: 3/8 inch (9.5 mm), nominal.
 - 4. Manufacturers:
 - a. Balco, Inc; Expansion Joint Fire Barrier, Floor/Roof - MetaBlock, 2 Hour (MBF2H): www.balcousa.com/#sle.
 - b. Substitutions: See Section 01 6000 - Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joint preparation and dimensions are acceptable and in accordance with manufacturer's requirements.
- B. Verify that frames and anchors installed by others are in correct locations and suitable for installation of remainder of assembly.

3.02 INSTALLATION

- A. Install components and accessories in accordance with manufacturer's instructions.
- B. Align work plumb and level, flush with adjacent surfaces.
- C. Rigidly anchor to substrate to prevent misalignment.

3.03 PROTECTION

- A. Do not permit traffic over unprotected floor joint surfaces.
- B. Provide strippable coating to protect finish surface.

END OF SECTION



SECTION 081113
HOLLOW METAL DOORS AND FRAMES
UPDATED MAY 2022

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Non-fire-rated hollow metal doors and frames.
- B. Hollow metal frames for wood doors.
- C. Fire-rated hollow metal doors and frames.
- D. Thermally insulated hollow metal doors with frames.
- E. Sound-rated hollow metal doors and frames.
- F. Hollow metal borrowed lites glazing frames.
- G. Accessories, including glazing, louvers, and matching panels.

1.02 RELATED REQUIREMENTS

- A. Section 087100 - Door Hardware.
- B. Section 088000 - Glazing: Glass for doors and borrowed lites.
- C. Section 099113 - Exterior Painting: Field painting.
- D. Section 099123 - Interior Painting: Field painting.

1.03 ABBREVIATIONS AND ACRONYMS

- A. ANSI - American National Standards Institute.
- B. ASCE - American Society of Civil Engineers.
- C. HMMA - Hollow Metal Manufacturers Association.
- D. NAAMM - National Association of Architectural Metal Manufacturers.
- E. NFPA - National Fire Protection Association.
- F. SDI - Steel Door Institute.
- G. UL - Underwriters Laboratories.

1.04 REFERENCE STANDARDS

- A. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.
- B. ANSI/SDI A250.4 - Test Procedure and Acceptance Criteria for Physical Endurance for Steel Doors, Frames and Frame Anchors; 2011.
- C. ANSI/SDI A250.8 - Specifications for Standard Steel Doors and Frames (SDI-100); 2014.
- D. ANSI/SDI A250.10 - Test Procedure and Acceptance Criteria for Prime Painted Steel Surfaces for Steel Doors and Frames; 2011.
- E. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2015.
- F. ASTM A1008/A1008M - Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable; 2016.
- G. ASTM A1011/A1011M - Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength; 2015.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- H. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009 (Reapproved 2016).
- I. ASTM E413 - Classification for Rating Sound Insulation; 2016.
- J. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2017.
- K. NAAMM HMMA 840 - Guide Specifications for Installation and Storage of Hollow Metal Doors and Frames; 2007.
- L. NAAMM HMMA 861 - Guide Specifications for Commercial Hollow Metal Doors and Frames; 2006.
- M. NFPA 80 - Standard for Fire Doors and Other Opening Protectives; 2016.
- N. NFPA 105 - Standard for Smoke Door Assemblies and Other Opening Protectives; 2016.
- O. NFPA 252 - Standard Methods of Fire Tests of Door Assemblies; 2012.
- P. SDI 117 - Manufacturing Tolerances for Standard Steel Doors and Frames; 2013.
- Q. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.
- R. UL 10C - Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.
- S. UL 1784 - Standard for Air Leakage Tests of Door Assemblies; Current Edition, Including All Revisions.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Materials and details of design and construction, hardware locations, reinforcement type and locations, anchorage and fastening methods, and finishes.
- C. Shop Drawings: Details of each opening, showing elevations, glazing, frame profiles, and any indicated finish requirements.
- D. Manufacturer's Qualification Statement.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section, with not less than three years documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years of documented experience.
- C. Maintain at project site copies of reference standards relating to installation of products specified.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Comply with NAAMM HMMA 840 or ANSI/SDI A250.8 (SDI-100) in accordance with specified requirements.
- B. Protect with resilient packaging; avoid humidity build-up under coverings; prevent corrosion and adverse effects on factory applied painted finish.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Hollow Metal Doors and Frames:
 - 1. Ceco Door, an Assa Abloy Group company; _____: www.assaabloydss.com
 - 2. Curries, an Assa Abloy Group company; _____: www.assaabloydss.com
 - 3. Steelcraft, an Allegion brand; _____: www.allegion.com
 - 4. All hardware locations to be per CECO standard locations.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.02 DESIGN CRITERIA

- A. Requirements for Hollow Metal Doors and Frames:
 - 1. Steel used for fabrication of doors and frames shall comply with one or more of the following requirements; Galvannealed steel conforming to ASTM A653/A653M, cold-rolled steel conforming to ASTM A1008/A1008M, or hot-rolled pickled and oiled (HRPO) steel conforming to ASTM A1011/A1011M, Commercial Steel (CS) Type B for each.
 - 2. Accessibility: Comply with ICC A117.1 and ADA Standards.
 - 3. Door Edge Profile: Manufacturers standard for application indicated.
 - 4. Typical Door Face Sheets: Flush.
 - 5. Zinc Coating for Typical Interior and/or Exterior Locations: Provide metal components zinc-coated (galvanized) and/or zinc-iron alloy-coated (galvannealed) by the hot-dip process in accordance with ASTM A653/A653M, with manufacturer's standard coating thickness, unless noted otherwise for specific hollow metal doors and frames.
 - a. Based on SDI Standards: Provide at least A40/ZF120 (galvannealed) when necessary, coating not required for typical interior door applications, and at least A60/ZF180 (galvannealed) for corrosive locations.
- B. Hollow Metal Panels: Same construction, performance, and finish as doors.
- C. Combined Requirements: If a particular door and frame unit is indicated to comply with more than one type of requirement, comply with the specified requirements for each type; for instance, an exterior door that is also indicated as being sound-rated must comply with the requirements specified for exterior doors and for sound-rated doors; where two requirements conflict, comply with the most stringent.

2.03 HOLLOW METAL DOORS

- A. Door Finish: Architect to confirm finish with BYU.
- B. Exterior Doors: Thermally insulated.
 - 1. Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - a. Level 3 - Extra Heavy-duty.
 - b. Physical Performance Level A, 1,000,000 cycles; in accordance with ANSI/SDI A250.4.
 - c. Model 1 - Full Flush.
 - d. Door Face Metal Thickness: 16 gage, 0.053 inch, minimum.
 - e. Zinc Coating: A60/ZF180 galvannealed coating; ASTM A653/A653M.
 - 2. Door Core Material: Manufacturers standard core material/construction and in compliance with requirements.
 - 3. Door Thickness: 1-3/4 inch, nominal.
 - 4. Weatherstripping: Refer to Section 087100.
- C. Interior Doors, Non-Fire Rated:
 - 1. Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - a. Level 2 - Heavy-duty.
 - b. Physical Performance Level B, 500,000 cycles; in accordance with ANSI/SDI A250.4.
 - c. Model 1 - Full Flush.
 - d. Door Face Metal Thickness: 18 gage, 0.042 inch, minimum.
 - 2. Door Core Material: Manufacturers standard core material/construction and in compliance with requirements.
 - 3. Door Thickness: 1-3/4 inch, nominal.
- D. Fire-Rated Doors:
 - 1. Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - a. Level 2 - Heavy-duty.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- b. Physical Performance Level B, 500,000 cycles; in accordance with ANSI/SDI A250.4.
- c. Model 1 - Full Flush.
- d. Door Face Metal Thickness: 18 gage, 0.042 inch, minimum.
- 2. Fire Rating: As indicated on Door Schedule, tested in accordance with UL 10C and NFPA 252 ("positive pressure fire tests").
- 3. Provide units listed and labeled by UL (DIR).
 - a. Attach fire rating label to each fire rated unit.
- 4. Smoke and Draft Control Doors (Indicated with letter "S" on Drawings and/or Door Schedule): Self-closing or automatic closing doors in accordance with NFPA 80 and NFPA 105, with fire-resistance-rated wall construction rated the same or greater than the fire-rated doors, and the following;
 - a. Maximum Air Leakage: 3.0 cfm/sq ft of door opening at 0.10 inch w.g. pressure, when tested in accordance with UL 1784 at both ambient and elevated temperatures.
 - b. Gasketing: Provide gasketing or edge sealing as necessary to achieve leakage limit.
 - c. Label: Include the "S" label on fire-rating label of door.
- 5. Door Core Material: Manufacturers standard core material/construction in compliance with requirements.
- 6. Door Thickness: 1-3/4 inch, nominal.
- E. Sound-Rated Interior Doors:
 - 1. Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - a. Level 2 - Heavy-duty.
 - b. Physical Performance Level B, 500,000 cycles; in accordance with ANSI/SDI A250.4.
 - c. Model 1 - Full Flush.
 - d. Door Face Metal Thickness: 18 gage, 0.042 inch, minimum.
 - 2. Sound Transmission Class (STC) Rating of Door and Frame Assembly: STC of 35, minimum, calculated in accordance with ASTM E413, and tested in accordance with ASTM E90.
 - 3. Door Thickness: 1-3/4 inch.
 - 4. Opening Force of Sound-Rated Doors, Non-Fire Rated: 5 lbs., maximum, in compliance with ADA Standards.

2.04 HOLLOW METAL FRAMES

- A. Comply with standards and/or custom guidelines as indicated for corresponding door in accordance with applicable door frame requirements.
- B. Frame Finish: Same as hollow metal door.
- C. Exterior Door Frames: Face welded type.
 - 1. Galvanizing: Components hot-dipped zinc-iron alloy-coated (galvannealed) in accordance with ASTM A653/A653M, with A40/ZF120 coating.
 - 2. **Frame Metal Thickness: 14 gage, 0.067 inch, minimum. Updated May 2022**
 - 3. Weatherstripping: Separate, see Section 087100.
- D. Interior Door Frames, Non-Fire Rated: Face welded type.
 - 1. **Frame Metal Thickness: 16 gage, 0.053 inch, minimum. Updated May 2022**
 - 2. Knock-down door frames are allowed in remodeling applications but not in new construction.
- E. Door Frames, Fire-Rated: Face welded type.
 - 1. Fire Rating: Same as door, labeled.
 - 2. **Frame Metal Thickness: 16 gage, 0.053 inch, minimum. Updated May 2022**
- F. Sound-Rated Door Frames: Face welded type.
 - 1. **Frame Metal Thickness: 16 gage, 0.053 inch, minimum. Updated May 2022**
- G. Frames for Wood Doors: Comply with frame requirements in accordance with corresponding door.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- H. Mullions for Pairs of Doors: Fixed, except where removable is indicated, with profile similar to jambs.
- I. Borrowed Lites Glazing Frames: Construction and face dimensions to match door frames, and as indicated on drawings.
- J. Frames in Masonry Walls: Size to suit masonry coursing with head member 4 inch high to fill opening without cutting masonry units.
- K. Frames Wider than 48 inches: Reinforce with steel channel fitted tightly into frame head, flush with top.
- L. Frames Installed Back-to-Back: Reinforce with steel channels anchored to floor and overhead structure.

2.05 FINISHES

- A. Primer: Rust-inhibiting, complying with ANSI/SDI A250.10, door manufacturer's standard.

2.06 ACCESSORIES

- A. Glazing: As specified in Section 088000, factory installed.
- B. Astragals for Double Doors: Specified in Section 087100.
- C. Mechanical Fasteners for Concealed Metal-to-Metal Connections: Self-drilling, self-tapping, steel with electroplated zinc finish.
- D. Grout for Frames: Portland cement grout with maximum 4 inch slump for hand troweling; thinner pumpable grout is prohibited.
- E. Silencers: Resilient rubber, fitted into drilled hole; provide three on strike side of single door, three on center mullion of pairs, and two on head of pairs without center mullions.
- F. Temporary Frame Spreaders: Provide for factory- or shop-assembled frames.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that opening sizes and tolerances are acceptable.
- C. Verify that finished walls are in plane to ensure proper door alignment.

3.02 INSTALLATION

- A. Install doors and frames in accordance with manufacturer's instructions and related requirements of specified door and frame standards or custom guidelines indicated.
- B. Install fire rated units in accordance with NFPA 80.
- C. Coordinate frame anchor placement with wall construction.
- D. Grout frames in masonry construction, using hand trowel methods; brace frames so that pressure of grout before setting will not deform frames.
- E. Install door hardware as specified in Section 087100.
- F. Comply with glazing installation requirements of Section 088000.
- G. Coordinate installation of electrical connections to electrical hardware items.
- H. Touch up damaged factory finishes in accordance with the painting sections of this specification.

3.03 TOLERANCES

- A. Clearances Between Door and Frame: Comply with related requirements of specified frame standards or custom guidelines indicated in accordance with SDI 117 or NAAMM HMMA 861.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



B. Maximum Diagonal Distortion: 1/16 inch measured with straight edge, corner to corner.

3.04 ADJUSTING

- A. Adjust for smooth and balanced door movement.
- B. Adjust sound control doors so that seals are fully engaged when door is closed.
- C. Test sound control doors for force to close, latch, and unlatch; adjust as necessary in compliance with requirements.

3.05 SCHEDULE

- A. Refer to Door and Frame Schedule on the drawings.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 081416
FLUSH WOOD DOORS**

PART 1 GENERAL

UPDATED MARCH 2022

1.01 SECTION INCLUDES

SEE BOLD FOR UPDATES

- A. Flush wood doors; flush and flush glazed configuration; fire-rated, non-rated, and acoustical.
- B. Transom panels.

1.02 RELATED REQUIREMENTS

- A. Section 062000 - Finish Carpentry: Wood door frames.
- B. Section 081113 - Hollow Metal Doors and Frames.
- C. Section 087100 - Door Hardware.
- D. Section 088000 - Glazing.
- E. Section 099123 - Interior Painting: Field finishing of doors.

1.03 REFERENCE STANDARDS

- A. ASTM C1048 - Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass; 2012.
- B. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009 (Reapproved 2016).
- C. ASTM E413 - Classification for Rating Sound Insulation; 2016.
- D. AWI/AWMAC/WI (AWS) - Architectural Woodwork Standards; 2014, with Errata (2016).
- E. AWMAC/WI (NAAWS) - North American Architectural Woodwork Standards, U.S. Version 3.1; 2016, with Errata (2017).
- F. NFPA 80 - Standard for Fire Doors and Other Opening Protectives; 2016.
- G. UL 10C - Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.
- H. UL 1784 - Standard for Air Leakage Tests of Door Assemblies; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Indicate door core materials and construction; veneer species, type and characteristics.
- C. Shop Drawings: Show doors and frames, elevations, sizes, types, swings, undercuts, beveling, blocking for hardware, factory machining, factory finishing, cutouts for glazing and other details.
- D. Samples: Submit two samples of door veneer, 12 x 12 inch in size illustrating wood grain, stain color, and sheen.
- E. Certificate: Submit labels and certificates required by quality assurance and quality control programs.
- F. Test Reports: Show compliance with specified requirements for the following:
 - 1. Sound-retardant doors and frames; sealed panel tests are not acceptable.
- G. Manufacturer's Installation Instructions: Indicate special installation instructions.
- H. Specimen warranty.
- I. Warranty, executed in Owner's name.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section, with not less than three years of documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified in this section, with not less than three years of documented experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Package, deliver and store doors in accordance with specified quality standard.
- B. Accept doors on site in manufacturer's packaging. Inspect for damage.
- C. Protect doors with resilient packaging sealed with heat shrunk plastic. Do not store in damp or wet areas; or in areas where sunlight might bleach veneer. Seal top and bottom edges if stored more than one week. Break seal on site to permit ventilation.

1.07 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Interior Doors: Provide manufacturer's warranty for the life of the installation.
- C. Include coverage for delamination of veneer, warping beyond specified installation tolerances, defective materials, and telegraphing core construction.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Wood Veneer Faced Doors:
 - 1. **Masonite: www.masonite.com** Updated March 2022
 - 2. Marshfield DoorSystems, Inc; ____: www.marshfielddoors.com.
 - 3. Oshkosh Door Company.
 - 4. VT Industries
 - 5. All hardware locations to be per CECO standard locations.
- B. Sound-Rated Wood Doors:
 - 1. Overly Door Company; ____: www.overly.com
 - 2. Oshkosh Door Company.

2.02 DOORS AND PANELS

- A. Doors: Refer to drawings for locations and additional requirements.
 - 1. Quality Standard: Custom Grade, Heavy Duty performance, in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), unless noted otherwise.
 - 2. Wood Veneer Faced Doors: 5-ply unless otherwise indicated.
- B. Interior Doors: 1-3/4 inches thick unless otherwise indicated; flush construction.
 - 1. Provide solid core doors at each location.
 - 2. Fire Rated Doors: Tested to ratings indicated on drawings in accordance with UL 10C - Positive Pressure; Underwriters Laboratories Inc (UL) labeled without any visible seals when door is open.
 - 3. Smoke and Draft Control Doors (Indicated as "S" on Drawings): In addition to required fire rating, provide door assemblies tested in accordance with UL 1784 with maximum air leakage of 3.0 cfm per sq ft of door opening at 0.10 inch wg pressure at both ambient and elevated temperatures for "S" label; if necessary, provide additional gasketing or edge sealing.
 - 4. Sound-Rated Doors: Minimum STC of 35, calculated in accordance with ASTM E413, tested in accordance with ASTM E90.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



C. Transom Panels: Same construction and finish as door; same performance rating as door.

2.03 DOOR AND PANEL CORES

- A. Non-Rated Solid Core and 20 Minute Rated Doors: Type particleboard core (PC), plies and faces as indicated.
- B. Fire-Rated Doors: Mineral core type, with fire resistant composite core (FD), plies and faces as indicated above; with core blocking as required to provide adequate anchorage of hardware without through-bolting.
- C. Sound-Rated Doors: Equivalent to type, with particleboard core (PC) construction as required to achieve STC rating specified; plies and faces as indicated above.

2.04 DOOR FACINGS

- A. Veneer Facing for Transparent Finish: Architect to confirm species type with BYU, veneer grade in accordance with quality standard indicated, plain sliced (flat cut), with Architect to confirm matching type with BYU between leaves of veneer, running match of spliced veneer leaves assembled on door or panel face.
 - 1. Vertical Edges: Same species as face veneer.
 - 2. "Running Match" each pair of doors and doors in close proximity to each other.
 - 3. Transoms: Continuous match to doors.
- B. Veneer Facing for Opaque Finish: Medium density overlay (MDO), in compliance with indicated quality standard.

2.05 DOOR CONSTRUCTION

- A. Fabricate doors in accordance with door quality standard specified.
- B. Cores Constructed with stiles and rails:
 - 1. Provide solid blocks at lock edge for hardware reinforcement.
 - 2. Provide solid blocking for other through bolted hardware.
- C. Where supplementary protective edge trim is required, install trim after veneer facing has been applied full-width.
- D. Factory machine doors for hardware other than surface-mounted hardware, in accordance with hardware requirements and dimensions.
- E. Factory fit doors for frame opening dimensions identified on shop drawings, with edge clearances in accordance with specified quality standard.
 - 1. Exception: Doors to be field finished.
- F. Provide edge clearances in accordance with the quality standard specified.

2.06 FACTORY FINISHING - WOOD VENEER DOORS

- A. Finish work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), Section 5 - Finishing for grade specified and as follows:
 - 1. Transparent:
 - a. System - 11, Polyurethane, Catalyzed.
 - b. Stain: As selected by Architect.
 - c. Sheen: Semigloss.
- B. Factory finish doors in accordance with approved sample.

2.07 ACCESSORIES

- A. Hollow Metal Door Frames: As specified in Section 081113.
- B. Glazed Openings:
 - 1. Heat-Strengthened and Fully Tempered Glass: ASTM C1048.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Glazing Stops: Wood, of same species as door facing, butted corners; prepared for countersink style tamper proof screws.
- D. Astragals for Non-Rated Double Doors: Steel, T shaped, overlapping and recessed at face edge.
- E. Astragals for Fire-Rated Double Doors: Steel, T shaped, overlapping and recessed at face edge, specifically for double doors.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that opening sizes and tolerances are acceptable.
- C. Do not install doors in frame openings that are not plumb or are out-of-tolerance for size or alignment.
- D. Do not install fire rated doors in a non-rated wall or opening.

3.02 INSTALLATION

- A. Install doors in accordance with manufacturer's instructions and specified quality standard.
 - 1. Install fire-rated doors in accordance with NFPA 80 requirements.
- B. Factory-Finished Doors: Do not field cut or trim; if fit or clearance is not correct, replace door.
- C. Use machine tools to cut or drill for hardware.
- D. Coordinate installation of doors with installation of frames and hardware.
- E. Coordinate installation of glazing.

3.03 TOLERANCES

- A. Conform to specified quality standard for fit and clearance tolerances.
- B. Conform to specified quality standard for telegraphing, warp, and squareness.

3.04 ADJUSTING

- A. Adjust doors for smooth and balanced door movement.
- B. Adjust closers for full closure.

3.05 SCHEDULE

- A. Refer to Door and Frame Schedule appended to this section.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 087100 DOOR HARDWARE

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Hardware for solid core wood, aluminum, and hollow metal doors.
- B. Hardware for fire-rated doors.
- C. Electrically operated and controlled hardware.
- D. Thresholds.
- E. Weatherstripping and gasketing.
- F. Note: Lock cylinders are furnished and installed by Owner (NIC)

1.02 PROJECT INFORMATION

- A. The architect must work with the following hardware consultant: ASSA ABLOY DSS - Steve Carter (385) 228-3541 steve.carter@assaabloy.com or another person approved by the BYU Access Services Shop Manager (801) 422-5499.
- B. The hardware must be coordinated through the BYU Access Services Shop: Lamar Howarth (801) 422-5499 or current shop manager and the BYU Construction PM assigned to this project.

1.03 RELATED REQUIREMENTS

- A. Section 062000 - Finish Carpentry: Wood door frames.
- B. Section 079200 - Joint Sealants: Sealants for setting exterior door thresholds.
- C. Section 080671 - Door Hardware Schedule: Schedule of door hardware sets.
- D. Section 081113 - Hollow Metal Doors and Frames.
- E. Section 081116 - Aluminum Doors and Frames.
- F. Section 081416 - Flush Wood Doors.
- G. Section 081700 - Integrated Door Opening Assemblies.
- H. Section 083323 - Overhead Coiling Doors: Door hardware, except cylinders.
- I. Section 083326 - Overhead Coiling Grilles: Door hardware, except cylinders.
- J. Section 083613 - Sectional Doors: Door hardware, except cylinders.
- K. Section 084313 - Aluminum-Framed Storefronts: Door hardware, except as noted in section.
- L. Section 084413 - Glazed Aluminum Curtain Walls: Door hardware, except cylinders.
- M. Section 084426 - Structural Glass Curtain Walls: Door hardware, except cylinders.
- N. Section 281000 - Access Control: Electronic access control devices.
- O. Section 284600 - Fire Detection and Alarm: Electrical connection to activate door closers.

1.04 REFERENCE STANDARDS

- A. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.
- B. BHMA (CPD) - Certified Products Directory; 2017.
- C. BHMA A156.1 - American National Standard for Butts and Hinges; 2016.
- D. BHMA A156.2 - American National Standard for Bored and Preassembled Locks & Latches; 2017.
- E. BHMA A156.3 - American National Standard for Exit Devices; 2014.
- F. BHMA A156.4 - American National Standard for Door Controls - Closers; 2013.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- G. BHMA A156.6 - American National Standard for Architectural Door Trim; 2015.
- H. BHMA A156.7 - American National Standard for Template Hinge Dimensions; 2016.
- I. BHMA A156.8 - American National Standard for Door Controls - Overhead Stops and Holders; 2015.
- J. BHMA A156.13 - American National Standard for Mortise Locks & Latches Series 1000; 2017.
- K. BHMA A156.15 - American National Standard for Release Devices - Closer Holder, Electromagnetic and Electromechanical; 2015.
- L. BHMA A156.16 - American National Standard for Auxiliary Hardware; 2013.
- M. BHMA A156.18 - American National Standard for Materials and Finishes; 2016.
- N. BHMA A156.21 - American National Standard for Thresholds; 2014.
- O. BHMA A156.22 - American National Standard for Door Gasketing and Edge Seal Systems, Builders Hardware Manufacturers Association; 2017.
- P. BHMA A156.25 - American National Standard for Electrified Locking Devices; 2013.
- Q. BHMA A156.26 - American National Standard for Continuous Hinges; 2012.
- R. BHMA A156.36 - American National Standard for Auxiliary Locks; 2016.
- S. BHMA A156.115 - American National Standard for Hardware Preparation in Steel Doors and Steel Frames; 2016.
- T. BHMA A156.115W - Hardware Preparation in Wood Doors with Wood or Steel Frames; 2006.
- U. DHI (H&S) - Sequence and Format for the Hardware Schedule; 1996.
- V. DHI (KSN) - Keying Systems and Nomenclature; 1989.
- W. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2017.
- X. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- Y. NFPA 80 - Standard for Fire Doors and Other Opening Protectives; 2016.
- Z. NFPA 101 - Life Safety Code; 2015.
- AA. NFPA 105 - Standard for Smoke Door Assemblies and Other Opening Protectives; 2016.
- AB. NFPA 252 - Standard Methods of Fire Tests of Door Assemblies; 2012.
- AC. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.
- AD. UL 10C - Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.
- AE. UL 1784 - Standard for Air Leakage Tests of Door Assemblies; Current Edition, Including All Revisions.

1.05 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate the manufacture, fabrication, and installation of products that door hardware is installed on.
- B. Sequence installation to ensure utility connections are achieved in an orderly and expeditious manner.
- C. Preinstallation Meeting: Convene a preinstallation meeting one week prior to commencing work of this section; attendance is required by affected installers and the following:
 - 1. Architect.
 - 2. Owner's Door Opening Consultant (ASSA ABLOY Steve Carter)
 - 3. Hardware Supplier.
 - 4. Hardware Installer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



5. Owner's Security Consultant.
 6. BYU Access Services - Lamar Howarth.
 7. BYU Construction Project Manager.
- D. Furnish templates for door and frame preparation to manufacturers and fabricators of products requiring internal reinforcement for door hardware.

1.06 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Manufacturer's catalog literature for each type of hardware, marked to clearly show products to be furnished for this project, and includes construction details, material descriptions, finishes, and dimensions and profiles of individual components.
- C. Shop Drawings - Door Hardware Schedule: Submit detailed listing that includes each item of hardware to be installed on each door. Use door numbering scheme as included in Contract Documents.
 1. Prepared by or under supervision of Architectural Hardware Consultant (AHC).
 2. Conform to DHI (H&S) using door numbers and hardware set numbers as indicated in construction documents.
 - a. Submit in vertical format, refer to Section 080671.
 3. List groups and suffixes in proper sequence.
 4. Provide complete description for each door listed.
 5. Provide manufacturer's and product names, and catalog numbers; include functions, types, styles, sizes and finishes of each item.
 6. Include account of abbreviations and symbols used in schedule.
- D. Shop Drawings - Electrified Door Hardware: Submit diagrams for power, signal, and control wiring for electrified door hardware that include details of interface with building safety and security systems. Provide elevations and diagrams for each electrified door opening as follows:
 1. Prepared by or under supervision of Architectural Hardware Consultant (AHC) and Electrified Hardware Consultant (EHC).
 2. Elevations: Submit front and back elevations of each door opening showing electrified devices with connections installed and an operations narrative describing how opening operates from either side at any given time.
 3. Diagrams: Submit point-to-point wiring diagram that shows each device in door opening system with related colored wire connections to each device.
- E. Manufacturer's Installation Instructions: Indicate special procedures and perimeter conditions requiring special attention.
- F. Maintenance Data: Include data on operating hardware, lubrication requirements, and inspection procedures related to preventative maintenance.
 1. Submit manufacturer's parts lists and templates.
- G. Warranty: Submit manufacturer's warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.
- H. Project Record Documents: Record actual locations of concealed equipment, services, and conduit.

1.07 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with minimum three years of documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified for commercial door hardware with at least three years of documented experience.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Supplier Qualifications: Company with certified Architectural Hardware Consultant (AHC) to assist in work of this section.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Package hardware items individually; label and identify each package with door opening code to match door hardware schedule.

1.09 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Warranty against defects in material and workmanship for period indicated, from Date of Substantial Completion.
 - 1. Closers: Three Years, minimum.
 - 2. Exit Devices: Three years, minimum.
 - 3. Locksets and Cylinders: Three years, minimum.
 - 4. Other Hardware: Two years, minimum.

PART 2 PRODUCTS

2.01 DESIGN AND PERFORMANCE CRITERIA

- A. Provide specified door hardware as required to make doors fully functional, compliant with applicable codes, and secure to extent indicated.
- B. Provide individual items of single type, of same model, and by same manufacturer.
- C. Provide door hardware products that comply with the following requirements:
 - 1. Applicable provisions of federal, state, and local codes.
 - 2. Accessibility: ADA Standards and ICC A117.1.
 - 3. Applicable provisions of NFPA 101.
 - 4. Fire-Rated Doors: NFPA 80, listed and labeled by qualified testing agency for fire protection ratings indicated, based on testing at positive pressure in accordance with NFPA 252 or UL 10C.
 - 5. Hardware on Fire-Rated Doors: Listed and classified by UL (DIR) or testing firm acceptable to authorities having jurisdiction as suitable for application indicated.
 - 6. Hardware for Smoke and Draft Control Doors (Indicated as "S" on Drawings): Provide door hardware that complies with local codes, and requirements of assemblies tested in accordance with UL 1784.
 - a. Air Leakage Rate: Tested in accordance with UL 1784, with air leakage rate not to exceed 3.0 cfm/sf of door opening at 0.10 inch of water for both ambient and elevated temperature tests.
 - 7. Listed and certified compliant with specified standards by BHMA (CPD).
 - 8. Auxiliary Hardware: BHMA A156.16.
 - 9. Hardware Preparation for Steel Doors and Steel Frames: BHMA A156.115.
 - 10. Hardware Preparation for Wood Doors with Wood or Steel Frames: BHMA A156.115W.
 - 11. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified.
- D. Electrically Operated and/or Controlled Hardware: Provide necessary power supplies, power transfer hinges, relays, and interfaces as required for proper operation; provide wiring between hardware and control components and to building power connection in compliance with NFPA 70.
 - 1. Refer to Section 281000 for additional access control system requirements.
- E. Lock Function: Provide lock and latch function numbers and descriptions of manufacturer's series. Refer to Section 080671 for listing of hardware sets.
- F. Fasteners:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Provide fasteners of proper type, size, quantity, and finish that comply with commercially recognized standards for proposed applications.
 - a. Aluminum fasteners are not permitted.
 - b. Provide phillips flat-head screws with heads finished to match door surface hardware unless otherwise indicated.
2. Provide machine screws for attachment to reinforced hollow metal and aluminum frames.
 - a. Self-drilling (Tek) type screws are not permitted.
3. Provide stainless steel machine screws and lead expansion shields for concrete and masonry substrates.
4. Provide wall grip inserts for hollow wall construction. Provide backing for all hardware in stud walls.
5. Fire-Rated Applications: Comply with NFPA 80.
 - a. Provide wood or machine screws for hinges mortised to doors or frames, strike plates to frames, and closers to doors and frames.
 - b. Provide steel through bolts for attachment of surface mounted closers, hinges, or exit devices to door panels unless proper door blocking is provided.

2.02 HINGES

A. Manufacturers:

1. Basis of Design: McKinney; an Assa Abloy Group company; www.assaabloydss.com.
2. McKinney; an Assa Abloy Group company; _____: www.assaabloydss.com
3. Hager Companies; _____: www.hagerco.com
4. Stanley, dormakaba Group; _____: www.stanleyhardwarefordoors.com
5. Substitutions: See Section 016000 - Product Requirements.

B. Hinges: Complying with BHMA A156.1, Grade 1.

1. Butt Hinges: Complying with BHMA A156.1 and BHMA A156.7 for templated hinges.
 - a. Provide hinge width required to clear surrounding trim.
2. Continuous Hinges: Complying with BHMA A156.26.
3. Provide hinges on every swinging door.
4. Provide five-knuckle full mortise butt hinges unless otherwise indicated.
5. Provide ball-bearing hinges at each door.
6. Provide non-removable pins on exterior out swinging doors.
7. Provide non-removable pins on interior out swinging doors at locations as indicated in Door Hardware Schedule.
8. Provide power transfer hinges where electrified hardware is mounted in door leaf.
9. Provide following quantity of butt hinges for each door:
 - a. Doors From 60 inches High up to 90 inches High: Three hinges.
 - b. Doors 90 inches High up to 120 inches High: Four hinges.
 - c. Doors From 42 inches wide up to 48 inches Wide: Four hinges.
 - d. Doors over 120 inches High: One additional hinge per each additional 30 inches in height.
 - e. Dutch Doors: Two hinges each leaf.

2.03 FLUSH BOLTS

A. Manufacturers:

1. Basis of Design: Rockwood, #555, an Assa Abloy Group company; www.assaabloydss.com..
2. Ives, an Allegion brand; _____: www.allegion.com/us
3. Trimco; _____: www.trimcohardware.com
4. Substitutions: See Section 016000 - Product Requirements.

B. Flush Bolts: Complying with BHMA A156.16, Grade 1.

1. Flush Bolt Throw: 3/4 inch, minimum.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Provides extension bolts in leading edge of door, one bolt into floor, one bolt into top of frame.
 - a. Pairs of Swing Doors: At inactive leaves, provide flush bolts of type as required to comply with code.
3. Provide dustproof floor strike for bolt into floor, except at metal thresholds.
4. Manual Flush Bolts: Provide lever extensions for top bolt at over-sized doors.
5. Self-Latching Flush Bolts: Automatically latch upon closing of door; manually retracted; located on inactive leaf of pair of doors.

2.04 EXIT DEVICES

- A. Manufacturers:
 1. Sargent; an Assa Abloy Group company; 88 series: www.assaabloydss.com.
- B. Exit Devices: Complying with BHMA A156.3, Grade 1.
 1. Lever design to match lockset trim.
 2. No mortise exit devices.
 3. No vertical rod exit devices.
 4. Provide rim style only.
 5. Provide cylinder with cylinder dogging or locking trim.
 6. Provide exit devices properly sized for door width and height.
 7. Provide strike as recommended by manufacturer for application indicated.
 8. Provide UL (DIR) listed exit device assemblies for fire-rated doors and panic device assemblies for non-fire-rated doors.

2.05 ELECTRIC STRIKES

- A. Manufacturers:
 1. Adams Rite; an Assa Abloy Group company; #7440: www.assaabloydss.com.
- B. Electric Strikes: Complying with BHMA A156.31, Grade 1.
 1. Provide UL (DIR) listed burglary-resistant electric strike; style to suit locks.
 2. Provide non-handed 24 VDC electric strike suitable for door frame material and scheduled lock configuration.
 3. Provide field selectable Fail Safe/Fail Secure modes.
 4. Connect electric strikes into fire alarm where non-rated doors are scheduled to release with fire or sprinkler alarm condition.

2.06 LOCK CYLINDERS NOT IN CONTRACT - BY OWNER

- A. Manufacturers:
 1. Basis of Design: ASSA Twin 6000. Provided and installed by BYU Access Services

2.07 CYLINDRICAL LOCKSET

- A. Manufacturers:
 1. Sargent; an Assa Abloy Group company; 10 Line: www.assaabloydss.com.
 2. Schlage, an Allegion brand; ND Series Clutch: www.allegion.com/us.
- B. Cylindrical Lockset (Bored): Complying with BHMA A156.2, Grade 1, 4000 Series.
 1. Bored Hole: 2-1/8 inch diameter.
 2. Latchbolt Throw: 1/2 inch, minimum.
 3. Backset: 2-3/4 inch unless otherwise indicated.
 4. Strikes: Provide manufacturer's standard strike for each latchset or lockset with strike box and curved lip extending to protect frame in compliance with indicated requirements.
 - a. Finish: To match lock or latch.
 - b. Extra-Long-Lip Strikes: Provide for locks used on frames with applied wood casing trim.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.08 MORTISE LOCKS - ONLY FOR SINGLE OCCUPANCY RESTROOMS

- A. Manufacturers:
 - 1. Sargent; an Assa Abloy Group company; 49-8266: www.assaabloydss.com.
 - 2. Schlage, an Allegion brand; _____: www.allegion.com/us
- B. Mortise Locks: Complying with BHMA A156.13, Grade 1, Security, 1000 Series.
 - 1. Latchbolt Throw: 3/4 inch, minimum.
 - 2. Deadbolt Throw: 1 inch, minimum.
 - 3. Backset: 2-3/4 inch unless otherwise indicated.
 - 4. Strikes: Provide manufacturer's standard strike for each latchset or lockset with strike box and curved lip extending to protect frame in compliance with indicated requirements.
 - a. Flat-Lip Strikes: Provide for locks with three piece antifricition latch bolts as recommended by manufacturer.
 - b. Extra-Long-Lip Strikes: Provide for locks used on frames with applied wood casing trim.
 - c. Finish: To match lock or latch.

2.09 ELECTROMECHANICAL LOCKSET (FOR INTERIOR APPLICATIONS ONLY)

- A. Manufacturers:
 - 1. Sargent; an Assa Abloy Group company; 10 Line IN120: www.assaabloydss.com.
- B. Electromechanical Locks: Complying with BHMA A156.25, Grade 1.
 - 1. Provide motor-driven or solenoid-driven locks, with strike that is applicable to frame.
 - 2. Type: Cylindrical (Bored).

2.10 AUXILIARY LOCKS (DEADLOCKS)

- A. Manufacturers:
 - 1. Basis of Design: Schlage B660 Series Deadbolts.
- B. Auxiliary Locks (Deadlocks): Complying with BHMA A156.36, Grade 1.
 - 1. Type: Bored (cylindrical).
 - 2. Application: Bored.
 - 3. Backset: 2-3/4 inch, unless otherwise indicated.
 - 4. Bolt Throw: 1/2 inch, with latch made of hardened steel.
 - 5. Provide strike that matches frame.

2.11 DOOR PULLS AND PUSH PLATES

- A. Manufacturers:
 - 1. Rockwood; an Assa Abloy Group company; 110 x 71F: www.assaabloydss.com.
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Door Pulls and Push Plates: Complying with BHMA A156.6.
 - 1. Pull Type: Straight, unless otherwise indicated.
 - 2. Push Plate Type: Flat, with square corners, unless otherwise indicated.
 - a. Edges: Beveled, unless otherwise indicated.
 - 3. Material: Stainless steel, unless otherwise indicated.
 - 4. Provide door pulls and push plates on doors without a lockset, latchset, exit device, or auxiliary lock unless otherwise indicated.
 - 5. Install pull plate and pull with through bolts for pull flush under push plate. No exposed through bolts on push plate.
 - 6. On solid doors, provide matching push plate on opposite faces.

2.12 DOOR PULLS AND PUSH BARS

- A. Manufacturers:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Rockwood; an Assa Abloy Group company; RM3311-20CTC-36" long with 3/8" mounting bolts: www.assaabloydss.com.
 2. IVES - Equal to Rockwood.
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Door Pulls and Push Bars: Complying with BHMA A156.6.
1. Bar Type: Push bar, unless otherwise indicated.
 2. Material: Stainless steel, unless otherwise indicated.

2.13 CLOSERS

- A. Manufacturers; Surface Mounted:
1. LCN, an Allegion brand; 4040XP Non-Handed Closers: www.allegion.com/us.
- B. Closers: Complying with BHMA A156.4, Grade 1.
1. Type: Surface mounted to door.
 2. Provide door closer on each exterior door.
 3. Provide door closer on each fire-rated and smoke-rated door.
 - a. Spring hinges are not an acceptable self-closing device, unless otherwise indicated.
 4. At corridor entry doors, mount closer on room side of door.
 5. At out swinging exterior doors, mount closer on interior side of door.

2.14 OVERHEAD STOPS AND HOLDERS

- A. Manufacturers:
1. Glynn-Johnson, an Allegion brand; 100ADJ: www.allegion.com/us.
- B. Overhead Stops and Holders (Door Checks): Complying with BHMA A156.8, Grade 1.
1. Provide stop for swinging doors as indicated in hardware schedule.
 2. Provide stop for all doors with automatic operator.

2.15 PROTECTION PLATES

- A. Manufacturers:
1. Rockwood; an Assa Abloy Group company; K1050: www.assaabloydss.com.
 2. Ives, an Allegion brand; _____: www.allegion.com/us
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Protection Plates: Complying with BHMA A156.6.
- C. Metal Properties: Stainless steel.
1. Metal, Standard Duty: Thickness 0.05 inch, minimum.
- D. Edges: Beveled, on four sides unless otherwise indicated.
- E. Fasteners: Countersunk screw fasteners.

2.16 ARMOR PLATES (VERIFY LOCATIONS WITH OWNER)

- A. Manufacturers:
1. Rockwood; an Assa Abloy Group company; [K1050]: www.assaabloydss.com
 2. Ives, an Allegion brand; _____: www.allegion.com/us
- B. Armor Plates: Provide on bottom half of push side of doors that require protection from objects moving through openings that may damage door surface.
1. Size: 16 inch high by 1-1/2 inch less door width (LDW) on pull side and 2 inch LDW on push side of door.

2.17 KICK PLATES

- A. Manufacturers:
1. Rockwood; an Assa Abloy Group company; [K1050]: www.assaabloydss.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Ives, an Allegion brand; _____: www.allegion.com/us
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Kick Plates: Provide along bottom edge of push side of every door with closer, except aluminum storefront and glass entry doors, unless otherwise indicated.
1. Size: 10 inch high by 2 inch less door width (LDW) on push side of door.

2.18 MOP PLATES (VERIFY LOCATIONS WITH OWNER)

- A. Manufacturers:
1. Rockwood; an Assa Abloy Group company; [K1050]: www.assaabloydss.co
 2. Ives, an Allegion brand; _____: www.allegion.com/us
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Mop Plates: Provide along bottom edge of pull side of doors to provide protection from cleaning liquids and equipment damage to door surface.
1. Size: 10 inch high by 1-1/2 inch less door width (LDW) on pull side and 2 inch LDW on push side of door.

2.19 DOOR EDGE PLATES (VERIFY LOCATIONS WITH OWNER)

- A. Manufacturers:
1. Rockwood; an Assa Abloy Group company; 306-RKW: www.assaabloydss.com.
 2. Ives, an Allegion brand; _____: www.allegion.com/us
- B. Door Edge Plates: Complying with BHMA A156.6.
1. Provide along latching edge of door to protect from damage as objects are moved through door opening.
 2. Material: Stainless steel, at least 0.050 inch thick.
 3. Type: Beveled edge, mortised into edge of door.

2.20 ELECTROMAGNETIC DOOR HOLDERS

- A. Manufacturers:
1. Rixson; an Assa Abloy Group company; 99X: www.assaabloydss.com.
 2. Substitutions: See Section 016000 - Product Requirements.
- B. Electromagnetic Door Holders: Complying with BHMA A156.15.
1. Type: Wall mounted, single unit, standard duty, with strike plate attached to door.
 2. Holding Force, Standard Duty: 40 lbs.-force, minimum.
 3. Voltage: 24 VDC, and provide power supplies by same manufacturer as holders.
 4. Fail safe; door released to close automatically when electrical current is interrupted - for security doors only.
 5. Provide interface with fire detectors and fire-alarm system for fire-rated door assemblies.

2.21 FLOOR STOPS

- A. Manufacturers:
1. Rockwood; an Assa Abloy Group company; 441H: www.assaabloydss.com.
 2. Substitutions: See Section 016000 - Product Requirements.
- B. Floor Stops: Complying with BHMA A156.16, Grade 1 and Resilient Material Retention Test as described in this standard.
1. Provide floor stops when wall surface is not available; be cautious not to create a tripping hazard.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.22 WALL STOPS

- A. Manufacturers:
 - 1. Basis of Design: _____.
 - 2. Rockwood; an Assa Abloy Group company; 409: www.assaabloydss.com.
 - 3. Substitutions: See Section 016000 - Product Requirements.
- B. Wall Stops: Complying with BHMA A156.16, Grade 1 and Resilient Material Retention Test as described in this standard.
 - 1. Provide wall stops to prevent damage to wall surface upon opening door.
 - 2. Type: Bumper, concave, wall stop.
 - 3. Material: Stainless steel housing with rubber insert.

2.23 ASTRAGALS

- A. Manufacturers:
 - 1. Pemko; an Assa Abloy Group company; _____: www.assaabloydss.com
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Astragals: Complying with BHMA A156.22.
 - 1. Provide surface mounted astragal to cover or fill space for full door height between pair of doors or door and adjacent jamb.
 - 2. Type: Split, two parts, and with sealing gasket.
 - 3. Material: Steel, with neoprene weatherstripping.
 - 4. Provide non-corroding fasteners at exterior locations.

2.24 THRESHOLDS

- A. Manufacturers:
 - 1. Pemko; an Assa Abloy Group company; _____: www.assaabloydss.com
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Thresholds: Complying with BHMA A156.21.
 - 1. Provide threshold at each exterior door, unless otherwise indicated.
 - 2. Type: Flat surface.
 - 3. Material: Aluminum.
 - 4. Threshold Surface: Fluted horizontal grooves across full width.
 - 5. Field cut threshold to profile of frame and width of door sill for tight fit.
 - 6. Provide non-corroding fasteners at exterior locations.

2.25 WEATHERSTRIPPING AND GASKETING

- A. Manufacturers:
 - 1. Pemko; an Assa Abloy Group company; _____: www.assaabloydss.com
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Weatherstripping and Gasketing: Complying with BHMA A156.22.
 - 1. Head and Jamb Type: Self-adhesive.
 - 2. Door Sweep Type: Encased in retainer.
 - 3. Material: Aluminum, with brush weatherstripping.
 - 4. Provide gasketing for smoke and draft control doors (Indicated as "S" on Drawings) that complies with local codes, requirements of assemblies tested in accordance with UL 1784.
 - 5. Provide frame-applied intumescent gasketing on wood doors that are labeled as smoke and draft control doors (Indicated as "S" on Drawings), unless otherwise indicated.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



6. Provide weatherstripping on each exterior door at head, jambs, and meeting stiles of door pairs, unless otherwise indicated; .
7. Provide door bottom sweep on each exterior door, unless otherwise indicated.
8. Provide sound-rated gasketing and automatic door bottom on doors indicated as "Sound-Rated", "Acoustical", or with "Sound Transmission Class (STC) rating"; fabricate as continuous gasketing, do not cut or notch gasketing material.

2.26 LATCH PROTECTOR

- A. Manufacturers:
 1. Rockwood; an Assa Abloy Group company; _____: www.assaabloydss.com
- B. Latch Protector: Provide on door to protect latch from being tampered with while in locked position.
 1. Type: Standard latch protector.
 2. Material: Stainless steel.

2.27 SILENCERS

- A. Manufacturers:
 1. Ives, an Allegion brand; _____: www.allegion.com/us
 2. Rockwood; an Assa Abloy Group company; _____: www.assaabloydss.com
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Silencers: Provide at equal locations on door frame to mute sound of door's impact upon closing.
 1. Single Door: Provide three on strike jamb of frame.
 2. Pair of Doors: Provide two on head of frame, one for each door at latch side.
 3. Material: Rubber, gray color.

2.28 WIRELESS ACCESS MANAGEMENT SYSTEMS

- A. Manufacturers:
 1. Basis of Design: Sargent 10 Line IN120.
- B. Wireless Access Management Systems: Complying with guidelines of BHMA A156.25, and including necessary hardware for fully functional system.
 1. Reader Formats: Provide proximity to activate access system functionality.
 2. Door Locking Hardware: Provide applicable cylindrical locksets or panic hardware in compliance with project access control requirements.

2.29 EXIT MOTION SENSOR

- A. Manufacturers:
 1. Basis of Design: Bosch DS160.
- B. Exit Motion Sensor: Interior passive infrared detection device to initiate door release of exit door magnetic lock.
 1. Power: 12 or 24 VDC.
 2. Provide adjustable detector face to allow for precise pattern configurations, and easy pattern adjustment.
 3. Provide relay that operates before transistor to prevent false alarms.
 4. Operating Temperature: 32 to 110 degrees F.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.30 KEY SWITCH

- A. Manufacturers:
 - 1. Securitron; an Assa Abloy Group company; _____: www.assaabloydss.com
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Key Switch: Mortise key type, single gang.
 - 1. Power: 12 or 24 VDC.
 - 2. Operating Temperature: 32 to 110 degrees F.

2.31 POWER SUPPLY

- A. Manufacturers:
 - 1. Basis of Design: Life Safety .
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Power Supply: Hard wired, with multiple zones providing eight (8) breakers for each output panel with individual control switches and LED's; UL (DIR) Class 2 listed.
 - 1. Power: 24 VDC; with 120 VAC power supply.
 - 2. Operating Temperature: 32 to 110 degrees F.
 - 3. Provide with emergency release terminals that release devices upon activation of fire alarm system.

2.32 FINISHES

- A. Finishes: Provide door hardware of same finish, unless otherwise indicated.
 - 1. Primary Finish: 626; satin chromium plated over nickel, with brass or bronze base material (former US equivalent US26D); BHMA A156.18.
 - 2. Exceptions:
 - a. Where base material metal is specified to be different, provide finish that is an equivalent appearance in accordance with BHMA A156.18.
 - b. Hinges for Fire-Rated Doors: Steel base material with painted finish, in compliance with NFPA 80.
 - c. Door Closer Covers and Arms: Color as selected by Architect from manufacturer's standard colors unless otherwise indicated.
 - d. Hardware for Aluminum Storefront Doors: Finished to match door panel finish, except at hand contact surfaces provide stainless steel with satin finish, unless otherwise indicated.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that doors and frames are ready to receive this work; labeled, fire-rated doors and frames are properly installed, and dimensions are as indicated on shop drawings.
- B. Verify that electric power is available to power operated devices and of correct characteristics.

3.02 INSTALLATION

- A. Install hardware in accordance with manufacturer's instructions and applicable codes.
- B. Install hardware on fire-rated doors and frames in accordance with applicable codes and NFPA 80.
- C. Install hardware for smoke and draft control doors in accordance with NFPA 105.
- D. Use templates provided by hardware item manufacturer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- E. Do not install surface mounted items until application of finishes to substrate are fully completed.
- F. All hardware mounting to be per CECO locations.
- G. Set exterior door thresholds with full-width bead of elastomeric sealant at each point of contact with floor providing a continuous weather seal; anchor thresholds with stainless steel countersunk screws.

3.03 FIELD QUALITY CONTROL

- A. Perform field inspection and testing under provisions of Section 014000 - Quality Requirements.
- B. Provide an Architectural Hardware Consultant (AHC) to inspect installation and certify that hardware and installation has been furnished and installed in accordance with manufacturer's instructions and as specified.

3.04 ADJUSTING

- A. Adjust work under provisions of Section 017000 - Execution and Closeout Requirements.
- B. Adjust hardware for smooth operation.
- C. Adjust gasketing for complete, continuous seal; replace if unable to make complete seal.

3.05 CLEANING

- A. Clean finished hardware in accordance with manufacturer's written instructions after final adjustments have been made.
- B. Clean adjacent surfaces soiled by hardware installation.
- C. Replace items that cannot be cleaned to manufacturer's level of finish quality at no additional cost.

3.06 PROTECTION

- A. Protect finished Work under provisions of Section 017000 - Execution and Closeout Requirements.
- B. Do not permit adjacent work to damage hardware or finish.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 088000
GLAZING**

PART 1 GENERAL

UPDATED 2/21

1.01 SECTION INCLUDES

SEE CHANGES IN BOLD

- A. Insulating glass units.
- B. Glazing units.
- C. Glazing compounds and accessories.

1.02 RELATED REQUIREMENTS

- A. Section 064100 - Architectural Wood Casework: Cabinets with requirements for glass shelves.
- B. Section 072500 - Weather Barriers.
- C. Section 084313 - Aluminum-Framed Storefronts: Glazing furnished as part of storefront assembly.
- D. Section 084413 - Glazed Aluminum Curtain Walls: Glazing furnished as part of wall assembly.

1.03 REFERENCE STANDARDS

- A. 16 CFR 1201 - Safety Standard for Architectural Glazing Materials; current edition.
- B. ANSI Z97.1 - American National Standard for Safety Glazing Materials Used in Buildings - Safety Performance Specifications and Methods of Test; 2015.
- C. ASCE 7 - Minimum Design Loads for Buildings and Other Structures; 2010, with 2013 Supplements and Errata.
- D. ASTM C864 - Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers; 2005 (Reapproved 2015).
- E. ASTM C920 - Standard Specification for Elastomeric Joint Sealants; 2014a.
- F. ASTM C1048 - Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass; 2012.
- G. ASTM C1172 - Standard Specification for Laminated Architectural Flat Glass; 2014.
- H. ASTM C1193 - Standard Guide for Use of Joint Sealants; 2016.
- I. ASTM C1376 - Standard Specification for Pyrolytic and Vacuum Deposition Coatings on Flat Glass; 2015.
- J. ASTM E119 - Standard Test Methods for Fire Tests of Building Construction and Materials; 2016a.
- K. ASTM E1300 - Standard Practice for Determining Load Resistance of Glass in Buildings; 2016.
- L. ASTM E2190 - Standard Specification for Insulating Glass Unit Performance and Evaluation; 2010.
- M. GANA (SM) - GANA Sealant Manual; 2008.
- N. **ICC (IBC) - International Building Code; 2018** **Updated 2/21**
- O. IGMA TB-3001 - Guidelines for Sloped Glazing; 2001.
- P. ITS (DIR) - Directory of Listed Products; current edition.
- Q. NFPA 252 - Standard Methods of Fire Tests of Door Assemblies; 2012.
- R. NFPA 257 - Standard on Fire Test for Window and Glass Block Assemblies; 2017.
- S. NFRC 100 - Procedure for Determining Fenestration Product U-factors; 2017.
- T. NFRC 200 - Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence; 2014, with Errata (2017).
- U. NFRC 300 - Test Method for Determining the Solar Optical Properties of Glazing Materials and Systems; 2017.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



- V. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.
- W. UL 9 - Standard for Fire Tests of Window Assemblies; Current Edition, Including All Revisions.
- X. UL 10B - Standard for Fire Tests of Door Assemblies; Current Edition, Including All Revisions.
- Y. UL 10C - Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.
- Z. UL 263 - Standard for Fire Tests of Building Construction and Materials; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene a preinstallation meeting two weeks before starting work of this section; require attendance by each of the affected installers.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data on Insulating Glass Unit and Glazing Unit Glazing Types: Provide structural, physical and environmental characteristics, size limitations, special handling and installation requirements.
- C. Product Data on Glazing Compounds and Accessories: Provide chemical, functional, and environmental characteristics, limitations, special application requirements. Identify available colors.
- D. Samples: Submit two samples 12 by 12 inch in size of glass units.
- E. Samples: Submit 6 inch long bead of glazing sealant, color as selected.
- F. Certificate: Certify that products of this section meet or exceed specified requirements.
- G. Warranty Documentation: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years of documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years documented experience.
- C. Testing Agency Qualifications: Independent firm specializing in performing testing and inspections of the type specified in this section.

1.07 MOCK-UPS

- A. See Section 014000 - Quality Requirements, for additional mock-up requirements.
- B. Provide on-site glazing mock-up with the specified glazing components.
- C. Locate where directed.
- D. Mock-ups may remain as part of the Work.

1.08 FIELD CONDITIONS

- A. Do not install glazing when ambient temperature is less than 40 degrees F.
- B. Maintain minimum ambient temperature before, during and 24 hours after installation of glazing compounds.

1.09 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Insulating Glass Units: Provide a ten (10) year manufacturer warranty to include coverage for seal failure, interpane dusting or misting, including providing products to replace failed units.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



- C. Laminated Glass: Provide a ten (10) year manufacturer warranty to include coverage for delamination, including providing products to replace failed units.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Glass Fabricators:
 - 1. Oldcastle Glass . (obe.com)
 - 2. Northwestern Industries Inc, NWI (nwiglass.com)
- B. Float Glass Manufacturers:
 - 1. Cardinal Glass Industries; _____: www.cardinalcorp.com
 - 2. Guardian Glass, LLC; _____: www.guardianglass.com
 - 3. Pilkington North America Inc; _____: www.pilkington.com/na
 - 4. **Trulite Glass & Aluminum Solutions; www.trulite.com**
 - 5. **Vitro Architectural Glass (formerly PPG Glass); _____: www.vitroglazings.com**
- C. Laminated Glass Manufacturers:
 - 1. Cardinal Glass Industries; _____: www.cardinalcorp.com
- D. Fire-Resistance-Rated Glass: Provide products as required to achieve indicated fire-rating period.
 - 1. Fabricators:
 - a. GGI - General Glass International; Pyrobel: www.generalglass.com/#sle.
 - 2. Manufacturers:
 - 3. Technical Glass Products; Pilkington Pyrostop: www.fireglass.com/#sle.
 - 4. Vetrotech North America; Contraflam: www.vetrotechusa.com/#sle.
- E. Plastic Films Manufacturers:
 - 1. 3M Window Film; _____: www.3m.com/#sle.
 - 2. Substitutions: Refer to Section 016000 - Product Requirements.

2.02 PERFORMANCE REQUIREMENTS - EXTERIOR GLAZING ASSEMBLIES

- A. Provide type and thickness of exterior glazing assemblies to support assembly dead loads, and to withstand live loads caused by positive and negative wind pressure acting normal to plane of glass.
 - 1. Design Pressure: Calculated in accordance with ASCE 7.
 - 2. Comply with ASTM E1300 for design load resistance of glass type, thickness, dimensions, and maximum lateral deflection of supported glass.
 - 3. Seismic Loads: Design and size glazing components to withstand seismic loads and sway displacement in accordance with the requirements of ASCE 7.
 - 4. Provide glass edge support system sufficiently stiff to limit the lateral deflection of supported glass edges to less than 1/175 of their lengths under specified design load.
 - 5. Glass thicknesses listed are minimum.
- B. Vapor Retarder and Air Barrier Seals: Provide completed assemblies that maintain continuity of building enclosure vapor retarder and air barrier.
 - 1. In conjunction with vapor retarder and joint sealer materials described in other sections.
 - a. Refer to Section 072500.
 - 2. To maintain a continuous vapor retarder and air barrier throughout the glazed assembly from glass pane to heel bead of glazing sealant.
- C. Thermal and Optical Performance: Provide exterior glazing products with performance properties as indicated. Performance properties are in accordance with manufacturer's published data as determined with the following procedures and/or test methods:
 - 1. Center of Glass U-Value: Comply with NFRC 100 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



2. Center of Glass Solar Heat Gain Coefficient (SHGC): Comply with NFRC 200 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
3. Solar Optical Properties: Comply with NFRC 300 test method.

2.03 GLASS MATERIALS

- A. Float Glass: Provide float glass based glazing unless noted otherwise.
1. **Annealed Type: Not approved for use on Campus.** Updated 2/21
 2. Kind FT - Fully Tempered Type: Complies with ASTM C1048.
 3. Fully Tempered Safety Glass: Complies with ANSI Z97.1 and 16 CFR 1201 criteria.
 4. Thicknesses: As indicated; provide greater thickness as required for exterior glazing wind load design.
- B. Laminated Glass: Float glass laminated in accordance with ASTM C1172.
1. Laminated Safety Glass: Complies with ANSI Z97.1 and 16 CFR 1201 test requirements for Category II.
 2. Polyvinyl Butyral (PVB) Interlayer: 0.030 inch thick, minimum.

2.04 INSULATING GLASS UNITS

- A. Manufacturers:
1. Cardinal Glass Industries; _____: www.cardinalcorp.com/#sle.
 2. Guardian Glass, LLC; _____: www.guardianglass.com/#sle.
 3. Pilkington North America Inc; _____: www.pilkington.com/na/#sle.
 4. Vitro Architectural Glass (formerly PPG Glass); _____: www.vitroglazings.com/#sle.
- B. Insulating Glass Units: Types as indicated.
1. Durability: Certified by an independent testing agency to comply with ASTM E2190.
 2. Coated Glass: Comply with requirements of ASTM C1376 for pyrolytic (hard-coat) or magnetic sputter vapor deposition (soft-coat) type coatings on flat glass; coated vision glass, Kind CV; coated overhead glass, Kind CO; or coated spandrel glass, Kind CS.
 3. Metal Edge Spacers: Aluminum, mitered and spigoted corners.
 4. Spacer Color: Aluminum.
 5. Edge Seal:
 - a. Dual-Sealed System: Provide polyisobutylene sealant as primary seal applied between spacer and glass panes, and silicone, polysulfide, or polyurethane sealant as secondary seal applied around perimeter.
 6. Color: Black.
 7. Purge interpane space with dry air, hermetically sealed.
 8. Breather Tubes: Provide tubes from air space for insulating glass units without inert type gas that have a change of altitude greater than 2500 feet between point of fabrication and point of installation to permit pressure equalization of air space.
 - a. Breather Tubes: Seal or crimp breather tubes upon installation in accordance with insulating glass fabricator's requirements.
- C. Type IG-1 - Insulating Glass Units: Vision glass, double glazed, sound attenuating.
1. Applications: Exterior glazing unless otherwise indicated.
 2. Space between lites filled with air.
 3. Outboard Lite: Fully tempered float glass, 1/4 inch thick, minimum.
 - a. Tint: Clear.
 - b. **Coating: Solarban 70 Solar Control LOW - E, on #2 surface.** Updated 2/21
 4. Inboard Lite: Fully tempered float glass, 1/4 inch thick, minimum.
 - a. Tint: Clear.
 5. Total Thickness: 1 inch. No unit larger than 35 SF.
 6. **Thermal Transmittance (U-Value), Summer - Center of Glass: .28, maximum. UpD 2/21**
 7. **Visible Light Transmittance (VLT): 64 percent, minimum. Updated 2/21**

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



8. **Solar Heat Gain Coefficient (SHGC): .27, maximum.** Updated 2/21
 9. **Visible Light Reflectance, Outside: 12 percent, maximum** Updated 2/21
 10. Glazing Method: Dry glazing method, gasket glazing.
- D. Type IG-3 - Insulating Glass Units: Spandrel glazing.
1. Applications: Exterior spandrel glazing unless otherwise indicated.
 - a. **Protect coating from damage during handling and following installation.**
 - b. **Owner inspection required prior to cover up.** Updated 2/21
 2. Space between lites filled with air.
 3. Outboard Lite: Fully tempered float glass, 1/4 inch thick, minimum.
 - a. Tint: Clear.
 - b. Coating: Same as on vision units, on #2 surface.
 4. Inboard Lite: Fully tempered float glass, 1/4 inch thick.
 - a. Tint: Clear.
 - b. **Opacifier: Ceramic frit, on #4 surface.** Updated 2/21
 - c. Opacifier Color: As selected by Architect.
 5. Total Thickness: 1 inch.
 6. **Thermal Transmittance (U-Value), Summer - Center of Glass: [.28], maximum. UpD 2/21**
 7. **Visible Light Reflectance, Outside: [12] percent, maximum** Updated 2/21
 8. Glazing Method: Dry glazing method, gasket glazing.
- E. Type IG-4 - Insulating Glass Units: Sloped glazing, laminated; IGMA TB-3001.
1. Applications: Exterior sloped glazing at 15 degrees or more from vertical, unless otherwise indicated.
 2. Space between lites filled with air.
 3. Outboard Lite: Fully tempered float glass, 1/4 inch thick, minimum. **3/8 inch thick, minimum at sloped glazing.** Updated 2/21
 - a. Tint: Clear.
 - b. **Coating: Solarban 70 Solar Control LOW-E, on #2 surface.** Updated 2/21
 4. Laminated Inboard Lite, Outer Pane: **Fully tempered float glass, 1/4 inch thick, minimum. 3/8 inch thick, minimum at sloped glazing.** Updated 2/21
 - a. Tint: Clear.
 5. Interlayer: Polyvinyl butyral (PVB); thickness as required.
 6. Laminated Inboard Lite, Inner Pane: **Fully tempered float glass, 1/4 inch thick, minimum. 3/8 inch thick, minimum at sloped glazing.** Updated 2/21
 - a. Tint: Clear.
 7. **Total Thickness: 1 1/4 inch.** Updated 2/21
 8. **Thermal Transmittance (U-Value), Summer - Center of Glass: .28, nominal.**
 9. **Visible Light Transmittance (VLT): 62 percent, nominal.**
 10. **Solar Heat Gain Coefficient (SHGC): .27, nominal.**
 11. **Visible Light Reflectance, Outside: 13 percent, nominal. Updated 2/21**
 12. Glazing Method: Dry glazing method, gasket glazing.
- F. Type IG-5 - Insulating Glass Units: Safety glazing.
1. Applications:
 - a. Glazed lites in exterior doors.
 - b. Glazed sidelights and panels next to doors.
 - c. Other locations required by applicable federal, state, and local codes and regulations.
 2. Space between lites filled with air.
 3. Glass Type: Same as Type 1G-1 using fully tempered float glass for both outboard and inboard lites.
 4. Tint: Clear.
 5. Total Thickness: 1 inch.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



- 6. **Thermal Transmittance (U-Value), Summer - Center of Glass:** .28, nominal.
- 7. **Visible Light Transmittance (VLT):** 64 percent, nominal.
- 8. **Solar Heat Gain Coefficient (SHGC):** .27, nominal.
- 9. **Visible Light Reflectance, Outside:** 12 percent, nominal. Updated 2/21

2.05 BASIS OF DESIGN - INSULATING GLASS UNITS

- A. Basis of Design - Insulating Glass Units: Vision glazing, with Low-E coating.
 - 1. Applications: Exterior insulating glass glazing unless otherwise indicated.
 - 2. Space between lites filled with air.
 - 3. Total Thickness: 1 inch.
 - 4. **Thermal Transmittance (U-Value), Summer - Center of Glass:** .28, nominal.
 - 5. **Visible Light Transmittance (VLT):** 64 percent, nominal.
 - 6. **Solar Heat Gain Coefficient (SHGC):** .27, nominal.
 - 7. **Visible Light Reflectance, Outside:** 12 percent, nominal. Updated 2/21
 - 8. Glazing Method: Dry glazing method, gasket glazing.
 - 9. Spacer Color: Black.
 - 10. Edge Seal:
 - 11. Color: Black.
 - 12. Purge interpane space with dry air, hermetically sealed.
 - 13. Basis of Design - Vitro Architectural Glass (formerly PPG Glass): www.vitroglazings.com/#sle.
 - 14. **Outboard Lite: Fully tempered float glass, 1/4 inch thick, minimum. Updated 2/21**
 - a. **Low-E Coating: Vitro Architectural Glass (formerly PPG Glass) Solarban 70 Solar Control LOW - E on #2 surface. Updated 2/21**
 - 15. Inboard Lite: Fully tempered float glass, 1/4 inch thick.
 - a. Glass: Clear.

2.06 GLAZING UNITS

- A. Type G-2 - Monolithic Interior Vision Glazing:
 - 1. Applications: Interior glazing unless otherwise indicated.
 - 2. Glass Type: Fully tempered float glass.
 - 3. Tint: Clear.
 - 4. Thickness: 1/4" or 1/2" inch, nominal, depending on size of pane and application.
 - 5. Glazing Method: Dry glazing method, gasket glazing.
- B. Type G-3 - Fire-Resistance-Rated Glazing: Type, thickness, and configuration of glazing that contains flame, smoke, and blocks radiant heat, as required to achieve indicated fire-rating period exceeding 45 minutes.
 - 1. Applications:
 - a. Glazing in fire-rated door assembly.
 - b. Glazing in fire-rated window assembly.
 - c. Glazing in sidelites, borrowed lites, and other glazed openings in fire-rated wall assemblies.
 - d. Other locations as indicated on drawings.
 - 2. **Steel Frames: Tru-View. Updated 2/21**
 - 3. Glass Type: Tempered glass outer layers filled with semi-solid fire retardant.
 - 4. Provide products listed by 1 or 1 and approved by authorities having jurisdiction.
 - 5. Safety Glazing Certification: 16 CFR 1201 Category II.
 - 6. Fire-Rating Period: As indicated on drawings.
 - 7. Markings for Fire-Resistance-Rated Glazing Assemblies: Provide permanent markings on fire-resistance-rated glazing in compliance with 1, local building code, and authorities having jurisdiction.
 - a. "W" - meets wall assembly criteria of ASTM E119 or UL 263 fire test standards.
 - b. "D" - meets fire door assembly criteria of NFPA 252, UL 10B, or UL 10C fire test standards.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



- c. "H" - meets fire door assembly hose stream test of NFPA 252, UL 10B, or UL 10C fire test standards.
 - d. "T" - meets temperature rise of not more than 450 degrees F above ambient at end of 30 minutes fire exposure in accordance with NFPA 252, UL 10B, or UL 10C fire test standards.
 - e. "XXX" - placeholder that represents fire-rating period, in minutes.
8. Products:
- a. Technical Glass Products; Pilkington Pyrostop: www.fireglass.com/#sle.
 - b. Vetrotech North America; Contraflam: www.vetrotechusa.com/#sle.
 - c. **Tru-View Frames: truframe.com** **Updated 2/21**
 - d. Substitutions: Refer to Section 016000 - Product Requirements.
- C. Type G-4 - Fire-Protection-Rated Glazing: Type, thickness, and configuration of glazing that contains flame, smoke, and does not block radiant heat, as required to achieve fire-doors indicated fire-rating period of 45 minutes or less.
1. Applications:
- a. Glazing in fire-rated door assembly.
 - b. Glazing in fire-rated window assembly.
 - c. Other locations as indicated on drawings.
2. **Steel Frames: Tru-View.** **Updated 2/21**
3. Glass Type: Safety ceramic glass.
4. Provide products listed by 2 or 2 and approved by authorities having jurisdiction.
5. Safety Glazing Certification: 16 CFR 1201 Category II.
6. Fire-Rating Period: As indicated on drawings.
7. Markings for Fire-Protection-Rated Glazing Assemblies: Provide permanent markings on fire-protection-rated glazing in compliance with 1, local building code, and authorities having jurisdiction
- a. "D" - meets fire door assembly criteria of NFPA 252, UL 10B, or UL 10C fire test standards.
 - b. "OH" - meets fire window assembly criteria including hose stream test of NFPA 257, or UL 9 fire test standards.
 - c. "H" - meets fire door assembly hose stream test of NFPA 252, UL 10B, or UL 10C fire tests standards.
 - d. "XXX" - placeholder that represents fire-rating period, in minutes.
8. Products:
- a. Technical Glass Products; Firelite: www.fireglass.com/#sle.
 - b. Vetrotech North America; Contraflam: www.vetrotechusa.com/#sle.
 - c. **Tru-View Frames: truframe.com** **Updated 2/21**
 - d. Substitutions: Refer to Section 016000 - Product Requirements.
- D. Type G-5 - Monolithic Safety Glazing: Non-fire-rated.
1. Applications:
- a. Glazed lites in doors, except fire doors.
 - b. Guardrails.
 - c. Glazed sidelights to doors, except in fire-rated walls and partitions.
 - d. Other locations required by applicable federal, state, and local codes and regulations.
 - e. Other locations indicated on drawings.
2. Glass Type: Fully tempered safety glass as specified.
3. Tint: Clear.
4. Thickness: 1/4 inch, nominal except use 1/2" thick at guardrails.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



2.07 GLAZING COMPOUNDS

- A. Type GC-5 - Silicone Sealant: Single component; neutral curing; capable of water immersion without loss of properties; non-bleeding, non-staining; ASTM C920, Type S, Grade NS, Class 25, Uses M, A, and G; with cured Shore A hardness range of 15 to 25; Standard color as selected by Architect.
- B. Manufacturers:
 - 1. Dow Corning Corporation; 795: www.dowcorning.com/construction.
 - 2. **No Substitutions.**

Updated 2/21

2.08 ACCESSORIES

- A. Setting Blocks: Neoprene, with 80 to 90 Shore A durometer hardness; ASTM C864 Option II. Length of 0.1 inch for each square foot of glazing or minimum 4 inch x width of glazing rabbet space minus 1/16 inch x height to suit glazing method and pane weight and area.
- B. Spacer Shims: EPDM, 50 to 60 Shore A durometer hardness; ASTM C864 Option II. Minimum 3 inch long x one half the height of the glazing stop x thickness to suit application, self adhesive on one face.
- C. Glazing Tape, Back Bedding Mastic Type: Preformed, butyl-based, 100 percent solids compound with integral resilient spacer rod applicable to application indicated; 5 to 30 cured Shore A durometer hardness; coiled on release paper; black color.
 - 1. Width: As required for application.
 - 2. Thickness: As required for application.
 - 3. Spacer Rod Diameter: As required for application.
- D. Glazing Gaskets: Resilient polyvinyl chloride extruded shape to suit glazing channel retaining slot; ASTM C864 Option II; color black.
- E. Glazing Clips: Manufacturer's standard type.

PART 3 EXECUTION

3.01 VERIFICATION OF CONDITIONS

- A. Verify that openings for glazing are correctly sized and within tolerances, including those for size, squareness, and offsets at corners.
- B. Verify that the minimum required face and edge clearances are being provided.
- C. Verify that surfaces of glazing channels or recesses are clean, free of obstructions that may impede moisture movement, weeps are clear, and support framing is ready to receive glazing system.
- D. Verify that sealing between joints of glass framing members has been completed effectively.
- E. Proceed with glazing system installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Clean contact surfaces with appropriate solvent and wipe dry within maximum of 24 hours before glazing. Remove coatings that are not tightly bonded to substrates.
- B. Seal porous glazing channels or recesses with substrate compatible primer or sealer.
- C. Prime surfaces scheduled to receive sealant where required for proper sealant adhesion.

3.03 INSTALLATION, GENERAL

- A. Install glazing in compliance with written instructions of glass, gaskets, and other glazing material manufacturers, unless more stringent requirements are indicated, including those in glazing referenced standards.
- B. Install glazing sealants in accordance with ASTM C1193, GANA (SM), and manufacturer's instructions.
- C. Do not exceed edge pressures around perimeter of glass lites as stipulated by glass manufacturer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



- D. Set glass lites of system with uniform pattern, draw, bow, and similar characteristics.
- E. Set glass lites in proper orientation so that coatings face exterior or interior as indicated.
- F. Prevent glass from contact with any contaminating substances that may be the result of construction operations such as, and not limited to the following; weld splatter, fire-safing, plastering, mortar droppings, etc.
- G. **Prevent spandrel glazing from contact with batt insulation.** **Updated 2/21**

3.04 INSTALLATION - DRY GLAZING METHOD (GASKET GLAZING)

- A. Application - Exterior and/or Interior Glazed: Set glazing infills from either the exterior or the interior of the building.
- B. Place setting blocks at 1/4 points with edge block no more than 6 inch from corners.
- C. Rest glazing on setting blocks and push against fixed stop with sufficient pressure on gasket to attain full contact.
- D. Install removable stops without displacing glazing gasket; exert pressure for full continuous contact.

3.05 FIELD QUALITY CONTROL

- A. Glass and Glazing product manufacturers to provide field surveillance of the installation of their products.
- B. Monitor and report installation procedures and unacceptable conditions.

3.06 CLEANING

- A. Remove excess glazing materials from finish surfaces immediately after application using solvents or cleaners recommended by manufacturers.
- B. Remove non-permanent labels immediately after glazing installation is complete.
- C. Clean glass and adjacent surfaces after sealants are fully cured.
- D. Clean glass on both exposed surfaces not more than 4 days prior to Date of Substantial Completion in accordance with glass manufacturer's written recommendations.

3.07 PROTECTION

- A. Remove and replace glass that is damaged during construction period prior to Date of Substantial Completion.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: February 20, 2024

Signature & Date: _____



SECTION 090561

COMMON WORK RESULTS FOR FLOORING PREPARATION

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. This section applies to all floors identified in the contract documents as to receive the following types of floor coverings:
 - 1. Resilient tile and sheet vinyl.
 - 2. Broadloom carpet.
 - 3. Carpet tile.
 - 4. Thin-set ceramic tile and stone tile.
 - 5. Porcelain Tile.
- B. Removal of existing floor coverings. Verify with owner if recycling is feasible.
- C. Preparation of new concrete floor slabs for installation of floor coverings.
- D. Testing of concrete floor slabs for moisture and alkalinity (pH).
- E. Remediation of concrete floor slabs due to unsatisfactory moisture or alkalinity (pH) conditions.
 - 1. Contractor shall perform all specified remediation of concrete floor slabs. If such remediation is indicated by testing agency's report and is due to a condition not under Contractor's control or could not have been predicted by examination prior to entering into the contract, a contract modification will be issued.
- F. Patching compound.
- G. Remedial floor coatings.
- H. Remedial floor sheet membrane.

1.02 REFERENCE STANDARDS

- A. ASTM C109/C109M - Standard Test Method for Compressive Strength of Hydraulic Cement Mortars (Using 2-in. or (50-mm) Cube Specimens); 2016a.
- B. ASTM C472 - Standard Test Methods for Physical Testing of Gypsum, Gypsum Plasters and Gypsum Concrete; 1999 (Reapproved 2014).
- C. ASTM F710 - Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2011.
- D. ASTM F1869 - Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride; 2011.
- E. ASTM F2170 - Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes; 2017.
- F. RFCI (RWP) - Recommended Work Practices for Removal of Resilient Floor Coverings; Resilient Floor Covering Institute; October 2011.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate scheduling of cleaning and testing, so that preliminary cleaning has been completed for at least 24 hours prior to testing.

1.04 SUBMITTALS

- A. Visual Observation Report: For existing floor coverings to be removed.
- B. Floor Covering and Adhesive Manufacturers' Product Literature: For each specific combination of substrate, floor covering, and adhesive to be used; showing:
 - 1. Moisture and alkalinity (pH) limits and test methods.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Manufacturer's required bond/compatibility test procedure.
- C. Testing Agency's Report:
 1. Description of areas tested; include floor plans and photographs if helpful.
 2. Summary of conditions encountered.
 3. Moisture and alkalinity (pH) test reports.
 4. Copies of specified test methods.
 5. Recommendations for remediation of unsatisfactory surfaces.
 6. Include certification of accuracy by authorized official of testing agency.
 7. Submit report directly to Owner.
 8. Submit report not more than two business days after conclusion of testing.
- D. Adhesive Bond and Compatibility Test Report.
- E. Copy of RFCI (RWP).
- F. Remedial Materials Product Data: Manufacturer's published data on each product to be used for remediation.
 1. Manufacturer's qualification statement.
 2. Manufacturer's statement of compatibility with types of flooring applied over remedial product.
 3. Test reports indicating compliance with specified performance requirements, performed by nationally recognized independent testing agency.
 4. Manufacturer's installation instructions.
 5. Specimen Warranty: Copy of warranty to be issued by coating manufacturer and certificate of underwriter's coverage of warranty.

1.05 QUALITY ASSURANCE

- A. Moisture and alkalinity (pH) testing shall be performed by an independent testing agency employed and paid by Contractor.
- B. Testing Agency Qualifications: Independent testing agency experienced in the types of testing specified.
 1. Submit evidence of experience consisting of at least 3 test reports of the type required, with project Owner's project contact information.
- C. Contractor's Responsibility Relating to Independent Agency Testing:
 1. Provide access for and cooperate with testing agency.
 2. Confirm date of start of testing at least 10 days prior to actual start.
 3. Allow at least 4 business days on site for testing agency activities.
 4. Achieve and maintain specified ambient conditions.
 5. Notify Architect and BYU Construction PM when specified ambient conditions have been achieved and when testing will start.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, handle, and protect products in accordance with manufacturer's instructions and recommendations.
- B. Deliver materials in manufacturer's packaging; include installation instructions.
- C. Keep materials from freezing.

1.07 FIELD CONDITIONS

- A. Maintain ambient temperature in spaces where concrete testing is being performed, and for at least 48 hours prior to testing, at not less than 65 degrees F or more than 85 degrees F.
- B. Maintain relative humidity in spaces where concrete testing is being performed, and for at least 48 hours prior to testing, at not less than 10 percent and not more than 60 percent.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 2 PRODUCTS

2.01 MATERIALS

- A. Patching Compound: Floor covering manufacturer's recommended product, suitable for conditions, and compatible with adhesive and floor covering. In the absence of any recommendation from flooring manufacturer, provide a product with the following characteristics:
 - 1. Cementitious moisture-, mildew-, and alkali-resistant compound, compatible with floor, floor covering, and floor covering adhesive, and capable of being feathered to nothing at edges.
 - 2. Latex or polyvinyl acetate additions are permitted; gypsum content is prohibited.
 - 3. Compressive Strength: 3000 psi, minimum, after 28 days, when tested in accordance with ASTM C109/C109M or ASTM C472, whichever is appropriate.

PART 3 EXECUTION

3.01 CONCRETE SLAB PREPARATION

- A. Follow recommendations of testing agency.
- B. Perform following operations in the order indicated:
 - 1. Preliminary cleaning.
 - 2. Moisture vapor emission tests; 3 tests in the first 1000 square feet and one test in each additional 1000 square feet, unless otherwise indicated or required by flooring manufacturer.
 - 3. Internal relative humidity tests; in same locations as moisture vapor emission tests, unless otherwise indicated.
 - 4. Alkalinity (pH) tests; in same locations as moisture vapor emission tests, unless otherwise indicated.
 - 5. Specified remediation, if required.
 - 6. Patching, smoothing, and leveling, as required.
 - 7. Other preparation specified.
 - 8. Adhesive bond and compatibility test.
 - 9. Protection.
- C. Remediations:
 - 1. Active Water Leaks or Continuing Moisture Migration to Surface of Slab: Correct this condition before doing any other remediation; re-test after correction.
 - 2. Excessive Moisture Emission or Relative Humidity: If an adhesive that is resistant to the level of moisture present is available and acceptable to flooring manufacturer, use that adhesive for installation of the flooring; if not, apply remedial floor coating or remedial sheet membrane over entire suspect floor area.
 - 3. Excessive Alkalinity (pH): If remedial floor coating is necessary to address excessive moisture, no additional remediation is required; if not, if an adhesive that is resistant to the level present is available and acceptable to the flooring manufacturer, use that adhesive for installation of the flooring; otherwise, apply a skim coat of specified patching compound over entire suspect floor area.

3.02 REMOVAL OF EXISTING FLOOR COVERINGS

- A. Comply with local, State, and federal regulations and recommendations of RFCI Recommended Work Practices for Removal of Resilient Floor Coverings, as applicable to floor covering being removed.
- B. Dispose of removed materials in accordance with local, State, and federal regulations and as specified.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.03 PRELIMINARY CLEANING

- A. Clean floors of dust, solvents, paint, wax, oil, grease, asphalt, residual adhesive, adhesive removers, film-forming curing compounds, sealing compounds, alkaline salts, excessive laitance, mold, mildew, and other materials that might prevent adhesive bond.
- B. Do not use solvents or other chemicals for cleaning.

3.04 MOISTURE VAPOR EMISSION TESTING

- A. Where the floor covering manufacturer's requirements conflict with either the referenced test method or this specification, comply with the manufacturer's requirements.
- B. Where this specification conflicts with the referenced test method, comply with the requirements of this section.
- C. Test in accordance with ASTM F1869 and as follows.
- D. Plastic sheet test and mat bond test may not be substituted for the specified ASTM test method, as those methods do not quantify the moisture content sufficiently.
- E. In the event that test values exceed floor covering manufacturer's limits, perform remediation as indicated. In the absence of manufacturer limits, perform remediation if test values exceed 3 pounds per 1000 square feet per 24 hours.
- F. Report: Report the information required by the test method.

3.05 INTERNAL RELATIVE HUMIDITY TESTING

- A. Where the floor covering manufacturer's requirements conflict with either the referenced test method or this specification, comply with the manufacturer's requirements.
- B. Where this specification conflicts with the referenced test method, comply with the requirements of this section.
- C. Test in accordance with ASTM F2170 Procedure A and as follows.
- D. Testing with electrical impedance or resistance apparatus may not be substituted for the specified ASTM test method, as the values determined are not comparable to the ASTM test values and do not quantify the moisture content sufficiently.
- E. In the event that test values exceed floor covering manufacturer's limits, perform remediation as indicated. In the absence of manufacturer limits, perform remediation if any test value exceeds 75 percent relative humidity.
- F. Report: Report the information required by the test method.

3.06 ALKALINITY TESTING

- A. Where the floor covering manufacturer's requirements conflict with either the referenced test method or this specification, comply with the manufacturer's requirements.
- B. The following procedure is the equivalent of that described in ASTM F710, repeated here for the Contractor's convenience.
- C. Use a wide range alkalinity (pH) test paper, its associated chart, and distilled or deionized water.
- D. Place several drops of water on a clean surface of concrete, forming a puddle approximately 1 inch in diameter. Allow the puddle to set for approximately 60 seconds, then dip the alkalinity (pH) test paper into the water, remove it, and compare immediately to chart to determine alkalinity (pH) reading.
- E. In the event that test values exceed floor covering manufacturer's limits, perform remediation as indicated. In the absence of manufacturer limits, perform remediation if alkalinity (pH) test value is over 10.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.07 PREPARATION

- A. See individual floor covering section(s) for additional requirements.
- B. Comply with recommendations of testing agency.
- C. Comply with requirements and recommendations of floor covering manufacturer.
- D. Fill and smooth surface cracks, grooves, depressions, control joints and other non-moving joints, and other irregularities with patching compound.
- E. Do not fill expansion joints, isolation joints, or other moving joints.

3.08 ADHESIVE BOND AND COMPATIBILITY TESTING

- A. Comply with requirements and recommendations of floor covering manufacturer.

3.09 PROTECTION

- A. Cover prepared floors with building paper or other durable covering.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 092116
GYPSUM BOARD ASSEMBLIES**

PART 1 GENERAL

UPDATED 2/21, 10/21

1.01 SECTION INCLUDES

SEE CHANGES IN BOLD

- A. Performance criteria for gypsum board assemblies.
- B. Metal stud wall framing.
- C. Metal channel ceiling framing.
- D. Acoustic insulation.
- E. Gypsum sheathing.
- F. Cementitious backing board.
- G. Gypsum wallboard.
- H. Joint treatment and accessories.
- I. Acoustic (sound-dampening) wall and ceiling board.

1.02 RELATED REQUIREMENTS

- A. Section 016116 - Volatile Organic Compound (VOC) Content Restrictions.
- B. Section 072100 - Thermal Insulation: Acoustic insulation.
- C. Section 072500 - Weather Barriers: Water-resistive barrier over sheathing.
- D. Section 078400 - Firestopping: Top-of-wall assemblies at fire rated walls.
- E. Section 093000 - Tiling: Tile backing board.

1.03 REFERENCE STANDARDS

- A. AISI S100-12 - North American Specification for the Design of Cold-Formed Steel Structural Members; American Iron and Steel Institute; 2012.
- B. ANSI A108.11 - American National Standard Specifications for Interior Installation of Cementitious Backer Units; 2010 (Reaffirmed 2016).
- C. ANSI A118.9 - American National Standard Specifications for Test Methods and Specifications for Cementitious Backer Units; 1999 (Reaffirmed 2016).
- D. ASTM A36/A36M - Standard Specification for Carbon Structural Steel; 2014.
- E. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2015.
- F. ASTM A1003/A1003M - Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members; 2015.
- G. ASTM C475/C475M - Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board; 2015.
- H. ASTM C645 - Standard Specification for Nonstructural Steel Framing Members; 2014.
- I. ASTM C665 - Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing; 2012.
- J. ASTM C754 - Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products; 2017.
- K. ASTM C840 - Standard Specification for Application and Finishing of Gypsum Board; 2016.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- L. ASTM C954 - Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs From 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness; 2015.
- M. ASTM C1002 - Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs; 2016.
- N. ASTM C1047 - Standard Specification for Accessories For Gypsum Wallboard and Gypsum Veneer Base; 2014a.
- O. ASTM C1177/C1177M - Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing; 2013.
- P. ASTM C1178/C1178M - Standard Specification for Coated Glass Mat Water-Resistant Gypsum Backing Panel; 2013.
- Q. ASTM C1280 - Standard Specification for Application of Exterior Gypsum Panel Products for Use as Sheathing; 2013a.
- R. ASTM C1288 - Standard Specification for Discrete Non-Asbestos Fiber-Cement Interior Substrate Sheets; 2014.
- S. ASTM C1325 - Specification for Non-Asbestos Fiber-Mat Reinforced Cementitious Backer Units; 2017.
- T. ASTM C1396/C1396M - Standard Specification for Gypsum Board; 2014a.
- U. ASTM C1629/C1629M - Standard Classification for Abuse-Resistant Nondecorated Interior Gypsum Panel Products and Fiber-Reinforced Cement Panels; 2015.
- V. ASTM D3273 - Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber; 2016.
- W. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009 (Reapproved 2016).
- X. GA-216 - Application and Finishing of Gypsum Board; 2016.
- Y. GA-226 - Application of Gypsum Board to Form Curved Surfaces; Gypsum Association; 2016.
- Z. GA-600 - Fire Resistance Design Manual; 2015.
- AA. UL (FRD) - Fire Resistance Directory; current edition.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate special details associated with fireproofing and acoustic seals.
- C. Product Data: Provide data on metal framing, gypsum board, accessories, and joint finishing system.
- D. Product Data: Provide manufacturer's data on partition head to structure connectors, showing compliance with requirements.
- E. Submit structural calculations and details stamped by a structural engineer licensed in the state of Utah showing the design of the members and their attachment to each other and to the building structure. **THE STRUCTURAL DESIGN MUST BE REVIEWED AND APPROVED BY THE STRUCTURAL ENGINEER OF RECORD.**

1.05 QUALITY ASSURANCE

- A. Installer Qualifications: Company specializing in performing gypsum board installation and finishing, with minimum 3 years of experience.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 2 PRODUCTS

2.01 GYPSUM BOARD ASSEMBLIES

- A. Provide completed assemblies complying with ASTM C840 and GA-216.
 - 1. See PART 3 for finishing requirements.
- B. Interior Partitions: Provide completed assemblies with the following characteristics:
 - 1. Acoustic Attenuation: STC as indicated calculated in accordance with ASTM E413, based on tests conducted in accordance with ASTM E90.
- C. Shaft Walls at HVAC Shafts: Provide completed assemblies with the following characteristics:
 - 1. Air Pressure Within Shaft: Sustained loads of 5 lb./sq ft with maximum mid-span deflection of L/240.
 - 2. Acoustic Attenuation: STC of 35-39 calculated in accordance with ASTM E413, based on tests conducted in accordance with ASTM E90.
- D. Fire Rated Assemblies: Provide completed assemblies with the following characteristics:
 - 1. Fire Rated Partitions: UL listed assembly No. _____; ___ hour rating.
 - 2. Fire Rated Ceilings and Soffits: One (1) hour fire rating.
 - 3. Fire Rated Structural Column Framing: UL listed assembly No. _____; ___ hour rating.
 - 4. Fire Rated Structural Beam Framing: UL listed assembly No. _____; ___ hour rating.
 - 5. Fire Rated Shaft Walls: UL listed assembly No. _____; ___ hour rating.
 - 6. Fire Rated Area Separation Walls: UL listed assembly No. _____; 1 hour rating.
 - 7. UL Assembly Numbers: Provide construction equivalent to that listed for the particular assembly in the current UL (FRD).

2.02 METAL FRAMING MATERIALS

- A. Manufacturers - Metal Framing, Connectors, and Accessories:
 - 1. Clarkwestern Dietrich Building Systems LLC; ____: www.clarkdietrich.com
 - 2. Jaimes Industries; ____: www.jaimesind.com
 - 3. Marino; ____: www.marinoware.com
 - 4. Phillips Manufacturing Co; ____: www.phillipsmfg.com
 - 5. **CEMCO Steel; www.cemcosteel.com** **Updated 2/21**
- B. Non-Loadbearing Framing System Components: ASTM C645; galvanized sheet steel, of size and properties necessary to comply with ASTM C754 for the spacing indicated, with maximum deflection of wall framing of L/360 at 5 psf.
 - 1. Studs: "C" shaped with flat or formed webs with knurled faces. (1 5/8" x 3 5/8" wide Typical at interior walls - 1 5/8" x 6" studs typical at exterior walls)
 - 2. Runners: U shaped, sized to match studs.
 - 3. Ceiling Channels: C-shaped.
 - 4. Furring: Hat-shaped sections, minimum depth of 7/8 inch.
 - 5. Resilient Furring Channels: 1/2 inch depth, for attachment to substrate through both legs; both legs expanded metal mesh.
 - a. Products:
 - 1) Same manufacturer as other framing materials.
- C. Shaft Wall Studs and Accessories: ASTM C645; galvanized sheet steel, of size and properties necessary to comply with ASTM C754 and specified performance requirements.
 - 1. Products:
 - a. Same manufacturer as other framing materials.
- D. Area Separation Wall Studs and Accessories: ASTM C645; galvanized sheet steel, of size and properties necessary to comply with specified performance requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- E. Ceiling Hangers: Type and size as specified in ASTM C754 for spacing required.
- F. Partition Head To Structure Connections: Provide track fastened to structure with legs of sufficient length to accommodate deflection, for friction fit of studs cut short and fastened as indicated on drawings.
- G. Non-Loadbearing Framing Accessories:
 - 1. Ceiling Hangers: Type and size as specified in ASTM C754 for spacing required.
 - 2. Partial Height Wall Framing Support: Provides stud reinforcement and anchored connection to floor.
 - a. Materials: ASTM A36/A36M formed sheet steel support member with factory-welded ASTM A1003/A1003M steel plate base.
 - 3. Framing Connectors: ASTM A653/A653M G90 galvanized steel clips; secures cold rolled channel to wall studs for lateral bracing.

2.03 BOARD MATERIALS

- A. Manufacturers - Gypsum-Based Board:
 - 1. American Gypsum Company; ____: www.americangypsum.com
 - 2. CertainTeed Corporation; ____: www.certainteed.com
 - 3. Georgia-Pacific Gypsum; Dense Shield Tile Baker: www.gpgypsum.com.
 - 4. USG Corporation; ____: www.usg.com
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Gypsum Wallboard: Paper-faced gypsum panels as defined in ASTM C1396/C1396M; sizes to minimize joints in place; ends square cut.
 - 1. Application: Use for vertical surfaces and ceilings, unless otherwise indicated.
 - 2. At Assemblies Indicated with Fire-Rating: Use type required by indicated tested assembly; if no tested assembly is indicated, use Type X board, UL or WH listed.
 - 3. Thickness:
 - a. Vertical Surfaces: 5/8 inch.
 - b. Ceilings: 5/8 inch.
 - c. ____: 1/4 inch.
 - d. Multi-Layer Assemblies: Thicknesses as indicated on drawings.
 - 4. Paper-Faced Products:
 - a. American Gypsum Company; FireBloc Type X Gypsum Wallboard.
 - b. Continental Building Products; Firecheck Type X.
 - c. Georgia-Pacific Gypsum; ToughRock Fireguard X.
 - d. National Gypsum Company; Gold Bond BRAND Fire-Shield Gypsum Board.
- C. Abuse Resistant Wallboard:
 - 1. Application: High-traffic areas indicated.
 - 2. Surface Abrasion: Level 2, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 3. Indentation: Level 1, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 4. Soft Body Impact: Level 1, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 5. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - 6. Paper-Faced Type: Gypsum wallboard as defined in ASTM C1396/C1396M.
 - 7. Type: Fire resistance rated Type X, UL or WH listed.
 - 8. Thickness: 5/8 inch.
 - 9. Edges: Tapered.
 - 10. Paper-Faced Products:
 - a. American Gypsum Company; M-Bloc AR Type X.
 - b. CertainTeed Corporation; Extreme Abuse Resistant Drywall with M2Tech.
 - c. Continental Building Products; Protecta AR 100 Type X with Mold Defense.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- d. Georgia-Pacific Gypsum; ToughRock Fireguard X Mold Guard Abuse-Resistant.
 - e. National Gypsum Company; Gold Bond Hi-Abuse XP Gypsum Board.
11. Products:
- a. American Gypsum Company; M-Bloc AR Type X.
 - b. Continental Building Products; Protecta AR 100 Type X with Mold Defense.
 - c. Continental Building Products; Rapid Deco Level 5 Type X with Protecta.
 - d. Georgia-Pacific Gypsum; ToughRock Fireguard X Mold Guard Abuse-Resistant.
 - e. National Gypsum Company; Gold Bond Hi-Abuse XP Gypsum Board.
- D. Impact Resistant Wallboard:
- 1. Application: High-traffic areas indicated.
 - 2. Surface Abrasion: Level 3, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 3. Indentation: Level 1, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 4. Soft Body Impact: Level 3, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 5. Hard Body Impact: Level 2, minimum, when tested in accordance with ASTM C1629/C1629M.
 - 6. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - 7. Paper-Faced Type: Gypsum wallboard as defined in ASTM C1396/C1396M.
 - 8. Type: Fire resistance rated Type X, UL or WH listed.
 - 9. Thickness: 5/8 inch.
 - 10. Edges: Tapered.
 - 11. Products:
 - a. American Gypsum Company; M-Bloc IR Type X.
 - b. Continental Building Products; Protecta HIR 300 Type X with Mold Defense.
 - c. National Gypsum Company; Gold Bond HI-Impact XP Gypsum Board.
 - d. Substitutions: See Section 016000 - Product Requirements.
- E. Backing Board For Wet Areas: One of the following products:
- 1. Application: Surfaces behind tile in wet areas including tub and shower surrounds and shower ceilings.
 - 2. Application: Horizontal surfaces behind tile in wet areas including countertops.
 - 3. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - 4. ANSI Cement-Based Board: Non-gypsum-based; aggregated Portland cement panels with glass fiber mesh embedded in front and back surfaces complying with ANSI A118.9 or ASTM C1325.
 - a. **Thickness: 5/8 inch. Update 10/21**
 - b. Products:
 - 1) National Gypsum Company; PermaBase Cement Board: www.nationalgypsum.com
 - 2) USG Corporation: www.usg.com
 - 5. ASTM Cement-Based Board: Non-gypsum-based, cementitious board complying with ASTM C1288.
 - a. **Thickness: 5/8 inch. Update 10/21**
 - b. Products:
 - 1) James Hardie Building Products, Inc; HardiBacker: www.jameshardie.com
 - 2) USG Durock Cement Board.
 - 3) Substitutions: See Section 016000 - Product Requirements.
 - 6. **Glass Mat Faced Board: Coated glass mat water-resistant gypsum backing panel as defined in ASTM C1178/C1178M. Update 10/21**
 - a. **Regular Type: Thickness 5/8 inch. (16 mm).**
 - b. **Fire-Resistance-Rated Type: Type X core, thickness 5/8 inch. (16 mm).**
 - c. **Products:**
 - 1) **CertainTeed Corporation; Diamondback Tile Backer: www.certainteed.com**

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 2) **CertainTeed Corporation; Diamondback Type X Tile Backer: www.certainteed.com**
- 3) **Georgia-Pacific Gypsum; DensShield Tile Backer: www.gpgypsum.com**
- 4) **Georgia-Pacific Gypsum; DensShield Fireguard Tile Backer; www.gpgypsum.com**
- 5) **Substitutions: See Section 016000 - Product Requirements.**

- F. Exterior Sheathing Board: Sizes to minimize joints in place; ends square cut.
 - 1. Application: Exterior sheathing, unless otherwise indicated.
 - 2. Glass Mat Faced Sheathing: Glass mat faced gypsum substrate as defined in ASTM C1177/C1177M.
 - 3. Paper-Faced Sheathing: Gypsum sheathing board as defined in ASTM C1396/C1396M, moisture resistant type with water repellent paper faces.
 - 4. At Assemblies Indicated with Fire-Rating: Use type required by indicated tested assembly; if no tested assembly is indicated, use Type X board, UL or WH listed.
 - 5. **Core Type: Regular and Type X, as indicated.** **Update 10/21**
 - 6. Type X Thickness: 5/8 inch.
 - 7. **Regular Board Thickness: 5/8 inch.** **Update 10/21**
 - 8. Edges: Square.
 - 9. **Glass Mat Faced Products:** **Update 10/21**
 - a. **American Gypsum Company; M-Glass Exterior Sheathing Type X. www.americangypsum.com.**
 - b. **American Gypsum Company; M-Glass 5/8" Exterior Sheathing: www.americangypsum.com**
 - c. **CertainTeed Corporation; GlasRoc 5/8" Exterior Sheathing: www.certainteed.com**
 - d. **CertainTeed Corporation; GlasRoc Type X Exterior Sheathing: www.certainteed.com**
 - e. **Georgia-Pacific Gypsum; DensGlass Sheathing.**
 - f. **Georgia-Pacific Gypsum; DensGlass Fireguard Sheathing.**
 - g. **USG Corporation; USG Securock Brand Ultralight Glass-Mat Sheathing: www.usg.com**
 - h. **USG Corporation; USG Securock Brand Ultralight Glass-Mat Sheathing Firecode X: www.usg.com**
 - i. **Substitutions: See Section 016000 - Product Requirements.**
 - 10. Paper-Faced Products:
 - a. American Gypsum Company; Exterior Gypsum Sheathing.
 - b. CertainTeed Corporation; Type X Sheathing Treated Core.
 - c. Substitutions: See Section 016000 - Product Requirements.

2.04 ACCESSORIES

- A. **Acoustic Insulation: As specified in Section 072100.** **Updated 10/21**
- B. Acoustic Sealant: Acrylic emulsion latex or water-based elastomeric sealant; do not use solvent-based non-curing butyl sealant.
- C. Water-Resistive Barrier: As specified in Section 072500.
- D. Beads, Joint Accessories, and Other Trim: ASTM C1047, rigid plastic, galvanized steel, or rolled zinc, unless noted otherwise.
 - 1. Rigid Corner Beads: Low profile, for 90 degree outside corners.
 - 2. Expansion Joints:
- E. Joint Materials: ASTM C475/C475M and as recommended by gypsum board manufacturer for project conditions.
 - 1. Tape: 2 inch wide, coated glass fiber tape for joints and corners, except as otherwise indicated.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Tape: 2 inch wide, creased paper tape for joints and corners, except as otherwise indicated.
 3. Ready-mixed vinyl-based joint compound.
 4. Powder-type vinyl-based joint compound.
 5. Chemical hardening type compound.
 6. Thinsets and mastics for backerboard installations.
- F. High Build Drywall Surfer: Vinyl acrylic latex-based coating for spray application, designed to take the place of skim coating and separate paint primer in achieving Level 5 finish.
1. Products:
 - a. CertainTeed Corporation; Level V Wall and Ceiling Primer/Surfer with M2Tech:
www.certainteed.com
- G. Screws for Fastening of Gypsum Panel Products to Cold-Formed Steel Studs Less than 0.033 inch in Thickness and Wood Members: ASTM C1002; self-piercing tapping screws, corrosion resistant.
- H. Screws for Fastening of Gypsum Panel Products to Steel Members from 0.033 to 0.112 inch in Thickness: ASTM C954; steel drill screws, corrosion resistant.
- I. Anchorage to Substrate: Tie wire, nails, screws, and other metal supports, of type and size to suit application; to rigidly secure materials in place.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that project conditions are appropriate for work of this section to commence.

3.02 SHAFT WALL INSTALLATION

- A. Shaft Wall Framing: Install in accordance with manufacturer's installation instructions.
1. Fasten runners to structure with short leg to finished side, using appropriate power-driven fasteners at not more than 24 inches on center.
 2. Install studs at spacing required to meet performance requirements.
- B. Shaft Wall Liner: Cut panels to accurate dimension and install sequentially between special friction studs.

3.03 FRAMING INSTALLATION

- A. Metal Framing: Install in accordance with ASTM C754 and manufacturer's instructions.
- B. Suspended Ceilings and Soffits: Space framing and furring members as indicated.
1. Level ceiling system to a tolerance of 1/1200.
 2. Laterally brace entire suspension system.
 3. Install bracing as required at exterior locations to resist wind uplift.
- C. Studs: Space studs at 16 inches on center.
1. Extend partition framing to structure where indicated and to ceiling in other locations..
 2. Partitions Terminating at Ceiling: Attach ceiling runner securely to ceiling track in accordance with manufacturer's instructions.
 3. Partitions Terminating at Structure: Attach extended leg top runner to structure, maintain clearance between top of studs and structure, and brace both flanges of studs with continuous bridging.
 4. Partitions Terminating at Structure: Attach top runner to structure, maintain clearance between top of studs and structure, and connect studs to track using specified mechanical devices in accordance with manufacturer's instructions; verify free movement of top of stud connections; do not leave studs unattached to track.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- D. Openings: Reinforce openings as required for weight of doors or operable panels, using not less than double studs at jambs.
- E. Standard Wall Furring: Install at concrete walls scheduled to receive gypsum board, not more than 4 inches from floor and ceiling lines and abutting walls. Secure in place on alternate channel flanges at maximum 16 inches on center.
 - 1. Orientation: Vertical.
 - 2. Spacing: As indicated.
- F. Acoustic Furring: Install resilient channels at maximum 24 inches on center. Locate joints over framing members.
- G. Furring for Fire Ratings: Install as required for fire resistance ratings indicated.
- H. Blocking: Install mechanically fastened steel sheet blocking for support of:
 - 1. Framed openings.
 - 2. Wall mounted cabinets.
 - 3. Plumbing fixtures.
 - 4. Toilet partitions.
 - 5. Toilet accessories.
 - 6. Wall mounted door hardware.

3.04 ACOUSTIC ACCESSORIES INSTALLATION

- A. Acoustic Insulation: Place tightly within spaces, around cut openings, behind and around electrical and mechanical items within partitions, and tight to items passing through partitions.
- B. Acoustic Sealant: Install in accordance with manufacturer's instructions.
 - 1. Place one bead continuously on substrate before installation of perimeter framing members.
 - 2. Place continuous bead at perimeter of each layer of gypsum board.
 - 3. Seal around all penetrations by conduit, pipe, ducts, and rough-in boxes, except where firestopping is provided.

3.05 BOARD INSTALLATION

- A. **Comply with ASTM C840, GA-216, and manufacturer's instructions. Install interior gypsum board horizontally, especially in Corridors and Highly Visible Locations.**
- B. Fire-Rated Construction: Install gypsum board in strict compliance with requirements of assembly listing.
- C. Exposed Gypsum Board in Interior Wet Areas: Seal joints, cut edges, and holes with water-resistant sealant.
- D. **Exterior Sheathing: Comply with ASTM C1280. Install sheathing vertically, with edges butted tight and ends occurring over firm bearing. Updated 10/21**
 - 1. Paper-Faced Sheathing: Immediately after installation, protect from weather by application of water-resistive barrier.
- E. Cementitious Backing Board: Install over steel framing members and plywood substrate where indicated, in accordance with ANSI A108.11 and manufacturer's instructions.
- F. Installation on Metal Framing: Use screws for attachment of gypsum board.
- G. Curved Surfaces: Apply gypsum board to curved substrates in accordance with GA-226.

3.06 INSTALLATION OF TRIM AND ACCESSORIES

- A. Control Joints: Place control joints consistent with lines of building spaces and as indicated.
 - 1. Not more than 30 feet apart on walls and ceilings over 50 feet long.
 - 2. At exterior soffits, not more than 30 feet apart in both directions.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Corner Beads: Install at external corners, using longest practical lengths.
- C. Edge Trim: Install at locations where gypsum board abuts dissimilar materials.
- D. Exterior Soffit Vents: Install according to manufacturer's written instructions and in locations indicated on drawings. Provide vent area specified.
- E. Exposed finished raw edges are not allowed.
- F. All metal fittings to be bedded and finished to designated finish level.

3.07 JOINT TREATMENT

- A. Glass Mat Faced Gypsum Board and Exterior Glass Mat Faced Sheathing: Use fiberglass joint tape, bedded and finished with chemical hardening type joint compound.
- B. Paper Faced Gypsum Board: Use paper joint tape, bedded with ready-mixed vinyl-based joint compound and finished with ready-mixed vinyl-based joint compound.
- C. Finish gypsum board in accordance with levels defined in ASTM C840, as follows:
 - 1. Level 5: Walls and ceilings to receive semi-gloss or gloss paint finish and other areas specifically indicated.
 - 2. Level 4: Walls and ceilings to receive paint finish or wall coverings, unless otherwise indicated.
 - 3. Level 2: In utility areas, behind cabinetry, and on backing board to receive tile finish.
 - 4. Level 1: Fire rated wall areas above finished ceilings, whether or not accessible in the completed construction.
- D. Tape, fill, and sand exposed joints, edges, and corners to produce smooth surface ready to receive finishes.
 - 1. Feather coats of joint compound so that camber is maximum 1/32 inch.
 - 2. Taping, filling, and sanding is not required at surfaces behind adhesive applied ceramic tile and fixed cabinetry.
- E. Where Level 5 finish is indicated, spray apply high build drywall surfacer over entire surface after joints have been properly treated; achieve a flat and tool mark-free finish.

3.08 TOLERANCES

- A. Maximum Variation of Finished Gypsum Board Surface from True Flatness: 1/8 inch in 10 feet in any direction.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 095100
ACOUSTICAL CEILINGS**

PART 1 GENERAL

1.01 SECTION INCLUDES

UPDATED OCTOBER 2022

- A. Suspended metal grid ceiling system.
- B. Acoustical units.
- C. Supplementary acoustical insulation above ceiling.

1.02 RELATED REQUIREMENTS

1.03 REFERENCE STANDARDS

- A. ASTM C635/C635M - Standard Specification for the Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings; 2013a.
- B. ASTM C636/C636M - Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels; 2013.
- C. ASTM E580/E580M - Standard Practice for Installation of Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels in Areas Subject to Earthquake Ground Motions; 2016.
- D. ASTM E1264 - Standard Classification for Acoustical Ceiling Products; 2014.
- E. UL (FRD) - Fire Resistance Directory; current edition.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Sequence work to ensure acoustical ceilings are not installed until building is enclosed, sufficient heat is provided, dust generating activities have terminated, and overhead work is completed, tested, and approved.
- B. Do not install acoustical units until after interior wet work is dry.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on suspension system components.
- C. Samples: Submit two samples 4x4 inch in size illustrating material and finish of acoustical units.
- D. Samples: Submit two samples each, 12 inches long, of suspension system main runner.
- E. Manufacturer's Installation Instructions: Indicate special procedures. Include information relative to compliance with seismic requirements contained in the International Building Code (IBC).
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
 - 2. Extra Acoustical Units: Quantity equal to 1 percent of total installed, not less than 100 sf.

1.06 QUALITY ASSURANCE

- A. Fire-Resistive Assemblies: Complete assembly listed and classified by 1 for the fire resistance indicated.
- B. Suspension System Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- C. Acoustical Unit Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.07 FIELD CONDITIONS

- A. Maintain uniform temperature of minimum 60 degrees F, and maximum humidity of 40 percent prior to, during, and after acoustical unit installation.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Acoustic Tiles/Panels:
 - 1. Armstrong World Industries, Inc: www.armstrong.com.
 - 2. USG: www.usg.com.
- B. Suspension Systems:
 - 1. Same as for acoustical units.
 - 2. Armstrong World Industries, Inc; Prelude XL: www.armstrong.com.
 - 3. USG; DONN DX/DL: www.usg.com.

2.02 ACOUSTICAL UNITS

- A. Acoustical Units - General: ASTM E1264, Class A.
 - 1. Units for Installation in Fire-Rated Suspension System: Listed and classified for the fire-resistive assembly as part of suspension system.
 - 2. VOC Content: Certified as Low Emission by one of the following:
- B. **Acoustical Panels Type ACT-1:** **Updated Oct 2022**
 - 1. **Size: 24 by 24 inches.**
 - 2. **Panel Edge: Square .**
 - 3. **Surface Pattern: Perforated.**
 - 4. **Surface Color: White.**
 - 5. **Suspension System: Exposed grid.**
 - 6. **Products:**
 - a. **USG Radar 22421.**
 - b. **Armstrong Fine Fissured 1713.**
- C. **Acoustical Panels Type ACT-2:**
 - 1. **Size: 24 by 24 inches,**
 - 2. **Panel Edge: Tegular.**
 - 3. **Surface Pattern: Perforated.**
 - 4. **Surface Color: White.**
 - 5. **Suspension System: Exposed grid.**
 - 6. **Products:**
 - a. **USG Frost 484.**
 - b. **Armstrong Ultima High NRC 1941A.**
- D. **Acoustical Panels Type ACT-3:**
 - 1. **Size: 24 by 24 inches.**
 - 2. **Panel Edge: Tegular.**
 - 3. **Surface Pattern: Perforated.**
 - 4. **Surface Color: White.**
 - 5. **Suspension System: Exposed grid.**
 - 6. **Products:**
 - a. **USG Sandrift 808.**

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.03 SUSPENSION SYSTEM(S)

- A. Suspension Systems - General: Complying with ASTM C635/C635M; die cut and interlocking components, with stabilizer bars, clips, splices, perimeter moldings, and hold down clips as required.
- B. Exposed Suspension System: Formed steel, commercial quality cold rolled; heavy-duty.
 - 1. Profile: Tee; 15/16 inch wide face.
 - 2. Construction: Double web.
 - 3. Finish: White Painted.
- C. Fire-Rated Exposed Steel Suspension System: Formed steel, commercial quality cold rolled; light-duty.
 - 1. Profile: Tee; 15/16 inch wide face.
 - 2. Construction: Double web.
 - 3. Fire Rating: Listed and classified for use in a 1 hour fire-resistive assembly.
 - 4. Finish: White painted.

2.04 ACCESSORIES

- A. Support Channels and Hangers: Galvanized steel; size and type to suit application, seismic requirements, and ceiling system flatness requirement specified.
- B. Perimeter Moldings: Same material and finish as grid.
 - 1. At Exposed Grid: Provide L-shaped molding for mounting at same elevation as face of grid.
- C. Touch-up Paint: Type and color to match acoustical and grid units.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that layout of hangers **and compression struts** will not interfere with other work.

3.02 INSTALLATION - SUSPENSION SYSTEM

- A. Install suspension system in accordance with manufacturer's instructions and as supplemented in this section. The installed system must comply with the International Building Code including the seismic requirements of the code and ASTM 580.
- B. Rigidly secure system, including integral mechanical and electrical components, for maximum deflection of 1:360.
- C. Locate system on room axis according to the reflected ceiling plan. Any changes to the ceiling layout must be approved by the owner and architect.
- D. Install after major above-ceiling work is complete. Coordinate the location of hangers **and compression struts** with other work. The suspension system must attach to structure and not to the work of any other trades. **Updated Oct 2022**
- E. Provide hanger clips during steel deck erection. Provide additional hangers and inserts as required.
- F. Hang suspension system independent of walls, columns, ducts, pipes and conduit. Where carrying members are spliced, avoid visible displacement of face plane of adjacent members.
- G. Where ducts or other equipment prevent the regular spacing of hangers, reinforce the nearest affected hangers and related carrying channels to span the extra distance.
- H. Do not support components on main runners or cross runners if weight causes total dead load to exceed deflection capability. Refer to manufacture engineering requirements for limitations.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- I. Support fixture loads using supplementary hangers located within 6 inches of each corner, or support components independently. Fixtures and equipment exceeding 56 pounds shall be supported to the structure by hangers approved by the ceiling manufacturer.
- J. Do not eccentrically load system or induce rotation of runners.
- K. Perimeter Molding: Install at intersection of ceiling and vertical surfaces and at junctions with other interruptions.
 - 1. Use longest practical lengths.
 - 2. Overlap and rivet corners.
- L. Install USG ACM-7 seismic clips or Armstrong BERC seismic clips in accordance with manufacture recommendations on all perimeter material less than 2". Install seismic clips strategically on wall side versus soffit site when grid terminates in perimeter molding at a soffit line.
- M. Each grid member that comes into the perimeter shall be supported by suspension wire connected to structure within 8" of the perimeter. The angle of the wire shall be less than 1 in 6. See ASTM 580/580M.
- N. Perimeter moldings shall be attached to studs or backing unless approved otherwise by owner and architect.
- O. Partition walls that connect to the ceiling grid below shall also be braced to the structure above using stud kickers @ 8'-0" o.c..
- P. Leave all ceiling grid work open and accessible as required for inspection by the BYU Construction PM before proceeding to place the ceiling tile in the grid.

3.03 INSTALLATION - ACOUSTICAL UNITS

- A. Install acoustical units in accordance with manufacturer's instructions.
- B. Fit acoustical units in place, free from damaged edges or other defects detrimental to appearance and function.
- C. Fit border trim neatly against abutting surfaces.
- D. Install units after above-ceiling work is complete.
- E. Install acoustical units level, in uniform plane, and free from twist, warp, and dents.
- F. Cutting Acoustical Units:
 - 1. Cut to fit irregular grid and perimeter edge trim.
 - 2. Make field cut edges of same profile as factory edges.
- G. Where round obstructions occur, provide preformed closures to match perimeter molding.
- H. Install hold-down clips on each panel to retain panels tight to grid system; comply with fire rating requirements.
- I. Install hold-down clips on panels within 20 ft of an exterior door.

3.04 TOLERANCES

- A. Maximum Variation from Flat and Level Surface: 1/8 inch in 10 feet.
- B. Maximum Variation from Plumb of Grid Members Caused by Eccentric Loads: 2 degrees.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 096813
TILE CARPETING**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Preparation for Not-in- Contract Carpet and base installation. The carpet and base will be furnished and installed by the owner.

1.02 REFERENCE STANDARDS

- A. ASTM F710 - Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2011.

1.03 FIELD CONDITIONS

- A. Store materials in area of installation for minimum period of 24 hours prior to installation.

PART 3 EXECUTION

2.01 EXAMINATION

- A. Verify that sub-floor surfaces are smooth and flat within tolerances specified for that type of work and are ready to receive carpet tile.
- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive carpet tile and wall base.
- C. Verify that sub-floor surfaces are dust-free and free of substances that could impair bonding of adhesive materials to sub-floor surfaces.
- D. Cementitious Sub-floor Surfaces: Verify that substrates are dry enough and ready for flooring installation by testing for moisture and pH.
 - 1. Test in accordance with ASTM F710.
 - 2. Obtain instructions if test results are not within limits recommended by flooring material manufacturer and adhesive materials manufacturer.
- E. Verify that required floor-mounted utilities are in correct location.

2.02 PREPARATION

- A. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- B. Remove sub-floor ridges and bumps. Fill minor or local low spots, cracks, joints, holes, and other defects with sub-floor filler.
- C. Apply, trowel, and float filler to achieve smooth, flat, hard surface. Prohibit traffic until filler is cured.
- D. Vacuum clean substrate.

2.03 CLEANING

- A. Remove excess adhesive without damage, from floor, base, and wall surfaces.
- B. Clean and vacuum carpet surfaces.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 096900
ACCESS FLOORING**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Adjustable height access flooring systems.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete: Requirements for floor flatness and levelness.
- B. Section 211300 - Fire-Suppression Sprinkler Systems: Underfloor fire extinguishing system.
- C. Section 238124 - Computer Room Air Conditioners - Floor Mounted.
- D. Section 260526 - Grounding and Bonding for Electrical Systems: Grounding and bonding of access floor system to building grounding system.
- E. Section 284600 - Fire Detection and Alarm: Underfloor smoke detection system.

1.03 REFERENCE STANDARDS

- A. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.
- B. ASCE 7 - Minimum Design Loads for Buildings and Other Structures; 2010, with 2013 Supplements and Errata.
- C. ASTM E2322 - Standard Test Method for Conducting Transverse and Concentrated Load Tests on Panels used in Floor and Roof Construction; 2003 (Reapproved 2015).
- D. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- E. CISCA (AF) - Recommended Test Procedures for Access Floors; 2007.
- F. ICC (IBC) - International Building Code; 2015.
- G. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2017.
- H. ICC-ES AC151 - Acceptance Criteria for Fixed-height, Low-profile, Raised Floor Systems; 2007.
- I. ICC-ES AC300 - Acceptance Criteria for Access Floors; 2010, with Editorial Revision (2014).
- J. NEMA LD 3 - High-Pressure Decorative Laminates; 2005.
- K. NFPA 75 - Standard for the Fire Protection of Information Technology Equipment; 2017.
- L. UL (FRD) - Fire Resistance Directory; current edition.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene one week before starting work of this section.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's data sheets including loading capacities, materials, finishes, dimensions of components, profiles, and accessories.
- C. Shop Drawings: Indicate floor layout, appurtenances or interruptions, edge details, ramps, grilles, registers, and stairs.
- D. Samples: Submit two samples of floor grid and panel, 12 by 12 inch in size illustrating finish.
- E. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.
- F. Manufacturer's Instructions: Indicate special procedures, perimeter conditions requiring special attention.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- G. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
 - 2. Panel Lifting Devices: One, of manufacturer's standard type.

1.06 QUALITY ASSURANCE

- A. Designer Qualifications: Design floor system structure layout for this project under direct supervision of a Professional Structural Engineer experienced in design of floors of the type required and licensed in Utah.
- B. Manufacturer Qualifications: Company specializing in manufacturing the types of products specified in this section, with minimum three years of documented experience.
- C. Installer Qualifications: Company specializing in performing the type of work required in this section and approved by access flooring manufacturer. Company must have a minimum of three years' experience installing this type of flooring.

1.07 MOCK-UP

- A. Construct access flooring system mock-up, 8 feet long by 8 feet wide, showing specified components and accessories.
- B. Locate where directed.
- C. Mock-up may remain as part of the Work.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Access Flooring - Adjustable Height:
 - 1. ASM Modular Systems, Inc; ____: www.asmproducts.com
 - 2. Haworth; ____: www.haworth.com
 - 3. Tate Access Floors, Inc; ____: www.tateaccessfloors.com
 - 4. Substitutions: See Section 016000 - Product Requirements.

2.02 PERFORMANCE REQUIREMENTS

- A. General: Comply with the following system requirements and as indicated for specified components.
 - 1. Test in accordance with CISCA (AF).
 - 2. Conform to requirements of NFPA 75.
 - 3. Conform to requirements of ICC-ES AC300.
 - 4. Conform to requirements of ICC-ES AC151.
 - 5. Accessibility: Conform to ICC A117.1 and ADA Standards.
 - 6. Structural Design Live Loads: Conform to requirements of ICC (IBC).
 - a. Uniformly Distributed Loads: In conformance with ICC (IBC) Table 1607.1, for access floor systems.
 - 1) Office Use: 50 pounds per sq ft.
 - 2) Computer Use: 100 pounds per sq ft.
 - b. Concentrated Loads: Over an area of 2.5 feet by 2.5 feet, 2000 pounds minimum, in conformance with ICC (IBC) Table 1607.1, for access floor systems.
 - 7. Seismic Performance: Access flooring designed to withstand effects of earthquake motions determined according to ASCE 7.
 - 8. Lateral Stability: Design system for lateral stability in all directions, with or without panels in place.
- B. Uniform Load: 200 pounds per square foot, when tested in accordance with CISCA (AF) and ASTM E2322.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Maximum Deflection: 0.04 inch.
- C. Concentrated Load: Over an area of 1 inch by 1 inch, 900 pounds at any location, when tested in accordance with CISCA (AF).
- D. Rolling Loads: Permanent deformation not to exceed 0.04 inch, when tested in accordance with CISCA (AF).
 1. Wheel A: 10 passes, with loading of 400 pounds.
 2. Wheel B: 10,000 passes, with loading of 400 pounds.
 3. Wheel C: 10,000 passes, with loading of 1500 pounds.
- E. Drop Impact Load: 75 pounds, when tested in accordance with CISCA (AF).
- F. Surface Burning Characteristics: Flame spread index of 25, maximum; smoke developed index of 75, maximum; when tested in accordance with ASTM E84.
- G. Electrical Grounding Connection: Listed and classified by Underwriters Laboratories as suitable for the purpose specified and indicated.

2.03 ACCESS FLOORING - ADJUSTABLE HEIGHT

- A. Factory-fabricated system consisting of removable floor panels and supporting understructure that allows access to space below floor without requiring removal of panels other than the one directly above the space to which access is needed; provide components and accessories required for complete installation.
- B. Configuration:
 1. Lay-in panels on bolted stringer understructure.
 2. Bolted panels on bolted stringer understructure.
- C. Components:
 1. Pedestal Assembly:
 - a. Material: Steel.
 - b. Finish: Manufacturer's standard.
 - c. Base: Manufacturer's standard shape and size in accordance with system performance requirements.
 - d. Column: Threaded supporting rod to permit 1-1/2 inch adjustment.
 - e. Head: Manufacturer's standard shape and size to accept specified configuration.
 - f. Maximum Pedestal Axial Load: 5000 pounds without permanent deformation, when tested in accordance with CISCA (AF).
 - g. Pedestal assembly must meet IBC seismic requirements.
 2. Stringers: Steel channels, box, or tee sections.
 - a. Stringer Load: 225 pounds, with a permanent set not to exceed 0.010 inch, when tested in accordance with CISCA (AF).
 3. Floor Panels:
 - a. Construction:
 - 1) Concrete core laminated with sheet steel plates.
 - 2) Perforated Floor Panels: Same material, size, and construction as floor panels with slide dampers for controlled air circulation.
 - b. Factory-Applied Finish: As selected from manufacturer's standard finishes for panel type specified.

2.04 ACCESSORIES - ADJUSTABLE HEIGHT

- A. Fascia Panels: Laminated construction as follows:
 1. Front and Back Face Sheets: Aluminum sheet, _____ inch thick.
 2. Core: Plywood.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Accessories: Include corner pieces, trim, reinforcing, and clip angles.
- B. Ramps: Same materials, structural strength, and construction as floor panels; flush extruded aluminum cover plates at junction with floor system.
 1. Ramp Surface: _____; Match flooring finish color as selected.
- C. Railings: Manufacturer's standard.
- D. Plenum Dividers: Galvanized steel sheet ____ inch thick.
- E. Air Grilles: Galvanized steel sheet; ____ inch blade size; with straight vanes and shut-off damper; with integral fire damper.
- F. Fire Damper: _____ type as specified in Section 233300.
- G. Electrostatic Grounding Connectors: Solid copper.
- H. Cable Cutout Protection: Manufacturer's standard type, self-extinguishing.
- I. Gaskets: Closed cell sponge rubber, preformed to suit.
- J. Wall Base: Extruded plastic angles.
- K. Sealant: Any water-based, moisture-curing, or chemically-curing joint sealant suitable for purpose and compatible with materials being sealed; except acrylic latex emulsion.

2.05 FABRICATION

- A. Fabrication Tolerances:
 1. Floor Panel Flatness: Plus or minus 0.02 inch in any direction.
 2. Floor Panel Width or Length From Specified Size: Plus or minus 0.02 inch.
 3. Floor Panel Squareness: Plus or minus 0.03 inch difference between opposite diagonal dimensions.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify field measurements are as indicated on shop drawings.
- B. Verify that substrates comply with tolerances, dimensioned clearances, and other requirements specified in other sections, and that substrates are clean, dry, and free of conditions and deleterious substances that might interfere with system installation.
- C. Verify substrates comply with minimum subfloor flatness (FF) and subfloor levelness (FL) as specified in Section 033000.
- D. Verify that required utilities are available, in proper location, and are ready for use.
- E. Start of installation constitutes acceptance of project conditions.

3.02 PREPARATION

- A. Vacuum clean substrate surfaces.

3.03 INSTALLATION - ADJUSTABLE HEIGHT ACCESS FLOORING

- A. Install components in accordance with manufacturer's instructions.
- B. Secure pedestal base plate to subfloor with adhesive and/or mechanical fasteners as required to meet seismic requirements.
- C. Install additional base units where grid pattern is interrupted by room appurtenances or at cut-outs.
- D. Install stringers and floor panels on pedestals with full bearing and proper fasteners.
- E. Install grilles as indicated on drawings.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- F. Close field cut floor panels with edge trim.
- G. Cut holes in floor panels to accommodate Owner equipment as indicated on drawings. Provide cable cut-out protection.
- H. Provide floor with edge trim and end closures. Provide lateral braces at stair edges and other locations where pedestals are not braced.
- I. Where underfloor space functions as an air distribution plenum, seal between edge panels and adjacent construction.
- J. Seal plenum dividers to structural floor and bottom of elevated floor and walls.
- K. Provide gaskets and sealant to ensure airtight seal where holes are cut in elevated floor for penetration of cable.
- L. Provide positive electrical earth grounding of entire floor assembly in accordance with NFPA 75.
- M. Fascia Panels:
 - 1. Install fascia panels at exposed sides.
 - 2. Secure panels to clip angles attached to structural floor and edge of floor panels.
 - 3. Install metal trim at intersection of fascia panels and access floor and at abutting walls and columns.
- N. Railings:
 - 1. Extend railing posts through floor panels to structural floor; secure to flange fittings anchored to structural floor.
 - 2. Brace posts in position at floor panels with floor collar retainers.
 - 3. Secure railings at walls with flanged fittings anchored to walls.
 - 4. Electrically ground railings to floor system.

3.04 TOLERANCES

- A. Maximum Out of Level Floor Panel Tolerance: 1/16 inch in 10 ft, non-cumulative.
- B. Gap Between Panels: 1/16 inch.

3.05 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

3.06 ADJUSTING

- A. Adjust pedestals to achieve a level floor and to assure adjacent floor panel surfaces are flush.

3.07 CLOSEOUT ACTIVITIES

- A. See Section 017800 - Closeout Submittals, for closeout submittals.

3.08 PROTECTION

- A. Do not permit traffic over unprotected floor surface.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 099123 INTERIOR PAINTING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Surface preparation.
- B. Field application of paints, stains, and varnishes.
- C. Materials for backpriming woodwork.
- D. Scope: Finish interior surfaces exposed to view, unless fully factory-finished and unless otherwise indicated.
 - 1. Both sides and edges of plywood backboards for electrical and telecom equipment before installing equipment.
 - 2. Elevator pit ladders.
 - 3. Surfaces inside cabinets.
 - 4. Prime surfaces to receive wall coverings.
 - 5. Mechanical and Electrical:
 - a. In finished areas, paint insulated and exposed pipes, conduit, boxes, insulated and exposed ducts, hangers, brackets, collars and supports, mechanical equipment, and electrical equipment, unless otherwise indicated.
 - b. In finished areas, paint shop-primed items.
 - c. Paint interior surfaces of air ducts and convector and baseboard heating cabinets that are visible through grilles and louvers with one coat of flat black paint to visible surfaces.
 - d. Paint dampers exposed behind louvers, grilles, and convector and baseboard cabinets to match face panels.
- E. Do Not Paint or Finish the Following Items:
 - 1. Items factory-finished unless otherwise indicated; materials and products having factory-applied primers are not considered factory finished.
 - 2. Items indicated to receive other finishes except prime surfaces to receive wall coverings.
 - 3. Items indicated to remain unfinished.
 - 4. Fire rating labels, equipment serial number and capacity labels, bar code labels, and operating parts of equipment.
 - 5. Stainless steel, anodized aluminum, bronze, terne coated stainless steel, and lead items.
 - 6. Marble, granite, slate, and other natural stones.
 - 7. Floors, unless specifically indicated.
 - 8. Ceramic and other tiles.
 - 9. Brick, architectural concrete, cast stone, integrally colored plaster and stucco.
 - 10. Glass.
 - 11. Concrete masonry units in utility, mechanical, and electrical spaces.
 - 12. Acoustical materials.
 - 13. Concealed pipes, ducts, and conduits.

1.02 RELATED REQUIREMENTS

- A. Section 016116 - Volatile Organic Compound (VOC) Content Restrictions.
- B. Section 055000 - Metal Fabrications: Shop-primed items.
- C. Section 055100 - Metal Stairs: Shop-primed items.
- D. Section 099113 - Exterior Painting.
- E. Section 099600 - High-Performance Coatings.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.03 DEFINITIONS

- A. Conform to ASTM D16 for interpretation of terms used in this section.

1.04 REFERENCE STANDARDS

- A. 40 CFR 59, Subpart D - National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency; current edition.
- B. ASTM D16 - Standard Terminology for Paint, Related Coatings, Materials, and Applications; 2016.
- C. ASTM D4258 - Standard Practice for Surface Cleaning Concrete for Coating; 2005 (Reapproved 2012).
- D. ASTM D4259 - Standard Practice for Abrading Concrete; 1988 (Reapproved 2012).
- E. ASTM D4260 - Standard Practice for Liquid and Gelled Acid Etching of Concrete; 2005 (Reapproved 2012).
- F. ASTM D4442 - Standard Test Methods for Direct Moisture Content Measurement of Wood and Wood-Based Materials; 2015.
- G. CARB (SCM) - Suggested Control Measure for Architectural Coatings; California Air Resources Board; 2007.
- H. MPI (APSM) - Master Painters Institute Architectural Painting Specification Manual; Current Edition, www.paintinfo.com.
- I. SCAQMD 1113 - South Coast Air Quality Management District Rule No.1113; current edition.
- J. SSPC V1 (PM1) - Good Painting Practice: Painting Manual, Volume 1; Fourth Edition.
- K. SSPC V2 (PM2) - Systems and Specifications: Steel Structures Painting Manual, Volume 2; Fourth Edition.
- L. SSPC-SP 1 - Solvent Cleaning; 2015.
- M. SSPC-SP 2 - Hand Tool Cleaning; 1982 (Ed. 2004).
- N. SSPC-SP 3 - Power Tool Cleaning; 1982 (Ed. 2004).
- O. SSPC-SP 6 - Commercial Blast Cleaning; 2007.
- P. SSPC-SP 13 - Surface Preparation of Concrete; (Reaffirmed 2015); 2003.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide complete list of products to be used, with the following information for each:
 - 1. Manufacturer's name, product name and/or catalog number, and general product category (e.g. "alkyd enamel").
 - 2. MPI product number (e.g. MPI #47).
 - 3. Cross-reference to specified paint system(s) product is to be used in; include description of each system.
 - 4. Manufacturer's installation instructions.
 - 5. If proposal of substitutions is allowed under submittal procedures, explanation of substitutions proposed.
- C. Samples: Submit three paper "draw down" samples, 8-1/2 by 11 inches in size, illustrating range of colors available for each finishing product specified.
 - 1. Where sheen is specified, submit samples in only that sheen.
 - 2. Where sheen is not specified, discuss sheen options with Architect and owner before preparing samples, to eliminate sheens definitely not required.
 - 3. Allow 30 days for approval process, after receipt of complete samples by Architect.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 4. Paint color submittals will not be considered until color submittals for major materials not to be painted, such as masonry, have been approved.
- D. Certification: By manufacturer that paints and finishes comply with VOC limits specified.
- E. Manufacturer's Instructions: Indicate special surface preparation procedures.
- F. Maintenance Data: Submit data including finish schedule showing where each product/color/finish was used, product technical data sheets, material safety data sheets (MSDS), care and cleaning instructions, touch-up procedures, repair of painted and finished surfaces, and color samples of each color and finish used.
- G. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
 - 2. Extra Paint and Finish Materials: 1 gallon of each color; from the same product run, store where directed.
 - 3. Label each container with color in addition to the manufacturer's label.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified, with minimum three years documented experience.
- B. Applicator Qualifications: Company specializing in performing the type of work specified with minimum 5 years' experience. Individuals applying products with experience in performing the type of work specified with 5 years' experience or working under direct on-site supervision of an individual meeting this requirement.

1.07 MOCK-UP

- A. See Section 014000 - Quality Requirements, for general requirements for mock-up.
- B. Locate where directed by Architect.
- C. Mock-up may remain as part of the work.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
- B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.
- C. Container Label with date purchased indicated.
- D. Paint Materials: Store at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.

1.09 FIELD CONDITIONS

- A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
- B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.
- C. Do not apply materials when relative humidity exceeds 85 percent; at temperatures less than 5 degrees F above the dew point; or to damp or wet surfaces.
- D. Minimum Application Temperatures for Paints: 50 degrees F for interiors unless required otherwise by manufacturer's instructions.
- E. Minimum Application Temperature for Varnish Finishes: 65 degrees F for interior, unless required otherwise by manufacturer's instructions.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- F. Provide lighting level of 80 ft candles measured mid-height at substrate surface.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Provide paints and finishes from the same manufacturer to the greatest extent possible.
 - 1. In the event that a single manufacturer cannot provide specified products, minor exceptions will be permitted provided approval by Architect and owner is obtained using the specified procedures for substitutions.
 - 2. Substitution of other products by the same manufacturer is preferred over substitution of products by a different manufacturer.
- B. Paints:
 - 1. PPG Paints: www.ppgpaints.com
 - 2. Sherwin-Williams Company: www.sherwin-williams.com
 - 3. Benjamin Moore: www.benjaminmoore.com.
 - 4. Manufacturers as listed below for the paint systems and substrates.
- C. Transparent Finishes:
 - 1. PPG Paints Deft Interior Clears/Polyurethanes: www.ppgpaints.com
 - 2. Sherwin-Williams Company: www.sherwin-williams.com
 - 3. [Benjamin Moore: www.benjaminmoore.com].
- D. Stains:
 - 1. PPG Paints Deft Interior Stains: www.ppgpaints.com
 - 2. Sherwin-Williams Company: www.sherwin-williams.com
 - 3. [Benjamin Moore: www.benjaminmoore.com].
- E. Primer Sealers: Same manufacturer as top coats.
- F. Substitutions: See Section 016000 - Product Requirements.

2.02 PAINTS AND FINISHES - GENERAL

- A. Paints and Finishes: Ready mixed, unless intended to be a field-catalyzed paint.
 - 1. Provide paints and finishes of a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating, with good flow and brushing properties, and capable of drying or curing free of streaks or sags.
 - 2. Provide materials that are compatible with one another and the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.
 - 3. Supply each paint material in quantity required to complete entire project's work from a single production run.
 - 4. Do not reduce, thin, or dilute paint or finishes or add materials unless such procedure is specifically described in manufacturer's product instructions.
- B. Volatile Organic Compound (VOC) Content:
 - 1. Provide paints and finishes that comply with the most stringent requirements specified in the following:
 - a. 40 CFR 59, Subpart D--National Volatile Organic Compound Emission Standards for Architectural Coatings.
 - b. SCAQMD 1113 Rule.
 - c. CARB (SCM).
 - d. Ozone Transport Commission (OTC) Model Rule, Architectural, Industrial, and Maintenance Coatings; www.otcair.org; specifically:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 1) Opaque, Flat: 50 g/L, maximum.
 - 2) Opaque, Non flat: 150 g/L, maximum.
 - 3) Opaque, High Gloss: 250 g/L, maximum.
 - 4) Varnishes: 350 g/L, maximum.
 - e. Architectural coatings VOC limits of Utah.
2. Determination of VOC Content: Testing and calculation in accordance with 40 CFR 59, Subpart D (EPA Method 24), exclusive of colorants added to a tint base and water added at project site; or other method acceptable to authorities having jurisdiction.
- C. Flammability: Comply with applicable code for surface burning characteristics.
- D. Sheens: Provide the sheens specified; where sheen is not specified, sheen will be selected later by Architect and owner from the manufacturer's full line.
- E. Colors: As indicated on drawings.
1. Allow for minimum of four colors for each system, unless otherwise indicated, without additional cost to Owner.
 2. Extend colors to surface edges; colors may change at any edge as directed by Architect.
 3. In finished areas, finish pipes, ducts, conduit, and equipment the same color as the wall/ceiling they are mounted on/under.
 4. In utility areas, finish equipment, piping, conduit, and exposed duct work in colors according to the color coding scheme indicated.

2.03 PAINT SYSTEMS - INTERIOR

- A. Interior gypsum board surfaces to be Painted, Unless Otherwise Indicated: Including gypsum board.
- B. Paint I-OP-GB - Interior gypsum board surfaces to be painted, Unless Otherwise Indicated. Normal spaces not requiring special systems for specific spaces and uses included below.
1. Primer: One coat, BM N534 UltraSpec
 - a. Finish coats: Two coats, BM 550 Regal Select Interior Pearl
 2. Option 2: PPG
 - a. Primer: One coat, PPG 1000 High Hiding Interior Primer Sealer
 - b. Finish Coats: Two coats, PPG Diamond 350 Semi-Gloss
 3. Option 3: Sherwin Williams
 - a. Primer: One coat, SW Contractors 152 Pro Primer White
 - b. Finish coats: Two coats, SW ProMar 200 Zero VOC Interior Latex Semi-Gloss Extra
 - c. Two top coats and one coat primer.
- C. Special use area - Animal or Chemical Laboratory Rooms surfaces to be painted, Unless Otherwise Indicated.
1. Special use areas include all painted surfaces such as gypsum board, ceilings, doors, door frames, railings, handrails, guardrails, and balustrades in Animal or Chemical Laboratory Rooms.
 2. Two top coats and one coat primer.
 3. Top Coat(s): Interior Epoxy-Modified Latex.
 - a. Products:
 - 1) PPG PSX 700 Gloss two coats with PPG Amerlock 400 primer coat.
 - 2) PPG Aquapon WB 98-1 Series with PPG primer per manufacturer recommendations.
- D. Ferrous metals except handrails, guardrails and metal stairways.
1. Products: Metal Doors and Frames:
 - a. Option 1: Primer: one coat BM HP04 ultra spec acrylic metal primer Finish Coats: BM P29 Ultra spec HP Acrylic DTM Semi-gloss.
 - b. Option 2: Rust oleum Primer Metalmax Finish Coats: Two coats Rust oleum Beyond S-38 Satin

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- c. Option 3: Primer SW Pro Industrial Procryl Universal Primer. Two Finish Coats: SW 6509-62822 Multi surface acrylic enamel.
- E. Dry Fall: Metals; exposed structure and overhead-mounted services in utilitarian spaces, including shop primed steel deck, structural steel, metal fabrications, galvanized ducts, galvanized conduit, and galvanized piping.
 - 1. Shop primer by others.
 - 2. One top coat _____.
 - 3. Top Coat: Latex Dry Fall.
 - a. Products:
 - 1) PPG Paints Speedhide Super Tech Water Based Interior Dry-Fog, 6-723XI, Flat.
 - 2) Sherwin-Williams Waterborne Acrylic Dryfall, Flat.
 - 4. Primer: As recommended by top coat manufacturer for specific substrate.
- F. Concrete Floors to be Painted.
 - 1. Two top coats and one coat primer.
 - 2. Top Coat(s): Latex Floor Paint, Gloss.
 - a. Products:
 - 1) PPG Paints Break-Through Interior/Exterior Gloss Water-Borne Acrylic, V71-610 Series.
 - 3. Primer: As recommended by top coat manufacturer for specific substrate.
- G. Transparent Finish on Wood.
 - 1. 1 top coat over sanding sealer over stain.
 - 2. Stain: Semi-Transparent Stain for Wood; MPI #90.
 - a. Products:
 - 3. Top Coat(s): Clear Water Based Varnish.
 - a. Products:
 - 1) PPG Paints Deft Interior Polyurethane WB Acrylic Satin, DFT 159.
 - 2) PPG Paints Deft Interior Polyurethane WB Acrylic Semi-Gloss, DFT 158
 - 3) Sherwin-Williams Wood Classics Waterborne Polyurethane Varnish, Satin.
- H. Transparent Finish on Concrete Floors.
 - 1. Sealer: Water Based for Concrete Floors.
 - a. Products:
 - 1) Spartan Straight Seal.
- I. Wood, Opaque, Latex, 3 Coat:
 - 1. One coat of latex primer sealer as recommended by top coat paint manufacturer.
 - 2. Semi-gloss: Two coats of latex enamel; PPG Regency, BM Regal Select, PPG Diamond 350.
- J. Concrete/Masonry, Opaque, Latex, 3 Coat:
 - 1. One coat of block filler. Follow top coat manufacturers recommendation.
 - 2. Two coats of latex enamel; _____.
 - a. Option 1: BM Ultraspec 571 Low Lustre
 - b. Option 2: PPG Regency Semi-Gloss
 - c. Option 3: Sherwin-Williams ProMar 200 Water based Acrylic, Semi-Gloss
- K. Guardrails, Handrails and metal stairways, Galvanized Metals, Unprimed, 3 Coat:
 - 1. One coat of PPG Amerlock 400 Epoxy primer.
 - 2. Two coats; PPG Pitthane Ultra Semi-Gloss.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.04 PRIMERS

- A. Primers: Provide the primer recommended by manufacturer of top coats.

2.05 ACCESSORY MATERIALS

- A. Accessory Materials: Provide primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials as required for final completion of painted surfaces.
- B. Patching Material: Latex filler.
- C. Fastener Head Cover Material: Latex filler.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Do not begin application of paints and finishes until substrates have been properly prepared.
- B. Verify that surfaces are ready to receive work as instructed by the product manufacturer.
- C. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially effect proper application.
- D. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.
- E. Test shop-applied primer for compatibility with subsequent cover materials.
- F. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces are below the following maximums:
 - 1. Gypsum Wallboard: 12 percent.
 - 2. Plaster and Stucco: 12 percent.
 - 3. Masonry, Concrete, and Concrete Masonry Units : 12 percent.
 - 4. Interior Wood: 15 percent, measured in accordance with ASTM D4442.
 - 5. Concrete Floors and Traffic Surfaces: 8 percent.

3.02 PREPARATION

- A. Clean surfaces thoroughly and correct defects prior to application.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Remove or repair existing paints or finishes that exhibit surface defects.
- D. Remove or mask surface appurtenances, including electrical plates, hardware, light fixture trim, escutcheons, and fittings, prior to preparing surfaces or finishing.
- E. Seal surfaces that might cause bleed through or staining of topcoat.
- F. Remove mildew from impervious surfaces by scrubbing with solution of tetra-sodium phosphate and bleach. Rinse with clean water and allow surface to dry.
- G. Concrete:
 - 1. Remove release agents, curing compounds, efflorescence, and chalk. Do not coat surfaces if moisture content or alkalinity of surfaces to be coated exceeds that permitted in manufacturer's written instructions.
 - 2. Clean surfaces with pressurized water. Use pressure range of 1500 to 4000 psi at 6 to 12 inches. Allow to dry.
 - 3. Clean concrete according to ASTM D4258. Allow to dry.
 - 4. Prepare surface as recommended by top coat manufacturer and according to SSPC-SP 13.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- H. Masonry:
 - 1. Remove efflorescence and chalk. Do not coat surfaces if moisture content or alkalinity of surfaces or if alkalinity of mortar joints exceed that permitted in manufacturer's written instructions. Allow to dry.
 - 2. Prepare surface as recommended by top coat manufacturer.
 - 3. Clean surfaces with pressurized water. Use pressure range of 600 to 1500 psi at 6 to 12 inches. Allow to dry.
- I. Concrete Floors and Traffic Surfaces: Remove contamination, acid etch, and rinse floors with clear water. Verify required acid-alkali balance is achieved. Allow to dry.
- J. Gypsum Board: Fill minor defects with filler compound. Spot prime defects after repair.
- K. Plaster: Fill hairline cracks, small holes, and imperfections with latex patching plaster. Make smooth and flush with adjacent surfaces. Wash and neutralize high alkali surfaces.
- L. Insulated Coverings: Remove dirt, grease, and oil from canvas and cotton.
- M. Aluminum: Remove surface contamination and oils and wash with solvent according to SSPC-SP 1.
- N. Copper: Remove contamination by steam, high pressure water, or solvent washing.
- O. Galvanized Surfaces:
 - 1. Remove surface contamination and oils and wash with solvent according to SSPC-SP 1.
 - 2. Prepare surface according to SSPC-SP 2.
- P. Ferrous Metal:
 - 1. Solvent clean according to SSPC-SP 1.
 - 2. Shop-Primed Surfaces: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with solvent. Prime bare steel surfaces. Re-prime entire shop-primed item.
 - 3. Remove rust, loose mill scale, and other foreign substances using methods recommended in writing by paint manufacturer and blast cleaning according to SSPC-SP 6 "Commercial Blast Cleaning". Protect from corrosion until coated.
- Q. Wood Surfaces to Receive Opaque Finish: Wipe off dust and grit prior to priming. Seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after primer has dried; sand between coats. Back prime concealed surfaces before installation.
- R. Wood Surfaces to Receive Transparent Finish: Wipe off dust and grit prior to sealing, seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after sealer has dried; sand lightly between coats. Prime concealed surfaces with gloss varnish reduced 25 percent with thinner.
- S. Glue-Laminated Beams: Prior to finishing, wash surfaces with solvent, remove grease and dirt.
- T. Wood Doors to be Field-Finished: Seal wood door top and bottom edge surfaces with clear sealer.
- U. Metal Doors to be Painted: Prime metal door top and bottom edge surfaces.

3.03 APPLICATION

- A. Remove unfinished louvers, grilles, covers, and access panels on mechanical and electrical components and paint separately.
- B. Apply products in accordance with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual".
- C. Where adjacent sealant is to be painted, do not apply finish coats until sealant is applied.
- D. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.
- E. Apply each coat to uniform appearance in thicknesses specified by manufacturer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- F. Dark Colors and Deep Clear Colors: Regardless of number of coats specified, apply as many coats as necessary for complete hide.
- G. Sand wood and metal surfaces lightly between coats to achieve required finish.
- H. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
- I. Wood to Receive Transparent Finishes: Tint fillers to match wood. Work fillers into the grain before set. Wipe excess from surface.
- J. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for general requirements for field inspection.
- B. Owner will provide field inspection.

3.05 CLEANING

- A. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.

3.06 PROTECTION

- A. Protect finishes until completion of project.
- B. Touch-up damaged finishes after Substantial Completion.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 102233
ACCORDION FOLDING PARTITIONS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Accordion folding partitions.
- B. Track, ceiling guards, and operating hardware.
- C. Sound-rated construction above ceiling to structure.

1.02 RELATED REQUIREMENTS

- A. Section 087100 - Door Hardware: Lock cylinders.
- B. Section 260533.13 - Conduit for Electrical Systems: Empty conduit from partition motor controller to disconnect.
- C. Section 260583 - Wiring Connections: Electrical characteristics and wiring connections.

1.03 REFERENCE STANDARDS

- A. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- B. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009 (Reapproved 2016).
- C. ASTM E413 - Classification for Rating Sound Insulation; 2016.
- D. ASTM E557 - Standard Guide for Architectural Design and Installation Practices for Sound Isolation between Spaces Separated by Operable Partitions; 2012.
- E. ASTM E596 - Standard Test Method for Laboratory Measurement of Noise Reduction of Sound-Isolating Enclosures; 1996 (Reapproved 2016).
- F. ASTM F793/F793M - Standard Classification of Wall Coverings by Use Characteristics; 2015.
- G. NEMA MG 1 - Motors and Generators; 2016.
- H. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on partition operation, hardware and accessories, track switching components, colors and finishes available.
- C. Shop Drawings: Indicate opening sizes, track layout, details of track and required supports, static and dynamic loads, adjacent construction and finish trim, and stacking sizes.
- D. Samples: Submit two samples of full manufacturer's color range for selection of colors.
- E. Samples: Submit two samples of surface finish, 12 by 12 inches size, illustrating quality.
- F. Manufacturer's Installation Instructions: Indicate special procedures.
- G. Manufacturer's Certificate: Certify that partition system meets or exceeds specified acoustic requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- H. Maintenance Data: Describe cleaning materials detrimental to vinyl fabric surfaces and hardware finish. Include recommended cleaning methods, cleaning materials, and stain removal methods.

1.05 QUALITY ASSURANCE

- A. Sound Transmission Class (STC): As indicated, calculated in accordance with ASTM E413, based on tests performed in accordance with ASTM E90, on panel size of 100 sq ft.
- B. Noise Isolation Classification (NIC): As indicated, calculated in accordance with ASTM E413, based on tests performed in accordance with ASTM E596.
- C. Design Requirements: Design partition track and anchors to support imposed loads with maximum deflection of 1/360 of span, attached to structural members indicated.
- D. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- E. Installer Qualifications: Company specializing in performing the work of this section with minimum three years' experience.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Basis of Design: Modernfold.
- B. Other Acceptable Manufacturers:
 - 1. Modernfold, a DORMA Group Company; _____: www.modernfold.com
 - 2. Panelfold, Inc; _____: www.panelfold.com
 - 3. Won-Door.
 - 4. Cornell
 - 5. Substitutions: See Section 016000 - Product Requirements.

2.02 ACCORDION FOLDING PARTITIONS

- A. Partition Construction: Acoustical.
 - 1. Frame: 14 gage, 1/8 inch steel pantograph hinge plates; 3/16 inch diameter vertical rods, galvanized; limiting mechanism; stacking straps and snaps.
 - 2. Surfacing: 22 gage, 0.0299 inch steel panels with sound absorbent liner.
 - 3. Finish: Vinyl coated fabric; color as selected.
 - 4. Internal air release mechanism.
 - 5. Acoustic seals at top, meeting mullions, jambs, and bottom.
 - 6. Sound Transmission Class (STC): As Designated by Architect.
 - 7. Noise Isolation Class (NIC): As designated by Architect.
 - 8. Trim: Jamb and meeting mullions.
 - 9. Ceiling guard.
 - 10. Manual operation.
- B. Finish Materials:
- C. Components:
- D. Electrical Characteristics and Components:
 - 1. Electrical Characteristics:
 - 2. Motor: NEMA MG 1, _____.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Electric Operator: 12 inches per second travelling speed; adjustable friction clutch brake actuated by solenoid controlled motor starter; enclosed limit switch; enclosed magnetic reversing starter.
 4. Control Station: One standard-keyed three-button (OPEN-STOP-CLOSE) constant pressure type; 24 volt circuit; surface mounted.
 5. Conduit and Outlet Boxes: Surface type in accordance with Section 260533.13.
 6. Wiring Terminations: Provide terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Enclose terminal lugs in terminal box sized to NFPA 70.
 7. Disconnect Switch: Factory mount disconnect switch in control panel.
 8. Limit Switches: Automatic type, at both extremes of travel, to prevent over-travel.
 9. Emergency Release: Mechanism to disengage motor drive system and permit manual operation.
- E. Track: Formed steel; 1-1/4 by 1-1/4 inches size; thickness and profile designed to support loads; steel sub-channel.
- F. Carriers: Nylon wheels on trolley carrier at top center of every second fold, with threaded pendant bolt for vertical adjustment.

2.03 FINISH MATERIALS

- A. Vinyl Coated Fabric: ASTM F793 Category VI, polyvinyl fluoride finish.
1. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84.
 2. Color: As indicated.

2.04 COMPONENTS

- A. Trim: Aluminum moldings, clear anodized.
- B. Ceiling Guard: Formed sheet steel, full width of partition when stacked; baked enamel finish; match ceiling color.
- C. Pocket Enclosures: Door, frame, and trim to match adjacent walls; design trailing jamb to latch on face of closed pocket door.
- D. Lock Cylinders: Specified in Section 087100.
- E. Hardware: Latching door handles of cast steel, satin chrome finish; master keyed to building keying system; jamb lock and pull bars.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that field measurements are as indicated.
- C. Verify track supports are laterally braced and will permit track to be leveled within 1/4 inch of required position and parallel to the floor surface.
- D. Verify floor flatness of 1/8 in 10 feet, non-cumulative.
- E. Verify wall plumbness of 1/8 in 10 feet, non-cumulative.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.02 PREPARATION

- A. Verify that required utilities are available, of the correct characteristics, in proper location, and ready for use.

3.03 INSTALLATION

- A. Install partition in accordance with manufacturer's instructions and ASTM E557.
- B. Install electric operator, wiring, and controls. Locate control station(s) as indicated.
- C. Fit and align partition assembly level and plumb.
- D. Lubricate moving components.

3.04 ADJUSTING

- A. Adjust partition assembly to provide smooth operation from stacked to full open position.
- B. Visually inspect partition in full open position for light leaks to identify a potential acoustical leak. Adjust to achieve light tight seal.

3.05 CLOSEOUT ACTIVITIES

- A. Demonstrate operation of partition and identify potential operational problems.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 123600 COUNTERTOPS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Countertops for architectural cabinet work.
- B. Countertops for manufactured casework.
- C. Wall-hung counters and vanity tops.
- D. Sinks molded into countertops.
- E. Epoxy resin sinks.

1.02 RELATED REQUIREMENTS

- A. Section 064100 - Architectural Wood Casework.
- B. Section 123553.19 - Wood Laboratory Casework: Laboratory countertops.
- C. Section 224000 - Plumbing Fixtures: Sinks.

1.03 REFERENCE STANDARDS

- A. ASTM A666 - Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2015.
- B. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- C. AWI (QCP) - Quality Certification Program; current edition at www.awiqcp.org.
- D. AWI/AWMAC/WI (AWS) - Architectural Woodwork Standards; 2014, with Errata (2016).
- E. AWMAC/WI (NAAWS) - North American Architectural Woodwork Standards, U.S. Version 3.1; 2016, with Errata (2017).
- F. IAPMO Z124 - Plastic Plumbing Fixtures; 2017.
- G. ISFA 2-01 - Classification and Standards for Solid Surfacing Material; 2013.
- H. NEMA LD 3 - High-Pressure Decorative Laminates; 2005.
- I. PS 1 - Structural Plywood; 2009.
- J. SEFA 2 - Installations; 2010.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Specimen warranty.
- C. Shop Drawings: Complete details of materials and installation; combine with shop drawings of cabinets and casework specified in other sections.
- D. Selection Samples: For each finish product specified, color chips representing manufacturer's full range of available colors and patterns.
- E. Verification Samples: For each finish product specified, minimum size 6 inches square, representing actual product, color, and patterns.
- F. Test Reports: Chemical resistance testing, showing compliance with specified requirements.
- G. Certificate: Submit labels and certificates required by quality assurance and quality control programs.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- H. Installation Instructions: Manufacturer's installation instructions and recommendations.
- I. Maintenance Data: Manufacturer's instructions and recommendations for maintenance and repair of countertop surfaces.

1.05 QUALITY ASSURANCE

- A. Installer Qualifications: Company specializing in performing work of the type specified in this section, with not less than three years of documented experience.
- B. Quality Certification:
 - 1. Comply with AWI (QCP) woodwork association quality certification service/program in accordance with requirements for work specified in this section: www.awiqcp.org/
 - 2. Provide labels or certificates indicating that the installed work complies with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS) requirements for grade or grades specified.
 - 3. Provide designated labels on shop drawings as required by certification program.
 - 4. Provide designated labels on installed products as required by certification program.
 - 5. Submit certifications upon completion of installation that verifies this work is in compliance with specified requirements.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened packaging until ready for installation.
- B. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

1.07 FIELD CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

PART 2 PRODUCTS

2.01 COUNTERTOPS

- A. Plastic Laminate Countertops: High-pressure decorative laminate (HPDL) sheet bonded to substrate.
 - 1. Laminate Sheet, Type ____: NEMA LD 3, Grade HGS, 0.048 inch nominal thickness.
 - a. Manufacturers:
 - 1) Formica Corporation; Web Address: www.formica.com/
 - 2) Panolam Industries International, Inc; Nevamar Standard HPL: www.panolam.com/
 - 3) Wilsonart; Web Address: www.wilsonart.com/
 - 4) Substitutions: See Section 016000 - Product Requirements.
 - b. Surface Burning Characteristics: Flame spread index of 25, maximum; smoke developed index of 450, maximum; when tested in accordance with ASTM E84.
 - c. NSF approved for food contact.
 - d. Wear Resistance: In addition to specified grade, comply with NEMA LD 3 High Wear Grade requirements for wear resistance.
 - e. Laminate Core Color: Same as decorative surface.
 - f. Finish: Matte or suede, gloss rating of 5 to 20.
 - 2. Exposed Edge Treatment: Square, substrate built up to minimum 1-1/4 inch thick; covered with matching laminate.
 - 3. Back and End Splashes: Same material, same construction.
 - 4. Fabricate in accordance with manufacturer's standard requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Chemical-Resistant Plastic Laminate Countertops: Chemical-resistant high-pressure decorative laminate (HPDL) sheet bonded to substrate.
1. Laminate Sheet: NEMA LD 3 Grade HGL, 0.039 inch nominal thickness.
 - a. Manufacturers:
 - 1) Formica Corporation; _____: www.formica.com/
 - 2) Panolam Industries International, Inc; Pionite ChemGuard: www.panolam.com/
 - 3) Wilsonart; _____: www.wilsonart.com/
 - 4) Substitutions: See Section 016000 - Product Requirements.
 - b. Surface Burning Characteristics: Flame spread index of 25, maximum; smoke developed index of 450, maximum; when tested in accordance with ASTM E84.
 - c. NSF approved for food contact.
 - d. Wear Resistance: In addition to specified grade, comply with NEMA LD 3 High Wear Grade requirements for wear resistance.
 - e. Finish: Matte or suede, gloss rating of 5 to 20.
 - f. Surface Color and Pattern: As selected by Architect from manufacturer's full line.
 2. Exposed Edge Treatment: Square, substrate built up to minimum 1-1/4 inch thick; covered with matching laminate.
 3. Back and End Splashes: Same material, same construction; minimum 4 inches high.
 4. Fabricate in accordance with manufacturer's standard requirements.
- C. Solid Surfacing Countertops: Solid surfacing sheet or plastic resin casting over continuous substrate.
1. Flat Sheet Thickness: 3/4 inch, minimum.
 2. Solid Surfacing Sheet and Plastic Resin Castings: Complying with ISFA 2-01 and NEMA LD 3; acrylic or polyester resin, mineral filler, and pigments; homogenous, non-porous and capable of being worked and repaired using standard woodworking tools; no surface coating; color and pattern consistent throughout thickness.
 - a. Manufacturers:
 - 1) Dupont; Corian: www.corian.com/
 - 2) Formica Corporation; Solid Surface: www.formica.com/
 - 3) Samsung Staron Solid Surfaces. www.staron.com
 - 4) Substitutions: See Section 016000 - Product Requirements.
 - b. Surface Burning Characteristics: Flame spread index of 25, maximum; smoke developed index of 450, maximum; when tested in accordance with ASTM E84.
 - c. NSF approved for food contact.
 - d. Sinks and Bowls: Integral castings; minimum 3/4 inch wall thickness; comply with IAPMO Z124.
 - e. Finish on Exposed Surfaces: Matte, gloss rating of 5 to 20.
 - f. Color and Pattern: As selected by Architect from manufacturer's full line.
 3. Other Components Thickness: 1/2 inch, minimum.
 4. Exposed Edge Treatment: Built up to minimum 1-1/4 inch thick; radiused edge; use marine edge at sinks.
 5. Back and End Splashes: Same sheet material, square top; minimum 4 inches high.
 6. Skirts: As indicated on drawings.
- D. Stainless Steel Countertops: ASTM A666, Type 304, stainless steel sheet; 16 gage, 0.0625 inch nominal sheet thickness.
1. Manufacturers:
 - a. Advance Tabco , www.advancetabco.com.
 - b. Onepointe Solutions, www.onepointesolutions.com.
 - c. Stainless Supply, www.stainlesssupply.com
 - d. E3 Fabrication, www.e3fabrication.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- e. Salt Lake City Stainless Steel, www.saltlakecitystainlesssteel.com
 - f. Stainless Steel Specialists, www.stainlesssteelspecialists.com
 - g. Substitutions: See Section 016000 - Product Requirements.
2. Finish: 4B satin brushed finish.
 3. Exposed Edge Shape: Bullnose with return; 5/8 inch radius, return to face of case; reinforced with hardwood or steel.
 4. Back and End Splashes: Same material; welded 1/4 inch radius coved joint to countertop; square top edge with 1 inch wide top surface and minimum 1/2 inch turndown.
 5. Splash Dimensions: 4 inch high by 1 inch thick, unless otherwise indicated.
 6. Sinks: Same material, same thickness; flush welded to counter; bottom sloped to outlet; radiused interior corners; drain outlet located in back corner.
 7. Troughs: Same material; bottom sloped to outlet.

2.02 MATERIALS

- A. Plywood for Supporting Substrate: PS 1 Exterior Grade, A-C veneer grade, minimum 5-ply; minimum 3/4 inch thick; join lengths using metal splines.
- B. Adhesives: Chemical resistant waterproof adhesive as recommended by manufacturer of materials being joined.

2.03 FABRICATION

- A. Fabricate tops and splashes in the largest sections practicable, with top surface of joints flush.
 1. Join lengths of tops using best method recommended by manufacturer.
 2. Fabricate to overhang fronts and ends of cabinets 1 inch except where top butts against cabinet or wall.
 3. Prepare all cutouts accurately to size; replace tops having improperly dimensioned or unnecessary cutouts or fixture holes.
- B. Provide back/end splash wherever counter edge abuts vertical surface unless otherwise indicated.
 1. Secure to countertop with concealed fasteners and with contact surfaces set in waterproof glue.
 2. Height: 4 inches, unless otherwise indicated.
- C. Solid Surfacing: Fabricate tops and wall panels up to 144 inches long in one piece; join pieces with adhesive sealant in accordance with manufacturer's recommendations and instructions.
 1. Integral sinks: Shop-mount securely to countertop with adhesives, using flush configuration, as per manufacturer's instructions, and as detailed on drawings.
- D. Stainless Steel: Fabricate tops up to 144 inches long in one piece including nosings and back and end splashes; accurately fitted mechanical field joints in lengths over that dimension are permitted.
 1. Weld joints; grind smooth and polish to match.
 2. Provide stainless steel hat channel stiffeners, welded or soldered to underside, where indicated on drawings.
 3. Provide wall clips for support of back/end splash turndowns.
 4. Sound Deadening: Apply water resistant, fire resistant sound deadening mastic to entire bottom surface.
 5. Integral sinks: Fabricate with corners rounded and coved, double-walls for sink compartment partitions, and drainboards. Factory-punch holes for fittings, and weld sinks to countertops.
- E. Wall-Mounted Counters: Provide skirts, aprons, brackets, and braces as indicated on drawings, finished to match.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 3 EXECUTION

3.01 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.
- C. Verify that wall surfaces have been finished and mechanical and electrical services and outlets are installed in proper locations.

3.02 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.03 INSTALLATION

- A. Install laboratory worksurface countertops in compliance with requirements of SEFA 2.
- B. Securely attach countertops to cabinets using concealed fasteners. Make flat surfaces level; shim where required.
- C. Attach plastic laminate countertops using screws with minimum penetration into substrate board of 5/8 inch.
- D. Attach stainless steel countertops using stainless steel fasteners and clips.
- E. Seal joint between back/end splashes and vertical surfaces.

3.04 TOLERANCES

- A. Variation From Horizontal: 1/8 inch in 10 feet, maximum.
- B. Offset From Wall, Countertops: 1/8 inch maximum; 1/16 inch minimum.
- C. Field Joints: 1/8 inch wide, maximum.

3.05 CLEANING

- A. Clean countertops surfaces thoroughly.

3.06 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Date of Substantial Completion.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 000110
TABLE OF CONTENTS
MECHANICAL SPECIFICATIONS**

SPECIFICATIONS

DIVISION 21 – FIRE SUPPRESSION SPECIFICATIONS

- 210500 – Common Work Results for Fire Suppression
- 210548 – Vibration and Seismic Controls for Fire Suppression Piping and Equipment
- 211300 – Fire Suppression Sprinkler Systems

DIVISION 22 – PLUMBING SPECIFICATIONS

- 220517 – Sleeves and Sleeve Seals for Plumbing Piping
- 220523 – General Duty Valves for Plumbing Piping
- 220529 – Hangers and Supports for Plumbing Piping and Equipment
- 220548 – Vibration and Seismic Controls for Plumbing Piping and Equipment
- 220553 – Identification for Plumbing Piping and Equipment
- 220719 – Plumbing Piping Insulation
- 220719.11 – Under Lavatory Pipe and Supply Covers
- 221005 – Plumbing Pipes
- 224000 – Plumbing Fixtures

DIVISION 23 – MECHANICAL SPECIFICATIONS

- 230100 – Mechanical Operations and Maintenance Manuals
- 230548 – Vibration and Seismic Controls for HVAC Piping and Equipment
- 230553 – Identification for HVAC Piping and Equipment
- 230593 – Testing, adjusting, and balancing for HVAC
- 230713 – Duct Insulation
- 230719 – HVAC Piping Insulation
- 230800 – Commissioning of HVAC
- 230923 – Direct Digital Control System for HVAC
- 230993 – Sequence of Operations for HVAC Controls
- 233100 – HVAC Ducts and Casings
- 233300 – Air Ducts Accessories
- 233600 – Air Terminals Units
- 233700 – Air Outlets and Inlets

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 210500

COMMON WORK RESULTS FOR FIRE SUPPRESSION

PART 1 GENERAL

THIS SECTION UPDATED COMPLETE OCTOBER 2020

1.01 SECTION INCLUDES

- A. Above ground piping.
- B. Escutcheons.
- C. Pipe, fittings, sleeves, escutcheons, seals, and connections for sprinkler systems.
- D. Expansion joints.
- E. Expansion loops.
- F. Pipe hangers and supports.
- G. Pipe sleeves.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 099113 - Exterior Painting: Preparation and painting of exterior fire protection piping systems.
- C. Section 099123 - Interior Painting: Preparation and painting of interior fire protection piping systems.
- D. Section 210523 - General-Duty Valves for Water-Based Fire-Suppression Piping.
- E. Section 210553 - Identification for Fire Suppression Piping and Equipment: Piping identification.
- F. Section 211200 - Fire-Suppression Standpipes: Standpipe design.
- G. Section 211300 - Fire-Suppression Sprinkler Systems: Sprinkler systems design.
- H. Section 220553 - Identification for Plumbing Piping and Equipment: Piping identification.

1.03 REFERENCE STANDARDS

- A. ASME A112.18.1 - Plumbing Supply Fittings; 2012.
- B. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Procedures; Welders; Braziers; and Welding, Brazing and Fusing Operators; 2017.
- C. ASME B16.1 - Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250; 2015.
- D. ASME B16.3 - Malleable Iron Threaded Fittings: Classes 150 and 300; 2016.
- E. ASME B16.4 - Gray Iron Threaded Fittings: Classes 125 and 250; 2016.
- F. ASME B16.5 - Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard; 2017.
- G. ASME B16.9 - Factory-Made Wrought Buttwelding Fittings; 2012.
- H. ASME B16.11 - Forged Fittings, Socket-welding and Threaded; 2016 (Errata 2017).
- I. ASME B16.18 - Cast Copper Alloy Solder Joint Pressure Fittings; 2012.
- J. ASME B16.22 - Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings; 2013.
- K. ASME B16.25 - Buttwelding Ends; 2012.
- L. ASME B36.10M - Welded and Seamless Wrought Steel Pipe; 2015.
- M. ASTM A47/A47M - Standard Specification for Ferritic Malleable Iron Castings; 1999 (Reapproved 2014).

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- N. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2012.
- O. ASTM A135/A135M - Standard Specification for Electric-Resistance-Welded Steel Pipe; 2009 (Reapproved 2014).
- P. ASTM A234/A234M - Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service; 2017.
- Q. ASTM A269/A269M - Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service; 2015a.
- R. ASTM A536 - Standard Specification for Ductile Iron Castings; 1984 (Reapproved 2014).
- S. ASTM A795/A795M - Standard Specification for Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Fire Protection Use; 2013.
- T. ASTM B32 - Standard Specification for Solder Metal; 2008 (Reapproved 2014).
- U. ASTM B75/B75M - Standard Specification for Seamless Copper Tube; 2011.
- V. ASTM B88 - Standard Specification for Seamless Copper Water Tube; 2016.
- W. ASTM B88M - Standard Specification for Seamless Copper Water Tube (Metric); 2016.
- X. ASTM C592 - Standard Specification for Mineral Fiber Blanket Insulation and Blanket-Type Pipe Insulation (Metal-Mesh Covered) (Industrial Type); 2016.
- Y. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- Z. ASTM D2239 - Standard Specification for Polyethylene (PE) Plastic Pipe (SIDR-PR) Based on Controlled Inside Diameter; 2012a.
- AA. ASTM D2609 - Standard Specification for Plastic Insert Fittings for Polyethylene (PE) Plastic Pipe; 2015.
- AB. ASTM E814 - Standard Test Method for Fire Tests of Penetration Firestop Systems; 2013a.
- AC. ASTM F438 - Standard Specification for Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40; 2015.
- AD. ASTM F439 - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80; 2013.
- AE. ASTM F442/F442M - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR); 2013.
- AF. ASTM F493 - Standard Specification for Solvent Cements for Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe and Fittings; 2014.
- AG. AWS A5.8M/A5.8 - Specification for Filler Metals for Brazing and Braze Welding; 2011-AMD 1.
- AH. AWS D1.1/D1.1M - Structural Welding Code - Steel; 2015 (with March 2016 Errata).
- AI. AWWA C105/A21.5 - Polyethylene Encasement for Ductile-Iron Pipe Systems; 2010.
- AJ. AWWA C110/A21.10 - Ductile-Iron and Gray-Iron Fittings; 2012.
- AK. AWWA C111/A21.11 - Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings; 2017.
- AL. AWWA C151/A21.51 - Ductile-Iron Pipe, Centrifugally Cast; 2009.
- AM. AWWA C606 - Grooved and Shouldered Joints; 2015.
- AN. ITS (DIR) - Directory of Listed Products; current edition.
- AO. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



AP. NFPA 14 - Standard for the Installation of Standpipe and Hose Systems; 2016.

AQ. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

AR. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 SUMMARY TABLE

Item	Spec Section	Summary
Design	211300 1.06.B	Design with a margin of safety of 10%.
Submittal	211300 1.05.C	Submit shop drawings, product data, and hydraulic calculations to AHJ and BYU Fire Marshal for approval.
Pipe Thickness	210500 2.02.A	Minimum Pipe Thickness Schedule Mains: Sch 10 Grooved Branch: Sch 10 Threaded Branch: Sch 30
Design	Division 210000	Design does not need to be FM approved.
Drain Discharge	210500 3.03.I	All drain valves shall be discharged to the exterior of the building.
Flex Hose Drops	211300 2.02.F	Minimum capability of 5 bends is required.
Control Valves	210500 3.03.H	To be installed 7'-0" maximum above finish floor.
Flow Switches	211300 2.03.E	To be key operated/activated for testing purposes.
Dry/Pre-action Valves	211300 2.03.A	Victaulic is the only approved manufacturer.
Exposed Pipe Fittings	210500 3.03.F	Shall have a minimum 1" outlet with a bushing to accommodate future remodels.
Exposed Areas	210500 3.03.E	Piping shall be installed as high as possible.
Dry Systems	210500 2.02.A	Black pipe shall be used. Galvanized is not acceptable.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturers catalogue information. Indicate valve data and ratings.
- C. Shop Drawings: Indicate pipe materials used, jointing methods, supports, floor and wall penetration seals. Indicate installation, layout, weights, mounting and support details, and piping connections. Include flow calculations.
- D. Manufacturer's Qualification Statement.
- E. Installer's Qualification Statement.
- F. Project Record Documents: Record actual locations of components and tag numbering.
- G. Operation and Maintenance Data: Include installation instructions and spare parts lists.
- H. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
 - 2. Extra Valve Stem Packings: One for each type and size of valve.
- I. Warranty Materials: Include all warranty certificates and schedule list of start and end dates for manufacturer equipment.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum five years documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified in this section.
 - 1. Minimum three years' experience for lead installers.
 - 2. Approved by manufacturer.
- C. Conform to UL (DIR) requirements.
- D. U.S. made domestic equipment, pipes, valves, and fittings.
- E. Valves: Bear UL (DIR) and ITS (DIR) or Warnock Hersey product listing label or marking. Provide manufacturer's name and pressure rating marked on valve body.
- F. Products Requiring Electrical Connection: Listed and classified as suitable for the purpose specified and indicated.
- G. Clean equipment, pipes, valves, and fittings of grease, metal cuttings, and sludge that may have accumulated from the installation and testing of the system.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store valves in shipping containers, with labeling in place.
- B. Provide temporary protective coating on cast iron and steel valves.
- C. Provide temporary end caps and closures on piping and fittings. Maintain in protected place until installation.

1.08 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Correct defective Work within a one year period after Date of Substantial Completion.
- C. 11 months after substantial completion, contractor shall meet with BYU personnel to ensure integrity of system and to address any warranty issues identified during meeting.

PART 2 PRODUCTS

2.01 FIRE PROTECTION SYSTEMS

- A. Sprinkler Systems: Conform to NFPA 13 (or NFPA 13R as applicable).
- B. Standpipe and Hose Systems: Conform to NFPA 14.
- C. Welding Materials and Procedures: Conform to ASME BPVC-IX.

2.02 ABOVE GROUND PIPING

- A. Steel Pipe: ASTM A795 Schedule 10, ASTM A53 Schedule 40, ASTM A135/A135M Schedule 10, or ASTM A795 Schedule 40 _____.
 - 1. Minimum Pipe Thickness Schedule
 - a. Mains: Sch 10
 - b. Grooved Branch: Sch 10
 - c. Threaded Branch: Sch 30
 - 2. Use Schedule
 - a. Conditioned Space: black pipe
 - b. Unconditioned Space: galvanized pipe
 - c. Dry System: black pipe

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Steel Fittings: ASME B16.9, wrought steel, buttwelded, ASME B16.25, buttweld ends, ASTM A234/A234M, wrought carbon steel or alloy steel, ASME B16.5, steel flanges and fittings, or ASME B16.11, forged steel socket welded and threaded.
 4. Cast Iron Fittings: ASME B16.1, flanges and flanged fittings and ASME B16.4, threaded fittings.
 5. Malleable Iron Fittings: ASME B16.3, threaded fittings and ASTM A47/A47M.
 6. Mechanical Grooved Couplings: Malleable iron housing clamps to engage and lock, "C" shaped elastomeric sealing gasket, steel bolts, nuts, and washers; galvanized for galvanized pipe.
 7. Mechanical Formed Fittings: Carbon steel housing with integral pipe stop and O-ring pocked and O-ring, uniformly compressed into permanent mechanical engagement onto pipe.
 8. Mechanical Saddle Tee: Victaulic 920, 920N, or 920 CROSS
- B. Copper Tube: ASTM B75/B75M or ASTM B88 (ASTM B88M), H58 drawn temper.
1. Type: Type L (B).
 2. Fittings: ASME B16.18, cast copper alloy or ASME B16.22, wrought copper and bronze solder joint, pressure type.
 3. Joints: AWS A5.8M/A5.8 Classification BCuP-3 or BCuP-4 copper/silver braze or ASTM B32, alloy Sn95 solder.
- C. Copper Tube: ASTM B88 (ASTM B88M), Type K (A), H58 drawn.
1. Fittings: ASME B16.18, cast copper alloy or ASME B16.22, wrought copper and bronze, grooved.
 2. Mechanical Grooved Couplings: Ductile iron housing with alkyd enamel paint coating clamps to engage and lock, "C" shaped elastomeric sealing gasket, steel bolts, nuts, and washers.

2.03 PIPE SLEEVES

- A. Vertical Piping:
1. Sleeve Length: 1 inch above finished floor.
 2. Provide sealant for watertight joint.
 3. Blocked Out Floor Openings: Provide 1-1/2 inch angle set in silicon adhesive around opening.
 4. Drilled Penetrations: Provide 1-1/2 inch angle ring or square set in silicone adhesive around penetration.
- B. Plastic, Sheet Metal, or Moisture-Resistant Fiber: Pipe passing through interior walls, partitions, and floors, unless steel or brass sleeves are specified below.
- C. Pipe Passing Through Below Grade Exterior Walls:
1. Provide watertight space with link rubber or modular seal between sleeve and pipe on both pipe ends.
- D. Pipe Passing Through Quarry Tile, Terrazzo, or Ceramic Tile Floors:
1. Connect sleeve with floor plate.
- E. Pipe Passing Through Concrete Beam Flanges, except where Brass Pipe Sleeves are Specified:
1. Galvanized steel pipe or black iron pipe with asphalt coating.
 2. Connect sleeve with floor plate except in mechanical rooms.
- F. Pipe Passing Through Mechanical, Laundry, and Animal Room Floors above Basement:
1. Galvanized steel pipe or black iron pipe with asphalt coating.
 2. Connect sleeve with floor plate except in mechanical rooms.
- G. Not required for wall hydrants for fire department connections or in drywall construction.
- H. Penetrations in concrete beam flanges are permitted but are prohibited through ribs or beams without prior approval from the Architect.
- I. Clearances:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Wall, Floor, Floor, Partitions, and Beam Flanges: 2 inch greater than external; pipe diameter.
2. All Rated Openings: Caulked tight with fire stopping material conforming to ASTM E814 in accordance with Section 078400 to prevent the spread of fire, smoke, and gases.

2.04 MANUFACTURED SLEEVE-SEAL SYSTEMS

- A. Manufacturers:
1. Advance Products & Systems, Inc; _____: www.apsonline.com
 2. The Metraflex Company; _____: www.metraflex.com
 3. Trumbull Industries.
 4. Garlock
 5. Substitutions: See Section 016000 - Product Requirements.
- B. Modular/Mechanical Seal:
1. Synthetic rubber interlocking links continuously fill annular space between pipe and wall/casing opening.
 2. Provide watertight seal between pipe and wall/casing opening.
 3. Elastomer element size and material in accordance with manufacturer's recommendations.
 4. Glass reinforced plastic pressure end plates.

2.05 ESCUTCHEONS

- A. Manufacturers:
1. Victaulic.
 2. Globe
 3. Reliable
 4. Substitutions: See Section 016000 - Product Requirements.
- B. Material:
1. Fabricate from nonferrous metal.
 2. Chrome-plated.
 3. Grade TP304, seamless tube, ASTM A269/A269M stainless steel.
 4. Metals and Finish: Comply with ASME A112.18.1.
- C. Construction:
1. One-piece for mounting on chrome-plated tubing or pipe and one-piece or split-pattern type elsewhere.
 2. Internal spring tension devices or setscrews to maintain a fixed position against a surface.

2.06 PIPE HANGERS AND SUPPORTS

- A. Hangers for Pipe Sizes 1/2 to 1-1/2 inch: Malleable iron, adjustable swivel, split ring.
- B. Hangers for Pipe Sizes 2 inches and Over: Carbon steel, adjustable, clevis.
- C. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.
- D. Wall Support for Pipe Sizes to 3 inches: Unistrut with clamp
- E. Wall Support for Pipe Sizes 4 inches and Over: Welded steel bracket and wrought steel clamp.
- F. Vertical Support: Steel riser clamp.
- G. Floor Support: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
- H. Copper Pipe Support: Carbon steel ring, adjustable, copper plated.
- I. Seismic Hangers and Couplings:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Provide coupling with a factory set disengagement rating of 140 percent to 160 percent of the static weight.
2. Provide resettable and reusable, break away couplings.
3. Provide tether cables to avoid excessive seismic joint movement.
4. Coupling to be manufactured from non-corrosive materials.
5. Manufacturers:
 - a. The Metraflex Company; Seismic Breakaway Hanger: www.metrafire.com
 - b. Substitutions: See Section 016000 - Product Requirements.

2.07 EXPANSION LOOPS - HOSE AND BRAID

- A. Manufacturers:
 1. The Metraflex Company; FireLoop: www.metrafire.com
 2. Substitutions: See Section 016000 - Product Requirements.
- B. Provide flexible loops with two flexible sections of hose and braid, two 90 degree elbows, and 180 degree return with support bracket and air release or drain plug.
- C. Provide flexible loops capable of movement in the x, y, and z planes. Flexible loops to impart no thrust loads to the building structure.
- D. Flexible Connectors: Flanged, braided type with wetted components of stainless steel, sized to match piping.
 1. Maximum Allowable Working Pressure: 150 psig at 120 degrees F.
 2. End Connections: Same as specified for pipe jointing.
 3. End Connections: Flanged ductile iron; complying with ASME B16.5 Class 125.
 4. End Connections: Threaded; complying with ASME B16.11.
 5. Provide necessary accessories including, but not limited to, swivel joints.

2.08 MECHANICAL COUPLINGS

- A. Manufacturers:
 1. Victaulic Company; FireLock Style 009H: www.victaulic.com
 2. Grinnell.
 3. Gruvlok.
 4. Substitutions: See Section 016000 - Product Requirements.
- B. Rigid Mechanical Couplings for Grooved Joints:
 1. Dimensions and Testing: Comply with AWWA C606.
 2. Minimum Working Pressure: 300 psig.
 3. Housing Material: Fabricate of ductile iron conforming to ASTM A536.
 4. Housing Coating: Factory applied orange enamel.
 5. Gasket Material: EPDM suitable for operating temperature range from minus 30 degrees F to 230 degrees F.
 6. Bolts and Nuts: Hot dipped galvanized or zinc electroplated steel.
 7. Provide stops for direct stab installation without field assembly.

PART 3 EXECUTION

3.01 INSTALLERS

- A. Western Automatic Sprinkler.
- B. Frontier Fire
- C. Delta Fire
- D. Kimco

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- E. The Safety Team / Triple A Fire
- F. Preferred Fire
- G. Substitutions: See Section 016000 - Product Requirements.

3.02 PREPARATION

- A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.
- B. Remove scale and foreign material, from inside and outside, before assembly.
- C. Prepare piping connections to equipment with flanges or unions.

3.03 INSTALLATION

- A. Install sprinkler system and service main piping, hangers, and supports in accordance with NFPA 13.
- B. Install standpipe piping, hangers, and supports in accordance with NFPA 14.
- C. Route piping in orderly manner, plumb and parallel to building structure. Maintain gradient.
- D. Install piping to conserve building space, to not interfere with use of space and other work.
- E. In areas with no ceiling, piping shall be installed as high as possible.
- F. In exposed piping situations, head fittings shall have a 1" minimum outlet with a bushing to accommodate future remodel work.
- G. Group piping, whenever practical, at common elevations.
- H. Floor control valves shall be installed 7'-0" maximum above finish floor, unless prior approval is received from BYU.
- I. All drain valves shall be discharged to the exterior of the building. In a below grade application, drain lines shall tie to an auxiliary drain, not a mop sink. Do not tie into any drain line without BYU approval.
- J. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.
- K. Inserts:
 - 1. Provide inserts for placement in concrete formwork.
 - 2. Provide inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
 - 3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
 - 4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.
 - 5. Where inserts are omitted, drill through concrete slab from below and provide through-bolt with recessed square steel plate and nut recessed into and grouted flush with slab.
- L. Pipe Hangers and Supports:
 - 1. Install hangers to provide minimum 1/2 inch space between finished covering and adjacent work.
 - 2. Place hangers within 12 inches of each horizontal elbow.
 - 3. Use hangers with 1-1/2 inch minimum vertical adjustment. Design hangers for pipe movement without disengagement of supported pipe.
 - 4. Support vertical piping at every floor. Support riser piping independently of connected horizontal piping.
 - 5. Where several pipes can be installed in parallel and at same elevation, provide multiple or trapeze hangers.
 - 6. Provide copper hangers and supports for copper piping.
 - 7. Prime coat exposed steel hangers and supports. Hangers and supports located in crawl spaces, pipe shafts, and suspended ceiling spaces are not considered exposed.
 - a. Painting of interior fire suppression systems is specified in Section 099123.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- b. Painting of exterior fire suppression systems is specified in Section 099113.
- M. Slope piping for dry systems and arrange all systems to drain at low points. Use eccentric reducers to maintain top of pipe level.
- N. Prepare pipe, fittings, supports, and accessories for finish painting. Where pipe support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welding.
 - 1. Painting of interior fire suppression systems is specified in Section 099123.
 - 2. Painting of exterior fire suppression systems is specified in Section 099113.
- O. Structural Considerations:
 - 1. Do not penetrate building structural members unless indicated.
 - 2. Locate flexible expansion loops at or near the building seismic joint.
- P. Provide sleeves when penetrating footings, floors, walls, and partitions. Seal pipe including sleeve penetrations to achieve fire resistance equivalent to fire separation required.
 - 1. Aboveground Piping:
 - a. Pack solid using mineral fiber conforming to ASTM C592.
 - b. Fill space with an elastomer caulk to a depth of 0.50 inch where penetrations occur between conditioned and unconditioned spaces.
 - 2. All Rated Openings: Caulk tight with fire stopping material conforming to ASTM E814 in accordance with Section 078400 to prevent the spread of fire, smoke, and gases.
 - 3. Caulk exterior wall sleeves watertight with lead and oakum or mechanically expandable chloroprene inserts with mastic-sealed components.
- Q. Manufactured Sleeve-Seal Systems:
 - 1. Install manufactured sleeve-seal systems in sleeves located in grade slabs and exterior concrete walls at piping entrances into building.
 - 2. Provide sealing elements of the size, quantity, and type required for the piping and sleeve inner diameter or penetration diameter.
 - 3. Locate piping in center of sleeve or penetration.
 - 4. Install field assembled sleeve-seal system components in annular space between sleeve and piping.
 - 5. Tighten bolting for a water-tight seal.
 - 6. Install in accordance with manufacturer's recommendations.
- R. Escutcheons:
 - 1. Install and firmly attach escutcheons at piping penetrations into finished spaces.
 - 2. Provide escutcheons on both sides of partitions separating finished areas through which piping passes.
 - 3. Attach plates at the underside only of suspended ceilings.
 - 4. Use chrome plated escutcheons in occupied spaces and to conceal openings in construction.
- S. When installing more than one piping system material, ensure system components are compatible and joined to ensure the integrity of the system. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.
- T. Die cut threaded joints with full cut standard taper pipe threads with Teflon tape and non-toxic joint compound applied to male threads only.

3.04 CLEANING

- A. Upon completion of work, clean all parts of the installation.
- B. Clean equipment, pipes, valves, and fittings of grease, metal cuttings, and sludge that may have accumulated from the installation and testing of the system.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



C. See Section 017419 - Construction Waste Management and Disposal, for additional requirements.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 210548

VIBRATION AND SEISMIC CONTROLS FOR FIRE SUPPRESSION PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Seismic control requirements.
- B. Seismic restraints for suspended components and equipment.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete.
- B. Section 055000 - Metal Fabrications: Materials and requirements for fabricated metal supports.
- C. Section 220548 - Vibration and Seismic Controls for Plumbing Piping and Equipment
- D. Section 230548 - Vibration and Seismic Controls for HVAC Piping and Equipment

1.03 DEFINITIONS

- A. Fire Suppression Component: Where referenced in this section in regards to seismic controls, applies to any portion of the fire suppression system subject to seismic evaluation in accordance with applicable codes, including distributed systems (e.g., piping).
- B. Seismic Restraint: Structural members or assemblies of members or manufactured elements specifically designed and applied for transmitting seismic forces between components and the seismic force-resisting system of the structure.

1.04 REFERENCE STANDARDS

- A. ASCE 7 - Minimum Design Loads for Buildings and Other Structures; 2010, with 2013 Supplements and Errata.
- B. FEMA E-74 - Reducing the Risks of Nonstructural Earthquake Damage; 2011.
- C. ICC (IBC) - International Building Code; 2015.
- D. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.
- E. UL 203A - Standard for Sway Brace Devices for Sprinkler System Piping; Current Edition, Including All Revisions.

1.05 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate selection and arrangement of vibration isolation and/or seismic control components with the actual equipment to be installed.
 - 2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 - 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.
 - 4. Seismic Controls:
 - a. Coordinate the arrangement of seismic restraints with piping, conduit, equipment, and other potential conflicts installed under other sections or by others.
 - b. Coordinate the work with other trades to accommodate relative positioning of essential and nonessential components in consideration of seismic interaction.
 - 5. Notify Architect of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.
- B. Sequencing:
 - 1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.



1.06 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Design Documents: Prepare and submit all information required for plan review and permitting by authorities having jurisdiction, including but not limited to floor plans, details, and calculations.
- C. Product Data: Provide manufacturer's standard catalog pages and data sheets for products, including materials, fabrication details, dimensions, and finishes.
 - 1. Vibration Isolators: Include rated load capacities and deflections; include information on color coding or other identification methods for spring element load capacities.
 - 2. Seismic Controls: Include seismic load capacities.
- D. Shop Drawings - Seismic Controls:
 - 1. Include dimensioned plan views and sections indicating proposed fire suppression component locations and distributed system routing, with locations and details of gravity supports and seismic restraints and associated attachments.
- E. Field quality control test reports.

1.07 QUALITY ASSURANCE

- A. Comply with applicable building code.
- B. Seismic Controls Designer Qualifications: Registered professional engineer licensed in Utah and with minimum five years experience designing seismic restraints for nonstructural components.
- C. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum five years documented experience.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 SEISMIC CONTROL REQUIREMENTS

- A. Design and provide fire suppression component restraints, supports, and attachments suitable for seismic loads determined in accordance with applicable codes, as well as gravity and operating loads and other structural design considerations of the installed location. Consider wind loads for outdoor fire suppression components.
- B. Seismic Design Criteria: ICC (IBC)/ASCE 7/NFPA 13.
- C. Component Importance Factor (Ip): Fire suppression components to be assigned a component importance factor (Ip) of 1.5 unless otherwise indicated.
- D. Seismic Restraints:
 - 1. Provide seismic restraints for fire suppression components except where exempt according to applicable codes and specified seismic design criteria, as approved by authorities having jurisdiction.
 - 2. Seismic restraint capacities to be verified by a Nationally Recognized Testing Laboratory (NRTL) or certified by an independent third-party registered professional engineer acceptable to authorities having jurisdiction.
- E. Seismic Attachments:
 - 1. Comply with support and attachment requirements of NFPA 13.
- F. Seismic Interactions:
 - 1. Include provisions to prevent seismic impact between fire suppression components and other structural or nonstructural components.
 - 2. Include provisions such that failure of a component, either essential or nonessential, does not cause the failure of an essential component.



3. Comply with minimum clearance requirements between other equipment, distribution systems, and associated supports and fire protection sprinkler system drops and sprigs.
- G. Seismic Relative Displacement Provisions:
1. Use suitable fittings or flexible connections, in accordance with NFPA 13.
 2. Provide clearance around fire suppression system piping extending through walls, floors, platforms, and foundations in accordance with NFPA 13.

2.02 MANUFACTURERS

- A. Substitutions: See Section 016000 - Product Requirements.

2.03 PERFORMANCE REQUIREMENTS

- A. General:
1. All vibration isolators, base frames and inertia bases to conform to all uniform deflection and stability requirements under all operating loads.
 2. Steel springs to function without undue stress or overloading.
 3. Steel springs to operate in the linear portion of the load versus deflection curve over deflection range of not less than 50 percent above specified deflection.
 4. Lateral to vertical stiffness ratio to not exceed 0.08 with spring deflection at minimum 75 percent of specified deflection.
 5. All equipment mounted on vibration isolated bases to have minimum operating clearance of 2 inches between the base and floor or support beneath unless noted otherwise.

2.04 SEISMIC RESTRAINTS FOR SUSPENDED COMPONENTS AND EQUIPMENT

- A. Products to be listed in accordance with the requirements of NFPA 13.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that mounting surfaces are ready to receive vibration isolation and/or seismic control components and associated attachments.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Comply with the requirements of NFPA 13.
- C. Install anchors and fasteners in accordance with ICC Evaluation Services, LLC (ICC-ES) evaluation report conditions of use where applicable.
- D. Secure fasteners according to manufacturer's recommended torque settings.
- E. Field-Welding (where approved by Architect): Comply with Section 055000.
- F. Install flexible piping connections to provide sufficient slack for vibration isolation and/or seismic relative displacements as indicated or as required.

3.03 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect vibration isolation and/or seismic control components for damage and defects.
- C. Correct deficiencies and replace damaged or defective vibration isolation and/or seismic control components.
- D. Submit detailed reports indicating inspection and testing results and corrective actions taken.
- E. Inspect isolated equipment after installation and submit report. Include static deflections.



F. Seismic inspection in the presence of Authority Having Jurisdiction, at time of hydrostatic test.

END OF SECTION



SECTION 211300
FIRE-SUPPRESSION SPRINKLER SYSTEMS
UPDATED MAY 2023

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Wet-pipe sprinkler system.
- B. System design, installation, and certification.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 083477 - Smoke and Fire Protective Curtain Assemblies: Smoke and fire curtains to be released by activation of sprinkler system.
- C. Section 210500 - Common Work Results for Fire Suppression: Pipe and fittings.
- D. Section 210523 - General-Duty Valves for Water-Based Fire-Suppression Piping.
- E. Section 210548 - Vibration and Seismic Controls for Fire Suppression Piping and Equipment.
- F. Section 210553 - Identification for Fire Suppression Piping and Equipment.
- G. Section 211200 - Fire-Suppression Standpipes.
- H. Section 260583 - Wiring Connections: Electrical characteristics and wiring connections.
- I. Section 284600 - Fire Detection and Alarm.

1.03 REFERENCE STANDARDS

- A. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2015.
- B. ICC-ES AC106 - Acceptance Criteria for Predrilled Fasteners (Screw Anchors) in Masonry Elements; 2015.
- C. ICC-ES AC193 - Acceptance Criteria for Mechanical Anchors in Concrete Elements; 2015.
- D. ITS (DIR) - Directory of Listed Products; current edition.
- E. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.
- F. NFPA 13R - Standard for the Installation of Sprinkler Systems in Low-Rise Residential Occupancies; 2016.
- G. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Conduct a preinstallation meeting prior to the start of the work of this section; require attendance by all affected installers. First install scope shall be determined at this meeting.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.
- C. Shop Drawings:
 - 1. Submit preliminary layout of finished ceiling areas indicating only sprinkler locations coordinated with ceiling installation.
 - 2. Indicate hydraulic calculations, detailed pipe layout, hangers and supports, seismic bracing, sprinklers, components and accessories. Indicate system controls.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Submit shop drawings, product data, and hydraulic calculations to AHJ and BYU Fire Marshal for approval. Submit proof of approval to Architect.
- D. Manufacturer's Certificate: Certify that system has been tested and meets or exceeds specified requirements and code requirements.
- E. Designer's Qualification Statement.
- F. Manufacturer's Qualification Statement.
- G. Installer's Qualification Statement.
- H. Operation and Maintenance Data: Include components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.
- I. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 1. See Section 016000 - Product Requirements, for additional provisions.
 2. Extra Sprinklers: Type and size matching those installed, in quantity required by referenced NFPA design and installation standard.
 3. Sprinkler Wrenches: For each sprinkler type.
- J. Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.

1.06 QUALITY ASSURANCE

- A. Designer Qualifications: Professional Fire Protection Engineer Utah or NICET Level III Technician.
- B. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.
- C. Water Velocity: the maximum water velocity shall not exceed 32 fps.
- D. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum five years documented experience.
- E. Installer Qualifications: Company specializing in performing the work of this section with minimum three years' experience and approved by manufacturer.
- F. Equipment and Components: Provide products that bear UL (DIR) label or marking. All products shall be domestic only.
- G. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified and indicated.

1.07 FIRST INSTALL

- A. Provide components for installation in first install.
- B. First install may remain as part of the Work.
- C. Owner shall be invited to participate.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.
- B. Schedule inspection of material with Owner prior to first install.

PART 2 PRODUCTS

2.01 SPRINKLER SYSTEM

- A. Sprinkler System: Provide coverage for entire building.
- B. Occupancy: comply with NFPA 13.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Water Supply: Determine volume and pressure from water flow test data.
 - 1. Contractor shall perform flow test.
- D. Interface system with building control system.
- E. Provide fire department connections where indicated.
- F. Storage Cabinet for Spare Sprinklers and Tools: Steel, in location designated.
- G. Pipe Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
 - 1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
 - 2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
 - 3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
 - 4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.

2.02 SPRINKLERS

- A. Suspended Ceiling Type: Concealed pendant type with matching screw on escutcheon plate.
 - 1. Response Type: Quick. **Updated May 2023: Concealed noted above**
 - 2. Coverage Type: Standard.
 - 3. Finish: Brass.
 - 4. Escutcheon Plate Finish: Enamel, color as selected.
 - 5. Fusible Link: Glass bulb type temperature rated for specific area hazard.
 - 6. Manufacturers:
 - a. Victaulic _____.
 - b. Globe _____.
 - c. Reliable _____.
- B. Exposed Area Type: Pendant or Upright type with guard in minimum 1" fitting with bushing.
 - 1. Response Type: Quick.
 - 2. Coverage Type: Standard.
 - 3. Finish: Brass.
 - 4. Fusible Link: Glass bulb type temperature rated for specific area hazard.
 - 5. Manufacturers:
 - a. Victaulic _____.
 - b. Globe _____.
 - c. Reliable _____.
- C. Sidewall Type: Semi-recessed horizontal sidewall type with matching push on escutcheon plate.
 - 1. Response Type: Quick.
 - 2. Coverage Type: Standard.
 - 3. Finish: Brass.
 - 4. Escutcheon Plate Finish: Enamel, color as selected.
 - 5. Fusible Link: Glass bulb type temperature rated for specific area hazard.
 - 6. Manufacturers:
 - a. Victaulic _____.
 - b. Globe _____.
 - c. Reliable _____.
- D. Dry Sprinklers: Semi-Recessed Pendant type with matching escutcheon plate.
 - 1. Response Type: Quick.
 - 2. Coverage Type: Standard.
 - 3. Finish: Brass.
 - 4. Escutcheon Plate Finish: Enamel, color as selected.
 - 5. Fusible Link: Glass bulb type temperature rated for specific area hazard.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 6. Manufacturers:
 - a. Victaulic _____.
 - b. Globe _____.
 - c. Reliable _____.
- E. Residential Sprinklers: Type as designed by engineer. _____.
 - 1. Response Type: Quick.
 - 2. Fusible Link: Glass bulb type temperature rated for specific area hazard.
- F. Flexible Drop System: Stainless steel, minimum of 5 bends.
 - 1. Application: Use to properly locate sprinkler heads.
 - 2. Include all supports and bracing.
 - 3. Provide braided type tube as required for the application.
 - 4. Manufacturers:
 - a. Victaulic Company; AH2 or AH2CC: www.victaulic.com.
 - b. Viking; Superflex _____.
 - c. Substitutions: See Section 016000 - Product Requirements.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with referenced NFPA design and installation standard.
- B. Install equipment in accordance with manufacturer's instructions.
- C. Place pipe runs to minimize obstruction to other work.
- D. Place piping in concealed spaces above finished ceilings.
- E. Place piping in exposed spaces as high as possible.
- F. Center sprinklers in two directions in ceiling tile and provide piping offsets as required.
 - 1. Exceptions as approved by Owner.
- G. Hydrostatically test entire system.
- H. All tests will be the responsibility of this contractor. If tests are not run or do not have the proper witness, then they will be run later and all damage caused by the system, or caused in uncovering the system for such test, will be borne by this contractor.
- I. Require test be witnessed by BYU Fire Marshal and Authority Having Jurisdiction.

3.02 INTERFACE WITH OTHER PRODUCTS

- A. Ensure required devices are installed and connected as required to fire alarm system.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 220517
SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Pipe sleeves.
- B. Manufactured sleeve-seal systems.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 099113 - Exterior Painting: Preparation and painting of exterior piping systems.
- C. Section 099123 - Interior Painting: Preparation and painting of interior piping systems.
- D. Section 220523 - General-Duty Valves for Plumbing Piping.
- E. Section 220553 - Identification for Plumbing Piping and Equipment: Piping identification.
- F. Section 220716 - Plumbing Equipment Insulation.
- G. Section 220719 - Plumbing Piping Insulation.

1.03 REFERENCE STANDARDS

- A. ASTM C592 - Standard Specification for Mineral Fiber Blanket Insulation and Blanket-Type Pipe Insulation (Metal-Mesh Covered) (Industrial Type); 2016.
- B. ASTM E814 - Standard Test Method for Fire Tests of Penetration Firestop Systems; 2013a.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate pipe materials used, jointing methods, supports, floor and wall penetration seals. Indicate installation, layout, weights, mounting and support details, and piping connections.
- C. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified this section.
 - 1. Minimum three years experience.
 - 2. Approved by manufacturer.
- C. Clean equipment, pipes, valves, and fittings of grease, metal cuttings, and sludge that may have accumulated from the installation and testing of the system.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store sleeve and sleeve seals in shipping containers, with labeling in place.
- B. Provide temporary protective coating on cast iron and steel sleeves if shipped loose.

PART 2 PRODUCTS

2.01 PIPE SLEEVES

- A. Manufacturers:
 - 1. Flexicraft Industries; Pipe Wall Sleeve: www.flexicraft.com/#sle.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: 12/18/2023

Signature & Date: _____



2. Link Seal;
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Vertical Piping:
1. Sleeve Length: 1 inch above finished floor.
 2. Provide sealant for watertight joint.
 3. Blocked Out Floor Openings: Provide 1-1/2 inch angle set in silicon adhesive around opening.
 4. Drilled Penetrations: Provide 1-1/2 inch angle ring or square set in silicone adhesive around penetration.
- C. Plastic or Sheet Metal: Pipe passing through interior walls, partitions, and floors, unless steel or brass sleeves are specified below.
- D. Pipe Passing Through Below Grade Exterior Walls:
1. Zinc coated or cast iron pipe.
 2. Provide watertight space with link rubber or modular seal between sleeve and pipe on both pipe ends.
- E. Pipe Passing Through Concrete Beam Flanges, except where Pipe Sleeves are Specified:
1. Galvanized steel pipe or black iron pipe with asphalt coating.
 2. Connect sleeve with floor plate except in mechanical rooms.
- F. Pipe Passing Through Mechanical, Laundry, and Animal Room Floors above Basement:
1. Galvanized steel pipe or black iron pipe with asphalt coating.
 2. Connect sleeve with floor plate except in mechanical rooms.
- G. Penetrations in concrete beam flanges are permitted but are prohibited through ribs or beams without prior approval from the Architect and/or Owner's Structural Engineer.
- H. Clearances:
1. Provide allowance for insulated piping.
 2. Wall, Floor, Partitions, and Beam Flanges: 1/2 inch greater than external pipe diameter including insulation.
 3. All Rated Openings: Caulked tight with fire stopping material conforming to ASTM E814 in accordance with Section 078400 to prevent the spread of fire, smoke, and gases.

2.02 MANUFACTURED SLEEVE-SEAL SYSTEMS

- A. Manufacturers:
1. Flexicraft Industries; PipeSeal: www.flexicraft.com/#sle.
 2. Link Seal.
 3. Metra Seal.
 4. Substitutions: See Section 016000 - Product Requirements.
- B. Modular/Mechanical Seal:
1. Synthetic rubber interlocking links continuously fill annular space between pipe and wall/casing opening.
 2. Provide watertight seal between pipe and wall/casing opening.
 3. Elastomer element size and material in accordance with manufacturer's recommendations.

PART 3 EXECUTION

3.01 PREPARATION

- A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.
- B. Remove scale and foreign material, from inside and outside, before assembly.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: 12/18/2023

Signature & Date: _____



3.02 INSTALLATION

- A. Route piping in orderly manner, plumb and parallel to building structure. Maintain gradient.
- B. Install piping to conserve building space, to not interfere with use of space and other work.
- C. Install piping and pipe sleeves to allow for expansion and contraction without stressing pipe, joints, or connected equipment.
- D. Inserts:
 - 1. Provide inserts for placement in concrete formwork.
 - 2. Provide inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
 - 3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
 - 4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.
- E. Structural Considerations:
 - 1. Do not penetrate building structural members unless indicated.
- F. Provide sleeves when forming penetrations for footings, floors, walls, and partitions. Seal pipe including sleeve penetrations to achieve fire resistance equivalent to fire separation required.
 - 1. Underground Piping: Caulk pipe sleeve watertight with specified building waterproofing membrane, and provide mechanically expandable chloroprene inserts with bitumen sealed metal components.
 - 2. Aboveground Piping:
 - a. Pack solid using mineral fiber conforming to ASTM C592.
 - b. Fill space with an elastomer caulk to a depth of 0.50 inch where penetrations occur between conditioned and unconditioned spaces.
 - 3. All Rated Openings: Caulk tight with fire stopping material conforming to ASTM E814 in accordance with Section 078400 to prevent the spread of fire, smoke, and gases.
 - 4. Caulk exterior wall sleeves watertight with specified building waterproofing membrane, and provide mechanically expandable chloroprene inserts with mastic-sealed components.
 - 5. Specified building waterproofing membrane shall be completed by manufacturer-certified waterproofing/air barrier installer.
- G. Manufactured Sleeve-Seal Systems:
 - 1. Install manufactured sleeve-seal systems in sleeves located in grade slabs and exterior concrete walls at piping entrances into building.
 - 2. Provide sealing elements of the size, quantity, and type required for the piping and sleeve inner diameter or penetration diameter.
 - 3. Locate piping in center of sleeve or penetration.
 - 4. Install field assembled sleeve-seal system components in annular space between sleeve and piping.
 - 5. Tighten bolting for a water-tight seal.
 - 6. Install in accordance with manufacturer's recommendations.
- H. When installing more than one piping system material, ensure system components are compatible and joined to ensure the integrity of the system. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided. No more than one pipe is permitted per sleeve.

3.03 CLEANING

- A. Upon completion of work, clean all parts of the installation.
- B. Clean equipment, pipes, valves, and fittings of grease, metal cuttings, and sludge that may have accumulated from the installation and testing of the system.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: 12/18/2023

Signature & Date: _____



C. See Section 017419 - Construction Waste Management and Disposal, for additional requirements.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: 12/18/2023

Signature & Date: _____



SECTION 220523 GENERAL-DUTY VALVES FOR PLUMBING PIPING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Applications.
- B. General requirements.
- C. Angle valves.
- D. Ball valves.
- E. Butterfly valves.
- F. Check valves.
- G. Gate valves.
- H. Globe valves.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 083100 - Access Doors and Panels.
- C. Section 220548 - Vibration and Seismic Controls for Plumbing Piping and Equipment.
- D. Section 220553 - Identification for Plumbing Piping and Equipment.
- E. Section 220716 - Plumbing Equipment Insulation.
- F. Section 220719 - Plumbing Piping Insulation.
- G. Section 221005 - Plumbing Piping.
- H. Section 221500 - General-Service Compressed-Air Systems.

1.03 ABBREVIATIONS AND ACRONYMS

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene copolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.
- D. NRS: Non-rising stem.
- E. OS&Y: Outside screw and yoke.
- F. PTFE: Polytetrafluoroethylene.
- G. RS: Rising stem.
- H. SWP: Steam working pressure.
- I. TFE: Tetrafluoroethylene.

1.04 REFERENCE STANDARDS

- A. API STD 594 - Check Valves: Flanged, Lug Wafer, and Butt-Welding; 2017.
- B. ASME B1.20.1 - Pipe Threads, General Purpose (Inch); 2013.
- C. ASME B16.1 - Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250; 2015.
- D. ASME B16.5 - Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard; 2017.
- E. ASME B16.10 - Face-to-Face and End-to-End Dimensions of Valves; 2017.
- F. ASME B16.18 - Cast Copper Alloy Solder Joint Pressure Fittings; 2012.



- G. ASME B16.34 - Valves - Flanged, Threaded and Welding End; 2017.
- H. ASME B31.9 - Building Services Piping; 2014.
- I. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Procedures; Welders; Brazers; and Welding, Brazing and Fusing Operators; 2017.
- J. ASTM A48/A48M - Standard Specification for Gray Iron Castings; 2003 (Reapproved 2016).
- K. ASTM A126 - Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings; 2004 (Reapproved 2014).
- L. ASTM A395/A395M - Standard Specification for Ferritic Ductile Iron Pressure-Retaining Castings for Use at Elevated Temperatures; 1999 (Reapproved 2014).
- M. ASTM A536 - Standard Specification for Ductile Iron Castings; 1984 (Reapproved 2014).
- N. ASTM B61 - Standard Specification for Steam or Valve Bronze Castings; 2015.
- O. ASTM B62 - Standard Specification for Composition Bronze or Ounce Metal Castings; 2017.
- P. AWWA C606 - Grooved and Shouldered Joints; 2015.
- Q. MSS SP-45 - Bypass and Drain Connections; 2003 (Reaffirmed 2008).
- R. MSS SP-67 - Butterfly Valves; 2011.
- S. MSS SP-70 - Cast Iron Gate Valves, Flanged and Threaded Ends; 2011.
- T. MSS SP-71 - Cast Iron Swing Check Valves, Flanged and Threaded Ends; 2011.
- U. MSS SP-72 - Ball Valves with Flanged or Butt-Welding Ends for General Service; 2010.
- V. MSS SP-80 - Bronze Gate, Globe, Angle and Check Valves; 2013.
- W. MSS SP-85 - Cast Iron Globe & Angle Valves, Flanged and Threaded Ends; 2011.
- X. MSS SP-110 - Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends; 2010.
- Y. MSS SP-125 - Gray Iron and Ductile Iron In-Line, Spring-Loaded, Center-Guided Check Valves; 2010.
- Z. NSF 61 - Drinking Water System Components - Health Effects; 2016.
- AA. NSF 372 - Drinking Water System Components - Lead Content; 2016.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on valves including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.
- C. Warranty: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.
- D. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, maintenance and repair data, and parts listings.

1.06 QUALITY ASSURANCE

- A. Manufacturer:
 - 1. Obtain valves for each valve type from single manufacturer.
 - 2. Company must specialize in manufacturing products specified in this section, with not less than three years of documented experience.
- B. Welding Materials and Procedures: Conform to ASME BPVC-IX.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Minimize exposure of operable surfaces by setting ball valves to open position.
 - 2. Protect valve parts exposed to piped medium against rust and corrosion.



3. Protect valve piping connections such as grooves, weld ends, threads, and flange faces.
 4. Adjust globe, gate, and angle valves to the closed position to avoid clattering.
 5. Secure check valves in either the closed position or open position.
 6. Adjust butterfly valves to closed or partially closed position.
- B. Use the following precautions during storage:
1. Maintain valve end protection and protect flanges and specialties from dirt.
 - a. Provide temporary inlet and outlet caps.
 - b. Maintain caps in place until installation.
 2. Store valves in shipping containers and maintain in place until installation.
 - a. Store valves indoors in dry environment.
 - b. Store valves off the ground in watertight enclosures when indoor storage is not an option.
- C. Exercise the following precautions for handling:
1. Handle large valves with sling, modified to avoid damage to exposed parts.
 2. Avoid the use of operating handles or stems as rigging or lifting points.

PART 2 PRODUCTS

2.01 APPLICATIONS

- A. See Drawings for specific valve locations.
- B. Listed pipe sizes shown using nominal pipe sizes (NPS) and nominal diameter (DN).
- C. Provide the following valves for the applications if not indicated on Drawings:
1. Shutoff: Ball, gate.
 2. Dead-End: For up to 2", Ball, 2-1/2" and above, Non rising stem gate valve, epoxy coated resilient wedge type.
 3. Throttling: Provide globe, angle, or ball.
 4. Swing Check (Pump Outlet):
 - a. 2 NPS and Smaller: Bronze swing check valves with bronze, nonmetallic, or stainless steel disc.
 - b. 2-1/2 NPS and Larger for Domestic Water: Iron swing check valves with closure control, metal, resilient, or stainless steel seat check valves.
 - c. 2-1/2 NPS and Larger for Sanitary Waste and Storm Drainage: Iron swing check valves with lever and weight or spring.
- D. Substitutions of valves with higher CWP classes or SWP ratings for same valve types are permitted when specified CWP ratings or SWP classes are not available.
- E. Required Valve End Connections for Non-Wafer Types:
1. Stainless Steel Pipe:
 - a. 2 NPS and Smaller: Threaded ends, mechanical compression fittings.
 - b. 2-1/2 NPS to 4 NPS: Mechanical compression fittings, grooved or flanged ends except where threaded valve-end option is indicated in valve schedules below.
 - c. 5 NPS and Larger: Grooved or flanged ends.
 2. Copper Tube:
 - a. 2 NPS and Smaller: Threaded ends, mechanical compression fittings, except where solder-joint valve-end option is indicated in valve schedules below.
 - b. 2-1/2 NPS to 4 NPS: Mechanical compression fittings, grooved or flanged ends except where threaded valve-end option is indicated in valve schedules below.
 - c. 5 NPS and Larger: Grooved or flanged ends.
 3. HDPE/HDPR Tube:
 - a. 2 NPS and Smaller: Threaded ends, mechanical compression fittings.
 - b. 2-1/2 NPS to 4 NPS: Mechanical compression fittings, grooved or flanged ends except where threaded valve-end option is indicated in valve schedules below.



- c. 5 NPS and Larger: Grooved or flanged ends.
 - 4. Cross-linked Polyethylene Tube:
 - a. 2 NPS and Smaller: Threaded ends, mechanical compression fittings.
 - b. 2-1/2 NPS to 4 NPS: Mechanical compression fittings, grooved or flanged ends except where threaded valve-end option is indicated in valve schedules below.
 - c. 5 NPS and Larger: Grooved or flanged ends.
- F. Low Pressure, Compressed Air Valves 150 psig or Less:
 - 1. 2 NPS and Smaller:
 - a. Bronze, Brass or Stainless Steel: Provide with solder-joint, threaded, or mechanical compression ends.
 - b. Ball: One piece, full port, stainless steel with stainless steel trim.
 - c. Bronze Lift Check: Class 150, nonmetallic disc.
 - d. Bronze Swing Check: Class 150, nonmetallic disc.
 - e. Bronze Gate: Class 150, NRS.
 - 2. 2-1/2 NPS and Larger:
 - a. Iron, 2-1/2 NPS to 4 NPS: Provide with threaded or flanged ends.
 - b. Iron Single-Flange Butterfly: 200 CWP, NBR Seat, ductile-iron disc.
 - c. Iron Grooved-End Butterfly: 175 CWP.
 - d. Iron Swing Check: Class 125, metal seats.
 - e. Iron Grooved-End Swing Check: 300 CWP.
 - f. Iron Center-Guided Check: Class 150, compact-wafer, resilient seat.
 - g. Iron Plate-Type Check: Class 150; single plate; metal seat.
 - h. Iron Gate: Class 125, NRS.
- G. Domestic, Hot and Cold Water Valves:
 - 1. 2 NPS and Smaller:
 - a. Bronze, Stainless Steel, and Brass: Provide with grooved, solder-joint, threaded, or mechanical compression ends.
 - b. Bronze Angle: Class 125, bronze disc.
 - c. Ball: Two piece, full port, stainless steel with stainless-steel trim.
 - d. Bronze Swing Check: Class 125, stainless steel disc.
 - e. Bronze Gate: Class 125, NRS.
 - f. Bronze Globe: Class 125, stainless steel disc.
 - 2. 2-1/2 NPS and Larger:
 - a. Iron, 2-1/2 NPS to 4 NPS: Provide with grooved, threaded, flanged, or mechanical compression ends.
 - b. Iron Ball: Class 150.
 - c. Iron Swing Check: Class 125, metal seats.
 - d. Iron Swing Check with Closure Control: Class 125, lever and spring.
 - e. Iron Grooved-End Swing Check: 300 CWP.
 - f. Iron Center-Guided Check: Class 125, compact-wafer, resilient seat.
 - g. Iron Plate-Type Check: Class 125; single plate; resilient seat.
 - h. Iron Gate: Class 125, NRS.
 - i. Iron Globe: Class 125.
 - j. Epoxy coated resilient wedge.
- H. Sanitary Waste, Storm Drainage, and Forced Main Water Valves:
 - 1. 2 NPS and Smaller:
 - a. Bronze, Stainless Steel and Brass: Provide with grooved, solder-joint, threaded, or mechanical compression ends.
 - b. Bronze Angle: Class 125, bronze disc.
 - c. Ball: Two piece, full port, stainless steel with stainless-steel trim.



- d. Bronze Swing Check: Class 125, stainless steel disc.
- e. Bronze Gate: Class 125, NRS.
- f. Bronze Globe: Class 125, stainless steel disc.
- 2. 2-1/2 NPS and Larger:
 - a. Iron, 2-1/2 NPS to 4 NPS: Provide with mechanical compression, threaded, flanged, or grooved ends.
 - b. Iron Ball: Class 150.
 - c. Iron Swing Check: Class 125, nonmetallic-to-metal seats.
 - d. Iron Swing Check with Closure Control: Class 125, lever and spring.
 - e. Iron Grooved-End Swing Check: 300 CWP.
 - f. Iron Gate: Class 125, NRS.
 - g. Iron Globe: Class 125.

2.02 GENERAL REQUIREMENTS

- A. Valve Pressure and Temperature Ratings: No less than rating indicated; as required for system pressures and temperatures.
- B. Valve Sizes: Match upstream piping unless otherwise indicated.
- C. Valve Actuator Types:
 - 1. Gear Actuator: Quarter-turn valves 8 NPS and larger.
 - 2. Handwheel: Valves other than quarter-turn types.
 - 3. Hand Lever: Quarter-turn valves 6 NPS and smaller.
- D. Valves in Insulated Piping: With 2 NPS stem extensions and the following features:
 - 1. Gate Valves: Rising stem.
 - 2. Ball Valves: Extended operating handle of non-thermal-conductive material, and protective sleeve that allows operation of valve without breaking the vapor seal or disturbing insulation.
 - 3. Butterfly Valves: Extended neck.
 - 4. Memory Stops: Fully adjustable after insulation is installed.
- E. Valve-End Connections:
 - 1. Threaded End Valves: ASME B1.20.1.
 - 2. Flanges on Iron Valves: ASME B16.1 for flanges on iron valves.
 - 3. Pipe Flanges and Flanged Fittings 1/2 NPS through 24 NPS: ASME B16.5.
 - 4. Solder Joint Connections: ASME B16.18.
 - 5. Grooved End Connections: AWWA C606.
 - 6. Mechanical Compression Connections:
 - 7. Cross-linked polyethylene:
- F. General ASME Compliance:
 - 1. Ferrous Valve Dimensions and Design Criteria: ASME B16.10 and ASME B16.34.
 - 2. Solder-joint Connections: ASME B16.18.
 - 3. Building Services Piping Valves: ASME B31.9.
- G. Valve Materials for Potable Water: NSF 61 and NSF 372.
- H. Bronze Valves:
 - 1. Fabricate from dezincification resistant material.
 - 2. Copper alloys containing more than 15 percent zinc are not permitted.
- I. Valve Bypass and Drain Connections: MSS SP-45.

2.03 BRASS BALL VALVES

- A. One-Piece, Reduced-Port with Stainless Steel Trim:
 - 1. Comply with MSS SP-110.
 - 2. CWP Rating: 600 psig.



3. Body: Forged brass.
 4. Ends: Threaded.
 5. Seats: PTFE.
 6. Stem: Stainless Steel.
 7. Ball: Stainless steel.
 8. Manufacturers:
 - a. Nibco.
 - b. Watts.
 - c. Apollo.
 - d. Milwaukee.
 - e. Viega.
 - f. Substitutions: See Section 016000 - Product Requirements.
- B. Two Piece, Full Port with Stainless Steel Trim:
1. Comply with MSS SP-110.
 2. SWP Rating: 150 psig.
 3. CWP Rating: 600 psig.
 4. Body: Forged brass.
 5. Ends: Mechanical Compression, Threaded or soldered.
 6. Seats: PTFE.
 7. Stem: Stainless Steel.
 8. Ball: Stainless Steel.
 9. Manufacturers:
 - a. Apollo.
 - b. Nibco.
 - c. Watts.
 - d. Milwaukee.
 - e. Viega.
 - f. Substitutions: See Section 016000 - Product Requirements.
- C. Three Piece, Full Port with Stainless Steel Trim:
1. Comply with MSS SP-110.
 2. SWP Rating: 150 psig.
 3. CWP Rating: 600 psig.
 4. Body: Forged brass.
 5. Ends: Mechanical Compression, Threaded, or soldered.
 6. Seats: PTFE.
 7. Stem: Stainless steel.
 8. Ball: Stainless steel, Stainless Steel.
 9. Manufacturers:
 - a. Apollo.
 - b. Nibco.
 - c. Watts.
 - d. Milwaukee.
 - e. Viega.
 - f. Substitutions: See Section 016000 - Product Requirements.

2.04 BRONZE BALL VALVES

- A. One Piece, Reduced Port with Stainless Steel Trim:
1. Comply with MSS SP-110.
 2. SWP Rating: 400 psig.
 3. CWP Rating: 600 psig.



4. Body: Bronze.
 5. Ends: Threaded, mechanical compression, or soldered.
 6. Seats: PTFE.
 7. Stem: Stainless steel.
 8. Ball: Stainless Steel
 9. Manufacturers:
 - a. Apollo Valves.
 - b. Viega LLC; _____: www.viega.us
 - c. Nibco.
 - d. Watts.
 - e. Milwaukee.
 - f. Substitutions: See Section 016000 - Product Requirements.
- B. Two Piece, Full Port with Stainless Steel Trim:
1. Comply with MSS SP-110.
 2. SWP Rating: 150 psig.
 3. CWP Rating: 600 psig.
 4. Body: Bronze.
 5. Ends: Threaded, mechanical compression, or soldered.
 6. Seats: PTFE.
 7. Stem: Stainless steel.
 8. Ball: Stainless Steel.
 9. Manufacturers:
 - a. Apollo Valves; _____: www.apollovalves.com
 - b. Viega LLC; _____: www.viega.us
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.
 - f. Substitutions: See Section 016000 - Product Requirements.
- C. Three Piece, Full Port with Stainless Steel Trim:
1. Comply with MSS SP-110.
 2. SWP Rating: 150 psig.
 3. CWP Rating: 600 psig.
 4. Body: Bronze.
 5. Ends: Threaded, mechanical compression, or soldered.
 6. Seats: PTFE
 7. Stem: Stainless steel.
 8. Ball: Stainless Steel.
 9. Manufacturers:
 - a. Apollo Valves; _____: www.apollovalves.com/#sle.
 - b. Viega LLC; _____: www.viega.us
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.
 - f. Substitutions: See Section 016000 - Product Requirements.

2.05 IRON BALL VALVES

- A. Class 125, Full Port, Stainless Steel Trim:
1. Comply with MSS SP-72.
 2. CWP Rating: 200 psig.
 3. Body: ASTM A536, Grade 65-45-12, ductile iron.



4. Ends: Flanged or Grooved..
5. Seats: PTFE.
6. Stem: Stainless steel.
7. Ball: Stainless steel.
8. Operator: Lever, with locking handle.
9. Manufacturers:
 - a. Apollo Valves; _____: www.apollovalves.com
 - b. Viega LLC.
 - c. Nibco.
 - d. Watts.
 - e. Milwaukee.
10. Not for use in potable water systems.

2.06 IRON, SINGLE FLANGE BUTTERFLY VALVES

- A. Lug type: Bi-directional dead-end service without use of downstream flange.
 1. Comply with MSS SP-67, Type I.
 2. CWP Rating: 200 psig.
 3. Body: ASTM A126, cast iron or ASTM A536, ductile iron.
 4. Stem: One or two-piece stainless steel.
 5. Seat: EPDM.
 6. Disc: Coated ductile iron.
 7. Manufacturers:
 - a. Apollo Valves; _____: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.

2.07 IRON, GROOVED-END BUTTERFLY VALVES

- A. CWP Rating: 175 psig (1200 kPa).
 1. Comply with MSS SP-67, Type I.
 2. Body: Coated ductile iron.
 3. Stem: Two-piece stainless steel.
 4. Disc: Coated ductile iron.
 5. Disc Seal: EPDM.
 6. Manufacturers:
 - a. Apollo Valves.
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.
 - f. Substitutions: See Section 016000 - Product Requirements.

2.08 BRONZE LIFT CHECK VALVES

- A. Class 125:
 1. Comply with MSS SP-80, Type 1, Metal Disc to Metal Seat, Type 2, Nonmetallic Disc to Metal Seat, and _____.
 2. CWP Rating: 200 psig.
 3. Design: Vertical flow.
 4. Body: Comply with ASTM B61 or ASTM B62, bronze.
 5. Ends: Threaded as indicated.
 6. Disc (Type 1): Bronze.



7. Disc (Type 2): NBR or _____.
8. Manufacturers:
 - a. Apollo Valves.
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.

2.09 BRONZE SWING CHECK VALVES

- A. Class 125: CWP Rating: 200 psig (1380 kPa) and _____.
 1. Comply with MSS SP-80, Type 3.
 2. Design: Horizontal flow.
 3. Body: Bronze, ASTM B62.
 4. Ends: Threaded as indicated.
 5. Disc: Bronze.
 6. Manufacturers:
 - a. Viega LLC.
 - b. Milwaukee.
 - c. Nibco.
 - d. Watts.

2.10 IRON SWING CHECK VALVES

- A. Class 125:
 1. Comply with MSS SP-71, Type I.
 2. Design: T-body style for clear or full waterways.
 3. CWP Rating: 200 psig.
 4. Design: Clear or full waterway.
 5. Body: ASTM A126, gray iron with bolted bonnet.
 6. Ends: Flanged as indicated.
 7. Trim: Composition.
 8. Seat Ring and Disc Holder: Bronze.
 9. Disc: PTFE or _____.
 10. Gasket: Asbestos free.
 11. Manufacturers:
 - a. Apollo Valves; _____: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.

2.11 IRON GROOVED-END SWING CHECK VALVES

- A. 300 CWP:
 1. CWP Rating: 300 psig.
 2. Body: ASTM A536, Grade 65-45-12 ductile iron.
 3. Seal: EPDM or Nitrile.
 4. Disc: Ductile iron.
 5. Coating: Black, non-lead paint.
 6. Manufacturers:
 - a. Apollo Valves; [_____]: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.



e. Watts.

2.12 IRON CENTER-GUIDED CHECK VALVES

- A. Class 125, Globe:
 - 1. Comply with MSS SP-125.
 - 2. CWP Rating: 200 psig.
 - 3. Body: ASTM A126, gray iron.
 - 4. Style: Spring loaded.
 - 5. Ends: Flanged.
 - 6. Metal Seat: Unleaded bronze.
 - 7. Resilient Seat: EPDM or NBR.
 - 8. Manufacturers:
 - a. Apollo Valves; [_____]: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.
 - f.
- B. Class 150, Compact-Wafer:
 - 1. Comply with MSS SP-125.
 - 2. CW P Rating: 300 psig.
- C. Class 150, Globe:
 - 1. Comply with MSS SP-125.
 - 2. CWP Rating: 300 psig.
 - 3. Style: Spring loaded.
 - 4. Ends: Flanged.

2.13 IRON PLATE TYPE CHECK VALVES

- A. Class 150, Dual-Plate:
 - 1. Comply with API STD 594.
 - 2. CWP Rating: 300 psig.
 - 3. Design: Wafer, spring-loaded plates.
 - 4. Body: ASTM A395/A395M or ASTM A536, ductile iron.
 - 5. Resilient Seat: EPDM or NBR.
 - 6. Manufacturers:
 - a. Apollo Valves; [_____]: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.
- B. Class 300, Dual-Plate:
 - 1. Comply with API STD 594.
 - 2. CWP Rating: 500 psig.
 - 3. Design: Wafer, spring-loaded plates.
 - 4. Body: ASTM A395/A395M or ASTM A536, ductile iron.
 - 5. Metal Seat: Unleaded bronze.
 - 6. Manufacturers:
 - a. Apollo Valves; [_____]: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.



- d. Nibco.
- e. Watts.

2.14 BRONZE GATE VALVES

- A. Non-Rising Stem (NRS) or Rising Stem (RS):
 - 1. Comply with MSS SP-80, Type I.
 - 2. Class 150: CWP Rating: 300 psig:.
 - 3. Body: ASTM B62, bronze with integral seat and screw-in bonnet.
 - 4. Ends: Threaded solder joint, or mechanical press joint.
 - 5. Stem: Unleaded bronze.
 - 6. Disc: Solid wedge; unleaded bronze.
 - 7. Packing: Asbestos free.
 - 8. Handwheel: Malleable iron, bronze, or aluminum.
 - 9. Manufacturers:
 - a. Apollo Valves; []: www.apollovalves.com
 - b. Viega LLC.
 - c. Milwaukee.
 - d. Nibco.
 - e. Watts.
 - f. Substitutions: See Section 016000 - Product Requirements.

2.15 IRON GATE VALVES

- A. NRS:
 - 1. Comply with MSS SP-70, Type I.
 - 2. Class 125: CWP Rating: 200 psig:, and Class 250: CWP Rating: 500 psig:.
 - 3. Body: ASTM A126, gray iron with bolted bonnet.
 - 4. Ends: Flanged.
 - 5. Trim: Stainless Steel.
 - 6. Disc: Solid wedge.
 - 7. Packing and Gasket: Asbestos free.
 - 8. Epoxy coated.
 - 9. Manufacturers:
 - a. Mueller
 - b. American.
 - c. Nibco.
 - d. Watts.
 - e. Substitutions: See Section 016000 - Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Discard all packing materials and verify that valve interior, including threads and flanges are completely clean without signs of damage or degradation that could result in leakage.
- B. Verify valve parts to be fully operational in all positions from closed to fully open.
- C. Confirm gasket material to be suitable for the service, to be of correct size, and without defects that could compromise effectiveness.
- D. Should valve be determined to be defective, replace with new valve.

3.02 INSTALLATION

- A. Provide union or flanges with valves to facilitate equipment removal and maintenance while maintaining system operation and full accessibility for servicing.



- B. Provide separate valve support as required and locate valve with stem at or above center of piping, maintaining unimpeded stem movement.
- C. Where valve support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welds.
- D. Install check valves where necessary to maintain direction of flow as follows:
 - 1. Lift Check: Install with stem plumb and vertical.
 - 2. Swing Check: Install horizontal maintaining hinge pin level.
 - 3. Orient plate-type and center-guided into horizontal or vertical position, between flanges.

END OF SECTION





SECTION 220529

HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Support and attachment components for equipment, piping, and other plumbing work.
- B. Retrofit piping cover system.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete: Concrete equipment pads.
- B. Section 055000 - Metal Fabrications: Materials and requirements for fabricated metal supports.

1.03 REFERENCE STANDARDS

- A. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- B. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2016a.
- C. ASTM A181/A181M - Standard Specification for Carbon Steel Forgings, for General - Purpose Piping; 2014.
- D. ASTM A36/A36M - Standard Specification for Carbon Structural Steel; 2014.
- E. ASTM A47/A47M - Standard Specification for Ferritic Malleable Iron Castings; 1999 (Reapproved 2014).
- F. ASTM B633 - Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel; 2015.
- G. ASTM D635 - Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Plastics in a Horizontal Position; 2014.
- H. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- I. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2016.
- J. MFMA-4 - Metal Framing Standards Publication; 2004.
- K. MSS SP-58 - Pipe Hangers and Supports - Materials, Design, Manufacture, Selection, Application, and Installation; 2009.
- L. NFPA 101 - Life Safety Code; 2015.
- M. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate sizes and arrangement of supports and bases with the actual equipment and components to be installed.
 - 2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 - 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.
 - 4. Coordinate the arrangement of supports with ductwork, piping, equipment and other potential conflicts installed under other sections or by others.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



5. Notify Architect of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.

B. Sequencing:

1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.

1.05 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturer's standard catalog pages and data sheets for metal channel (strut) framing systems, nonpenetrating rooftop supports, post-installed concrete and masonry anchors, and thermal insulated pipe supports.

1. Fiberglass Channel (Strut) Framing Systems: Include requirements for strength derating according to ambient temperature.

C. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

1.06 QUALITY ASSURANCE

A. Comply with current adopted version of IMC and/or ANSI/MSS SP-58.

B. Installer Qualifications for Field-Welding: As specified in Section 055000.

1.07 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 SUPPORT AND ATTACHMENT COMPONENTS

A. General Requirements:

1. Comply with current adopted version of IMC and or ANSI/MSS SP-58.

2. Provide all required hangers, supports, anchors, fasteners, fittings, accessories, and hardware as necessary for the complete installation of plumbing work.

3. Provide products listed, classified, and labeled as suitable for the purpose intended, where applicable.

4. Where support and attachment component types and sizes are not indicated, select in accordance with manufacturer's application criteria as required for the load to be supported with a minimum safety factor as specified by structural engineer. Include consideration for vibration, equipment operation, and shock loads where applicable.

5. Do not use wire, chain, perforated pipe strap, or wood for permanent supports unless specifically indicated or permitted.

6. Steel Components: Use corrosion resistant materials suitable for the environment where installed.

a. Indoor Dry Locations: Use zinc-plated steel or approved equivalent unless otherwise indicated.

b. Outdoor and Damp or Wet Indoor Locations: Use galvanized steel, stainless steel, or approved equivalent unless otherwise indicated.

c. Zinc-Plated Steel: Electroplated in accordance with ASTM B633.

d. Galvanized Steel: Hot-dip galvanized after fabrication in accordance with ASTM A123/A123M or ASTM A153/A153M.

B. Materials for Metal Fabricated Supports: Comply with Section 055000.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



C. Metal Channel (Strut) Framing Systems:

1. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation; _____: www.cooperindustries.com
 - b. Thomas & Betts Corporation; _____: www.tnb.com
 - c. Unistrut, a brand of Atkore International Inc; _____: www.unistrut.com
 - d. Miro Industries _____.
 - e. Substitutions: See Section 016000 - Product Requirements.
2. Comply with MFMA-4.
3. Channel Material:
 - a. Indoor Dry Locations: Use painted steel, zinc-plated steel, or galvanized steel.
 - b. Outdoor and Damp or Wet Indoor Locations: Use galvanized steel.
4. Minimum Channel Thickness: Steel sheet, 12 gage, 0.1046 inch.
5. Minimum Channel Dimensions: 1-5/8 inch width by 1-5/8 inch height.

D. Fiberglass Channel (Strut) Framing Systems: Factory-fabricated continuous-slot fiberglass channel (strut) and associated fittings, accessories, and hardware required for field-assembly of supports.

1. Channel Material: Use polyester resin or vinyl ester resin.
2. Minimum Channel Dimensions: 1-5/8 inch width by 1 inch height.
3. Flammability: Fire retardant with NFPA 101, Class A flame spread index (maximum of 25) when tested in accordance with ASTM E84; self-extinguishing in accordance with ASTM D635.

E. Hanger Rods: Threaded zinc-plated steel unless otherwise indicated.

1. Minimum Size, Unless Otherwise Indicated or Required:
 - a. Equipment Supports: 1/2 inch diameter.
 - b. Piping 2" and smaller: 3/8 inch diameter.
 - c. Piping 2-1/2" to 4": 1/2 inch diameter.
 - d. Piping larger than 4": refer to engineered drawings and/or manufacturer's requirements.
 - e. Trapeze Support for Multiple Pipes: refer to engineered drawings and/or manufacturer's requirements.

F. Thermal Insulated Pipe Supports:

1. General Construction and Requirements:
 - a. Insulated pipe supports to be provided at hanger, support, and guide locations on pipe requiring insulation or additional support.
 - b. Surface Burning Characteristics: Flame spread index/smoke developed index of 5/30, maximum, when tested in accordance with 1 or 1.
 - c. Pipe supports to be provided for nominally sized, 2-1/2 inch to 18 inch iron pipes.
 - d. Insulation inserts to consist of calcium silicate insulation surrounded by a 90 degree galvanized steel jacketing.
2. PVC Jacket:
 - a. Minimum Service Temperature: Minus 40 degrees F.
 - b. Maximum Service Temperature: 180 degrees F.
 - c. Moisture Vapor Transmission: 0.0071 perm inch, when tested in accordance with ASTM E96/E96M.
 - d. Thickness: 60 mil.
 - e. Connections: Brush on welding adhesive.
3. Pipe insulation protection shields to be provided at the hanger points and guide locations on pipes requiring insulation as indicated on drawings.

G. Pipe Supports:

1. Liquid Temperatures Up To 140 degrees F:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- a. Overhead Support: MSS SP-58 Types 1, 3 through 12.
- b. Support From Below: MSS SP-58 Types 35 through 38.
2. Operating Temperatures from 140 to 446 degrees F:
 - a. Overhead Support: MSS SP-58 Type 1 or 3 through 12, with appropriate saddle of MSS SP-58 Type 40 for insulated pipe.
 - b. Roller Support: MSS SP-58 Types 41 or 43 through 46, with appropriate saddle of MSS SP-58 Type 39 for insulated pipe.
 - c. Sliding Support: MSS SP-58 Types 35 through 38.
- H. Beam Clamps: MSS SP-58 Types 19 through 23, 25 or 27 through 30 based on required load.
 1. Material: ASTM A36/A36M carbon steel or ASTM A181/A181M forged steel.
 2. Provide clamps with hardened steel cup-point set screws and lock-nuts for anchoring in place.
- I. Riser Clamps:
 1. Provide copper plated clamps for copper tubing support.
 2. For insulated pipe runs, provide two bolt-type clamps designed for installation under insulation.
- J. Strut Clamps: Two-piece pipe clamp.
- K. Strut-Mount Vibration-Damping Routing Clamps (for refrigeration piping).
 1. Zinc-plated steel or stainless steel clamp with TPE cushion.
 - a. Adjustable metal body with oil and chemical resistant TPE cushion.
 - b. Manufacturers:
 - 1) Hydra-Zorb:
 - 2) Substitutions: See Section 016000 - Product Requirements.
- L. Insulation Clamps: Two bolt-type clamps designed for installation under insulation.
- M. Pipe Hangers: For a given pipe run, use hangers of the same type and material.
 1. Material: Malleable iron, ASTM A47/A47M; or carbon steel, ASTM A36/A36M.
 2. Provide coated or plated hangers to isolate steel hangers from dissimilar metal tube or pipe.
- N. Intermediate Pipe Guides: Use pipe clamps with oversize pipe sleeve that provides clearance around pipe.
 1. Pipe Diameter 6 inches and Smaller: Provide minimum clearance of 0.16 inch.
 2. Pipe Diameter 8 inches: Provide U-bolts with double nuts providing minimum clearance of 0.28 inch.
 3. Pipe Diameter 8 inches: 0.625 inch U-bolt.
 4. Pipe Diameter 10 inches: 0.75 inch U-bolt.
 5. Pipe Diameter 12 to 16 inches: 0.875 inch U-bolt.
 6. Pipe Diameter 18 to 30 inches: 1 inch U-bolt.
- O. Pipe Alignment Guides: Galvanized steel.
 1. Pipe Diameter 8 inches and Smaller: Spider or sleeve type.
 2. Pipe Diameter 10 inches and Larger: Roller type.
 3. Pipe Diameter 18 to 30 inches: 1 inch U-bolt.
- P. Dielectric Barriers: Provide between metallic supports and metallic piping and associated items of dissimilar type; acceptable dielectric barriers include rubber or plastic sheets or coatings attached securely to pipe or item.
- Q. Nonpenetrating Rooftop Supports for Low-Slope Roofs:
 1. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation; _____: www.cooperindustries.com
 - b. Unistrut, a brand of Atkore International Inc; _____: www.unistrut.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- c. Miro Industries.
 - d. Substitutions: See Section 016000 - Product Requirements.
 - 2. Provide steel pedestals with thermoplastic or rubber base that rest on top of roofing membrane, not requiring any attachment to the roof structure and not penetrating the roofing assembly, with support fixtures as specified. Ensure that slip sheet is provided between the pipe support and roofing membrane.
 - 3. Base Sizes: As required to distribute load sufficiently to prevent indentation of roofing assembly.
 - 4. Attachment/Support Fixtures: As recommended by manufacturer, same type as indicated for equivalent indoor hangers and supports.
 - 5. Mounting Height: Provide minimum clearance of 12 inches under supported component to top of roofing.
- R. Pipe Shields for Insulated Piping:
- 1. General Construction and Requirements:
 - a. Surface Burning Characteristics: Comply with 1 or 1.
 - b. Shields Material: 180 degree galvanized steel or aluminum jacketing.
 - c. Maximum Insulated Pipe Outer Diameter: 12-5/8 inch.
 - d. Minimum Service Temperature: Minus 40 degrees F.
 - e. Maximum Service Temperature: 178 degrees F.
 - f. Pipe shields to be provided at hanger, support, and guide locations on pipe requiring insulation or additional support.
- S. Anchors and Fasteners:
- 1. Unless otherwise indicated and where not otherwise restricted, use the anchor and fastener types indicated for the specified applications.
 - 2. Concrete: Use preset concrete inserts, expansion anchors, or screw anchors.
 - 3. Solid or Grout-Filled Masonry: Use expansion anchors or screw anchors.
 - 4. Hollow Masonry: Use toggle bolts.
 - 5. Hollow Stud Walls: Use toggle bolts.
 - 6. Steel: Use beam clamps, machine bolts, or welded threaded studs.
 - 7. Sheet Metal: Use sheet metal screws.
 - 8. Wood: Use wood screws.
 - 9. Plastic and lead anchors are not permitted.
 - 10. Powder-actuated fasteners are permitted only as follows:
 - a. Where approved by Architect.
 - b. Use only threaded studs; do not use pins.
 - 11. Hammer-driven anchors and fasteners are permitted only as follows:
 - a. Nails are permitted for attachment of nonmetallic boxes to wood frame construction (when specified).
 - b. Staples are permitted for attachment of nonmetallic-sheathed cable to wood frame construction (when specified).
 - 12. Preset Concrete Inserts: Continuous metal channel (strut) and spot inserts specifically designed to be cast in concrete ceilings, walls, and floors.
 - a. Comply with MFMA-4.
 - b. Channel Material: Use galvanized steel.
 - c. Minimum Channel Thickness: Steel sheet, 12 gage, 0.1046 inch minimum base metal thickness.
 - 13. Post-Installed Concrete and Masonry Anchors: Evaluated and recognized by ICC Evaluation Service, LLC (ICC-ES) for compliance with applicable building code.
- T. Pipe Installation Accessories:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Copper Pipe Supports: Use pre-manufactured support.
2. PEX Pipe Supports: Use pre-manufactured support, except where allowed by Architect.
3. CPVC Pipe Supports: Use pre-manufactured support, except where allowed by Architect.
4. Thermal Insulated Pipe Supports: Use pre-manufactured support, except where allowed by Architect.
5. Overhead Pipe Supports: Use pre-manufactured support, except where allowed by Architect.
6. Plenum Pipe Supports: Use pre-manufactured support, except where allowed by Architect.
7. Telescoping Pipe Supports: Use pre-manufactured support, except where allowed by Architect.
8. Inserts and Clamps: Use pre-manufactured support, except where allowed by Architect.

2.02 RETROFIT PIPING COVER SYSTEM

A. General Requirements:

1. Surface Burning Characteristics: Flame spread index/smoke developed index of 20/250, maximum, when tested in accordance with ASTM E84 or UL 723.

B. Materials:

1. Piping Cover System: Removal-resistant, modular, snap-fit cover units, clips, and anchors for use with CPVC, steel, and copper piping systems.
2. Cover Units: L-shaped and U-shaped cross-section units of flame retardant resin material, paintable finish.
3. Unit Length: Per manufacturer.
4. Provide coupling fittings for joining units end to end and prefabricated inside and outside corner fittings and end caps as required.
5. Provide mounting clips to secure covers to wall-ceiling per manufacturer requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive support and attachment components.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install anchors and fasteners in accordance with ICC Evaluation Services, LLC (ICC-ES) evaluation report conditions of use where applicable.
- C. Provide independent support from building structure. Do not provide support from piping, ductwork, conduit, or other systems.
- D. Do not provide support from suspended ceiling support system or ceiling grid.
- E. Unless specifically indicated or approved by Architect, do not provide support from roof deck.
- F. Do not penetrate or otherwise notch or cut structural members without approval of Structural Engineer.
- G. Field-Welding (where approved by Architect): Comply with Section 055000.
- H. Provide thermal insulated pipe supports complete with hangers and accessories. Install thermal insulated pipe supports during the installation of the piping system.
- I. Equipment Support and Attachment:
 1. Use metal fabricated supports or supports assembled from metal channel (strut) to support equipment as required.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Use metal channel (strut) secured to studs to support equipment surface-mounted on hollow stud walls when wall strength is not sufficient to resist pull-out.
 3. Use metal channel (strut) to support surface-mounted equipment in wet or damp locations to provide space between equipment and mounting surface.
 4. Unless otherwise indicated, mount floor-mounted equipment on properly sized 4 inch high concrete pad constructed in accordance with Section 033000.
 5. Securely fasten floor-mounted equipment. Do not install equipment such that it relies on its own weight for support.
- J. Preset Concrete Inserts: Use manufacturer-provided closure strips to inhibit concrete seepage during concrete pour.
- K. Secure fasteners according to manufacturer's recommended torque settings.
- L. Remove temporary supports.

3.03 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect support and attachment components for damage and defects.
- C. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.
- D. Correct deficiencies and replace damaged or defective support and attachment components.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 220548

VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Vibration isolation requirements.
- B. Seismic control requirements.
 - 1. Includes requirements for seismic qualification of equipment not specified in this section.
- C. Equipment support bases.
- D. Vibration isolators.
- E. Seismic restraints for suspended components and equipment.

1.02 RELATED REQUIREMENTS

- A. Section 014533 - Code-Required Special Inspections: Statement of Special Inspections; additional requirements for code-required special inspections.
- B. Section 033000 - Cast-in-Place Concrete.
- C. Section 055000 - Metal Fabrications: Materials and requirements for fabricated metal supports.
- D. Section 220529 - Hangers and Supports for Plumbing Piping and Equipment.
- E. Section 230548 - Vibration and Seismic Controls for HVAC Piping and Equipment.

1.03 DEFINITIONS

- A. Plumbing Component: Where referenced in this section in regards to seismic controls, applies to any portion of the plumbing system subject to seismic evaluation in accordance with applicable codes, including distributed systems (e.g., piping).
- B. Seismic Restraint: Structural members or assemblies of members or manufactured elements specifically designed and applied for transmitting seismic forces between components and the seismic force-resisting system of the structure.

1.04 REFERENCE STANDARDS

- A. ASCE 7 - Minimum Design Loads for Buildings and Other Structures; 2010, with 2013 Supplements and Errata.
- B. ASCE 19 - Structural Applications of Steel Cables for Buildings; 2016.
- C. ASHRAE (HVACA) - ASHRAE Handbook - HVAC Applications; 2015.
- D. ICC (IBC) - International Building Code; 2015.
- E. ICC-ES AC156 - Acceptance Criteria for Seismic Certification by Shake-Table Testing of Nonstructural Components; 2010, with Editorial Revision (2015).
- F. MFMA-4 - Metal Framing Standards Publication; 2004.
- G. IAS AC172 - Accreditation Criteria for Fabricator Inspection Programs for Structural Steel; 2017.
- H. SMACNA (SRM) - Seismic Restraint Manual Guidelines for Mechanical Systems; Sheet Metal and Air Conditioning Contractors' National Association; 2008.

1.05 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate selection and arrangement of vibration isolation and/or seismic control components with the actual equipment to be installed.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.
 4. Seismic Controls:
 - a. Coordinate the arrangement of seismic restraints with piping, conduit, equipment, and other potential conflicts installed under other sections or by others.
 - b. Coordinate the work with other trades to accommodate relative positioning of essential and nonessential components in consideration of seismic interaction.
 5. Notify Architect of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.
- B. Sequencing:
1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.

1.06 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Design Documents: Prepare and submit all information required for plan review and permitting by authorities having jurisdiction, including but not limited to floor plans, details, and calculations.
- C. Product Data: Provide manufacturer's standard catalog pages and data sheets for products, including materials, fabrication details, dimensions, and finishes.
 1. Vibration Isolators: Include rated load capacities and deflections; include information on color coding or other identification methods for spring element load capacities.
 2. Seismic Controls: Include seismic load capacities.
- D. Shop Drawings - Vibration Isolation Systems:
 1. Include dimensioned plan views and sections indicating proposed arrangement of vibration isolators; indicate equipment weights and static deflections.
 2. Vibration-Isolated Equipment Support Bases: Include base weights, including concrete fill where applicable; indicate equipment mounting provisions.
- E. Shop Drawings - Seismic Controls:
 1. Include dimensioned plan views and sections indicating proposed plumbing component locations and distributed system routing, with locations and details of gravity supports and seismic restraints and associated attachments.
 2. Identify mounting conditions required for equipment seismic qualification.
 3. Identify anchor manufacturer, type, minimum embedment, minimum spacing, minimum member thickness, and minimum edge distance requirements.
 4. Indicate proposed arrangement of distributed system trapeze support groupings.
 5. Indicate proposed locations for distributed system flexible fittings and/or connections.
 6. Indicate locations of seismic separations where applicable.
 7. Include point load drawings indicating design loads transmitted to structure at each attachment location.
- F. Seismic Design Data:
 1. Compile information on project-specific characteristics of actual installed plumbing components necessary for determining seismic design forces required to design appropriate seismic controls.
 2. Include structural calculations, stamped or sealed by seismic controls designer, demonstrating suitability of seismic controls for seismic design forces.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.07 QUALITY ASSURANCE

- A. Comply with ICC (IBC).
- B. Maintain at the project site a copy of each referenced document that prescribes execution requirements.
- C. Seismic Controls Designer Qualifications: Registered professional engineer licensed in Utah and with minimum five years' experience designing seismic restraints for nonstructural components.
 - 1. Designer may be employed by the manufacturer of the seismic restraint products.
- D. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 VIBRATION ISOLATION REQUIREMENTS

- A. Provide vibration isolation systems to reduce vibration transmission to supporting structure from vibration-producing plumbing equipment and/or plumbing connections to vibration-isolated equipment.
- B. Comply with applicable general recommendations of ASHRAE (HVACA), where not in conflict with other specified requirements:
- C. General Requirements:
 - 1. Select vibration isolators to provide required static deflection.
 - 2. Select vibration isolators for uniform deflection based on distributed operating weight of actual installed equipment.
 - 3. Select seismic type vibration isolators to comply with seismic design requirements, including conditions of equipment seismic certification where applicable.
 - 4. Select vibration isolators for outdoor equipment to comply with wind design requirements.
- D. Equipment Isolation: As indicated on drawings.

2.02 SEISMIC CONTROL REQUIREMENTS

- A. Provide plumbing component restraints, supports, and attachments suitable for seismic loads determined in accordance with applicable codes, as well as gravity and operating loads and other structural design considerations of the installed location. Consider wind loads for outdoor plumbing components.
- B. Seismic Design Criteria: As indicated on drawings.
- C. Component Importance Factor (Ip) [if building is determined to be Risk Category IV]: Plumbing components essential to life safety to be assigned a component importance factor (Ip) of 1.5 as indicated or as required. This includes but is not limited to :
 - 1. Plumbing components required to function for life safety purposes after an earthquake.
 - 2. Plumbing components that support or otherwise contain hazardous substances.
- D. Seismic Qualification of Equipment [if building is determined to be Risk Category IV]:
 - 1. Provide special certification for plumbing equipment furnished under other sections and assigned a component importance factor (Ip) of 1.5, certifying that equipment will remain operable following a design level earthquake.
 - 2. Seismic qualification to be by shake table testing in accordance with recognized testing standard procedure, such as ICC-ES AC156, acceptable to authorities having jurisdiction.
 - 3. Notify Architect and obtain direction where mounting restrictions required by conditions of seismic certification conflict with specified requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



4. Seismically qualified equipment to be furnished with factory-installed labels referencing certificate of compliance and associated mounting restrictions.
- E. Premanufactured Modular Plumbing Equipment: Where not otherwise seismically qualified, premanufactured modules 6 feet high and taller furnished under other sections to be designed in accordance with seismic provisions for nonbuilding structures.
- F. Seismic Restraints:
 1. Provide seismic restraints for plumbing components except where exempt according to applicable codes and specified seismic design criteria, as approved by authorities having jurisdiction.
 2. Seismic Restraint Exemptions:
 - a. Exemptions for Seismic Design Category D, E, and F:
 - 1) Discrete plumbing components that are positively attached to the structure where either of the following apply:
 - (a) The component weighs 400 pounds or less, has a center of mass located 4 feet or less above the adjacent floor level, flexible connections are provided between the component and associated ductwork, piping, and conduit, and the component importance factor (I_p) is 1.0.
 - (b) The component weighs 20 pounds or less or, in the case of a distributed system, 5 pounds per foot or less.
 - 2) Plumbing piping with component importance factor (I_p) of 1.0 and nominal pipe size of 3 inch or less, or with component importance factor (I_p) of 1.5 and nominal pipe size of 1 inch or less, where flexible connections, expansion loops, or other assemblies are provided between piping and associated components, and where piping is positively attached to the structure; exemption does not apply to piping constructed of low-deformability materials (e.g., cast iron, glass, nonductile plastics).
 - b. Plumbing Piping Exemptions, All Seismic Design Categories:
 - 1) Plumbing piping where flexible connections, expansion loops, or other assemblies are provided between piping and associated components, where piping is positively attached to the structure, and where one of the following apply:
 - (a) Trapeze supported piping weighing less than 10 pounds per foot, where all pipes supported meet size requirements for exemption as single pipes described under specific seismic design category exemptions above.
 - (b) Trapeze supported piping with trapeze assemblies using 3/8 inch diameter rod hangers not exceeding 12 inches in length from support point connection to the supporting structure, where all pipes supported have a component importance factor (I_p) of 1.0 and meet size requirements for exemption as single pipes described under specific seismic design category exemptions above, and where the total weight supported by any single trapeze is 100 pounds or less.
 - (c) Trapeze supported piping with trapeze assemblies using 1/2 inch diameter rod hangers not exceeding 12 inches in length from support point connection to the supporting structure, where all pipes supported have a component importance factor (I_p) of 1.0 and meet size requirements for exemption as single pipes described under specific seismic design category exemptions above, and where the total weight supported by any single trapeze is 200 pounds or less.
 - (d) Trapeze supported piping with trapeze assemblies using 1/2 inch diameter rod hangers not exceeding 24 inches in length from support point connection to the supporting structure, where all pipes supported have a component importance factor (I_p) of 1.0 and meet size requirements for exemption as single pipes

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



described under specific seismic design category exemptions above, and where the total weight supported by any single trapeze is 100 pounds or less.

- (e) Hanger supported piping with individual rod hangers 3/8 inch or 1/2 inch in diameter not exceeding 12 inches in length from support point connection to the supporting structure, where pipe has a component importance factor (I_p) of 1.0 and meets size requirements for exemption as single pipes described under specific seismic design category exemptions above, and where the total weight supported by any single rod is 50 pounds or less.

3. Seismic Restraint Systems:

- a. Except where otherwise restricted, use of either cable or rigid restraints is permitted.
- b. Use only cable restraints to restrain vibration-isolated plumbing components, including distributed systems.
- c. Use only one restraint system type for a given plumbing component or distributed system (e.g., piping) run; mixing of cable and rigid restraints on a given component/run is not permitted.
- d. Size restraint elements, including anchorage, to resist seismic loads as necessary to restrain plumbing component in all lateral directions; consider bracket geometry in anchor load calculations.
- e. Use rod stiffener clips to attach bracing to hanger rods as required to prevent rod buckling from vertical (upward) compressive load introduced by cable or rigid restraints loaded in tension, in excess of downward tensile load due to supported plumbing component weight.
- f. Select hanger rods and associated anchorage as required to accommodate vertical (downward) tensile load introduced by rigid restraints loaded in compression, in addition to downward tensile load due to supported plumbing component weight.
- g. Clevis hangers may only be used for attachment of transverse restraints; do not use for attachment of longitudinal restraints.
- h. Where seismic restraints are attached to clevis hangers, provide clevis bolt reinforcement accessory to prevent clevis hanger deformation.
- i. Do not introduce lateral loads on open bar joist chords or the weak axis of beams, or loads in any direction at other than panel points unless approved by project Structural Engineer of Record.

G. Seismic Attachments:

- 1. Attachments to be bolted, welded, or otherwise positively fastened without consideration of frictional resistance produced by the effects of gravity.
- 2. Post-Installed Concrete and Masonry Anchors: Evaluated and recognized by ICC Evaluation Service, LLC (ICC-ES) or qualified evaluation service acceptable to authorities having jurisdiction for compliance with applicable building code, and qualified for seismic applications; concrete anchors to be qualified for installation in both cracked and uncracked concrete.
- 3. Do not use power-actuated fasteners.
- 4. Do not use friction clips (devices that rely on mechanically applied friction to resist loads). Beam clamps may be used for supporting sustained loads where provided with restraining straps.
- 5. Comply with anchor minimum embedment, minimum spacing, minimum member thickness, and minimum edge distance requirements.

H. Seismic Interactions:

- 1. Include provisions to prevent seismic impact between plumbing components and other structural or nonstructural components.
- 2. Include provisions such that failure of a component, either essential or nonessential, does not cause the failure of an essential component.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Comply with minimum clearance requirements between plumbing equipment, distribution systems, and associated supports and fire protection sprinkler system drops and sprigs.

I. Seismic Relative Displacement Provisions:

1. Use suitable fittings or flexible connections to accommodate:
 - a. Relative displacements at connections between components, including distributed systems (e.g., piping); do not exceed load limits for equipment utility connections.
 - b. Relative displacements between component supports attached to dissimilar parts of structure that may move differently during an earthquake.
 - c. Design displacements at seismic separations.
 - d. Anticipated drifts between floors.

2.03 EQUIPMENT SUPPORT BASES

A. Manufacturers:

1. Vibration-Isolated Equipment Support Bases:
 - a. Kinetics Noise Control, Inc; _____: www.kineticsnoise.com
 - b. Mason Industries; _____: www.mason-ind.com
 - c. Substitutions: See Section 016000 - Product Requirements.

2.04 VIBRATION ISOLATORS

A. Manufacturers:

1. Vibration Isolators:
 - a. Kinetics Noise Control, Inc; _____: www.kineticsnoise.com
 - b. Mason Industries; _____: www.mason-ind.com
 - c. Substitutions: See Section 016000 - Product Requirements.

B. General Requirements:

1. Resilient Materials for Vibration Isolators: Oil, ozone, and oxidant resistant.
2. Spring Elements for Spring Isolators:
 - a. Color code or otherwise identify springs to indicate load capacity.
 - b. Lateral Stability: Minimum lateral stiffness to vertical stiffness ratio of 0.8.
 - c. Designed to operate in the linear portion of their load versus deflection curve over deflection range of not less than 50 percent above specified deflection.
 - d. Designed to provide additional travel to solid of not less than 50 percent of rated deflection at rated load.
 - e. Selected to provide designed deflection of not less than 75 percent of specified deflection.
 - f. Selected to function without undue stress or overloading.

C. Vibration Isolators for Non seismic Applications:

1. Resilient Material Isolator Pads:
 - a. Description: Single or multiple layer pads utilizing elastomeric (e.g., neoprene, rubber) isolator material.
 - b. Pad Thickness: As required for specified minimum static deflection; minimum 0.25 inch thickness.
 - c. Multiple Layer Pads: Provide bonded, galvanized sheet metal separation plate between each layer.

2.05 SEISMIC RESTRAINT SYSTEMS

A. Manufacturers:

1. Seismic Restraint Systems:
 - a. AFCON, a brand of Anvil International; _____: www.anvilintl.com
 - b. Eaton Corporation; _____: www.eaton.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- c. Kinetics Noise Control, Inc; _____: www.kineticsnoise.com
 - d. Mason Industries; _____: www.mason-ind.com
 - e. Substitutions: See Section 016000 - Product Requirements.
- B. Description: System components and accessories specifically designed for field assembly and attachment of seismic restraints.
- C. Cable Restraints:
- 1. Comply with ASCE 19.
 - 2. Cables: Pre-stretched, galvanized steel wire rope with certified break strength.
 - 3. Cable Connections: Use only swaged end fittings. Cable clips and wedge type end fittings are not permitted in accordance with ASCE 19.
 - 4. Use protective thimbles for cable loops where potential for cable damage exists.
- D. Rigid Restraints: Use MFMA-4 steel channel (strut), steel angle, or steel pipe for structural element; suitable for both compressive and tensile design loads.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that conditions are satisfactory for installation prior to starting work.

3.02 CODE-REQUIRED SPECIAL INSPECTIONS (ENGINEER OF RECORD TO VERIFY APPLICABILITY OF THIS SECTION)

- A. Arrange work to accommodate tests and/or inspections performed by Special Inspection Agency employed by Owner or Architect in accordance with Section 014533 and statement of special inspections as required by applicable building code.
- B. Frequency of Special Inspections: Where special inspections are designated as continuous or periodic, arrange work accordingly.
 - 1. Periodic Special Inspections: Special Inspection Agency to be present in the area where work is being performed and observe the work part-time or intermittently and at the completion of the work.
- C. Seismic special inspections include, but are not limited to:
 - 1. Seismically Qualified Equipment: Verification that label, anchorage, and mounting comply with the certificate of compliance.
 - 2. Installation and anchorage of piping systems designed to carry hazardous materials and their associated mechanical units for Seismic Design Categories C, D, E, and F; periodic inspection.
 - 3. Installation and anchorage of vibration isolation systems for Seismic Design Categories C, D, E, and F where the approved Contract Documents require a nominal clearance of 1/4 inch or less between equipment support frame and seismic restraint; periodic inspection.
 - 4. Verification of required clearances between plumbing equipment, distribution systems, and associated supports and fire protection sprinkler system drops and sprigs for Seismic Design Categories C, D, E, and F; periodic inspection.
- D. Prior to starting work, Contractor to submit written statement of responsibility to authorities having jurisdiction and to Owner acknowledging awareness of special requirements contained in the statement of special inspections.
- E. Special Inspection Agency services do not relieve Contractor from performing inspections and testing specified elsewhere.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.03 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install anchors and fasteners in accordance with ICC Evaluation Services, LLC (ICC-ES) evaluation report conditions of use where applicable.
- C. Secure fasteners according to manufacturer's recommended torque settings.
- D. Field-Welding (where approved by Architect): Comply with Section 055000.
- E. Install flexible piping connections to provide sufficient slack for vibration isolation and/or seismic relative displacements as indicated or as required.
- F. Seismic Controls:
 - 1. Use only specified components, anchorage, and hardware evaluated by seismic design. Comply with conditions of seismic certification where applicable.
 - 2. Seismic Restraint Systems:
 - a. Do not attach seismic restraints and gravity supports to dissimilar parts of structure that may move differently during an earthquake.
 - b. Install restraints within permissible angles in accordance with seismic design.
 - c. Install cable restraints straight between component/run and structural attachment; do not bend around other nonstructural components or structural elements.
 - d. Install cable restraints for vibration-isolated components slightly slack to prevent short-circuiting of isolation.
 - e. Install hanger rod stiffeners where indicated using only specified clamps; do not weld stiffeners to hanger rod.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect vibration isolation and/or seismic control components for damage and defects.
- C. Vibration Isolation Systems:
 - 1. Verify isolator static deflections.
 - 2. Verify vibration isolation performance during normal operation; investigate sources of isolation short circuits.
- D. Correct deficiencies and replace damaged or defective vibration isolation and/or seismic control components.
- E. Submit detailed reports indicating inspection and testing results and corrective actions taken.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 220553

IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 GENERAL

UPDATED NOV 2021

1.01 SECTION INCLUDES

THIS COMPLETE SECTION IS UPDATED.

- A. For identification for plumbing piping and equipment comply with Section 230553 - Identification for HVAC Piping and Equipment.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 220719 PLUMBING PIPING INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Flexible elastomeric cellular insulation.
- B. Cellular melamine insulation.
- C. Glass Fiber insulation.
- D. Jackets and accessories.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 099113 - Exterior Painting: Painting insulation jacket.
- C. Section 099123 - Interior Painting: Painting insulation jacket.
- D. Section 221005 - Plumbing Piping: Placement of hangers and hanger inserts.
- E. Section 232113 - Hydronic Piping: Placement of hangers and hanger inserts.
- F. Section 232213 - Steam and Steam Condensate Piping: Placement of hangers and hanger inserts.
- G. Section 232300 - Refrigerant Piping: Placement of inserts.

1.03 REFERENCE STANDARDS

- A. ASTM A666 - Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2015.
- B. ASTM B209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2014.
- C. ASTM B209M - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric); 2014.
- D. ASTM C14 - Standard Specification for Nonreinforced Concrete Sewer, Storm Drain, and Culvert Pipe; 2015a.
- E. ASTM C177 - Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus; 2013.
- F. ASTM C195 - Standard Specification for Mineral Fiber Thermal Insulating Cement; 2007 (Reapproved 2013).
- G. ASTM C449 - Standard Specification for Mineral Fiber Hydraulic-Setting Thermal Insulating and Finishing Cement; 2007 (Reapproved 2013).
- H. ASTM C518 - Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2017.
- I. ASTM C533 - Standard Specification for Calcium Silicate Block and Pipe Thermal Insulation; 2013.
- J. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2016.
- K. ASTM C547 - Standard Specification for Mineral Fiber Pipe Insulation; 2017.
- L. ASTM C552 - Standard Specification for Cellular Glass Thermal Insulation; 2016a.
- M. ASTM C553 - Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications; 2013.
- N. ASTM C578 - Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation; 2016.



- O. ASTM C585 - Standard Practice for Inner and Outer Diameters of Thermal Insulation for Nominal Sizes of Pipe and Tubing; 2010 (Reapproved 2016).
- P. ASTM C591 - Standard Specification for Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation; 2017.
- Q. ASTM C610 - Standard Specification for Molded Expanded Perlite Block and Pipe Thermal Insulation; 2016.
- R. ASTM C795 - Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel; 2008 (Reapproved 2013).
- S. ASTM C1410 - Standard Specification for Cellular Melamine Thermal and Sound-Absorbing Insulation; 2014.
- T. ASTM C1695 - Standard Specification for Fabrication of Flexible Removable and Reusable Blanket Insulation for Hot Service; 2010 (Reapproved 2015).
- U. ASTM D1056 - Standard Specification for Flexible Cellular Materials--Sponge or Expanded Rubber; 2014.
- V. ASTM D2842 - Standard Test Method for Water Absorption of Rigid Cellular Plastics; 2012.
- W. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- X. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009 (Reapproved 2016).
- Y. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2016.
- Z. ASTM G21 - Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi; 2015.
- AA. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.
- C. Manufacturer's Instructions: Indicate installation procedures that ensure acceptable workmanship and installation standards will be achieved.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with not less than three years of documented experience.
- B. Applicator Qualifications: Company specializing in performing the type of work specified in this section with minimum three years of experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Accept materials on site, labeled with manufacturer's identification, product density, and thickness.

1.07 FIELD CONDITIONS

- A. Maintain ambient conditions required by manufacturers of each product.
- B. Maintain temperature before, during, and after installation for minimum of 24 hours.
- C. Protect from moisture, sun, elements.



PART 2 PRODUCTS

2.01 REGULATORY REQUIREMENTS

- A. Surface Burning Characteristics: Flame spread index/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84 or UL 723.
- B. Insulation shall have a 'K' value that meets the minimum requirements of the latest International Energy Conservation Code (IECC).

2.02 CELLULAR MELAMINE

- A. Manufacturers:
 - 1. TECHLITE; _____
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: Flexible preformed open-cell polymeric foam tubing, slit lengthwise for installation, complying with applicable requirements of ASTM C1410.
 - 1. 'K' Value: ASTM C177; 0.25 at 75 degrees F.
 - 2. Minimum Service Temperature: Minus 40 degrees F.
 - 3. Maximum Service Temperature: 350 degrees F.
 - 4. Density: 0.56 lb/cu ft.
 - 5. Factory-Applied Jacketing Material: PVC, flexible with UV resistant and flame retardant additives.
 - a. Color: White.
 - 6. Jacketing material to be field-applied.

2.03 GLASS FIBER

- A. Manufacturers:
 - 1. CertainTeed Corporation; _____
 - 2. Johns Manville Corporation; _____
 - 3. Knauf Insulation; Earthwool 1000 Degree Pipe Insulation
 - 4. Owens Corning Corporation
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: ASTM C547 and ASTM C795; semi-rigid, noncombustible, end grain adhered to jacket.
 - 1. 'K' Value: ASTM C177, 0.24 at 75 degrees F.
 - 2. Maximum Service Temperature: 650 degrees F.
 - 3. Maximum Moisture Absorption: 0.2 percent by volume.
- C. Vapor Barrier Jacket: White Kraft paper with glass fiber yarn, bonded to aluminized film; moisture vapor transmission when tested in accordance with ASTM E96/E96M of 0.02 perm-inches.
- D. Vapor Barrier Lap Adhesive: Compatible with insulation.
- E. Insulating Cement/Mastic: ASTM C195; hydraulic setting on mineral wool.

2.04 FLEXIBLE ELASTOMERIC CELLULAR INSULATION

- A. Manufacturer:
 - 1. Aeroflex USA, Inc; _____
 - 2. Armacell LLC; AP Armaflex
 - 3. K-Flex USA LLC; Insul-Tube
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: Preformed flexible elastomeric cellular rubber insulation complying with ASTM C534/C534M Grade 1; use molded tubular material wherever possible.
 - 1. Minimum Service Temperature: Minus 40 degrees F.
 - 2. Maximum Service Temperature: 220 degrees F.
 - 3. Connection: Waterproof vapor barrier adhesive.



- C. Elastomeric Foam Adhesive: Air dried, contact adhesive, compatible with insulation.
 - 1. Manufacturers:
 - a. Substitutions: See Section 016000 - Product Requirements.

2.05 JACKETS

- A. PVC Plastic.
 - 1. Manufacturers:
 - a. Johns Manville Corporation; _____
 - b. Substitutions: See Section 016000 - Product Requirements.
 - 2. Jacket: One piece molded type fitting covers and sheet material, white color.
 - a. Minimum Service Temperature: 0 degrees F.
 - b. Maximum Service Temperature: 150 degrees F.
 - c. Moisture Vapor Permeability: 0.002 perm inch, maximum, when tested in accordance with ASTM E96/E96M.
 - d. Thickness: 10 mil.
 - e. Connections: Brush-on welding adhesive and/or tacks.
 - 3. Covering Adhesive Mastic: Compatible with insulation.
- B. Aluminum Jacket: ASTM B209 (ASTM B209M) formed aluminum sheet.
 - 1. Thickness: 0.016 inch sheet.
 - 2. Finish: Smooth or embossed.
 - 3. Joining: Longitudinal slip joints and 2 inch laps.
 - 4. Fittings: 0.016 inch thick die shaped fitting covers with factory attached protective liner.
 - 5. Metal Jacket Bands: 3/8 inch wide; 0.015 inch thick aluminum, or
 - 6. Metal Jacket Bands: 3/8 inch wide; 0.010 inch thick stainless steel.
- C. Stainless Steel Jacket: ASTM A666, Type 316 stainless steel.
 - 1. Thickness: 0.010 inch.
 - 2. Finish: Smooth for interior applications, corrugated for exterior.
 - 3. Metal Jacket Bands: 3/8 inch wide; 0.010 inch thick stainless steel.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that piping has been tested before applying insulation materials.
- B. Verify that surfaces are clean and dry, with foreign material removed.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install in accordance with North American Insulation Manufacturers Association (NAIMA) National Insulation Standards.
- C. Exposed Piping: Locate insulation and cover seams in least visible locations.
- D. Insulated pipes conveying fluids below ambient temperature: Insulate entire system including fittings, valves, unions, flanges, strainers, flexible connections, roof drain bodies, and expansion joints.
- E. Install cellular melamine with factory-applied jackets with a manufacturer-approved adhesive along seams, both straight lap joints and circumferential lap joints.
 - 1. Install seal over seams with factory-approved room temperature vulcanization (RTV) silicone sealant to ensure a positive vapor barrier seal in outdoor and sanitary washdown environments.
- F. Glass fiber insulated pipes conveying fluids below ambient temperature:
 - 1. Provide vapor barrier jackets, factory-applied or field-applied. Secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive. Secure with outward clinch expanding staples and vapor barrier mastic.



2. Insulate fittings, joints, and valves with molded insulation of like material and thickness as adjacent pipe. Finish with glass cloth and vapor barrier adhesive or PVC fitting covers.
- G. For hot piping conveying fluids 140 degrees F or less, do not insulate flanges and unions at equipment, but bevel and seal ends of insulation.
- H. For hot piping conveying fluids over 140 degrees F, insulate flanges and unions at equipment.
- I. Glass fiber insulated pipes conveying fluids above ambient temperature:
1. Provide standard jackets, with or without vapor barrier, factory-applied or field-applied. Secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive. Secure with outward clinch expanding staples.
 2. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe. Finish with glass cloth and adhesive or PVC fitting covers.
- J. Inserts and Shields:
1. Application: Piping 2 inches diameter or larger.
 2. Shields: Galvanized steel between pipe hangers or pipe hanger rolls and inserts.
 3. Insert Location: Between support shield and piping and under the finish jacket.
 4. Insert Configuration: Minimum 6 inches long, of same thickness and contour as adjoining insulation; may be factory fabricated.
 5. Insert Material: Hydrous calcium silicate insulation or other heavy density insulating material suitable for the planned temperature range.
- K. **Continue insulation through walls, sleeves, pipe hangers, and other pipe penetrations.** Finish at supports, protrusions, and interruptions. At fire separations, refer to Section 078400.
- L. Pipe Exposed in Mechanical Equipment Rooms or Finished Spaces (less than 10 feet above finished floor): Finish exposed pipe in Mechanical Equipment Rooms with PVC jacket and fitting covers. Finish exposed pipe in Finished Spaces with paper and foil scrim suitable for application of paint, or PVC jacket and fitting covers. Coordinate with owner.
- M. Exterior Applications: Provide vapor barrier jacket. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe, and finish with glass mesh reinforced vapor barrier cement. Cover with aluminum jacket with seams located on bottom side of horizontal piping.
- N. Minimum pipe insulation thicknesses (in inches):
1. Cold Piping:
 - a. Potable cold water piping, chilled domestic water supply and return, roof drain bodies, interior above-ground storm water piping, including roof drain, deck drain and landscape drain piping and plumbing vents within 6 lineal feet of roof or wall outlet.
 - 1) Glass fiber with jacket, self sealing lap: 1" thickness.
 - 2) Flexible elastomeric: 1/2" thickness.
 2. Hot Piping:
 - a. Potable hot water piping, potable hot water recirculating piping and hot drain piping.
 - 1) Glass fiber with jacket, self sealing lap: 1" thick for pipe sizes up to and including 2"; 1-1/2" thick for pipe sizes over 2".
 - 2) Flexible elastomeric: 1/2" thick for pipe sizes up to and including 2" (largest size permitted) with contact cement or heat fused joints.



FT (°F)	Insulation Conductivity		Nominal pipe or tube size (inches)				
	Conductivity	TR (°F)	< 1	1 to < 1½	1½ to < 4	4 to < 8	≥ 8
> 350	0.32 – 0.34	250	4.5	5.0	5.0	5.0	5.0
251 – 350	0.29 – 0.32	200	3.0	4.0	4.5	4.5	4.5
201 – 250	0.27 – 0.30	150	2.5	2.5	2.5	3.0	3.0
141 – 200	0.25 – 0.29	125	1.5	1.5	2.0	2.0	2.0
105 – 140	0.21 – 0.28	100	1.0	1.0	1.5	1.5	1.5
40 – 60	0.21 – 0.27	75	0.5	0.5	1.0	1.0	1.0
< 40	0.20 – 0.26	50	0.5	1.0	1.0	1.0	1.5

FT = Fluid Operating Temperature Range and Usage

TR = Mean Temperature Rating

Conductivity units are shown in $\frac{\text{hr}\cdot\text{ft}\cdot\text{in}}{\text{h}\cdot\text{ft}^2\cdot\text{°F}}$

END OF SECTION



SECTION 220719.11
UNDER-LAVATORY PIPE AND SUPPLY COVERS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Under-lavatory pipe and supply covers.

1.02 RELATED REQUIREMENTS

- A. Section 011000 - Summary: Owner-furnished fixtures.
- B. Section 221005 - Plumbing Piping.

1.03 REFERENCE STANDARDS

- A. 28 CFR 36 - Nondiscrimination by Public Accommodations and in Commercial Facilities; Final Rule; Department of Justice; current edition.
- B. 36 CFR 1191 - Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines; current edition.
- C. ABA Standards - ABA Accessibility Standards; 2004, with 2015 amendments.
- D. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.
- E. ASME A112.18.9 - Protectors/Insulators for Exposed Waste and Supplies on Accessible Fixtures; 2011.
- F. ASTM C177 - Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus; 2013.
- G. ASTM C518 - Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2017.
- H. ASTM C1822 - Standard Specification for Insulating Covers on Accessible Lavatory Piping; 2015.
- I. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- J. ASTM G21 - Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi; 2015.
- K. ATBCB ADAAG - Americans with Disabilities Act Accessibility Guidelines; 2004.
- L. IAPMO (UPC) - Uniform Plumbing Code; 2012.
- M. ICC (IBC) - International Building Code; 2015.
- N. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2017.
- O. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide catalog illustrations of covers, sizes, and finishes.
- C. Manufacturer's Instructions: Indicate installation methods and procedures.
- D. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

1.06 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.

PART 2 PRODUCTS

2.01 UNDER-LAVATORY PIPE AND SUPPLY COVERS

- A. Manufacturers:
 - 1. IPS.
 - 2. Plumberex Specialty Products, Inc; _____: www.plumberex.com
- B. Basis of Design: IPS Truebro SoftGuard Plus.
 - 1. Anti-Microbial finish, Hook and Loop (Velcro) fastening system, suitable for Schedule 40 P-traps and flexible braided hoses..
 - 2. 1/8" pliable PVC Shell finish Soft Guard Plus on all drainage piping including hot and cold water valve and supplies under lavatories to comply with ADA, IBC, and UPC standards. Covers shall be secured by joining internal hook and loop fastening system.
- C. General:
 - 1. Insulate exposed drainage piping including hot, cold, and tempered water supplies under lavatories or sinks per ADA Standards.
 - 2. Adhesives, sewing threads, and two-ply laminated materials are prohibited.
 - 3. Provide with Velcro fastening system or approved equivalent.
 - 4. Exterior Surfaces: Smooth nonabsorbent with no finger recessed indentations for easy cleaning.
 - 5. Construction: 1/8 inch PVC with antimicrobial, antifungal, and ultraviolet light (UV) resistant properties.
 - a. Provide one piece injected molded design with internal bridge at top of J-bend to prevent separating.
 - b. Comply with ASTM C1822 for covers on accessible lavatory piping.
 - c. Comply with ASME A112.18.9 for covers on accessible lavatory piping.
 - d. Thermal Resistance: R value of 0.504 or lower when tested by ASTM C177.
 - e. Thermal Conductivity: K value of 0.358 or density of 21.61 pcf per ASTM C518.
 - f. Microbial and Fungal Resistance for Interior and Exterior: Comply with ASTM G21.
- D. ASTM E84 Compliant, Under-Lavatory Insulators:
 - 1. Manufacturers:
 - a. IPS True Bro
 - b. Plumberex Specialty Products, Inc: Plumberex Trap Gear; www.plumberex.com
 - 2. Construction: Soft, non-laminated, flexible PVC with antimicrobial, antifungal, and UV-resistant properties. Fusion molded one piece universal design for multiple P-trap configurations. Adhesives, sewing threads, and two ply laminated materials shall not be allowed. Exterior surfaces shall be smooth nonabsorbent with no finger recessed indentations for easy cleaning. Supply riser shall be flexible and a minimum of 15 inches in length.
 - 3. Provide with weep hole for condensation drainage and ventilation.
 - 4. Fasteners: Reusable, fusion bonded Velcro and tamper resistant snap-locking fasteners with no sharp or abrasive external surfaces. **No cable tie fasteners allowed.**
 - 5. Comply with:
 - a. ASTM E84/UL 723 to comply with flame spread and smoke development rating of 25/450.
 - b. ASTM C1822 Type I.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- c. ADA Standards.
 - d. 36 CFR 1191.
 - e. ICC (IBC).
 - f. ADAAG Standards 2004 and 28 CFR 36.
 - g. GSA and DOD ABA Standards.
 - h. ICC A117.1.
 - i. IAPMO (UPC).
6. Color: White.
- E. Under-Lavatory Covers with Snap-Lock Fasteners:
- 1. Manufacturers:
 - a. IPS True Bro.
 - b. Plumberex Specialty Products, Inc: Plumberex Pro-Extreme; www.plumberex.com
 - 2. Construction: PVC with antimicrobial, antifungal, and UV-resistant properties, one piece injected molded design with internal bridge at top of J-bend to prevent separating.
 - 3. Fasteners: Reusable, snap-locking fasteners with no sharp or abrasive external surfaces. **No cable ties allowed.**
 - 4. Maintenance: Valve and supply cover shall be accessible for maintenance without removal and with removable, reusable access cap.
 - 5. Comply with:
 - a. ASTM C1822 Type III.
 - b. ADA Standards.
 - c. 36 CFR 1191.
 - d. ADAAG Standards and 28 CFR 36.
 - e. GSA and DOD ABA Standards.
 - f. ICC A117.1.
 - g. Requirement to protect against contact with sharp or abrasive surfaces.
 - 6. Provide with weep hole for condensation drainage and ventilation.
 - 7. Color: White.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that walls, floor finishes, lavatories, and piping are prepared and ready for installation of under-lavatory guards.
- B. Confirm location and size of fixtures and piping before installation.

3.02 INSTALLATION

- A. Install under-lavatory guards according to manufacturer's written instructions.

3.03 CLEANING

- A. Clean installed under-lavatory guards.
- B. See Section 017419 - Construction Waste Management and Disposal, for additional requirements.

3.04 PROTECTION

- A. Protect installed products from damage due to subsequent construction operations.
- B. Repair or replace damaged products before Date of Substantial Completion.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 221005 PLUMBING PIPING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Pipe, pipe fittings, specialties, and connections for piping systems.
 - 1. Sanitary sewer.
 - 2. Chemical resistant sewer.
 - 3. Domestic water.
 - 4. Storm water.
 - 5. Natural Gas.
 - 6. Flanges, unions, and couplings.
 - 7. Pipe hangers and supports.
 - 8. Manufactured sleeve-seal systems.
 - 9. Valves.
 - 10. Flow controls.
 - 11. Water pressure reducing valves.
 - 12. Relief valves.
 - 13. Strainers.

1.02 RELATED REQUIREMENTS

- A. Section _____: Roof penetrations.
- B. Section 078400 - Firestopping.
- C. Section 083100 - Access Doors and Panels.
- D. Section 099113 - Exterior Painting.
- E. Section 099123 - Interior Painting.
- F. Section 220516 - Expansion Fittings and Loops for Plumbing Piping.
- G. Section 220548 - Vibration and Seismic Controls for Plumbing Piping and Equipment.
- H. Section 220553 - Identification for Plumbing Piping and Equipment.
- I. Section 220719 - Plumbing Piping Insulation.
- J. Section 312316 - Excavation.
- K. Section 312323 - Fill.
- L. Section 330110.58 - Disinfection of Water Utility Piping Systems.

1.03 REFERENCE STANDARDS

- A. ANSI Z21.22 - American National Standard for Relief Valves and Automatic Gas Shutoff Devices for Hot Water Supply Systems; 2015.
- B. ANSI Z223.1 - National Fuel Gas Code; 2016.
- C. ASME B16.1 - Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250; 2015.
- D. ASME B16.3 - Malleable Iron Threaded Fittings: Classes 150 and 300; 2016.
- E. ASME B16.4 - Gray Iron Threaded Fittings: Classes 125 and 250; 2016.
- F. ASME B16.18 - Cast Copper Alloy Solder Joint Pressure Fittings; 2012.
- G. ASME B16.22 - Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings; 2013.
- H. ASME B16.23 - Cast Copper Alloy Solder Joint Drainage Fittings - DWV; 2016.
- I. ASME B16.26 - Cast Copper Alloy Fittings for Flared Copper Tubes; 2013.



- J. ASME B16.29 - Wrought Copper and Wrought Copper Alloy Solder Joint Drainage Fittings - DWV; 2012.
- K. ASME B31.1 - Power Piping; 2016.
- L. ASME B31.9 - Building Services Piping; 2014.
- M. ASME BPVC-IV - Boiler and Pressure Vessel Code, Section IV - Rules for Construction of Heating Boilers; 2017.
- N. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Procedures; Welders; Brazers; and Welding, Brazing and Fusing Operators; 2017.
- O. ASSE 1003 - Performance Requirements for Water Pressure Reducing Valves for Domestic Water Distribution Systems; 2009.
- P. ASTM A47/A47M - Standard Specification for Ferritic Malleable Iron Castings; 1999 (Reapproved 2014).
- Q. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2012.
- R. ASTM A74 - Standard Specification for Cast Iron Soil Pipe and Fittings; 2017.
- S. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- T. ASTM A234/A234M - Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service; 2017.
- U. ASTM A269/A269M - Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service; 2015a.
- V. ASTM B32 - Standard Specification for Solder Metal; 2008 (Reapproved 2014).
- W. ASTM B42 - Standard Specification for Seamless Copper Pipe, Standard Sizes; 2015a.
- X. ASTM B68/B68M - Standard Specification for Seamless Copper Tube, Bright Annealed; 2011.
- Y. ASTM B75/B75M - Standard Specification for Seamless Copper Tube; 2011.
- Z. ASTM B88 - Standard Specification for Seamless Copper Water Tube; 2016.
- AA. ASTM B88M - Standard Specification for Seamless Copper Water Tube (Metric); 2016.
- AB. ASTM B813 - Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube; 2016.
- AC. ASTM B828 - Standard Practice for Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings; 2016.
- AD. ASTM C14 - Standard Specification for Nonreinforced Concrete Sewer, Storm Drain, and Culvert Pipe; 2015a.
- AE. ASTM C14M - Standard Specification for Nonreinforced Concrete Sewer, Storm Drain, Culvert Pipe and (Metric); 2015a.
- AF. ASTM C76 - Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe; 2016.
- AG. ASTM C76M - Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe (Metric); 2016.
- AH. ASTM C443 - Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets; 2012 (Reapproved 2017).
- AI. ASTM C443M - Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets (Metric); 2011 (Reapproved 2017).



- AJ. ASTM C564 - Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings; 2014.
- AK. ASTM D1785 - Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Pipe, Schedules 40, 80, and 120; 2015.
- AL. ASTM D2235 - Standard Specification for Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings; 2004 (Reapproved 2016).
- AM. ASTM D2239 - Standard Specification for Polyethylene (PE) Plastic Pipe (SIDR-PR) Based on Controlled Inside Diameter; 2012a.
- AN. ASTM D2241 - Standard Specification for Poly (Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series); 2015.
- AO. ASTM D2466 - Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 40; 2017.
- AP. ASTM D2513 - Standard Specification for Polyethylene (PE) Gas Pressure Pipe, Tubing, and Fittings; 2016a.
- AQ. ASTM D2564 - Standard Specification for Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems; 2012.
- AR. ASTM D2609 - Standard Specification for Plastic Insert Fittings for Polyethylene (PE) Plastic Pipe; 2015.
- AS. ASTM D2661 - Standard Specification for Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe and Fittings; 2014.
- AT. ASTM D2665 - Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings; 2014.
- AU. ASTM D2683 - Standard Specification for Socket-Type Polyethylene Fittings for Outside Diameter-Controlled Polyethylene Pipe and Tubing; 2014.
- AV. ASTM D2729 - Standard Specification for Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings; 2011.
- AW. ASTM D2846/D2846M - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Hot- and Cold-Water Distribution Systems; 2017a.
- AX. ASTM D2855 - Standard Practice for the Two-Step (Primer & Solvent Cement) Method of Joining Poly (Vinyl Chloride) (PVC) or Chlorinated Poly (Vinyl Chloride) (CPVC) Pipe and Piping Components with Tapered Sockets; 2015.
- AY. ASTM D3034 - Standard Specification for Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings; 2016.
- AZ. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- BA. ASTM F437 - Standard Specification for Threaded Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80; 2015.
- BB. ASTM F438 - Standard Specification for Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40; 2015.
- BC. ASTM F439 - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80; 2013.
- BD. ASTM F441/F441M - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe, Schedules 40 and 80; 2015.
- BE. ASTM F442/F442M - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR); 2013.
- BF. ASTM F477 - Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe; 2014.



- BG. ASTM F493 - Standard Specification for Solvent Cements for Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe and Fittings; 2014.
- BH. ASTM F628 - Standard Specification for Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe With a Cellular Core; 2012e2.
- BI. ASTM F679 - Standard Specification for Poly(Vinyl Chloride) (PVC) Large-Diameter Plastic Gravity Sewer Pipe and Fittings; 2016.
- BJ. ASTM F708 - Standard Practice for Design and Installation of Rigid Pipe Hangers; 1992 (Reapproved 2014).
- BK. ASTM F876 - Standard Specification for Crosslinked Polyethylene (PEX) Tubing; 2015a.
- BL. ASTM F877 - Standard Specification for Crosslinked Polyethylene (PEX) Plastic Hot- and Cold-Water Distribution Systems; 2011a.
- BM. ASTM F1281 - Standard Specification for Crosslinked Polyethylene/Aluminum/Crosslinked Polyethylene (PEX-AL-PEX) Pressure Pipe; 2011.
- BN. ASTM F1282 - Standard Specification for Polyethylene/Aluminum/Polyethylene (PE-AL-PE) Composite Pressure Pipe; 2010.
- BO. AWS A5.8M/A5.8 - Specification for Filler Metals for Brazing and Braze Welding; 2011-AMD 1.
- BP. AWS D1.1/D1.1M - Structural Welding Code - Steel; 2015 (with March 2016 Errata).
- BQ. AWWA C105/A21.5 - Polyethylene Encasement for Ductile-Iron Pipe Systems; 2010.
- BR. AWWA C110/A21.10 - Ductile-Iron and Gray-Iron Fittings; 2012.
- BS. AWWA C111/A21.11 - Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings; 2017.
- BT. AWWA C151/A21.51 - Ductile-Iron Pipe, Centrifugally Cast; 2009.
- BU. AWWA C550 - Protective Interior Coatings for Valves and Hydrants; 2013.
- BV. AWWA C606 - Grooved and Shouldered Joints; 2015.
- BW. AWWA C651 - Disinfecting Water Mains; 2014.
- BX. AWWA C900 - Polyvinyl Chloride (PVC) Pressure Pipe, 4 In. Through 12 In. (100 mm Through 300 mm), for Water Transmission and Distribution; 2016.
- BY. AWWA C901 - Polyethylene (PE) Pressure Pipe and Tubing, 1/2 In. (13 mm) Through 3 In. (76 mm), for Water Service; 2008.
- BZ. CISPI 301 - Standard Specification for Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste and Vent Piping Applications; 2009 (Revised 2012).
- CA. CISPI 310 - Specification for Coupling for Use in Connection with Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications; 2011 (Revised 2012).
- CB. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2015.
- CC. ICC-ES AC106 - Acceptance Criteria for Predrilled Fasteners (Screw Anchors) in Masonry Elements; 2015.
- CD. ICC-ES AC193 - Acceptance Criteria for Mechanical Anchors in Concrete Elements; 2015.
- CE. ICC-ES AC308 - Acceptance Criteria for Post-Installed Adhesive Anchors in Concrete Elements; 2016.
- CF. MSS SP-58 - Pipe Hangers and Supports - Materials, Design, Manufacture, Selection, Application, and Installation; 2009.
- CG. MSS SP-67 - Butterfly Valves; 2011.
- CH. MSS SP-70 - Cast Iron Gate Valves, Flanged and Threaded Ends; 2011.
- CI. MSS SP-71 - Cast Iron Swing Check Valves, Flanged and Threaded Ends; 2011.



- CJ. MSS SP-80 - Bronze Gate, Globe, Angle and Check Valves; 2013.
- CK. MSS SP-110 - Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends; 2010.
- CL. NSF 61 - Drinking Water System Components - Health Effects; 2016.
- CM. NSF 372 - Drinking Water System Components - Lead Content; 2016.
- CN. PPI TR-4 - PPI Listing of Hydrostatic Design Basis (HDB), Hydrostatic Design Stress (HDS), Strength Design Basis (SDB), Pressure Design Basis (PDB), and Minimum Required Strength (MRS) Ratings For Thermoplastic Piping Materials or Pipe; 2016.
- CO. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on pipe materials, pipe fittings, valves, and accessories. Provide manufacturers catalog information. Indicate valve data and ratings.
- C. Welder Certificate: Include welders certification of compliance with ASME BPVC-IX.
- D. Shop Drawings: For non-penetrating rooftop supports, submit detailed layout developed for this project, with design calculations for loadings and spacings.
- E. Project Record Documents: Record actual locations of valves.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.

1.05 QUALITY ASSURANCE

- A. Perform work in accordance with applicable codes.
- B. Valves: Manufacturer's name and pressure rating marked on valve body.
- C. Welding Materials and Procedures: Conform to ASME BPVC-IX.
- D. Welder Qualifications: Certified in accordance with ASME BPVC-IX.
- E. Identify pipe with marking including ASTM material classification, ASTM specification, potable water certification, water pressure rating.
- F. All pipe, fittings, and products shall be domestic only.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Accept valves on site in shipping containers with labeling in place. Inspect for damage.
- B. Provide temporary protective coating on cast iron and steel valves.
- C. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.
- D. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.

1.07 FIELD CONDITIONS

- A. Do not install underground piping when bedding is wet or frozen.

PART 2 PRODUCTS

2.01 GENERAL REQUIREMENTS

- A. Potable Water Supply Systems: Provide piping, pipe fittings, and solder and flux (if used), that comply with NSF 61 and NSF 372 for maximum lead content; label pipe and fittings.
- B. Plenum-Installed Acid Waste Piping: Flame-spread index equal or below 25 and smoke-spread index equal or below 50 according to ASTM E84 or UL 723 tests.



2.02 SANITARY SEWER PIPING, BURIED BEYOND 5 FEET OF BUILDING

- A. Refer to Division 33, section 333113, Site Sanitary Sewerage Gravity Piping.

2.03 SANITARY SEWER PIPING, BURIED WITHIN 5 FEET OF BUILDING

- A. Cast Iron Pipe: CISPI 301, hubless.
 - 1. Fittings: Cast iron.
 - 2. Joints: CISPI 310, neoprene gasket and extra heavy stainless steel clamp and shield assemblies.
- B. PVC Pipe: ASTM D2665 or ASTM D3034.
 - 1. Fittings: PVC.
 - 2. Joints: Solvent welded, with ASTM D2564 solvent cement.
 - 3. Pipe: Solid core.

2.04 SANITARY SEWER PIPING, ABOVE GRADE

- A. Cast Iron Pipe: CISPI 301, hubless, service weight.
 - 1. Fittings: Cast iron.
 - 2. Joints: CISPI 310, neoprene gaskets and stainless steel clamp-and-shield assemblies.
- B. Steel Pipe: ASTM A53/A53M Schedule 40, galvanized, using one of the following joint types:
 - 1. Flanged Joints: ASME B16.1 cast iron fittings.
 - 2. Threaded Joints: ASME B16.4 cast iron fittings.
 - 3. Grooved Joints: AWWA C606 grooved pipe, fittings of same material, and mechanical couplings.
- C. PVC Pipe (permitted for trap arms only): ASTM D2729.
 - 1. Fittings: PVC.
 - 2. Joints: Solvent welded, with ASTM D2564 solvent cement.
 - 3. Pipe: Solid core.

2.05 CHEMICAL RESISTANT SEWER PIPING

- A. PP Pipe: Polypropylene, flame retardant.
 - 1. Fittings: Polypropylene.
 - 2. Joints: Electrical resistance fusion.
 - 3. Manufacturers:
 - a. IPEX USA, LLC; Enfield Electrofusion: www.ipexna.com
 - b. Orion.
 - c. Aquatherm.
 - d. Substitutions: See Section 016000 - Product Requirements.

2.06 DOMESTIC WATER PIPING, BURIED BEYOND 5 FEET OF BUILDING

- A. Refer to Division 33, section 331416, Site Water Utility Distribution Piping

2.07 DOMESTIC WATER PIPING, BURIED WITHIN 5 FEET OF BUILDING

- A. Copper Pipe: ASTM B42, annealed.
 - 1. Fittings: ASME B16.26, cast bronze.
 - 2. Joints: None.
- B. Ductile Iron Pipe: AWWA C151/A21.51.
 - 1. Fittings: Ductile or gray iron, standard thickness.
 - 2. Joints: AWWA C111/A21.11, styrene butadiene rubber (SBR) or vulcanized SBR gasket with 3/4 inch diameter rods.
- C. PE Pipe: ASTM D2239.
 - 1. Fittings: ASTM D2609, PE.
 - 2. Joints: Mechanical with clamp.



3. Fusion weld.
- D. Cross-Linked Polyethylene (PEX) Pipe: ASTM F876 or ASTM F877.
 1. Manufacturers:
 - a. Uponor, Inc; _____: www.uponorengineering.com
 - b. Viega LLC; PureFlow PEX with Corrugated Sleeve: www.viega.us
 - c. Substitutions: See Section 016000 - Product Requirements.
 2. PPI TR-4 Pressure Design Basis:
 - a. 160 psig at maximum 73 degrees F.
 - b. 100 psig at maximum 180 degrees F.
 - c. 80 psig at maximum 200 degrees F.
 3. Fittings: Brass and copper.
 4. Fittings: Brass and engineered polymer (EP) ASTM F1960.
 5. Joints: Mechanical compression fittings.
- E. PP (Pressure-rated Polypropylene): ASTM F2389.
 1. Pipe and fittings shall be polypropylene material of type PP-R or PP-RCT in accordance with ASTM F2389.
 2. Manufacturers:
 - a. Aquatherm
 - b. Nupi
 - c. Substitutions: See Section 016000 - Product Requirements.

2.08 DOMESTIC WATER PIPING, ABOVE GRADE

- A. Copper Tube: ASTM B88 (ASTM B88M), Type L (B), Drawn (H).
 1. Fittings: ASME B16.18, cast copper alloy or ASME B16.22, wrought copper and bronze.
 2. Fittings: Cast iron, epoxy coated.
 3. Joints: ASTM B32, alloy Sn95 solder, BCuP copper/silver braze.
 4. Joints: Grooved mechanical couplings.
 5. Joints: Mechanical Press Sealed Fittings; Pressed type, NSF 61 and NSF 372 approved or certified, utilizing EPDM, non toxic synthetic rubber sealing elements.
 - a. Manufacturers:
 - 1) Anvil International; _____: www.anvilintl.com
 - 2) Apollo Valves; _____: www.apollovalves.com
 - 3) Grinnell Products, a Tyco Business; _____: www.grinnell.com
 - 4) Viega LLC; _____: www.viega.com
 - 5) Substitutions: See Section 016000 - Product Requirements.
- B. Cross-Linked Polyethylene (PEX) Pipe: ASTM F876 or ASTM F877.
 1. Housing applications only, where approved. Branch lines only.
 2. Manufacturers:
 - a. Uponor, Inc; _____: www.uponorengineering.com
 - b. Viega LLC; _____: www.viega.com
 - c. Zurn Industries, LLC; _____: www.zurn.com
 - d. Substitutions: See Section 016000 - Product Requirements.
 3. PPI TR-4 Pressure Design Basis:
 - a. 160 psig at maximum 73 degrees F.
 - b. 100 psig at maximum 180 degrees F.
 - c. 80 psig at maximum 200 degrees F.
 4. Fittings: Brass and copper.
 5. Fittings: Brass and engineered polymer (EP) ASTM F1960.
 6. Joints: Mechanical compression fittings.
- C. Stainless Steel Pipe: ASTM A269/A269M, Grade TP304 alloy.



1. Mechanical Press Sealed Fittings: Pressed type, NSF 61 and NSF 372 approved or certified, utilizing EPDM, non toxic synthetic rubber sealing elements.
 - a. Manufacturers:
 - 1) Apollo Valves; _____: www.apollovalves.com
 - 2) Grinnell Products, a Tyco Business; _____: www.grinnell.com
 - 3) Viega LLC; _____: www.viega.com
 - 4) Substitutions: See Section 016000 - Product Requirements.

- D. PP (Pressure-rated Polypropylene): ASTM F2389.
 1. Pipe and fittings shall be polypropylene material of type PP-R or PP-RCT in accordance with ASTM F2389.
 2. Manufacturers:
 - a. Aquatherm
 - b. Nupi
 - c. Substitutions: See Section 016000 - Product Requirements.

2.09 STORM WATER PIPING, BURIED BEYOND 5 FEET OF BUILDING

- A. Refer to Division 33, section 334100, Subdrainage.

2.10 STORM WATER PIPING, BURIED WITHIN 5 FEET OF BUILDING

- A. Cast Iron Pipe: CISPI 301, hubless, service weight.
 1. Fittings: Cast iron.
 2. Joints: Neoprene gaskets and extra heavy stainless steel clamp-and-shield assemblies.
- B. PVC Pipe: ASTM D2665 or ASTM D3034.
 1. Fittings: PVC.
 2. Joints: Solvent welded, with ASTM D2564 solvent cement.
 3. Pipe: Solid core.

2.11 STORM WATER PIPING, ABOVE GRADE

- A. Cast Iron Pipe: CISPI 301, hubless, service weight.
 1. Fittings: Cast iron.
 2. Joints: Neoprene gaskets and stainless steel clamp-and-shield assemblies.

2.12 NATURAL GAS PIPING, BURIED WITHIN 5 FEET OF BUILDING

- A. Polyethylene Pipe: ASTM D2513, SDR 11.
 1. Anode-less risers, per AHJ.
 2. Fittings: ASTM D2683 or ASTM D2513 socket type.
 3. Joints: Fusion welded.

2.13 NATURAL GAS PIPING, ABOVE GRADE

- A. Steel Pipe: ASTM A53/A53M Schedule 40 black.
 1. Fittings: ASME B16.3, malleable iron, or ASTM A234/A234M, wrought steel welding type.
 2. Joints: Threaded or welded to ASME B31.1.
 3. Paint exposed piping with 3 part epoxy, colors to be approved by owner.

2.14 FLANGES, UNIONS, AND COUPLINGS

- A. Unions for Pipe Sizes 3 Inches and Under:
 1. Ferrous pipe: Class 150 malleable iron threaded unions.
 2. Copper tube and pipe: Class 150 bronze unions with soldered joints.
- B. Flanges for Pipe Size Over 1 Inch:
 1. Ferrous Pipe: Class 150 malleable iron threaded or forged steel slip-on flanges; preformed neoprene gaskets.
 2. Copper Tube and Pipe: Class 150 slip-on bronze flanges; preformed neoprene gaskets.



- C. Mechanical Couplings for Grooved and Shouldered Joints: Two or more curved housing segments with continuous key to engage pipe groove, circular C-profile gasket, and bolts to secure and compress gasket.
1. Dimensions and Testing: In accordance with AWWA C606.
 2. Housing Material: Provide ASTM A47/A47M malleable iron, ductile iron, or _____, galvanized.
 3. Gasket Material: EPDM suitable for operating temperature range from minus 30 degrees F to 230 degrees F.
 4. Bolts and Nuts: Hot dipped galvanized or zinc-electroplated steel.
 5. When pipe is field grooved, provide coupling manufacturer's grooving tools.
 6. Manufacturers:
 - a. Grinnell Products, a Tyco Business; _____: www.grinnell.com
 - b. Substitutions: See Section 016000 - Product Requirements.
- D. Mechanical Press Fittings, 1/2" to 4":
1. Manufacturers:
 - a. Viega LLC; [_____]: www.viega.com
 - b. Apollo Valves; [_____]: www.apollovalves.com
 - c. Nibco.
 - d. Substitutions: See Section 016000 - Product Requirements.
- E. No-Hub Couplings:
1. Gasket Material: Neoprene complying with ASTM C564.
 2. Heavy Duty Band Material: Stainless steel.
 3. Eyelet Material: Stainless steel.
- F. Dielectric Connections: Nipple type for pipes sizes less than 2". 2" and larger, flange type is permitted.

2.15 PIPE HANGERS AND SUPPORTS

- A. Provide hangers and supports that comply with MSS SP-58.
1. If type of hanger or support for a particular situation is not indicated, select appropriate type using MSS SP-58 recommendations.
 2. Overhead Supports: Individual steel rod hangers attached to structure or to trapeze hangers.
 - a. As per drawings.
 3. Trapeze Hangers: Welded steel channel frames attached to structure.
 4. Vertical Pipe Support: Steel riser clamp.
 5. Floor Supports: Steel pedestal with floor flange; fixture attachment.
 6. Rooftop Supports for Low-Slope Roofs: See section 3.03D. Steel pedestals with bases that rest on top of roofing membrane, not requiring any attachment to the roof structure and not penetrating the roofing assembly, with support fixtures as specified; and as follows:
 - a. Bases: High density polypropylene.
 - b. Base Sizes: As required to distribute load sufficiently to prevent indentation of roofing assembly.
 - c. Steel Components: Stainless steel, or carbon steel hot-dip galvanized after fabrication in accordance with ASTM A123/A123M.
 - d. Attachment/Support Fixtures: As recommended by manufacturer, same type as indicated for equivalent indoor hangers and supports; corrosion resistant material.
 - e. Height: Provide minimum clearance of 6 inches under pipe to top of roofing.
 - f. Manufacturers:
 - 1) PHP Systems/Design; _____: www.phpsd.com
 - 2) Uni-Strut.
 - 3) Miro Industries.
 - 4) Substitutions: See Section 016000 - Product Requirements.



- B. Plumbing Piping - Drain, Waste, and Vent:
 - 1. Hangers for Pipe Sizes 1/2 Inch to 1-1/2 Inches: Malleable iron, adjustable, clevis.
 - 2. Hangers for Pipe Sizes 2 Inches and Over: Carbon steel, adjustable, clevis.
 - 3. Wall Support for Pipe Sizes 2-1/2 and Over: Welded steel bracket and wrought steel clamp.
 - 4. Floor Support: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and steel support.
 - 5. Copper Pipe Support: Carbon steel ring, adjustable, copper plated.
- C. Plumbing Piping - Water:
 - 1. Hangers for Pipe Sizes 1/2 Inch to 1-1/2 Inches: Malleable iron, adjustable, clevis.
 - 2. Hangers for Cold Pipe Sizes 2 Inches and Over: Carbon steel, adjustable, clevis.
 - 3. Hangers for Hot Pipe Sizes 2 Inches to 4 Inches: Carbon steel, adjustable, clevis.
 - 4. Hangers for Hot Pipe Sizes 6 Inches and Over: Carbon steel, adjustable, clevis.
 - 5. Wall Support for Pipe Sizes 4 Inches and Over: Welded steel bracket and wrought steel clamp.
 - 6. Wall Support for Hot Pipe Sizes 6 Inches and Over: Unistrut supports with cast iron pipe roll.
 - 7. Floor Support for Cold Pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and steel support.
 - 8. Floor Support for Hot Pipe Sizes to 4 Inches: Cast iron adjustable pipe saddle, locknut, nipple, floor flange, and steel support.
 - 9. Floor Support for Hot Pipe Sizes 6 Inches and Over: Adjustable cast iron pipe roll and stand, steel screws, and steel support.
 - 10. Copper Pipe Support: Carbon steel ring, adjustable, copper plated.
- D. Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
 - 1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
 - 2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
 - 3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
 - 4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.
 - 5. Concrete Adhesive Type Anchors: Complying with ICC-ES AC308.
 - 6. Substitutions: See Section 016000 - Product Requirements.

2.16 MANUFACTURED SLEEVE-SEAL SYSTEMS

- A. Modular/Mechanical Seal:
 - 1. Synthetic rubber interlocking links continuously fill annular space between pipe and wall/casing opening.
 - 2. Provide watertight seal between pipe and wall/casing opening.
 - 3. Elastomer element size and material in accordance with manufacturer's recommendations.
 - 4. Glass reinforced plastic pressure end plates.

2.17 BALL VALVES

- A. Manufacturers:
 - 1. Nibco, Inc; _____: www.nibco.com
 - 2. Viega LLC; _____: www.viega.us
 - 3. Apollo.
 - 4. Watts.
 - 5. Milwaukee.
 - 6. Substitutions: See Section 016000 - Product Requirements.
- B. Construction, 4 Inches and Smaller: MSS SP-110, Class 150, 400 psi CWP, bronze or ductile iron body, 304 stainless steel ball and stem, regular port, teflon seats and stuffing box ring, blow-out proof stem, lever handle, solder, threaded, grooved, or Mechanical Press ends.

2.18 BUTTERFLY VALVES

- A. Manufacturers:
 - 1. Nibco



2. Apollo
 3. Watts
 4. Victaulic
- B. Construction 1-1/2 Inches and Larger: MSS SP-67, 200 psi CWP, cast or ductile iron body, elastomer coated ductile iron disc, resilient replaceable EPDM seat, wafer ends, extended neck, 10 position lever handle.
- C. Provide gear operators for valves 8 inches and larger, and chain-wheel operators for valves mounted over 8 feet above floor.

2.19 FLOW CONTROLS

- A. Manufacturers:
1. ITT Bell & Gossett; Model [____]: www.bellgossett.com
 2. Griswold Controls; Model [____]: www.griswoldcontrols.com
 3. Taco, Inc; Model [____]: www.taco-hvac.com
 4. Watts
 5. Substitutions: See Section 016000 - Product Requirements.
 6. Construction: Class 125, Brass or bronze body, temperature and pressure test plug on inlet, blowdown/backflush drain.
 7. Calibration: Control flow within 5 percent of selected rating, over operating pressure range of 10 times minimum pressure required for control, maximum minimum pressure 3.5 psi.

2.20

2.21 WATER PRESSURE REDUCING VALVES

- A. Manufacturers:
1. Amtrol Inc; _____: www.amtrol.com
 2. Cla-Val Company; _____: www.cla-val.com
 3. Watts Regulator Company; _____: www.wattsregulator.com
 4. Wilkins
 5. Victaulic
 6. Substitutions: See Section 016000 - Product Requirements.
- B. Up to 2 Inches:
1. ASSE 1003, bronze body, stainless steel, and thermoplastic internal parts, fabric reinforced diaphragm, strainer, threaded single union ends. No roll seal type valves permitted.
- C. Over 2 Inches:
1. ASSE 1003, cast iron body with interior lining complying with AWWA C550, bronze fitted, elastomeric diaphragm and seat disc, flanged.

2.22 RELIEF VALVES

- A. Pressure:
1. Manufacturers:
 - a. Cla-Val Co; Model _____: www.cla-val.com
 - b. Watts Regulator Company; Model _____: www.wattsregulator.com
 - c. Substitutions: See Section 016000 - Product Requirements.
 2. ANSI Z21.22, AGA certified, bronze body, teflon seat, steel stem and springs, automatic, direct pressure actuated.
- B. Temperature and Pressure:
1. Manufacturers:
 - a. Cla-Val Co; Model _____: www.cla-val.com
 - b. Watts Regulator Company; Model _____: www.wattsregulator.com
 - c. Substitutions: See Section 016000 - Product Requirements.



2. ANSI Z21.22, AGA certified, bronze body, teflon seat, stainless steel stem and springs, automatic, direct pressure actuated, temperature relief maximum 210 degrees F, capacity ASME BPVC-IV certified and labelled.

2.23 STRAINERS

- A. Manufacturers:
 1. Watts
 2. Armstrong International, Inc; Model _____: www.armstronginternational.com
 3. Substitutions: See Section 016000 - Product Requirements.
- B. Size 2 inch and Under:
 1. Threaded brass body for 175 psi CWP, Y pattern with 1/32 inch stainless steel perforated screen.
 2. Class 150, threaded bronze body 300 psi CWP, Y pattern with 1/32 inch stainless steel perforated screen.
 3. Installer to remove plug and install ball valve and male hose thread adaptor in its place.
- C. Size 1-1/2 inch to 4 inch:
 1. Class 125, flanged iron body, Y pattern with 1/16 inch stainless steel perforated screen.
 2. Installer to remove plug and install ball valve and male hose thread adaptor in its place.
- D. Size 5 inch and Larger:
 1. Class 125, flanged iron body, basket pattern with 1/8 inch stainless steel perforated screen.
 2. Installer to remove plug and install ball valve and male hose thread adaptor in its place.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that excavations are to required grade, dry, and not over-excavated.

3.02 PREPARATION

- A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.
- B. Remove scale and dirt, on inside and outside, before assembly.
- C. Prepare piping connections to equipment with flanges or unions.

3.03 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Provide non-conducting dielectric nipples or flanges wherever jointing dissimilar metals.
- C. Route piping in orderly manner and maintain gradient. Route parallel and perpendicular to walls.
- D. Piping is not permitted on roofs unless specifically indicated on drawings.
- E. Install piping to maintain headroom, conserve space, and not interfere with use of space.
- F. Group piping whenever practical at common elevations.
- G. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment. Refer to Section 220516.
- H. Provide clearance in hangers and from structure and other equipment for installation of insulation and access to valves and fittings.
 1. Refer to Section 220719.
- I. Provide access where valves and fittings are not exposed.
 1. Coordinate size and location of access doors with Section 083100, and with architectural plans.
- J. Establish elevations of buried piping outside the building to ensure not less than 3 ft of cover.
- K. Where pipe support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welding.



- L. Provide support for utility meters in accordance with requirements of utility companies.
- M. Prepare exposed, unfinished pipe, fittings, supports, and accessories ready for finish painting.
 - 1. Painting of interior plumbing systems and components is specified in Section 099123.
 - 2. Painting of exterior plumbing systems and components is specified in Section 099113.
- N. Excavate in accordance with Section 312316.
- O. Backfill in accordance with Section 312323.
- P. Install bell and spigot pipe with bell end upstream.
- Q. Install valves with stems upright or horizontal, not inverted. Refer to Section 220523.
- R. Install water piping to ASME B31.9.
- S. Copper Pipe and Tube: Make soldered joints in accordance with ASTM B828, using specified solder, and flux meeting ASTM B813; in potable water systems use flux also complying with NSF 61 and NSF 372. For mechanical press joints, refer to manufacturer's instructions.
- T. PVC Pipe: Make solvent-welded joints in accordance with ASTM D2855.
- U. Sleeve pipes passing through partitions, walls and floors.
- V. Inserts:
 - 1. Provide inserts for placement in concrete formwork.
 - 2. Provide inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
 - 3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
 - 4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.
- W. Pipe Hangers and Supports:
 - 1. Install in accordance with ASME B31.9.
 - 2. Support horizontal piping as indicated.
 - 3. Install hangers to provide minimum 1/2 inch space between finished covering and adjacent work.
 - 4. Place hangers within 12 inches of each horizontal elbow.
 - 5. Use hangers with 1-1/2 inch minimum vertical adjustment. Design hangers for pipe movement without disengagement of supported pipe.
 - 6. Support vertical piping as per plumbing code and local AHJ requirements, and at minimum at every floor. Support riser piping independently of connected horizontal piping.
 - 7. Where several pipes can be installed in parallel and at same elevation, provide multiple or trapeze hangers.
 - 8. Provide copper plated hangers and supports for copper piping.
 - 9. Prime coat exposed steel hangers and supports. Hangers and supports located in crawl spaces, pipe shafts, and suspended ceiling spaces are not considered exposed.
 - a. Painting of interior plumbing systems and components is specified in Section 099123.
 - b. Painting of exterior plumbing systems and components is specified in Section 099113.
 - 10. Provide hangers adjacent to motor driven equipment with vibration isolation; refer to Section 220548.
 - 11. Support cast iron drainage piping at every joint.
- X. Manufactured Sleeve-Seal Systems:
 - 1. Install manufactured sleeve-seal systems in sleeves located in grade slabs and exterior concrete walls at piping entrances into building.
 - 2. Provide sealing elements of the size, quantity, and type required for the piping and sleeve inner diameter or penetration diameter.
 - 3. Locate piping in center of sleeve or penetration.
 - 4. Install field assembled sleeve-seal system components in annular space between sleeve and piping.



5. Tighten bolting for a water-tight seal.
 6. Install in accordance with manufacturer's recommendations.
- Y. When installing more than one piping system material, ensure system components are compatible and joined to ensure the integrity of the system. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

3.04 APPLICATION

- A. Install unions downstream of valves and at equipment or apparatus connections.
- B. Install ball or butterfly valves for shut-off and to isolate equipment, part of systems, or vertical risers.
- C. Install globe valves for throttling, bypass, or manual flow control services.
- D. Provide lug end butterfly valves adjacent to equipment when provided to isolate equipment.
- E. Provide spring loaded check valves on discharge of water pumps.
- F. Provide flow controls in water recirculating systems where indicated.

3.05 TOLERANCES

- A. Drainage Piping: Establish invert elevations within 1/2 inch vertically of location indicated and slope to drain at minimum of 1/4 inch per foot slope or per plumbing code.

3.06 DISINFECTION OF DOMESTIC WATER PIPING SYSTEM

- A. Disinfect water distribution system in accordance with Section 330110.58.
- B. Prior to starting work, verify system is complete, flushed and clean.
- C. Ensure acidity (pH) of water to be treated is between 7.4 and 7.6 by adding alkali (caustic soda or soda ash) or acid (hydrochloric).
- D. Inject disinfectant, free chlorine in liquid, powder, tablet or gas form, throughout system to obtain 50 to 80 mg/L residual.
- E. Bleed water from outlets to ensure distribution and test for disinfectant residual at minimum 15 percent of outlets.
- F. Maintain disinfectant in system for 24 hours.
- G. If final disinfectant residual tests less than 25 mg/L, repeat treatment.
- H. Flush disinfectant from system until residual is equal to that of incoming water or 1.0 mg/L.
- I. Take samples no sooner than 24 hours after flushing, from 10 percent of outlets and from water entry, and analyze in accordance with AWWA C651.

3.07 SERVICE CONNECTIONS

- A. Provide new sanitary sewer services. Before commencing work check invert elevations required for sewer connections, confirm inverts and ensure that these can be properly connected with slope for drainage and cover to avoid freezing.
- B. Provide new water service complete with code approved backflow prevention assembly, water meter with by-pass valves, pressure reducing valve, and sand strainer. If service enters below grade and rises through floor, cast in place. If service enters through wall, provide with link seal between concrete core wall and service pipe, or temporary sleeve which is removed and link seal placed in space between service pipe and concrete. Provide anchor plate support at wall, either cast inside wall or bolted inside building.

END OF SECTION



SECTION 224000 PLUMBING FIXTURES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Lavatories.
- B. Sinks.
- C. Under-lavatory pipe supply covers.

1.02 RELATED REQUIREMENTS

- A. Section 011000 - Summary: Owner-furnished fixtures.
- B. Section 064100 - Architectural Wood Casework: Preparation of counters for sinks and lavatories.
- C. Section 079200 - Joint Sealants: Sealing joints between fixtures and walls and floors.
- D. Section 114000 - Foodservice Equipment: Food service sinks.
- E. Section 115300 - Laboratory Equipment: Laboratory sinks.
- F. Section 123600 - Countertops: Preparation of counters for sinks and lavatories.
- G. Section 221005 - Plumbing Piping.
- H. Section 221006 - Plumbing Piping Specialties.
- I. Section 223000 - Plumbing Equipment.
- J. Section 260583 - Wiring Connections: Electrical characteristics and wiring connections.

1.03 REFERENCE STANDARDS

- A. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.
- B. ASME A112.18.9 - Protectors/Insulators for Exposed Waste and Supplies on Accessible Fixtures; 2011.
- C. ASTM C177 - Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus; 2013.
- D. ASTM C518 - Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2017.
- E. ASTM C1822 - Standard Specification for Insulating Covers on Accessible Lavatory Piping; 2015.
- F. ASTM G21 - Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi; 2015.
- G. IAPMO Z124 - Plastic Plumbing Fixtures; 2017.
- H. ANSI Z358.1 - American National Standard for Emergency Eyewash and Shower Equipment; 2014.
- I. ASHRAE Std 18 - Methods of Testing for Rating Drinking-Water Coolers with Self-Contained Mechanical Refrigeration; 2013.
- J. ASME A112.6.1M - Supports for Off-the-Floor Plumbing Fixtures for Public Use; 1997 (Reaffirmed 2017).
- K. ASME A112.18.1 - Plumbing Supply Fittings; 2012.
- L. ASME A112.18.9 - Protectors/Insulators for Exposed Waste and Supplies on Accessible Fixtures; 2011.
- M. ASME A112.19.1 - Enamelled Cast Iron and Enamelled Steel Plumbing Fixtures; 2013.
- N. ASME A112.19.2 - Ceramic Plumbing Fixtures; 2013.
- O. ASME A112.19.3 - Stainless Steel Plumbing Fixtures; 2017.



- P. ASME A112.19.4M - Porcelain Enameled Formed Steel Plumbing Fixtures; 1994 (R2009).
- Q. ASME A112.19.5 - Flush Valves and Spuds for Water Closets, Urinals, and Tanks; 2017.
- R. ASME A112.19.15 - Bathtub/Whirlpool Bathtubs with Pressure Sealed Doors; 2012.
- S. ASSE 1014 - Performance Requirements for Backflow Prevention Devices for Hand-Held Showers; 2005.
- T. ASSE 1070 - Performance Requirements for Water Temperature Limiting Devices; 2015.
- U. ASTM C1822 - Standard Specification for Insulating Covers on Accessible Lavatory Piping; 2015.
- V. ASTM D570 - Standard Test Method for Water Absorption of Plastics; 1998 (Reapproved 2010).
- W. ASTM D638 - Standard Test Method for Tensile Properties of Plastics; 2014.
- X. ASTM D696 - Standard Test Method for Coefficient of Linear Thermal Expansion of Plastics Between - 30 C and 30 C with a Vitreous Silica Dilatometer; 2016.
- Y. ASTM D785 - Standard Test Method for Rockwell Hardness of Plastics and Electrical Insulating Materials; 2008 (Reapproved 2015).
- Z. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- AA. IAPMO Z124 - Plastic Plumbing Fixtures; 2017.
- AB. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2017.
- AC. ISFA 2-01 - Classification and Standards for Solid Surfacing Material; 2013.
- AD. NEMA LD 3 - High-Pressure Decorative Laminates; 2005.
- AE. NSF 61 - Drinking Water System Components - Health Effects; 2016.
- AF. NSF 372 - Drinking Water System Components - Lead Content; 2016.
- AG. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide catalog illustrations of fixtures, sizes, rough-in dimensions, utility sizes, trim, and finishes.
- C. Manufacturer's Instructions: Indicate installation methods and procedures.
- D. Maintenance Data: Include fixture trim exploded view and replacement parts lists.
- E. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

1.06 FIRST INSTALL

- A. Provide components for installation in first install.
- B. First install may remain as part of the Work.
- C. Owner shall be invited to participate.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Accept fixtures on site in factory packaging. Inspect for damage.
- B. Protect installed fixtures from damage by securing areas and by leaving factory packaging in place to protect fixtures and prevent use.



1.08 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Provide five year manufacturer warranty for electric water cooler.

PART 2 PRODUCTS

2.01 GENERAL

- A. Potable Water Systems: Provide plumbing fittings and faucets that comply with NSF 61 and NSF 372 for maximum lead content; label pipe and fittings.

2.02 REGULATORY REQUIREMENTS

- A. Comply with applicable codes for installation of plumbing systems.
- B. Comply with UL (DIR) requirements.
- C. Perform work in accordance with local health department regulations.
- D. Provide certificate of compliance from Authority Having Jurisdiction indicating approval of installation.

2.03 LAVATORIES

- A. Lavatory Manufacturers:
 - 1. Kohler Company; _____K-2005 (preferred);
 - 2. Zurn Industries, Inc; _____Z5360;
 - 3. Sloan Valve Company; [_____]SS-3003;
 - 4. Karran Sinks, stainless steel undermount; "Edge Series" Model E303;
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Vitreous China Wall Hung Basin: ASME A112.19.2; vitreous china wall hung lavatory, _____ with 4 inch high back, rectangular basin with splash lip, front overflow, and soap depression.
 - 1. Drilling Centers: 4 inch.
 - 2. Drilling: Single hole.
- C. Undercounter Stainless Steel Basin:
 - 1. .18" seamless undermount, made from T304, .18-gauge stainless steel, soft satin brushed finish, sound absorption pads on all bowl walls and bottom.
 - 2. Inside bowl dimensions, length; 15-1/2", width; 12", depth; 5-3/4".
 - 3. Manufacturer and model: Karran.
 - 4. Provide with outlet strainer for non-overflow, type sink with breather tube. Proflo Model PF311CP or equal by Kohler and tail piece with 1/4" breather tube connection with breather tube provided and extended up to just below the bottom of the counter.
- D. Supply Faucet Manufacturers:
 - 1. Chicago;
 - 2. Zurn Industries, Inc; _____
 - 3. Sloan Valve Company;
 - 4. Substitutions: See Section 016000 - Product Requirements.
- E. Supply Faucet: ASME A112.18.1; chrome plated combination supply fitting with open grid strainer, water economy aerator with maximum flow of 1.0 gallons per minute, indexed handles.
- F. Sensor Operated Faucet: Cast brass, chrome plated, deck mounted with sensor located on neck of spout.
 - 1. Spout Style: Standard.
 - 2. Power Supply: Battery, easily replaceable, lithium, minimum 200,000 cycles.
 - 3. Power Supply: 24 VAC.
 - a. Cord and plug.
 - b. For 24V applications, provide transformer.
 - 4. Power Supply: Self-generating, hydro-powered turbine charging rechargeable battery.



5. Mixing Valve: External, mounted under lavatory..
 6. Water Supply: 3/8 inch compression connections.
 7. Aerator: Vandal resistant, 0.5 GPM, laminar flow device.
 - a. The Chicago Faucet Company: E66VPJKABCP;
 - b. Sloan Valve Company: ETF-843;
 - c. Zurn: P6900-20N;
 8. Automatic Shut-off: 30 seconds.
 9. Sensor range: Factory set at a minimum of 3 inch adjustable up to 24 inch.
 10. Sensor range: Automatically adjusts.
 11. Finish: Polished chrome.
 12. Accessory: 4 inch deck plate.
 13. Sensor Operated Faucet Manufacturers:
 - a. The Chicago Faucet Company; _____(Hytronic) 116.201.AB.1;
 - b. Sloan Valve Company; _____EAF-150;
 - c. Zurn Industries, Inc; AquaSense Z6913;
 - d. Substitutions: See Section 016000 - Product Requirements.
- G. Thermostatic Mixing Valve: Thermostatic mixing valve, ASSE 1070 listed, with combination stop, strainer, and check valves, and flexible stainless steel connectors.
1. Manufacturers:
 - a. Symmons;.
 - b. Powers;
 - c. Watts;
 - d. Zurn;
 - e. Honeywell;
 - f. Apollo;
 - g. Substitutions: See Section 016000 - Product Requirements.
- H. Provide lavatory with combination stop and strainer.
- I. Accessories:
1. Chrome plated 17 gage, 0.0538 inch brass P-trap with clean-out plug and arm with escutcheon.
 2. Quarter turn stops.
 3. PEX supplies.
 4. Carrier:
 - a. Manufacturers:
 - 1) Jay R. Smith MFG. Co; _____
 - 2) JOSAM Company; _____
 - 3) Zurn Industries, Inc; _____
 - 4) Substitutions: See Section 016000 - Product Requirements.
 - b. ASME A112.6.1M; cast iron and steel frame with tubular legs, lugs for floor and wall attachment, threaded studs for fixture hanger, bearing plate and studs.

2.04 SINKS

- A. Sink Manufacturers:
1. Kohler Company; _____:
 2. Just Mfg;
 3. Elkay;
 4. Substitutions: See Section 016000 - Product Requirements.
- B. Single Compartment Bowl
1. ASME A112.19.3; _____ by _____ by _____ inch inside bowl dimensions minimum 18 gauge, _____ inch Type 304 stainless steel, self rimming or undermount and undercoated, with ledge ba



- ck drilled for trim. For undermount, supply sink without ledge back and mount faucet on countertop.
2. Drain: 3-1/2 inch stainless steel strainer tailpiece.
- C. Double Compartment Bowl:
1. ASME A112.19.3; _____ by _____ by _____ inch inside bowl dimensions minimum 18 gauge, _____ inch thick, Type 304 stainless steel, self-rimming or undermount and undercoated, with ledge back drilled for trim. For undermount, supply sink without ledge back and mount faucet on countertop.
 2. Drain: 3-1/2 inch stainless steel strainer and tailpiece.
- D. Sink Faucets:
1. Manufacturer:
 - a. The Chicago Faucet Company;
 - b. Kohler;
 - c. T&S Brass;
 - d. Moen;
 - e. Substitutions: See Section 016000 - Product Requirements.
 2. Two Handled Faucet:
 - a. Type: Deck-mount, wrist-blade operated faucet with mounting plate.
 - b. Outlet: laminar flow.
 - c. ASTM A112.18:1, ADA Standards, and NSF 61 compliant assembly.
 - d. Materials: Brass body with polished chrome finish and quarter turn ceramic cartridge.
- E. Accessories: Provide braided or PEX supply lines, quarter turn ball-type stop valve, slip-joint p-trap and stainless steel basket strainer.

2.05 UNDER-LAVATORY PIPE SUPPLY COVERS

- A. Manufacturers:
1. Plumberex Specialty Products, Inc; Handy-Shield MAXX;
 2. TrueBro: Softguard Plus;
 3. Substitutions: See Section 016000 - Project Requirements.
- B. General:
1. Insulate exposed drainage piping including hot, cold and tempered water supplies under lavatories or sinks per ADA Standards.
 2. Construction: 1/8 inch PVC with antimicrobial, antifungal and UV resistant properties.
 - a. Velco fastening system.
 - b. Comply with ASTM E84 for flame and smoke development.
 - c. Comply with ASME A112.18.9 for covers on accessible lavatory piping.
 - d. Comply with ICC A117.1.
 3. Color: High gloss white.
- B. Fountain: 304 stainless steel with underside vandal proof cowling, hooded elevated anti-squirt push-button bubbler with stream guard, automatic stream regulator, mounting bracket, screwdriver stop.
- D. Outlet 3-inch P-trap:
- E. Accessories:
1. 5 feet of 1/2 inch diameter plain end reinforced plastic hose.
 2. Hose clamp hanger.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that walls and floor finishes are prepared and ready for installation of fixtures.
- B. Verify that electric power is available and of the correct characteristics.



- C. Confirm that millwork is constructed with adequate provision for the installation of counter top lavatories and sinks.

3.02 PREPARATION

- A. Rough-in fixture piping connections in accordance with minimum sizes indicated in plumbing fixture schedule for particular fixtures.

3.03 INSTALLATION

- A. Install each fixture with trap, easily removable for servicing and cleaning.
- B. Provide PEX supplies to fixtures with stops, reducers, and escutcheons.
- D. Install components level and plumb.
- E. Install and secure fixtures in place with wall carriers or wall supports and bolts.

3.04 INTERFACE WITH WORK OF OTHER SECTIONS

- A. Review millwork shop drawings. Confirm location and size of fixtures, carriers, wall supports, and openings before rough-in and installation.

3.05 ADJUSTING

- A. Adjust stops or valves for intended water flow rate to fixtures without splashing, noise, or overflow.

3.06 CLEANING

- A. Clean plumbing fixtures and equipment.
- B. See Section 017419 - Construction Waste Management and Disposal, for additional requirements.

3.07 PROTECTION

- A. Protect installed products from damage due to subsequent construction operations.
- B. Do not permit use of fixtures by construction personnel.
- C. Repair or replace damaged products before Date of Substantial Completion.

END OF SECTION



SECTION 230100

MECHANICAL OPERATION AND MAINTENANCE MANUALS

PART 1 GENERAL

THE 230000 HAS BEEN COMPLETELY UPDATED

1.01 SECTION INCLUDES

FEBRUARY 2023

- A. Operation and Maintenance Data.

1.02 RELATED REQUIREMENTS

- A. Section 013000 - Administrative Requirements: Submittal procedures, project meetings, progress schedules and documentation, reports, coordination.
- B. Section 017800 - Closeout Submittals: Project record documents, operation and maintenance (O&M) data, warranties and bonds.

1.03 SUMMARY

- A. Furnish one set of bound operation and maintenance manuals and two thumb drives with electronic copies of maintenance manuals in pdf format.

1.04 PURPOSE

- A. The Operation and Maintenance Manual is prepared to provide a ready reference to all important pieces of mechanical and electrical equipment installed on the project including completed start-up documentation. It is also to provide the necessary operating and maintenance data for use by service personnel. It is also to provide information required for checking equipment performance or for planning of physical plant expansion or redesign.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 ASSEMBLY OF DURABLE OPERATION AND MAINTENANCE MANUALS

- A. Assemble operation and maintenance data into durable manual(s) for Owner's personnel use, with data arranged in divisions as outlined below.
- B. Binders: Commercial quality, 8-1/2 by 11 inch three D side ring binders with durable plastic covers; 4 inch maximum ring size. When multiple binders are used, correlate data into related consistent groupings. The number of binders, however, shall be based upon not filling them beyond 2 1/2 inch thickness.
- C. Cover: Identify each binder with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.
- D. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Architect, Consultants, Contractor and subcontractors, with names of responsible parties.
- E. Tables of Contents: List every division separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.
 - 1. Master Table of Contents shall be (Include, in Project Operation and Maintenance Manual, only divisions used in project. Modify Table of Contents for each project manual.):
 - a. Plumbing Equipment
 - 1) 1131 - Plumbing Air System
 - 2) 1132 - Water Softener
 - 3) 1133 - Plumbing Pressure System
 - 4) 1135 - Water Heater
 - 5) 1136 - Plumbing Pump
 - 6) 1138 - Plumbing Delivery System

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 7) 1139 - Water Cooler
- 8) 113A - Grease Trap / Septic Tanks
- 9) 113C - Fire Sprinkling System
- 10) 113D - Gas Suppression System
- 11) 113E - Pool Treatment System
- 12) 113F - Lab Vacuum System
- 13) 113G - Backflow Preventer

b. HVAC Equipment

- 1) 1141 - Boilers and Boiler Accessories
- 2) 1143 - Thermal Storage System
- 3) 1144 - Steam Condensate System
- 4) 1145 - HVAC Piping System
- 5) 1146 - Heating Water Pump
- 6) 1147 - HVAC Expansion Tanks
- 7) 1148 - Terminal Heating/Cooling Units
- 8) 1149 - Furnace
- 9) 114A - Coil
- 10) 114B - Filter / Filter Rack
- 11) 114C - Damper
- 12) 114D - Motor Speed Controller (VFD)
- 13) 114F - Chiller
- 14) 114G - Packaged Heating/Cooling Unit
- 15) 114H - Humidifier / Dehumidifier
- 16) 114I - Cooling Tower
- 17) 114J - Chilled Water Pump
- 18) 114K - Condenser Water Pump
- 19) 114L - Condensing Unit
- 20) 114M - Air Handling Unit
- 21) 114N - Exhaust Fan
- 22) 114O - Air Control (VAV) Box
- 23) 114R - Heat Exchanger
- 24) 114S - Evaporative Cooler
- 25) 114T - Temperature Control System
- 26) 114U - HVAC Water Filter / Treatment
- 27) 114W - Fume Hoods
- 28) 114X - Dust Collector / Paint Booth
- 29) 114Y - HVAC Delivery System

- F. Dividers: Provide tabbed dividers for each division of equipment; identify the division name on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
- G. Text: Manufacturer's printed data, or typewritten data on 20 pound paper.
- H. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
- I. Arrangement of Contents: Organize each volume in parts as follows:
1. Project Directory.
 2. Table of Contents, of all volumes, and of current volume.
 3. Operation and Maintenance Data: Arranged by division, and then by piece of equipment.
 - a. Source data.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- b. Outline drawings, special construction details, “as built” electrical wiring and control diagrams for all major and supplementary systems.
- c. Manufacturer's test or calculated performance data and certified test curves (where applicable).
- d. Installation, operating, and maintenance instructions, including a complete parts list and sectional drawing with parts identification numbers. Mark with model, size and plan number.
- e. Manufacturer’s brochure marked to indicate exact equipment purchased. Brochures on component parts supplied by a manufacturer with their equipment, but not manufactured directly by them, shall also be included.
- f. The serial numbers of each item of equipment installed are to be listed with the model numbers and plan symbols.
- g. A copy of the approved submittals for each piece of equipment.
- h. A copy of the completed equipment start up report.
- i. A copy of all testing, adjusting and balancing reports.
- j. Wiring diagrams, marked with model and size and plan symbol.
- k. The index shall contain the name and address of the manufacturer and, if different, where replacement and repair parts may be obtained.

3.02 ORGANIZATION OF DIGITAL OPERATION AND MAINTENANCE MANUAL

- A. Assemble operation and maintenance data into an electronic format for Owner's use, with data arranged in divisions.
- B. Furnish two electronic copies of Mechanical Operation and Maintenance Manual to owner on a readable and downloadable thumb drive.
- C. Create a directory for each division used in project. Name directories using the same format as the Master Table of Contents, shown above.
- D. Compile scanned PDF files or manufacturer furnished PDF files together into a single division PDF file duplicating divisions found in the durable Operation and Maintenance Manual.
- E. Populate the division directories/folders with the division PDF files.
- F. No Table of Contents is required for the electronic copy of the Mechanical Operation and Maintenance Manual.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230548

VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Match specification section 220548 for requirements for vibration isolation requirements.
- B. Match specification section 220548 for requirements for seismic control requirements.
- C. Match specification section 220548 for requirements for equipment support bases.
- D. Match specification section 220548 for requirements for vibration isolators.
- E. Match specification section 220548 for requirements for seismic restraints for suspended components and equipment.
- F. Seismic snubber assemblies.
- G. Roof curbs.

1.02 RELATED REQUIREMENTS

- A. Section 014533 - Code-Required Special Inspections.
- B. Section 033000 - Cast-in-Place Concrete.
- C. Section 220548 - Vibration and Seismic Controls for Plumbing Piping and Equipment.

1.03 DEFINITIONS

- A. HVAC Component: Where referenced in this section in regards to seismic controls, applies to any portion of the HVAC system subject to seismic evaluation in accordance with applicable codes, including distributed systems (e.g., ductwork, piping).
- B. Seismic Restraint: Structural members or assemblies of members or manufactured elements specifically designed and applied for transmitting seismic forces between components and the seismic force-resisting system of the structure.

1.04 REFERENCE STANDARDS

- A. ASCE 7 - Minimum Design Loads for Buildings and Other Structures; 2010, with 2013 Supplements and Errata.
- B. ASCE 19 - Structural Applications of Steel Cables for Buildings; 2016.
- C. ASHRAE (HVACA) - ASHRAE Handbook - HVAC Applications; 2015.
- D. ICC (IBC) - International Building Code (current adopted version)
- E. ICC-ES AC156 - Acceptance Criteria for Seismic Certification by Shake-Table Testing of Nonstructural Components; 2010, with Editorial Revision (2015).
- F. MFMA-4 - Metal Framing Standards Publication; 2004.
- G. IAS AC172 - Accreditation Criteria for Fabricator Inspection Programs for Structural Steel; 2017.
- H. SMACNA (SRM) - Seismic Restraint Manual Guidelines for Mechanical Systems; Sheet Metal and Air Conditioning Contractors' National Association; 2008.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for products, including materials, fabrication details, dimensions, and finishes.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Seismic Design Data:
 - 1. Compile information on project-specific characteristics of actual installed HVAC components necessary for determining seismic design forces required to design appropriate seismic controls.
 - a. Component operating weight and center of gravity.
 - b. Component elevation in the building in relation to the roof elevation (z/h).
 - c. Component importance factor (I_p).
 - d. For distributed systems, component materials and connection methods.
 - e. Component amplification factor (a_p) and component response modification factor (R_p), determined in accordance with ASCE 7 tables.
 - 2. Include structural calculations, stamped or sealed by seismic controls designer, demonstrating suitability of seismic controls for seismic design forces.
- D. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
- E. Field quality control test reports.

1.06 QUALITY ASSURANCE

- A. Comply with applicable building code.
- B. Seismic Controls Designer Qualifications: Registered professional engineer licensed in Utah and with minimum five years' experience designing seismic restraints for nonstructural components.
 - 1. Designer may be employed by the manufacturer of the seismic restraint products.
- C. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 SEISMIC SNUBBER ASSEMBLIES

- A. Manufacturers:
 - 1. External Seismic Snubber Assemblies:
 - a. Kinetics Noise Control, Inc; _____: www.kineticsnoise.com
 - b. Mason Industries; _____: www.mason-ind.com
 - c. Substitutions: See Section 016000 - Product Requirements.
 - 2. Source Limitations: Furnish external seismic snubber assemblies and associated accessories produced by the same manufacturer as the vibration isolators and obtained from a single supplier.
- B. Description: Steel snubbing assemblies designed for external attachment to both equipment and supporting structure that, as part of a complete system, restrain equipment motion in all directions during a seismic event while maintaining vibration isolation during normal operation.
- C. Seismic Snubbing Elements:
 - 1. Air Gap: Between 0.125 inches and 0.25 inches unless otherwise indicated.
 - 2. Points of Contact: Cushioned with resilient material, minimum 0.25 inch thick; capable of being visually inspected for damage and replaced.

2.02 ROOF CURBS

- A. Seismic Type Non-Isolated Curb and Fabricated Equipment Piers:
 - 1. Location: Between structure and rooftop equipment.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Construction: Steel.
3. Weather exposed components consist of corrosion resistant materials.
4. Stamped seismic curb design and installation as per curb manufacturer or curb supplier.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that mounting surfaces are ready to receive vibration isolation and/or seismic control components and associated attachments.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Secure fasteners according to manufacturer's recommended torque settings.

3.03 INSTALLATION - SEISMIC

- A. Comply with:
 1. ASHRAE (HVACA) Handbook - HVAC Applications.
 2. SMACNA (SRM).
- B. Seismic Snubbers:
 1. Provide on all isolated equipment, piping and ductwork.
 2. Provide minimum of four seismic snubbers located close to isolators.
 3. Snub all other equipment between 0.15 inch and 0.25 inch clearance.
- C. Floor and Base-Mounted Equipment, Vibration Isolated Equipment and associated Vibration and Seismic Controls for Connections:
 1. Install equipment anchorage items designed to resist seismic design force in any direction.
 2. Install vibration and seismic controls designed to include base and isolator requirements.
 3. Provide flexible connections between equipment and interconnected piping.
 4. Provide isolators and restraints designed for amplified code forces per ASCE 7 and with demonstrated ability to resist required forces including gravity, operational and seismic forces.
 5. Where equipment is not designed to be point loaded, provide base capable of transferring gravity and seismic demands from equipment to isolator base plate anchorage.
 6. Where concrete floor thickness is less than required for expansion anchor installation, install through bolt in lieu of expansion anchor.
- D. Suspended Mechanical Equipment:
 1. Provide supports and bracing to resist seismic design force in any direction.
 2. Provide flexible connections between equipment and interconnected piping.
 3. Brace equipment hung from spring mounts using cable or other bracing that will not transmit vibration to the structure.
 4. Use of proprietary restraint systems with a certificate of compliance, verified and listed by an accredited inspection body is acceptable (pending shop drawing approval), as an alternative to project specific seismic bracing design.
- E. Wall mounted Mechanical Equipment:
 1. Provide support and bracing to resist seismic design force in any direction.
 2. Install backing plates or blocking as required to deliver load to primary wall framing members.
 3. Anchoring to gypsum wallboard, plaster or other wall finish that has not been engineered to resist imposed loads is not permitted.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



F. Ductwork:

1. Provide seismic bracing for ducts with cross sectional area greater than 6 sq ft (independent of duct contents).
2. Provide seismic bracing for all ducts containing hazardous materials.
3. Provide supports, braces, and anchors to resist gravity and seismic design forces.
4. Install ducts and duct risers designed to accommodate interstory drift.
5. Independently support in-line devices weighing more than 20 pounds.
6. Independently support and brace all in-line devices weighing more than 75 pounds.
7. Provide unbraced piping attached to braced in-line equipment with adequate flexibility to accommodate differential displacements.
8. Positively attach dampers, louvers, diffusers and similar appurtenances to ductwork with mechanical fasteners.
9. Install duct supports designed to resist not less than 150 percent of the duct weight.
10. The use of power driven fasteners is prohibited in the hanging of ducts weighing over 10 pounds per lineal foot for seismic design categories D, E, and F.
11. Use of proprietary restraint systems with a certificate of compliance, verified and listed by an IAS AC172 accredited inspection body or otherwise accepted by applicable codes is acceptable (pending shop drawing approval), as an alternative to project specific seismic bracing design.

G. Tanks:

1. Install tank anchorage, tank legs and/or supporting structure designed to resist design force.
2. Provide flexible connections between tank and interconnected piping.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect vibration isolation and/or seismic control components for damage and defects.
- C. Seismic Controls:
 1. Verify snubbing element air gaps.
- D. Correct deficiencies and replace damaged or defective vibration isolation and/or seismic control components.
- E. Submit detailed reports indicating inspection and testing results and corrective actions taken.

3.05 SCHEDULE - AS SPECIFIED ON DRAWINGS.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230553
IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Nameplates.
- B. Tags.
- C. Pipe markers.

1.02 RELATED REQUIREMENTS

- A. Section 099123 - Interior Painting: Identification painting.

1.03 REFERENCE STANDARDS

- A. ASME A13.1 - Scheme for the Identification of Piping Systems; 2015.
- B. ASTM D709 - Standard Specification for Laminated Thermosetting Materials; 2017.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. List: Submit list of wording, symbols, letter size, and color coding for mechanical identification.
- C. Product Data: Provide manufacturers catalog literature for each product required.
- D. Manufacturer's Installation Instructions: Indicate special procedures, and installation.
- E. Project Record Documents: Record actual locations of tagged valves.

PART 2 PRODUCTS

2.01 IDENTIFICATION APPLICATIONS

- A. Scheduled Equipment: Nameplates.
- B. Air Handling Units: Nameplates.
- C. Air Terminal Units: Adhesive label or legible hand-written permanent marker.
- D. Automatic Control Sensors, Relays, Actuators: Adhesive label or legible hand-written permanent marker at closest junction box.
- E. Control Panels: Nameplates.
- F. Dampers: Adhesive label or legible hand-written permanent marker at closest junction box.
- G. Heat Transfer Equipment: Nameplates.
- H. Piping: Pipe markers.
- I. Pumps: Nameplates.
- J. Tanks: Nameplates.
- K. Valves: Tags.
- L. Water Treatment Devices: Nameplates.

2.02 NAMEPLATES

- A. Manufacturers:
 - 1. Advanced Graphic Engraving, LLC; _____
 - 2. Brimar Industries, Inc; _____; www.pipemarker.com
 - 3. Craftmark Pipe Markers; _____
 - 4. Kolbi Pipe Marker Co; _____

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



5. Seton Identification Products, a Tricor Direct Company; _____
 6. Substitutions: See Section 016000 - Product Requirements.
- B. Letter Color: White.
- C. Letter Height: 1/4 inch.
- D. Background Color: Black.
- E. Plastic: Comply with ASTM D709.

2.03 TAGS

- A. Manufacturers:
1. Advanced Graphic Engraving; _____: www.advancedgraphicengraving.com
 2. Brady Corporation; _____
 3. Brimar Industries, Inc; _____
 4. Craftmark Pipe Markers; _____
 5. Kolbi Pipe Marker Co; _____
 6. Seton Identification Products, a Tricor Company; _____
 7. Substitutions: See Section 016000 - Product Requirements.
- B. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inch diameter.
- C. Metal Tags: Brass with stamped letters; tag size minimum 1-1/2 inch diameter with smooth edges.

2.04 PIPE MARKERS

- A. Manufacturers:
1. Brady Corporation; _____
 2. Brimar Industries, Inc; _____
 3. Craftmark Pipe Markers; _____
 4. Kolbi Pipe Marker Co; _____
 5. Seton Identification Products, a Tricor Company; _____
 6. Substitutions: See Section 016000 - Product Requirements.
- B. Color: Comply with ASME A13.1.
- C. Plastic Pipe Markers: Factory fabricated, flexible, semi-rigid plastic, preformed to fit around pipe or pipe covering; minimum information indicating flow direction arrow and identification of fluid being conveyed.
- D. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.
- E. Underground Plastic Pipe Markers: Bright colored continuously printed plastic ribbon tape, minimum 6 inches wide by 4 mil thick, manufactured for direct burial service.

PART 3 EXECUTION

3.01 PREPARATION

- A. Degrease and clean surfaces to receive adhesive for identification materials.

3.02 INSTALLATION

- A. Install nameplates with corrosive-resistant mechanical fasteners, or adhesive. Apply with sufficient adhesive to ensure permanent adhesion.
- B. Install tags with corrosion resistant chain.
- C. Install plastic pipe markers in accordance with manufacturer's instructions.
- D. Install plastic tape pipe markers complete around pipe in accordance with manufacturer's instructions.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230593

TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 GENERAL

UPDATED FULL SECTION

1.01 GENERAL CONDITIONS

FEBRUARY 2023

- A. Mechanical Contractor shall be responsible to verify if a Commissioning Agent is retained by Owner for the current project. If no Commissioning Agent is hired, then it shall be the responsibility of the Mechanical Contractor to provide commissioning services as per specification section 230800.
- B. The Testing, Adjusting, and Balancing (TAB) Contractor is responsible for all work in this section in coordination with BYU Construction Project Manager.
- C. Work of this section shall be subject to the requirements of the General Conditions of this contract, the General Mechanical Requirements, General Electrical Requirements and other sections where this work shares a responsibility.
- D. Startup of mechanical systems shall be the responsibility of the Mechanical Contractor and his subcontractors with the participation of the Electrical Contractor related to electrical work and the General Contractor related to general construction items.
- E. Testing and balancing shall be the responsibility of the Mechanical Contractor under the direction of the General Contractor with the full participation of all the mechanical and electrical trades employed on the project and shall include the participation of an independent testing and balance contractor to coordinate all elements of the TAB work and to perform special technical services outlined herein.
- F. TAB Contractor shall coordinate all work with BYU Construction Project Manager. BYU Construction Project Manager shall coordinate work with BYU Commissioning representatives, BYU Air Conditioning Shop representatives, BYU Mechanical Shop representatives, and Owner contracted Digital Controls Supplier and Programmer.

1.02 SECTION INCLUDES

- A. Testing, Adjustment, and Balancing of:
 - 1. Air conditioning equipment including air distribution devices, supply ducts, air handling units, condensing units, fans, coils, and related equipment.
 - 2. Hydronic systems including pumps, water distributions systems, chillers, boilers, heat exchangers, coils and related equipment.
- B. System Commissioning - Extent of Work:
 - 1. The work required by this section includes, but is not necessarily limited to the following:
 - a. The pre-startup inspection of all systems and subsequent correction of any incorrect items. (PFAT)
 - b. The initial first run inspections. (FAT)
 - c. System operations inspections.
 - 2. The intent of this work is to provide for proper installation, startup, service and operation of the mechanical systems in preparation for system balance.
 - 3. Repair, replacement or adjustment of each item shall be performed by the installing contractor.
 - 4. Involves all new construction and those elements of existing construction which are affected by this project.
- C. Testing and Balancing - Extent of Work:
 - 1. This work incorporates a confirming checkout of construction work, an individual component activation and an overall system activation into one work program which shall serve as the transition period from Contractor's job to Owner's facility.
 - 2. The TAB Contractor shall be skilled in the operation and manipulation of systems and in the direction of parties involved in the work.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Conduct and participate in the startup and verification of all mechanical systems installed and modified in the contract; test, adjust and balance these systems to obtain optimum performance at a level which minimizes the required energy input, prepare and submit at completion a report of work done and the final system condition obtained, participate in the instruction of Owner's personnel in the proper operation of systems and equipment.
4. Involves all new construction and those elements of existing construction which are affected by this project.

1.03 RELATED REQUIREMENTS

- A. Section 012100 - Allowances: Inspection and testing allowances.
- B. Section 014000 - Quality Requirements: Employment of testing agency and payment for services.
- C. Section 019113 - General Commissioning Requirements: Commissioning requirements that apply to all types of work.
- D. Section 250500 - Common Work Results for Integrated Automation.

1.04 REFERENCE STANDARDS

- A. Testing, Adjusting, and Balancing Bureau (TABB) - International Standards for Environmental Systems Balance.
- B. AABC (NSTSB) - AABC National Standards for Total System Balance, 7th Edition; 2016.
- C. ASHRAE Std 110 - Methods of Testing Performance of Laboratory Fume Hoods; 2016.
- D. ASHRAE Std 111 - Measurement, Testing, Adjusting, and Balancing of Building HVAC Systems; 2008.
- E. NEBB (TAB) - Procedural Standards for Testing Adjusting and Balancing of Environmental Systems; 2015, with Errata (2017).
- F. SMACNA (TAB) - HVAC Systems Testing, Adjusting and Balancing; 2002.

1.05 DEFINITIONS

- A. Adjusting: Varying of system flow by modifying settings of dampers and valves, in combination with varying speeds to obtain optimum operating conditions for the entire system.
- B. Balancing: Proportioning of air and hydronic flows through system mains, branches, and terminal devices using standardized procedures to obtain specified air or hydronic flow while imposing the least amount of restriction on the HVAC system.
- C. Testing: Use of specialized and calibrated instruments to measure temperatures, pressures, rotational speeds, electrical characteristics, air and hydronic flow in velocities or quantities used in evaluating the performance of a HVAC system.

1.06 QUALITY ASSURANCE

- A. Representatives of the General Contractor, Mechanical Contractor, etc., and the Electrical Contractor shall be available on a daily basis through the commissioning and adjustment period. These representatives shall be experienced journeymen with prior experience in system operation and with specific experience on the construction project.
- B. Qualifications of Test and Balance Firm:
 1. Testing and Balancing shall be performed by a testing agency who specializes in testing, adjusting and balancing of heating, ventilating, air-moving equipment, air-conditioning systems and hydronic systems and have a minimum of one year of experience.
 2. Testing agency shall have successfully completed a minimum of five projects of similar size and scope.
 3. Testing agency shall be a certified member to TABB, AABC, and/or NEBB.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 4. Test and Balance Firm shall provide documentation of items 1 - 3 prior to start of project.
- 5. Balance agencies approved for this work:
 - a. Payson Sheet Metal, Payson, UT. (801) 465-3018
 - b. Substitutions: See Section 012500. Alternate contractors require owner approval. See Mechanical Bid Breakdown form.

C. Certifications:

- 1. TAB technician shall be certified by a nationally recognized certifying agency.

D. Perform total system balance in accordance with Testing, Adjusting and Balancing Bureau (TABB) – Quality Assurance Program for Environmental Systems Balance, AABC National Standards for Field Measurements and Instrumentation and/or Total System Balance and/or NEBB Quality Assurance Program – Conformance Certification.

E. The balancing work including air and hydronic portions shall be performed by the same firm having total responsibility for the final testing, adjusting and balancing of the entire system.

F. The independent testing and balancing firm shall furnish all necessary tools, scaffolding and ladders that are required and shall provide all required instruments, take all readings and make all necessary adjustments.

G. After all tests and adjustments are made, a detailed written report shall be prepared and submitted for review, and shall bear the signature of the professional supervising the work. Final acceptance of this project will not be made until a complete and satisfactory report is received. Furnish two (2) copies of the report.

H. Testing of laboratory fume hoods (**when fume hoods are included in project**):

- 1. Product Data sheets for all equipment proposed for use in on-site as-installed testing.
- 2. Sample Test Report.
- 3. List of laboratory fume hoods to be tested. Submit a minimum of one week prior to commencement of testing.
- 4. Test data demonstrating that each type of fume hood provided for the project has been successfully tested in the factory as per requirements of Section 115313.

1.07 PROJECT CONDITIONS

- A. Testing, adjusting and balancing shall commence after HVAC systems installation is complete and in working order. Associated areas of general construction shall be in place including interior and exterior doors, windows, walls and ceilings.

1.08 SPECIAL WARRANTY

- A. Provide warranty for period of 120 days following submission of completed report, during which time, Owner may request a recheck of up to 10% of total number of terminals, or resetting of any outlet, coil, or device listed in the report.
- B. Warranty shall meet the requirements of the following program(s):
 - 1. TABB – International Quality Assurance Program
 - 2. AABC - National Project Performance Guarantee
 - 3. NEBB - Conformance Certification

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PFAT (PRE-FUNCTIONAL ACCEPTANCE TESTING)

- A. If a Commissioning Agent other than the balance firm is employed on the project, the PFAT requirements shall be performed by the commissioning firm. Otherwise the requirements shall be performed by the balance firm.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Prior to the commencing of testing, adjusting and balancing of environmental system(s), verify the following conditions:
1. Removal of shipping stops.
 2. Vibration isolators properly aligned and adjusted.
 3. Flexible connections properly aligned.
 4. Belts properly adjusted.
 5. Belts guards and safety shields in place.
 6. Systems are started and operating in a safe and normal condition.
 7. Thermal overload protection is in place for fans, pumps, chillers, and other equipment.
 8. Safety controls, safety valves and high or low limits in operation.
 9. All systems properly filled.
 10. Pumps are rotating correctly.
 11. Start-up/construction strainers have been removed and all pertinent strainers are clean and in place.
 12. Gauges and/or test ports are properly located for balancing.
 13. Service and balance valves are fully open.
 14. Hydronic systems are pressure tested, flushed, filled, and properly vented.
 15. Leak testing on duct system has been performed in accordance with SMACNA standards or as specified.
 16. Air coil fins are cleaned and combed.
 17. Access doors are closed and duct end caps are in place.
 18. Air outlets are installed and connected.
 19. Fans and motors are rotating correctly.
 20. Duct and fan systems are clean.
 21. Final filters are clean and properly installed.
 22. Automatic and manual dampers are installed correctly, operable and fully open.
 23. Fire and volume dampers are in place and open.
 24. Temperature control systems are installed, complete and operable.
 25. Voltages match nameplate.
 26. All interlocks are wired and verified.
 27. All other items necessary to provide for proper startup.
 - a. If deficiencies are evident, submit Deficiency Report to Engineer/Architect. Do not begin testing, adjusting and balancing of environmental systems until deficiencies have been remedied.

3.02 FIRST RUN INSPECTION

- A. If a Commissioning Agent other than the balance firm is employed on the project, the first run inspection requirements shall be performed by the commissioning firm. Otherwise the requirements shall be performed by the balance firm.
- B. Verify that Prestartup Inspection has been successfully completed to ensure proper operation.
- C. Check for the following items:
1. All specified air and water filters installed.
 2. Excessive vibration or noise.
 3. Loose components.
 4. Initial control settings.
 5. Motor amperages.
 6. Heat buildup in motors, bearings, etc.
 7. Control system is properly calibrated and functioning as required.
- D. Correct all items which are not operating properly.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.03 FAT (FUNCTIONAL ACCEPTANCE TESTING)

- A. If a Commissioning Agent other than the balance firm is employed on the project, the FAT requirements shall be performed by the commissioning firm. Otherwise the requirements shall be performed by the balance firm.
- B. Observe mechanical systems under operating conditions for up to six months' time (one seasonal change) to insure proper operation under varying conditions, such as day-night and heating-cooling.
 - 1. Check the following items:
 - a. Visual checks to air flow for "best guess" settings for preparation for system air balancing under section applying.
 - b. Control operation, on-off sequences, system cycling, etc.
 - c. Visual checks of water flow, seals, packing safety valves, operation pressures and temperature.
 - d. Cleaning of excessive oil or grease.
 - e. Dampers close tightly.
 - f. Valves close tightly.
 - g. System leaks.
 - h. All other items pertaining to the proper operation of the mechanical system whether specifically listed or not.

3.04 TOTAL MECHANICAL SYSTEM BALANCE

- A. The mechanical systems balance involves elements of the work of the General Contractor, the Electrical Contractor, the Mechanical Contractor, the Sheet Metal Contractor and the Controls Contractor. Total system balance requires all elements be not only individually correct, but also correct as a composite system. Therefore, participation of all parties shall be required in the test and balance procedure.
- B. Prior to the beginning of the work, a written description of the balance methods, equivalent to be used, and procedures of action shall be submitted to the Engineer/Owner for review and comment.
- C. The testing and balance specialist shall review the contract drawings during the bid period and shall advise the Engineer of any modifications to the layout which may be needed to facilitate the balance procedure. Modifications will be incorporated into the contract by Addendum during the bidding period.
- D. The test and balance specialist shall visit the project at 50%, 80% and 90% completion, making a thorough inspection of those items which will affect his subsequent work and provide a report. Mechanical Contractor shall coordinate progress visits with test and balance specialist and BYU Project Manager. Test and balance specialist shall advise the Contractor in writing, with a copy to the Engineer/Architect, of any work required by the contract which is not being performed adequately. This is in addition to the regular inspection efforts of the Architect and Engineer. Particularly note the needed valves, dampers, access doors, thermometers, pressure gauges, belts and drives, diffuser styles, strainers and filters, etc.

3.05 MAJOR EQUIPMENT

- A. The Testing and Balancing Contractor shall work with the Controls Contractor, and Electrician in placing heat exchangers, pumps, fans and other major equipment in operation. The factory representative of the equipment manufacturer shall also participate in a team effort to place the system(s) in operation, adapt to all anticipated operating modes and make adjustments as required to obtain correct operation. The Design Engineer and the Owner's Representative shall witness the final operating sequences.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.06 CONTROL SYSTEMS

- A. The Testing and Balancing Contractor shall go through the entire control system with the Controls Contractor, verifying proper operation of each and every device and the proper function of each system. Certify such effort in the report.

3.07 ON SITE FUME HOOD TESTING (WHEN FUME HOODS ARE INCLUDED IN PROJECT)

- A. General: Test fume hoods as installed to assess airflow velocity, airflow visualization, and level of containment. Perform tests with static mode (set sash position) conditions. Conduct testing as outlined below for 100% of the hoods provided in the Project.
- B. Preparation: Visit the project site to confirm that construction activities related to the fume hood system(s) and equipment are complete. Review design documents and Contractor's submittals. Verify that mechanical ventilation systems serving the space are functioning and operating in the normal mode. Notify Owner in writing, if conditions exist which preclude proper fume hood testing. Starting of testing constitutes acceptance of site conditions.
- C. Testing Requirements:
 - 1. Perform the following tests, in order:
 - a. Airflow Velocity Test.
 - b. Airflow Visualization Test.
 - c. Tracer Gas Containment Test (Where lab safety level requires, as per BYU Risk Management).
 - 2. If more than one test procedure is selected, proceed to the next test only if any unsafe condition discovered during current test has been successfully rectified.
 - 3. Airflow Velocity Test: Comply with Section 9 of NEBB (FHT) Fume Hood Testing Standard - current edition.
 - 4. Airflow Visualization Test: Comply with Section 10 of NEBB (FHT) Fume Hood Testing Standard - current edition.
 - 5. Tracer Gas Containment Test (Where lab safety level requires, as per BYU Risk Management):
 - a. Conduct a static mode test of the hood and laboratory configuration. Conduct testing in accordance with ASHRAE Std 110, except as modified herein:
 - 1) Test hood with simulated scientific apparatus set-up within the hood. Apparatus to consist of: two (2) each 1 gal. round paint cans, one (1) 1' by 1' by 1' cardboard box, and three (3) each 6" by 6" by 12" high cardboard boxes. Position these items from 6 to 10 inches behind the sash, randomly distributed, and supported off of the work surface by 2 inch by 2 inch by 2 inch block of any material.
 - 2) 6 liters per minute release rate for tracer gas.
 - 3) Conduct only at the center position for the manikin.
 - 4) Each tracer gas test duration to be 5 minutes.
 - 5) Acceptable test results will be 0.05 PPM or better.
 - 6) At the conclusion of each 5-minute test there will be three rapid walk-by at 1' behind the manikin. Each walk-by to be spaced 30 seconds apart. If a rise in test gas concentration occurs, it cannot exceed 0.10 ppm and must return to 0.05 ppm within 15 seconds.
 - 7) There must be a minimum of three and a maximum of five people in the space in which the fume hood is located during the test procedure.
 - 8) Representatives of the Architect, Engineer, Owner, and Contractor must witness the tests.
 - 9) Test of Alarm: Shut off the fume hood exhaust and verify that the individual fume hood alarm activates.
 - 10) Test individual controls: Test any controls that are provided at the fume hood such as unoccupied cycle override, alarm override, etc.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



6. Reporting Requirements: Organize and include, at a minimum, the following information:
 - a. Report Title.
 - b. Report Certification.
 - c. Table of Contents.
 - d. Report Summary/ Remarks.
 - e. Appropriate Forms.
 - f. Instrument Calibration.
 - g. List of Abbreviations Used.
 - h. A room layout drawing for each tested item. Identify: walls; doors; fume hood(s); other present environmental enclosures (e.g. biological safety cabinet(s), laminar flow hood(s), canopy hood(s), etc.); location and airflow pattern of all air supply, return, and exhaust grilles, registers and diffusers.

3.08 AIR SYSTEM BALANCE

- A. Before any adjustments are made, check the systems for such items as dirty filters, duct leakage, filter leakage, damper leakage, equipment vibrations, correct damper operations, etc. Adjust all fan systems major duct sections, registers, diffusers, etc., to deliver design air quantities within $\pm 5\%$. Individual air outlets, when one of three or more serve a space may have a tolerance of $\pm 10\%$ of the average.
- B. Adjust supply, exhaust and recirculation air systems toward air quantities shown on drawings. Establish a proper relationship between supply and exhaust. Follow proportional balance procedures outlined by AABC, SMACNA and/or TABB for such work.
- C. All thermal boxes, air flow measuring stations, and other devices shall be calibrated and verified for proper function.
- D. Distribution system shall be further adjusted to obtain uniform space temperatures free from objectionable drafts and noise within the capabilities of the system. Any changes to the design are to be submitted for approval and fully documented.
- E. Exchange sheaves and/or belts as needed to adjust the RPM of all fans so they handle specified air quantity.
- F. All balance procedures shall follow allowed procedure from the REFERENCE STANDARDS section (1.04 above).
- G. Provide system schematic with required and actual air quantities recorded at each outlet or inlet.

3.09 HYDRONIC SYSTEMS

- A. Before adjustments are made, clean strainers, check temperature control valve operations, check pump rotation, adjust pressure reducing valves, as required by sections, 3.01, 3.02, 3.03 of this specification section. Assure that system water treatment has been inspected and approved by Owner water treatment specialist.
- B. Using system flow meters, pressure gauges, and/or contact pyrometer, adjust the quantity of fluid handled by each pump and supplied to each coil, heat exchanger, etc., to meet design requirements. Adjust hydronic systems to provide $\pm 10\%$ of required design quantities.
 1. Remove and trim pump impellers where throttling, and/or speed control exceeds 10% of adequate flow.
- C. Verify all hydronic system controls for proper function for coils, heat exchangers, and all other equipment with control valves.
- D. Use proportional balance techniques so that in every case, at least one terminal valve is set for full flow at wide open, and at least one branch is wide open at full flow, other equivalent.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.10 MISCELLANEOUS

- A. Observe and note all furnished thermal overload protection in the data sheets. If thermal overload protection is incorrect, the trade which furnished the overload devices shall furnish and install the correct size overload protection devices. It shall be the responsibility of the balancing firm to confirm that proper overload protection has been installed at the completion of the job.
- B. Measure and set any special conditions such as minimum air quantities; coordinate outside air, return air and relief air damper operation; check and adjust outside and return air intakes so that the system will deliver substantially the same volume on either; make tests and record data as required in "REPORT" below.
- C. Permanently mark setting of valves, dampers, and other adjustment devices allowing for settings to be restored. Set and lock memory stops.
- D. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring thermostats to specified settings.
- E. Upon request, based on perceived need, make 24-hour space temperature recordings. Any required re-balance of the system shall be performed without additional cost to the project.
- F. Upon request, a representative of the balancing firm performing the work shall demonstrate fluid flow quantities shown in the report by reading back outlets or terminals selected specifically or at random by the Design Engineer, or the Owner. It is understood that the operating mode of the system shall be the same for read-back as it was during balancing. If any system is found to be outside the specified balance requirements, the balancing agency shall re-balance the entire system and resubmit a new balance report at no cost to the Owner.

3.11 REPORT

- A. Provide (1) one bound report and (1) one searchable electronic pdf copy containing a general information sheet listing instruments used, method of balancing, altitude correction, and manufacturer's grille, register and diffuser data.
- B. Electric Motors:
 - 1. Manufacturer.
 - 2. Model/Frame.
 - 3. HP/BHP.
 - 4. Phase, voltage, amperage; nameplate, actual, no load.
 - 5. RPM.
 - 6. Service factor.
 - 7. Starter size, rating, heater elements.
 - 8. Sheave Make/Size/Bore.
- C. Belt Drives:
 - 1. Identification/location.
 - 2. Required driven RPM.
 - 3. Drive and sheave on fan or other device, record bore size, outside diameter of sheave or pitch diameter or make and model of sheave, and RPM
 - 4. Belt, manufacturer, size and quantity.
 - 5. Motor sheave, record bore size, outside diameter of sheave or pitch diameter or make and model of sheave, and RPM
 - 6. Center to center distance, maximum, minimum, and actual.
 - 7. Rotational direction, recorded on motor and drive side of fan
- D. Pumps:
 - 1. Identification/number.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Manufacturer.
 4. Size/model.
 5. Impeller.
 6. Service.
 7. Design flow rate, pressure drop.
 8. Actual flow rate, pressure drop.
 9. Discharge pressure.
 10. Suction pressure.
 11. Total operating head pressure.
 12. Shut off, discharge and suction pressures.
 13. Shut off, total head pressure.
- E. Combustion Equipment:
1. Boiler manufacturer.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Model number.
 4. Serial number.
 5. Water flow, design and actual.
 6. Heat output, design and actual entering and leaving water temperatures with calculated heat output.
- F. Air Cooled Condensers:
1. Identification/number.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Manufacturer.
 4. Model number.
 5. Serial number.
 6. Entering DB air temperature, design and actual.
 7. Leaving DB air temperature, design and actual.
 8. Number of compressors, refrigerant suction/discharge pressures.
 9. Refrigerant type.
- G. Chillers:
1. Identification/number.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Manufacturer.
 4. Capacity.
 5. Model number.
 6. Serial number.
 7. Evaporator entering water temperature, design and actual.
 8. Evaporator leaving water temperature, design and actual.
 9. Evaporator pressure drop, design and actual.
 10. Evaporator water flow rate, design and actual.
 11. Condenser entering water temperature.
 12. Condenser pressure drop, design and actual.
 13. Condenser water flow rate, design and actual.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



14. Number of compressors, refrigerant suction/discharge pressures.
 15. Refrigerant type.
- H. Cooling Tower:
1. Tower identification/number.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Manufacturer.
 4. Model number.
 5. Serial number.
 6. Rated capacity.
 7. Entering air WB temperature, specified and actual.
 8. Leaving air WB temperature, specified and actual.
 9. Ambient air DB temperature.
 10. Condenser water entering temperature.
 11. Condenser water leaving temperature.
 12. Condenser water flow rate.
 13. Fan RPM.
- I. Heat Exchangers:
1. Identification/number.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Service.
 4. Manufacturer.
 5. Model number.
 6. Serial number.
 7. Primary water entering temperature, design and actual.
 8. Primary water leaving temperature, design and actual.
 9. Primary water flow, design and actual.
 10. Primary water pressure drop, design and actual.
 11. Secondary water leaving temperature, design and actual.
 12. Secondary water flow, design and actual.
 13. Secondary water pressure drop, design and actual.
- J. Cooling Coils:
1. Identification/number.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Service.
 4. Manufacturer.
 5. Water flow, design and actual.
- K. Heating Coils and ATU Reheat Coils:
1. Identification/number.
 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 3. Service.
 4. Manufacturer.
 5. Water flow, design and actual.
- L. Electric Duct Heaters and ATU Reheat :
1. Manufacturer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Identification/number.
 3. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 4. Model number.
 5. Design kW.
 6. Number of stages, control type.
 7. Phase, voltage, amperage.
 8. Test voltage (each phase).
 9. Test amperage (each phase).
 10. Air flow, specified and actual.
 11. Temperature rise, specified and actual.
- M. Air Moving Equipment:
1. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 2. Manufacturer.
 3. Model number.
 4. Serial number.
 5. Arrangement/Class/Discharge.
 6. Air flow, specified and actual.
 7. Return air flow, specified and actual.
 8. Outside air flow, specified and actual.
 9. Static pressure profile across each component.
 10. Total static pressure (total external), specified and actual.
 11. Inlet pressure.
 12. Discharge pressure.
 13. Filter type, MERV rating, sizes and quantity.
 14. Filter differential pressure.
- N. Return Air/Outside Air:
1. Identification/location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 2. Design air flow.
 3. Actual air flow.
 4. Design return air flow.
 5. Actual return air flow.
 6. Design outside air flow.
 7. Actual outside air flow.
 8. Return air temperature.
 9. Outside air temperature.
 10. Mixed air temperature.
 11. Design outside/return air ratio.
 12. Actual outside/return air ratio.
- O. Exhaust/Relief Air Fans:
1. Identification/location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 2. Manufacturer.
 3. Model number.
 4. Serial number.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



5. Air flow, specified and actual, equipment data sheet shall show inlet totals and a fan flow rate measured nearest possible to fan to quantify leakage rate for exhaust fans.
 6. Total static pressure (total external), specified and actual.
 7. Inlet pressure.
 8. Discharge pressure.
 9. Fan RPM.
- P. Duct Traverses:
1. System zone/branch.
 2. Duct size.
 3. Area.
 4. Design air flow.
 5. Test velocity.
 6. Test air flow.
 7. Duct static pressure.
 8. Air temperature.
 9. Air correction factor, if required, by necessary device..
- Q. Duct Leak Tests:
1. Description of ductwork under test.
 2. Duct design operating pressure.
 3. Duct design test static pressure.
 4. Duct capacity, air flow.
 5. Maximum allowable leakage duct capacity times leak factor.
 6. Test apparatus:
 - a. Blower.
 - b. Orifice, tube size.
 - c. Orifice size.
 - d. Calibrated.
 7. Test static pressure.
 8. Test orifice differential pressure.
 9. Leakage.
- R. Air Flow Measuring Stations:
1. Identification/location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 2. System.
 3. Size.
 4. Area.
 5. Calibration factor, and method used for calibration.
 6. Design air flow.
 7. Test velocity.
 8. Test air flow.
- S. Room Pressure Monitors:
1. Identification/location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 2. Manufacturer.
 3. Model number.
 4. Design differential pressure/setpoint.
 5. Actual differential pressure.
 6. Supply air CFM.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 7. Return/exhaust air CFM.
- T. Air Terminal Unit Data:
 - 1. Manufacturer.
 - 2. Type, constant, variable, cooling only, dual duct.
 - 3. Identification/number.
 - 4. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 - 5. Inlet size.
 - 6. K-factor
 - 7. Minimum design air flow.
 - 8. Maximum cooling design air flow.
 - 9. Maximum cooling actual air flow.
 - 10. Maximum heating design air flow.
 - 11. Maximum heating actual air flow.
 - 12. Unoccupied design air flow.
 - 13. Unoccupied actual air flow.
- U. Air Distribution Tests:
 - 1. Air terminal number
 - a. This number is to correlate to a set of 11"x17" mechanical plans with the numbers clearly identified, and in which it is easy to see supply, return, and exhaust air ducts, see section above.
 - 2. Room number/location, the room numbers shown on the report are to correlate to a set of 11"x17" mechanical plans with the numbers clearly identified, and in which it is easy to see supply, return, and exhaust air inlets and outlets.
 - 3. Terminal type.
 - 4. Terminal size.
 - 5. Area factor, when used for balancing, all units for area shall be clearly identified and shall all be recorded on the report using the same units. If different units are used on the report, then the report will be rejected, and the balance report will be changed such that only one unit of area is shown on the reports.
 - 6. Design air flow.
 - 7. Test (final) air flow.
 - 8. Percent of design air flow.
- V. Water Flow Measuring Stations:
 - 1. Identification/number.
 - 2. Location, clearly identified on the balance reports, and clearly shown on a set of 11"x17" mechanical plans.
 - 3. Size.
 - 4. Manufacturer.
 - 5. Model number.
 - 6. Serial number.
 - 7. Design flow rate.
 - 8. Design pressure drop.
 - 9. Actual/final pressure drop.
 - 10. Actual/final flow rate.
 - 11. Calibration factor, and method used for calibration.
- W. Water Flow Balancing Valves:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Identification/location, the numbers on the report are to correlate to a set of 11"x17" mechanical plans with the numbers clearly identified, and in which it is easy to see supply and return; and the difference between chilled water and heating water
 2. Manufacturer.
 3. Design flow rate.
 4. Actual inlet and outlet pressure.
 5. Actual flow rate (GPM), all pressure dependent valves with fixed or changing orifice type valves shall have recorded flow rates. For systems that have automatic or pressure independent control valves, the actual flows shall not be recorded unless there is a measuring device in the piping. Pressure readings that show the valve has the required pressures to function is all that is required. For valves that have flow setpoints that need to be set, the reports shall clearly show the final setpoints on these types of valves.
 6. Setpoint identification/number.
- X. Balancing data sheets shall indicate the required and actual CFM of all supply, return and exhaust outlets or inlets, and be totaled and summarized by systems.
- Y. Hydronic balancing data sheets shall list required temperature or pressure differentials used for balancing coils, radiators, condensers, etc. Sheets shall show in comparison final as-balanced versus design values.
- Z. Include a reduced set of contract drawings with inlets, and outlets marked for easy identification using the same identification method used in the data sheets.
- AA. Note any abnormal or notable conditions not covered in the above.
- AB. Keep a daily log of all work performed, with a list of work scheduled for each day and the workers on the job.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 230713
DUCT INSULATION**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Duct insulation.
- B. Duct liner.
- C. Insulation jackets.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 099113 - Exterior Painting: Painting insulation jackets.
- C. Section 099123 - Interior Painting: Painting insulation jackets.
- D. Section 220553 - Identification for Plumbing Piping and Equipment.
- E. Section 230553 - Identification for HVAC Piping and Equipment.
- F. Section 233100 - HVAC Ducts and Casings: Glass fiber ducts.

1.03 REFERENCE STANDARDS

- A. ASTM B209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2014.
- B. ASTM B209M - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric); 2014.
- C. ASTM C177 - Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus; 2013.
- D. ASTM C518 - Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2017.
- E. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2016.
- F. ASTM C553 - Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications; 2013.
- G. ASTM C612 - Standard Specification for Mineral Fiber Block and Board Thermal Insulation; 2014.
- H. ASTM C795 - Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel; 2008 (Reapproved 2013).
- I. ASTM C916 - Standard Specification for Adhesives for Duct Thermal Insulation; 2014.
- J. ASTM C1071 - Standard Specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material); 2016.
- K. ASTM C1290 - Standard Specification for Flexible Fibrous Glass Blanket Insulation Used to Externally Insulate HVAC Ducts; 2016.
- L. ASTM C1410 - Standard Specification for Cellular Melamine Thermal and Sound-Absorbing Insulation; 2014.
- M. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- N. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2016.
- O. ASTM G21 - Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi; 2015.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- P. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005 (Rev. 2009).
- Q. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.
- C. Manufacturer's Instructions: Indicate installation procedures necessary to ensure acceptable workmanship and that installation standards will be achieved.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products of the type specified in this section with not less than three years of documented experience.
- B. Applicator Qualifications: Company specializing in performing the type of work specified in this section, with minimum three years of experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Accept materials on site in original factory packaging, labelled with manufacturer's identification, including product density and thickness.
- B. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original wrapping.
- C. Materials not protected will be rejected and replaced at installers expense.

1.07 FIELD CONDITIONS

- A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements.
- B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

2.01 REGULATORY REQUIREMENTS

- A. Surface Burning Characteristics: Flame spread index/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84 or UL 723.

2.02 GLASS FIBER, FLEXIBLE

- A. Manufacturer:
 - 1. CertainTeed Corporation; _____: www.certainteed.com/#sle.
 - 2. Johns Manville; _____
 - 3. Knauf Insulation;
 - 4. Owens Corning Corporation; _____
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: ASTM C553; flexible, noncombustible blanket.
 - 1. 'K' value: 0.36 at 75 degrees F, when tested in accordance with ASTM C518.
 - 2. Maximum Service Temperature: 250 degrees F.
 - 3. Maximum Water Vapor Absorption: 5.0 percent by weight.
- C. Vapor Barrier Jacket:
 - 1. 0.0032 inch vinyl or Kraft paper with glass fiber yarn and bonded to aluminum film.
 - 2. Moisture Vapor Permeability: 0.02 perm inch, when tested in accordance with ASTM E96/E96M.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Secure with staples, bands, wires, pressure sensitive tape, anchors, corner angles and similar accessories as recommended by insulation manufacturer.
- D. Vapor Barrier Tape:
1. Vinyl or kraft paper reinforced with glass fiber yarn and bonded to aluminized film, with pressure sensitive rubber based adhesive.
- E. Outdoor Vapor Barrier Mastic:
1. Manufacturers:
 - a. Carlisle HVAC Products; _____
 - b. Childers; _____
 - c. Henry Co.;
 - d. W. R. Meadows;
 - e. Substitutions: See Section 016000 - Product Requirements.
 2. Single component, liquid applied, elastomeric polymer based vapor barrier and insulation adhesive.
- F. Tie Wire: Stainless steel, 16 gage, 0.0508 inch diameter.

2.03 GLASS FIBER, RIGID

- A. Manufacturer:
1. CertainTeed Corporation; _____: www.certainteed.com/#sle.
 2. Johns Manville; _____
 3. Knauf Insulation; _____
 4. Owens Corning Corporation;
 5. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: ASTM C612; rigid, noncombustible blanket.
1. 'K' Value: 0.24 at 75 degrees F, when tested in accordance with ASTM C518.
 2. Maximum Service Temperature: 250 degrees F.
 3. Maximum Water Vapor Absorption: 5.0 percent.
 4. Maximum Density: 10 lb./cu ft.
- C. Indoor Vapor Barrier Jacket:
1. Vinyl or Kraft paper with glass fiber yarn and bonded to aluminized film.
 2. Moisture Vapor Permeability: 0.02 perm inch, when tested in accordance with ASTM E96/E96M.
 3. Secure with pressure sensitive tape.
- D. Vapor Barrier Tape:
1. Vinyl or Kraft paper reinforced with glass fiber yarn and bonded to aluminized film, with pressure sensitive rubber based adhesive.
 2. Vapor barrier tape shall be compatible with vapor barrier.
- E. Indoor Vapor Barrier Finish:
1. Vinyl emulsion type acrylic, compatible with insulation, white color.
- F. Exterior Vapor Barrier Finish:
1. Manufacturers:
 - a. Carlisle HVAC Products, Hard cast;
 - b. Childers;
 - c. Henry Co.;
 - d. W. R. Meadows;
 2. Single component, liquid applied, elastomeric polymer based vapor barrier and insulation adhesive.
- G. Insulation Fastening:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Stick pins: Galvanized steel, welded with integral or press-on head or mastic applied.
2. Tie Wire: Stainless steel, 16 gage, 0.0508 inch diameter.

2.04 JACKETS

- A. Aluminum Jacket: ASTM B209 (ASTM B209M). Use only where specified on drawings.
1. Thickness: 0.016 inch sheet.
 2. Finish: Smooth.
 3. Joining: Longitudinal slip joints and 2 inch laps.
 4. Fittings: 0.016 inch thick die shaped fitting covers with factory attached protective liner.
 5. Metal Jacket Bands: 3/8 inch wide; 0.015 inch thick aluminum.

2.05 DUCT LINER

- A. Manufacturers:
1. CertainTeed Corporation; _____: www.certainteed.com/#sle.
 2. Johns Manville; _____
 3. Knauf Insulation; _____
 4. Owens Corning Corporation;
 5. Substitutions: See Section 016000 - Product Requirements.
- B. Glass Fiber Insulation: Non-corrosive, incombustible glass fiber complying with ASTM C1071; flexible blanket; impregnated surface and edges coated with poly vinyl acetate polymer, acrylic polymer, or black composite.
1. Fungal Resistance: No growth when tested according to ASTM G21.
 2. Apparent Thermal Conductivity: Maximum of 0.31 at 75 degrees F.
 3. Service Temperature: Up to 250 degrees F.
 4. Rated Velocity on Coated Air Side for Air Erosion: 5,000 fpm, minimum.
 5. Minimum Noise Reduction Coefficients:
 - a. 1/2 inch Thickness: 0.30.
 - b. 1 inch Thickness: 0.45.
 - c. 1-1/2 inches Thickness: 0.60.
 - d. 2 inch Thickness: 0.70.
- C. Adhesive: Waterproof, fire-retardant type, ASTM C916.
- D. Liner Fasteners: Galvanized steel, welded with integral or press-on head.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that ducts have been tested before applying insulation materials.
- B. Verify that surfaces are clean, foreign material removed, and dry.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install in accordance with NAIMA National Insulation Standards.
- C. Insulated ducts conveying air below ambient temperature:
1. Provide insulation with vapor barrier jackets.
 2. Insulate all unlined ductwork with 1" thick flexible glass fiber insulation, unless otherwise noted on drawings.
 3. Continue insulation through walls, sleeves, hangers, and other duct penetrations.
 4. Insulate entire system including fittings, joints, and flanges. Finish with tape.
- D. Insulated ducts conveying air above ambient temperature:
1. Provide with or without standard vapor barrier jacket.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Insulate all unlined ductwork with 1" thick flexible glass fiber insulation, unless otherwise noted on drawings.
 3. Continue insulation through walls, sleeves, hangers, and other duct penetrations.
 4. Insulate entire system including fittings, joints, and flanges. Finish with tape.
- E. Lined Ductwork:
1. Except as otherwise indicated, omit external insulation on ductwork where internal insulation or sound absorbing linings have been installed.
 2. Line all supply air ductwork mains with 1" thick acoustic lining, unless otherwise noted on drawings.
- F. External Duct Insulation Application:
1. All external ductwork shall have a fluid applied vapor barrier adhesive applied directly to ductwork.
 2. Insulate all ductwork with 2" thick rigid glass fiber insulation.
 3. Secure insulation to ductwork with wires and seal insulation joints with vapor barrier adhesive or tape.
 4. Cover insulated ductwork with aluminum jacket with seams and drain holes located on bottom side of horizontal ductwork.
- G. Duct Liner Application:
1. Adhere insulation with adhesive for 90 percent coverage.
 2. Secure insulation with mechanical liner fasteners. Refer to SMACNA (DCS) for spacing.
 3. Seal and smooth joints. Seal and coat transverse joints.
 4. Seal liner surface penetrations with adhesive.
 5. Duct dimensions indicated are net inside dimensions required for air flow. Increase duct size to allow for insulation thickness.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230719
HVAC PIPING INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Refrigeration piping insulation.
- B. Flexible removable and reusable blanket insulation.
- C. Jackets and accessories.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 099123 - Interior Painting: Painting insulation jacket.
- C. Section 232113 - Hydronic Piping: Placement of hangers and hanger inserts.
- D. Section 232300 - Refrigerant Piping: Placement of inserts.

1.03 REFERENCE STANDARDS

- A. ASTM C195 - Standard Specification for Mineral Fiber Thermal Insulating Cement; 2007 (Reapproved 2013).
- B. ASTM C449 - Standard Specification for Mineral Fiber Hydraulic-Setting Thermal Insulating and Finishing Cement; 2007 (Reapproved 2013).
- C. ASTM C518 - Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2017.
- D. ASTM C533 - Standard Specification for Calcium Silicate Block and Pipe Thermal Insulation; 2013.
- E. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2016.
- F. ASTM C547 - Standard Specification for Mineral Fiber Pipe Insulation; 2017.
- G. ASTM C552 - Standard Specification for Cellular Glass Thermal Insulation; 2016a.
- H. ASTM C553 - Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications; 2013.
- I. ASTM C578 - Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation; 2016.
- J. ASTM C585 - Standard Practice for Inner and Outer Diameters of Thermal Insulation for Nominal Sizes of Pipe and Tubing; 2010 (Reapproved 2016).
- K. ASTM C591 - Standard Specification for Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation; 2017.
- L. ASTM C610 - Standard Specification for Molded Expanded Perlite Block and Pipe Thermal Insulation; 2016.
- M. ASTM C795 - Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel; 2008 (Reapproved 2013).
- N. ASTM C1410 - Standard Specification for Cellular Melamine Thermal and Sound-Absorbing Insulation; 2014.
- O. ASTM C1695 - Standard Specification for Fabrication of Flexible Removable and Reusable Blanket Insulation for Hot Service; 2010 (Reapproved 2015).
- P. ASTM D412 - Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers-- Tension; 2016.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- Q. ASTM D570 - Standard Test Method for Water Absorption of Plastics; 1998 (Reapproved 2010).
- R. ASTM D1056 - Standard Specification for Flexible Cellular Materials--Sponge or Expanded Rubber; 2014.
- S. ASTM D2842 - Standard Test Method for Water Absorption of Rigid Cellular Plastics; 2012.
- T. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- U. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2016.
- V. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.
- C. Manufacturer's Instructions: Indicate installation procedures that ensure acceptable workmanship and installation standards will be achieved.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with not less than three years of documented experience.
- B. Applicator Qualifications: Company specializing in performing the type of work specified in this section with minimum three years of experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Accept materials on site, labeled with manufacturer's identification, product density, and thickness.
- B. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original wrapping.
- C. Materials not protected will be rejected and replaced at installers expense.

1.07 FIELD CONDITIONS

- A. Maintain ambient conditions required by manufacturers of each product.
- B. Maintain temperature before, during, and after installation for minimum of 24 hours.

PART 2 PRODUCTS

2.01 REGULATORY REQUIREMENTS

- A. Surface Burning Characteristics: Flame spread index/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84 or UL 723.
- B. Insulation shall have a 'K' value that meets the minimum requirements of the latest International Energy Conservation Code (IECC).

2.02 GLASS FIBER

- A. Manufacturers:
 - 1. CertainTeed Corporation
 - 2. Johns Manville Corporation
 - 3. Knauf Insulation;
 - 4. Owens Corning Corporation;
 - 5. Armstrong World Industries;
 - 6. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: ASTM C547 and ASTM C795; rigid molded, noncombustible.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. 'K' Value: ASTM C177, 0.24 at 75 degrees F.
 2. Maximum Service Temperature: 850 degrees F.
 3. Maximum Moisture Absorption: 0.2 percent by volume.
- C. Insulation: ASTM C547 and ASTM C795; rigid molded, noncombustible, with wicking material to transport condensed water to the outside of the system for evaporation to the atmosphere.
1. 'K' Value: ASTM C177, 0.23 at 75 degrees F.
 2. Maximum Service Temperature: 220 degrees F.
 3. Maximum Moisture Absorption: 0.2 percent by volume.
- D. Insulation: ASTM C547 and ASTM C795; semi-rigid, noncombustible, end grain adhered to jacket.
1. 'K' Value: ASTM C177, 0.24 at 75 degrees F.
 2. Maximum Service Temperature: 650 degrees F.
 3. Maximum Moisture Absorption: 0.2 percent by volume.
- E. Vapor Barrier Jacket: White kraft paper with glass fiber yarn, bonded to aluminized film; moisture vapor transmission when tested in accordance with ASTM E96/E96M of 0.02 perm-inches.
- F. Tie Wire: 0.048 inch stainless steel with twisted ends on maximum 12 inch centers.
- G. Vapor Barrier Lap Adhesive: Compatible with insulation.
- H. Insulating Cement/Mastic: ASTM C195; hydraulic setting on mineral wool.
- I. Fibrous Glass Fabric:
1. Cloth: Untreated; 9 oz/sq yd weight.
 2. Blanket: 1.0 lb./cu ft density.
 3. Weave: 5 by 5.
- J. Indoor Vapor Barrier Finish:
1. Cloth: Untreated; 9 oz/sq yd weight.
 2. Vinyl emulsion type acrylic, compatible with insulation, black or white color.
- K. Outdoor Vapor Barrier Mastic: Vinyl emulsion type acrylic or mastic, compatible with insulation, black color.
- L. Outdoor Breather Mastic: Vinyl emulsion type acrylic or mastic, compatible with insulation, black color.
- M. Insulating Cement: ASTM C449.

2.03 FLEXIBLE ELASTOMERIC CELLULAR INSULATION

- A. Manufacturers:
1. Aeroflex USA, Inc; Aerocel Stay-Seal with Protape (SSPT):
 2. Armacell LLC; AP Armaflex:
 3. K-Flex USA LLC; K-Flex Titan:
 4. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: Preformed flexible elastomeric cellular rubber insulation complying with ASTM C534/C534M Grade 1; use molded tubular material wherever possible.
1. Minimum Service Temperature: Minus 40 degrees F.
 2. Maximum Service Temperature: 180 degrees F.
 3. Connection: Waterproof vapor barrier adhesive.
- C. Elastomeric Foam Adhesive: Air dried, contact adhesive, compatible with insulation.

2.04 JACKETS

- A. PVC Plastic.
1. Jacket: One piece molded type fitting covers and sheet material, off-white color.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- a. Minimum Service Temperature: 0 degrees F.
 - b. Maximum Service Temperature: 150 degrees F.
 - c. Moisture Vapor Permeability: 0.002 perm inch, maximum, when tested in accordance with ASTM E96/E96M.
 - d. Thickness: 10 mil.
 - e. Connections: Brush on welding adhesive.
2. Covering Adhesive Mastic: Compatible with insulation.
- B. ABS Plastic:
1. Jacket: One piece molded type fitting covers and sheet material, off-white color.
 - a. Minimum Service Temperature: Minus 40 degrees F.
 - b. Maximum Service Temperature: 180 degrees F.
 - c. Moisture Vapor Permeability: 0.012 perm inch, when tested in accordance with ASTM E96/E96M.
 - d. Thickness: 30 mil.
 - e. Connections: Brush on welding adhesive.
- C. Aluminum Jacket: ASTM B209 (ASTM B209M) formed aluminum sheet.
1. Thickness: 0.016 inch sheet.
 2. Finish: Embossed.
 3. Joining: Longitudinal slip joints and 2 inch laps.
 4. Fittings: 0.016 inch thick die shaped fitting covers with factory attached protective liner.
 5. Metal Jacket Bands: 3/8 inch wide; 0.015 inch thick aluminum.
- D. Stainless Steel Jacket: ASTM A666, Type 304 stainless steel.
1. Thickness: 0.010 inch.
 2. Finish: Smooth.
 3. Metal Jacket Bands: 3/8 inch wide; 0.010 inch thick stainless steel.

2.05 ACCESSORIES

- A. General Requirements:
1. Provide required accessories in accordance with and subject to the recommendations of the insulation manufacturer.
 2. Furnish compatible materials which do not contribute to corrosion, soften, or otherwise attack surfaces to which applied, in either the wet or dry state.
 3. Comply with ASTM C795 requirements for materials to be used on stainless steel surfaces.
 4. Supply materials that are asbestos free.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that piping has been tested before applying insulation materials.
- B. Verify that surfaces are clean and dry, with foreign material removed.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install in accordance with NAIMA National Insulation Standards.
- C. Exposed Piping: Locate insulation and cover seams in least visible locations.
- D. Insulated pipes conveying fluids below ambient temperature; insulate entire system including fittings, valves, unions, flanges, strainers, flexible connections, in-line pump bodies, and expansion joints.
- E. Orient all insulation and jacketing seams on bottom of pipe.
- F. Glass fiber insulated pipes conveying fluids below ambient temperature:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. Provide vapor barrier jackets, factory-applied or field-applied; secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive. Secure with outward clinch expanding staples and vapor barrier mastic.
 2. Insulate fittings, joints, and valves with molded insulation of like material and thickness as adjacent pipe. Finish with glass cloth and vapor barrier adhesive or PVC fitting covers.
- G. For hot piping conveying fluids 140 degrees F or less, do not insulate flanges and unions at equipment, but bevel and seal ends of insulation.
- H. For hot piping conveying fluids over 140 degrees F, insulate flanges and unions at equipment.
- I. For fan coil unit and VAV reheat coil piping, conveying fluids over 140 degrees F, do not insulate (valve train) shut-off valves, strainers, control valve, air bleeds, circuit setters, and unions at equipment. Insulate pipe from last fitting to coil if 12" long or greater. Bevel and seal ends of insulation.
- J. Glass fiber insulated pipes conveying fluids above ambient temperature.
1. Provide standard jackets, with or without vapor barrier, factory-applied or field-applied. Secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive. Secure with outward clinch expanding staples.
 2. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe. Finish with glass cloth and adhesive or PVC fitting covers.
- K. Inserts and Shields:
1. Application: Piping 1-1/2 inches diameter or larger.
 2. Shields: Galvanized steel between pipe hangers or pipe hanger rolls and inserts.
 3. Insert location: Between support shield and piping and under the finish jacket.
 4. Insert Configuration: Minimum 6 inches long, of same thickness and contour as adjoining insulation; may be factory fabricated.
 5. Insert Material: Hydrous calcium silicate insulation, for 2-1/2" pipe or larger, or other heavy density insulating material suitable for the planned temperature range.
- L. Continue insulation through walls, sleeves, pipe hangers, and other pipe penetrations. Finish at supports, protrusions, and interruptions. At fire separations, refer to Section 078400.
- M. Exterior Applications: Provide vapor barrier jacket. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe, and finish with glass mesh reinforced vapor barrier cement. Cover with aluminum jacket with seams located on bottom side of horizontal piping. Provide two coats of UV resistant finish for flexible elastomeric cellular insulation without jacketing.
- N. Heat Traced Piping: Insulate fittings, joints, and valves with insulation of like material, thickness, and finish as adjoining pipe. Size insulation large enough to enclose pipe and heat tracer. Cover with aluminum jacket with seams located on bottom side of horizontal piping.

3.03 PIPING INSULATION SCHEDULE

- A. Condensate and Equipment Drain Water below 60 Deg F:
1. All Pipe Sizes: Insulation shall be one of the following:
 - a. Flexible elastomeric:
 - 1) 1/2 inch thick.
 - b. Glass fiber:
 - 1) 1/2 inch thick.
- B. Chilled Water, above 40 Deg F:
1. All pipe sizes: Insulation shall be one of the following:
 - a. Flexible elastomeric:
 - 1) 1 1/2 inch thick.
 - b. Glass fiber:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 1) 1 1/2 inch thick.
- C. Heating Hot Water Supply and Return, 200 Deg F and below:
 - 1. 1 1/2 inch and smaller:
 - a. Glass fiber:
 - 1) 1 1/2 inch thick.
 - 2. 2 inch and larger:
 - a. Glass fiber:
 - 1) 2 inch thick.
- D. Refrigerant Suction and Hot Gas Piping:
 - 1. All pipe sizes:
 - a. Flexible elastomeric:
 - 1) 1 inch thick.

3.04 INDOOR FIELD APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory applied jacket, install the field applied jacket over the factory applied jacket
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping:
 - 1. PVC:
 - a. White: 30 mils thick.

3.05 OUTDOOR FIELD APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory applied jacket, install the field applied jacket over the factory applied jacket
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, exposed:
 - 1. Aluminum, Embossed:
 - a. 0.016 inch thick.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230800
COMMISSIONING OF HVAC

PART 1 GENERAL

1.01 SUMMARY

- A. See Section 019113 - General Commissioning Requirements for overall objectives; comply with the requirements of Section 019113.
- B. This section covers the Contractor's responsibilities for commissioning; each subcontractor or installer responsible for the installation of a particular system or equipment item to be commissioned is responsible for the commissioning activities relating to that system or equipment item.
- C. The Commissioning Authority (CxA) will be employed by the owner and directs and coordinates all commissioning activities and provides Prefunctional Checklists and Functional Test Procedures for Contractor's use.
- D. The entire HVAC system is to be commissioned, including commissioning activities for the following specific items:
 - 1. Control system.
 - 2. Major and minor equipment items.
 - 3. Piping systems and equipment.
 - 4. Ductwork and accessories.
 - 5. Terminal units.
 - 6. Sound control devices.
 - 7. Vibration control devices.
 - 8. Variable frequency drives.
 - 9. Special Ventilation:
 - a. Fume hoods.
 - b. Laboratory pressurization.
 - c. Specialty fans.
 - d. Egress pressurization.
 - 10. Other equipment and systems explicitly identified elsewhere in Contract Documents as requiring commissioning.
- E. The Prefunctional Checklist and Functional Test requirements specified in this section are in addition to, not a substitute for, inspection or testing specified in other sections.

1.02 RELATED REQUIREMENTS

- A. Section 017800 - Closeout Submittals: Scope and procedures for operation and maintenance manuals and project record documents.
- B. Section 017900 - Demonstration and Training: Scope and procedures for Owner personnel training.
- C. Section 019113 - General Commissioning Requirements: Commissioning requirements that apply to all types of work.
- D. Section 230923 - Direct-Digital Control System for HVAC.
- E. Section 230913 - Instruments and Control Elements.
- F. Section 230993 - Sequence of Operations for HVAC Controls.
- G. Section 230593 - Testing, Adjusting, and Balancing for HVAC.

1.03 REFERENCE STANDARDS

- A. ASHRAE Guideline 1.1 - The HVAC&R Technical Requirements for the Commissioning Process; 2007 (Errata 2012).

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.04 SUBMITTALS

- A. Updated Submittals: Keep the Commissioning Authority informed of all changes to control system documentation made during programming and setup; revise and resubmit when substantial changes are made.
- B. Prefunctional Checklists and Functional Test Procedures for Control System: Detailed written plan indicating the procedures to be followed to test, checkout and adjust the control system prior to full system Functional Testing; include at least the following for each type of equipment controlled:
 - 1. System name.
 - 2. List of devices.
 - 3. Step-by-step procedures for testing each controller after installation, including:
 - a. Process of verifying proper hardware and wiring installation.
 - b. Process of downloading programs to local controllers and verifying that they are addressed correctly.
 - c. Process of performing operational checks of each controlled component.
 - d. Plan and process for calibrating valve and damper actuators and all sensors.
 - e. Description of the expected field adjustments for transmitters, controllers and control actuators should control responses fall outside of expected values.
 - 4. Copy of proposed log and field checkout sheets to be used to document the process; include space for initial and final read values during calibration of each point and space to specifically indicate when a sensor or controller has “passed” and is operating within the contract parameters.
 - 5. Description of the instrumentation required for testing.
 - 6. Indicate what tests on what systems should be completed prior to TAB using the control system for TAB work. Coordinate with the Commissioning Authority and TAB contractor for this determination.
- C. Startup Reports, Prefunctional Checklists, and Trend Logs: Submit for approval of Commissioning Authority.
- D. HVAC Control System O&M Manual Requirements. In addition to documentation specified elsewhere, compile and organize at minimum the following data on the control system:
 - 1. Specific step-by-step instructions on how to perform and apply all functions, features, modes, etc. mentioned in the controls training sections of this specification and other features of this system. Provide an index and clear table of contents. Include the detailed technical manual for programming and customizing control loops and algorithms.
 - 2. Full as-built set of control drawings.
 - 3. Full as-built sequence of operations for each piece of equipment.
 - 4. Full points list; in addition to the information on the original points list submittal, include a listing of all rooms with the following information for each room:
 - a. Floor.
 - b. Room number.
 - c. Room name.
 - d. Air handler unit ID.
 - e. Reference drawing number.
 - f. Air terminal unit tag ID.
 - g. Heating and/or cooling valve tag ID.
 - h. Minimum air flow rate.
 - i. Maximum air flow rate.
 - 5. Full print out of all schedules and set points after testing and acceptance of the system.
 - 6. Full as-built print out of software program.
 - 7. Electronic copy on disk of the entire program for this facility.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



8. Marking of all system sensors and thermostats on the as-built floor plan and HVAC drawings with their control system designations.
 9. Maintenance instructions, including sensor calibration requirements and methods by sensor type, etc.
 10. Control equipment component submittals, parts lists, etc.
 11. Warranty requirements.
 12. Copies of all checkout tests and calibrations performed by the Contractor (not commissioning tests).
 13. Organize and subdivide the manual with permanently labeled tabs for each of the following data in the given order:
 - a. Sequences of operation.
 - b. Control drawings.
 - c. Points lists.
 - d. Controller and/or module data.
 - e. Thermostats and timers.
 - f. Sensors and DP switches.
 - g. Valves and valve actuators.
 - h. Dampers and damper actuators.
 - i. Program setups (software program printouts).
- E. Project Record Documents: See Section 017800 for additional requirements.
1. Submit updated version of control system documentation, for inclusion with operation and maintenance data.
 2. Show actual locations of all static and differential pressure sensors (air, water and building pressure) and air-flow stations on project record drawings.
- F. Training Plan: In addition to requirements specified in Section 017900, include:
1. Follow the recommendations of ASHRAE Guideline 1.1.
 2. Control system manufacturer's recommended training.
 3. Demonstration and instruction on function and overrides of any local packaged controls not controlled by the HVAC control system.
- G. Training Manuals: See Section 017900 for additional requirements.
1. Provide a USB drive with one electronic copy of the controls training manuals in a separate manual from the O&M manuals.

PART 2 PRODUCTS

2.01 TEST EQUIPMENT

- A. CxA shall provide all standard testing equipment required to verify startup and initial checkout and required functional performance testing; unless otherwise noted such testing equipment will NOT become the property of Owner.
- B. Equipment-Specific Tools: Where special testing equipment, tools and instruments are specific to a piece of equipment, are only available from the vendor, and are required in order to accomplish startup or Functional Testing, provide such equipment, tools, and instruments as part of the work at no extra cost to Owner; such equipment, tools, and instruments are to become the property of Owner.

PART 3 EXECUTION

3.01 PREPARATION

- A. Cooperate with the Commissioning Authority in development of the Prefunctional Checklists and Functional Test Procedures.
- B. Furnish additional information requested by the Commissioning Authority.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Prepare a preliminary schedule for HVAC pipe and duct system testing, flushing and cleaning, equipment start-up and testing, adjusting, and balancing start and completion for use by the Commissioning Authority; update the schedule as appropriate.
- D. Notify the Owner's representative at least 48 hours before pipe and duct system testing, flushing, cleaning, startup of each piece of equipment and testing, adjusting, and balancing will occur; when commissioning activities not yet performed or not yet scheduled will delay construction, notify at least 48 hours ahead of time and be proactive in seeing that the Owner's representative has the scheduling information needed to efficiently execute the commissioning process.
- E. Upon approval from the Owner's representative, put all HVAC equipment and systems into operation and continue operation during each working day of testing, adjusting, and balancing and commissioning, as required.
 - 1. Include cost of sheaves and belts that may be required for testing, adjusting, and balancing.
- F. Provide test holes in ducts and plenums to allow air measurements and air balancing; close with an approved plug.
- G. Provide temperature and pressure taps in accordance with Contract Documents.

3.02 INSPECTING AND TESTING - GENERAL

- A. CxA shall submit startup plans, startup reports, and Prefunctional Checklists for each item of equipment or other assembly to be commissioned.
- B. CxA shall perform the Functional Tests for each item of equipment or other assembly to be commissioned.
- C. Valve stroke, damper stroke, and VFD speed setup and check (CxA to coordinate this work with the control contractor through Owner's representative. Control contractor to initiate commands and adjustment of devices. CxA to verify.) :
 - 1. For all valve/damper actuator positions and VFD speeds checked, verify the actual position or speed against the control system readout.
 - 2. Set pump/fan to normal operating mode.
 - 3. If valve/damper: command closed; visually verify that valve/damper is closed and adjust output zero signal as required. If VFD: command to minimum speed; visually verify VFD at minimum speed and adjust output zero signal as required.
 - 4. If valve/damper: command open; visually verify that valve/damper is open and adjust output signal as required. If VFD: command to maximum speed if conditions allow (if unable to run equipment at full speed test VFD with load disconnected); visually verify VFD at maximum speed and adjust output signal as required.
 - 5. Command valve/damper or VFD speed to a few intermediate positions. Verify position/signal.
 - 6. If actual valve/damper position or VFD speed does not reasonably correspond, replace actuator, signal conditioner, or add pilot positioner (for pneumatics).
- D. Coil Valve Leak Through Check:
 - 1. Air Handler and FCU Coil Drain Down: Not for 3-way valves.
 - a. Put systems in normal mode.
 - b. If cooling coil valve, remove all call for cooling; if heating coil valve, put system in full cooling.
 - c. Close isolation valve on supply side of coil, open air bleed cap, open drain-down cock and drain water from coil.
 - d. If water does not stop draining, there may be a leak through the control valve.
 - e. Return all to normal when done.
- E. Deficiencies: Correct deficiencies and re-inspect or re-test, as applicable, at no extra cost to Owner.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.03 TAB COORDINATION

- A. TAB: Testing, adjusting, and balancing of HVAC.
- B. Coordinate commissioning schedule with TAB schedule through the Owner's representative.

3.04 CONTROL SYSTEM FUNCTIONAL TESTING

- A. Prefunctional Checklists for control system components will require a signed and dated certification that all system programming is complete as required to accomplish the requirements of Contract Documents and the detailed Sequences of Operation documentation submittal.
- B. Do not start Functional Testing until all controlled components have themselves been successfully Functionally Tested in accordance with Contract Documents.
- C. Using a skilled technician who is familiar with this building, execute the Functional Testing of the control system as required by the Commissioning Authority.
- D. Functional Testing of the control system constitutes demonstration and trend logging of control points monitored by the control system.
 - 1. Perform all trend logging specified in Prefunctional Checklists and Functional Test procedures.
- E. Functionally Test integral or stand-alone controls in conjunction with the Functional Tests of the equipment they are attached to, including any interlocks with other equipment or systems; further testing during control system Functional Test is not required unless specifically indicated below.
- F. Demonstrate the following to the Commissioning Authority during testing of controlled equipment; coordinate with commissioning of equipment.
 - 1. Setpoint changing features and functions.
 - 2. Sensor calibrations.
- G. Demonstrate to the Commissioning Authority:
 - 1. That all specified functions and features are set up, debugged and fully operable.
 - 2. That scheduling features are fully functional and setup, including holidays.
 - 3. That all graphic screens and value readouts are completed.
 - 4. Correct date and time setting in central computer.
 - 5. That field panels read the same time as the central computer; sample 10 percent of field panels; if any of those fail, sample another 10 percent; if any of those fail test all remaining units at no extra cost to Owner.
 - 6. Functionality of field panels using local operator keypads and local ports (plug-ins) using portable computer/keypad; demonstrate 100 percent of panels and 10 percent of ports; if any ports fail, sample another 10 percent; if any of those fail, test all remaining units at no extra cost to Owner.
 - 7. Power failure and battery backup and power-up restart functions.
 - 8. Global commands features.
 - 9. Security and access codes.
 - 10. Occupant over-rides (manual, telephone, key, keypad, etc.).
 - 11. O&M schedules and alarms.
 - 12. Occupancy sensors and controls.
 - 13. All control strategies and sequences not tested during controlled equipment testing.
- H. If the control system, integral control components, or related equipment do not respond to changing conditions and parameters appropriately as expected, as specified and according to acceptable operating practice, under any of the conditions, sequences, or modes tested, correct all systems, equipment, components, and software required at no additional cost to Owner.

3.05 OPERATION AND MAINTENANCE MANUALS

- A. See Section 017800 for additional requirements.
- B. Add design intent documentation furnished by Architect to manuals prior to submission to Owner.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Submit manuals related to items that were commissioned to Commissioning Authority for review; make changes recommended by Commissioning Authority.
- D. Commissioning Authority will add commissioning records to manuals after submission to Owner.

3.06 DEMONSTRATION AND TRAINING

- A. See Section 017900 for additional requirements.
- B. Demonstrate operation and maintenance of HVAC system to Owner's personnel; if during any demonstration, the system fails to perform in accordance with the information included in the O&M manual, stop demonstration, repair or adjust, and repeat demonstration. Demonstrations may be combined with training sessions if appropriate.
- C. These demonstrations are in addition to, and not a substitute for, Prefunctional Checklists and demonstrations to the Commissioning Authority during Functional Testing.
- D. Provide hands-on training of Owner's designated personnel on operation and maintenance of the HVAC system, control system, and all equipment items indicated to be commissioned. Provide durations of training as sufficient or as needed.
- E. TAB Review: Instruct Owner's personnel during and concurrent with TAB, on the following:
 - 1. Review final TAB report, explaining the layout and meanings of each data type.
 - 2. Discuss any outstanding deficient items in control, ducting or design that may affect the proper delivery of air or water.
 - 3. Identify and discuss any terminal units, duct runs, diffusers, coils, fans and pumps that are close to or are not meeting their design capacity.
 - 4. Discuss any temporary settings and steps to finalize them for any areas that are not finished.
 - 5. Other salient information that may be useful for facility operations, relative to TAB.
- F. Provide the services of manufacturer representatives to assist where necessary.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230923
DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. System description.
- B. Operator interface.
- C. Controllers.
- D. Power supplies and line filtering.
- E. System software.
- F. Controller software.
- G. HVAC control programs.
- H. Chiller control programs.

1.02 RELATED REQUIREMENTS

- A. Section 230913 - Instruments and Control Elements.
- B. Section 230993 - Sequence of Operations for HVAC Controls.
- C. Section 260583 - Wiring Connections: Electrical characteristics and wiring connections.
- D. Section 284600 - Fire Detection and Alarm.

1.03 REFERENCE STANDARDS

- A. ASHRAE Std 135 - BACnet - A Data Communication Protocol for Building Automation and Control Networks; 2017.
- B. ASHRAE Std 147 - Reducing the Release of Halogenated Refrigerants From Refrigerating and Air-Conditioning Equipment and Systems; 2013.
- C. Bluetooth CS - Bluetooth Core Specification; 2016, Addendum 2017.
- D. IEEE 802.11 - IEEE Standard for Information Technology--Telecommunications and Information Exchange Between Systems Local and Metropolitan Area Networks--Specific Requirements - Part 11: Wireless LAN Medium Access Control (MAC) and Physical Layer (PHY) Specifications ; 2016, with Errata (2017).
- E. IEEE 802.15.4 - IEEE Standard for Low-Rate Wireless Networks; 2015.
- F. LonMark Interoperability Guide - LonMark Application-Layer Interoperability Guide and LonMark Layer 1-6 Interoperability Guide; Version 3.4; 2005.
- G. LonMark SCPT List - LonMark SCPT Master List; Version 15; 2014.
- H. LonMark SNVT List - LonMark SNVT Master List; Version 15; 2014.
- I. Modbus (PS) - The Modbus Organization Communications Protocol; Latest Update.
- J. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Conduct a preinstallation meeting prior to the start of the work of this section; require attendance by all affected installers.
- B. Mechanical controls and components shall be furnished by the owner and contractor installed.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide data for each system component and software module.
- C. Shop Drawings:
 - 1. Indicate communication trunk cable schematic showing programmable control unit locations and connected unit addressing.
 - 2. List connected data points, including connected control unit and input device.
 - 3. Coordinate graphics design to ensure implementation of current owner's standard.
 - 4. Show system configuration with peripheral devices, batteries, power supplies, diagrams, modems, and interconnections.
 - 5. Indicate description and sequence of operation of operating, user, and application software.
- D. Manufacturer's Instructions: Indicate manufacturer's installation instructions for all manufactured components.
- E. Project Record Documents: Record actual locations of control components, including control units, thermostats, transformers, routing devices, and system sensors.
 - 1. Revise shop drawings to reflect actual installation and operating sequences.
- F. Operation and Maintenance Data:
 - 1. Include interconnection wiring diagrams complete field installed systems with identified and numbered, system components and devices.
 - 2. Include inspection period, cleaning methods, cleaning materials recommended, and calibration tolerances.
- G. Warranty: Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer with a copy returned to the Owner.

1.06 QUALITY ASSURANCE

- A. Perform work in accordance with NFPA 70.
- B. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with minimum three years of documented experience.
- C. Installer Qualifications: Company specializing in performing work of the type specified and with minimum five years of documented experience.
- D. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for purpose specified and indicated.

1.07 WARRANTY

- A. See Section 017800 - Closeout Submittals for additional warranty requirements.
- B. Correct defective Work within a one year period after Substantial Completion.
- C. Provide a minimum one year manufacturer's warranty for all control devices and components after Substantial Completion.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Delta Controls; _____: www.deltacontrols.com
- B. Honeywell International, Inc; _____: www.honeywell.com
- C. Johnson Controls, Inc; _____: www.johnsoncontrols.com
- D. Siemens AG, Building Technologies Division; _____: www.siemens.com
- E. Substitutions: See Section 016000 - Product Requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.02 SYSTEM DESCRIPTION

- A. Automatic temperature control field monitoring and control system using field programmable micro-processor based units with communications to the Owner furnished Building Management System.
- B. Base system on distributed system of fully intelligent, stand-alone controllers, operating in a multi-tasking, multi-user environment network, with central and remote hardware, software, and interconnecting wire and conduit.
- C. Include computer software and hardware, operator input/output devices, control units, local area networks (LAN), routers, sensors, control devices, actuators.
- D. Controls for variable air volume terminals, radiation, reheat coils, unit heaters, fan coils, and the like when directly connected to the control units. Individual terminal unit control is specified in Section 230913.
- E. Provide control systems consisting of thermostats, control valves, dampers and operators, indicating devices, interface equipment and other apparatus and accessories required to operate mechanical systems, and to perform functions specified.
- F. Include installation and calibration, supervision, adjustments, and fine tuning necessary for complete and fully operational system for both heating and cooling seasons.

2.03 CONTROLLERS

A. BUILDING CONTROLLERS

- 1. General:
 - a. Manage global strategies by one or more, independent, standalone, microprocessor based controllers.
 - b. Provide sufficient memory to support controller's operating system, database, and programming requirements. Memory requirements shall not exceed 60% of capacity for application, system, and network controllers at turnover to Owner.
 - c. Share data between networked controllers.
 - d. Controller operating system manages input and output communication signals allowing distributed controllers to share real and virtual object information and allowing for central monitoring and alarms.
 - e. Utilize real-time clock for all time related functions.
 - f. Controller may assume predetermined failure mode and generate alarm notification upon detection of abnormal operation.
 - g. Communication with other network devices to be based on assigned protocol.
- 2. Communication:
 - a. Controller to reside on a BACnet network using ISO 8802-3 (ETHERNET) Data Link/Physical layer protocol. LonWorks, Modbus, or other communication protocols may be use upon approval of Owner.
 - b. Perform routing when connected to a network of custom application and application specific controllers.
 - c. Provide service communication port for connection to a portable operator's terminal or hand held device with compatible protocol.
- 3. External Input-Output (I-O) Data Bus:
 - a. Variable frequency drives (VFD's).
 - b. Specific wired and wireless data integration modules.
 - c. Multiple Input Output (I-O) Module:
 - 1) IAQ: Temperature, humidity, and CO2.
 - 2) Occupancy: Light and thermal sensing with multi-colored LED feedback.
 - 3) Basis of Design: Delta Controls; Sensor Hub: www.deltacontrols.com
- 4. Anticipated Environmental Ambient Conditions:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- a. Outdoors and/or in Wet Ambient Conditions:
 - 1) Mount within waterproof, non-condensing enclosures.
 - 2) Rated for operation at 32 to 130 degrees F.
 - b. Conditioned Space:
 - 1) Mount within dustproof, non-condensing enclosures.
 - 2) Rated for operation at 32 to 130 degrees F.
 - 5. Provisions for Serviceability:
 - a. Diagnostic LEDs for power, communication, and processor.
 - b. Make all wiring connections to field removable, modular terminal strips, or to a termination card connected by a ribbon cable.
 - 6. Memory: In the event of a power loss, maintain all BIOS and programming information for a minimum of 72 hours.
 - 7. Power and Noise Immunity:
 - a. Maintain operation at 90 to 110 percent of nominal voltage rating.
 - b. Perform orderly shutdown below 80 percent of nominal voltage.
 - c. Operation protected against electrical noise of 5 to 120 Hz and from keyed radios up to 5 W. at 3 feet.
- B. CUSTOM APPLICATION CONTROLLERS**
- 1. General:
 - a. Provide sufficient memory to support controller's operating system, database, and programming requirements. Memory requirements shall not exceed 60% of capacity for application, system, and network controllers at turnover to Owner.
 - b. Share data between networked, microprocessor based controllers.
 - c. Controller operating system manages input and output communication signals allowing distributed controllers to share real and virtual object information and allowing for central monitoring and alarms.
 - d. Utilize real-time clock for all time related functions.
 - e. Controller may assume predetermined failure mode and generate alarm notification upon detection of abnormal operation.
 - f. Communication with other network devices to be based on assigned protocol.
 - 2. Communication:
 - a. Controller to reside on a BACnet network using MS/TP Data Link/Physical layer protocol. LonWorks, Modbus, or other communication protocols may be use upon approval of Owner.
 - b. Provide service communication port for connection to a portable operator's terminal or hand held device with compatible protocol.
 - 3. Anticipated Environmental Ambient Conditions:
 - a. Outdoors and/or in Wet Ambient Conditions:
 - 1) Mount within waterproof, non-condensing enclosures.
 - 2) Rated for operation at 32 to 130 degrees F..
 - b. Conditioned Space:
 - 1) Mount within dustproof, non-condensing enclosures.
 - 2) Rated for operation at 32 to 130 degrees F.
 - 4. Provisions for Serviceability:
 - a. Diagnostic LED's for power, communication, and processor.
 - b. Make all wiring connections to field removable, modular terminal strips, or to a termination card connected by a ribbon cable.
 - 5. Memory: In the event of a power loss, maintain all BIOS and programming information for a minimum of 72 hours.
 - 6. Power and Noise Immunity:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- a. Maintain operation at 90 to 110 percent of nominal voltage rating.
- b. Perform orderly shutdown below 80 percent of nominal voltage.
- c. Operation protected against electrical noise of 5 to 120 Hz and from keyed radios up to 5 W. at 3 feet.

C. APPLICATION SPECIFIC CONTROLLERS

- 1. General:
 - a. Not fully user programmable, microprocessor based controllers dedicated to control specific equipment.
 - b. Customized for operation within the confines of equipment served.
 - c. Communication with other network devices to be based on assigned protocol.
- 2. Communication:
 - a. Controller to reside on a BACnet network using MS/TP Data Link/Physical layer protocol. LonWorks, Modbus, or other communication protocols may be use upon approval of Owner.
 - b. Provide service communication port for connection to a portable operator's terminal or hand held device with compatible protocol.
- 3. Anticipated Environmental Ambient Conditions:
 - a. Outdoors and/or in Wet Ambient Conditions:
 - 1) Mount within waterproof, non-condensing enclosures.
 - 2) Rated for operation at 32 to 130 degrees F..
 - b. Conditioned Space:
 - 1) Mount within dustproof, non-condensing enclosures.
 - 2) Rated for operation at 32 to 130 degrees F.
- 4. Provisions for Serviceability:
 - a. Diagnostic LEDs for power, communication, and processor.
 - b. Make all wiring connections to field removable, modular terminal strips, or to a termination card connected by a ribbon cable.
- 5. Memory: In the event of a power loss, maintain all BIOS and programming information for a minimum of 72 hours.
- 6. Power and Noise Immunity:
 - a. Maintain operation at 90 to 110 percent of nominal voltage rating.
 - b. Perform orderly shutdown below 80 percent of nominal voltage.
 - c. Operation protected against electrical noise of 5 to 120 Hz and from keyed radios up to 5 W at 3 feet.
- 7. Smart Sensor (SS):
 - a. Manufacturers:
 - 1) Delta Controls: www.deltacontrols.com
 - 2) JCI.
 - 3) Siemens.
 - 4) Substitutions: See Section 016000 - Product Requirements.
 - b. Features: Built-in display and cool-warm adjust slider or knob as indicated on plans.
 - c. Inputs: 3-universal (configurable).
 - d. Output: 4-externally power binary.
 - e. Occupancy Feedback: Alphanumeric display with changeable background color.
 - f. Temperature Sensor: Platinum, 1,000 ohms RTD element inside insulated thermoplastic enclosure.
 - g. Combined Senor Monitoring Range:
 - 1) Humidity: 0 to 100 percent (non-condensing).
 - 2) CO2 (Carbon Dioxide): 0 to 2,000 ppm.
 - h. Communications Protocol: BACnet MS/TP per ASHRAE Std 135.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- i. Certification: BACnet Testing Laboratory (BTL) certified device listed under the BACnet Smart Sensor (B-SS) device profile in compliance with ASHRAE Std 135.

D. INPUT/OUTPUT INTERFACE

1. Hardwired inputs and outputs tie into the DDC system through building, custom application, or application specific controllers.
2. All Input/Output Points:
 - a. Protect controller from damage resulting from any point short-circuiting or grounding and from voltage up to 24 volts of any duration.
 - b. Provide universal type for building and custom application controllers where input or output is software designated as either binary or analog type with appropriate properties.
3. Binary Inputs:
 - a. Allow monitoring of On/Off signals from remote devices.
 - b. Provide wetting current of 12 mA minimum, compatible with commonly available control devices and protected against the effects of contact bounce and noise.
 - c. Sense dry contact closure with power provided only by the controller.
4. Pulse Accumulation Input Objects: Conform to all requirements of binary input objects and accept up to 10 pulses per second.
5. Analog Inputs:
 - a. Allow for monitoring of low voltage 0 to 10 VDC, 4 to 20 mA current, or resistance signals (thermistor, RTD).
 - b. Compatible with and field configurable to commonly available sensing devices.
6. Binary Outputs:
 - a. Used for On/Off operation or a pulsed low-voltage signal for pulse width modulation control.
 - b. Outputs provided with three position (On/Off/Auto) override switches.
 - c. Status lights for building and custom application controllers to be selectable for normally open or normally closed operation.
7. Analog Outputs:
 - a. Monitoring signal provides a 0 to 10 VDC or a 4 to 20 mA output signal for end device control.
 - b. Provide status lights and two position (AUTO/MANUAL) switch for building and custom application controllers with manually adjustable potentiometer for manual override on building and custom application controllers.
 - c. Drift to not exceed 0.4 percent of range per year.
8. Tri State Outputs:
 - a. Coordinate two binary outputs to control three point, floating type, electronic actuators without feedback.
 - b. Limit the use of three point, floating devices to the following zone and terminal unit control applications:
 - 1) VAV terminal units.
 - 2) Zone dampers.
 - c. Control algorithms run the zone actuator to one end of its stroke once every 24 hours for verification of operator tracking.

2.04 POWER SUPPLIES AND LINE FILTERING

- A. Power Supplies:
 1. Provide UL listed control transformers with Class 2 current limiting type or over-current protection in both primary and secondary circuits for Class 2 service as required by the NEC.
 2. Limit connected loads to 80 percent of rated capacity.
 3. Match DC power supply to current output and voltage requirements.
 4. Unit to be full wave rectifier type with output ripple of 5.0 mV maximum peak to peak.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



5. Provide over-voltage and over-current protection to withstand a 150 percent current overload for 3 seconds minimum without trip-out or failure.
6. Operational Ambient Conditions: 32 to 120 degrees F.
7. Line voltage units UL recognized and CSA approved.
8. Provide ventilation for any enclosed power supplies.

B. Power Line Filtering:

1. Provide 120 volt transient voltage and surge suppression component for each powered control panel.

2.05 SYSTEM SOFTWARE

A. System Features:

1. HTML5 and Java-enabled user interface (UI), and includes a JavaScript data interface library (BajaScript).
2. Supports an unlimited number of users over the internet/intranet with a standard web browser (depending on the host PC resources).
3. Optional enterprise-level data archival using SQL, MySQL or Oracle databases, and HTTP/HTML/XML, CSV or text formats.
4. Audit Trail" of database changes, database storage and backup, global time functions, calendar, central scheduling, control and energy management routines.
5. Sophisticated alarm processing and routing, including email alarm acknowledging.
6. Access to alarms, logs, graphics, schedules and configuration data with a standard web browser.
7. Follows industry best practices for cyber security, with support for features such as strong, hashed passwords, TLS for secure communications and certificate management tools for authentication.
8. A built-in Security Dashboard provides a comprehensive and actionable view of the security posture of your Niagara deployment HTML-based help system that includes comprehensive online system documentation.
9. Supports multiple Niagara-based stations connected to a local Ethernet network or the internet.
10. Provides online/offline use of the Niagara Framework® Workbench graphical configuration tool and a comprehensive Java Object Library.
11. Direct Ethernet-based driver support for most Open IP field bus protocols (see supported drivers document).
12. Utilize tags to quickly navigate to buildings, systems and equipment when diagnosing operational problems or emergencies.
13. FIPS 140-2 Level 1 conformance.
14. Integrate with other applications, such as work order management, analytics, etc.
15. Graphics:
 - a. Graphic package shall conform to Owner's current custom graphics layout.

B. Workstation System Applications:

1. Automatic System Database Save and Restore Functions:
 - a. Current database copy of each Building Controller is automatically stored on hard disk.
 - b. Automatic update occurs upon change in any system panel.
 - c. In the event of database loss in any system panel, the first workstation to detect the loss automatically restores the database for that panel unless disabled by the operator.
2. Manual System Database Save and Restore Functions by Operator with Password Clearance:
 - a. Save database from any system panel.
 - b. Clear a panel database.
 - c. Initiate a download of a specified database to any system panel.
3. Software provided allows system configuration and future changes or additions by operators under proper password protection.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



4. On-line Help:
 - a. Context-sensitive system assists operator in operation and editing.
 - b. Available for all applications.
 - c. Relevant screen data provided for particular screen display.
 - d. Additional help available via hypertext.
5. Security:
 - a. Operator log-on requires user name and password to view, edit, add, or delete data.
 - b. System security selectable for each operator.
 - c. System supervisor sets passwords and security levels for all other operators.
 - d. Operator passwords to restrict functions accessible to viewing and/or changing system applications, editor, and object.
 - e. Automatic, operator log-off results from keyboard or mouse inactivity during user-adjustable, time period.
 - f. All system security data stored in encrypted format.
6. System Diagnostics:
 - a. Operations Automatically Monitored:
 - 1) Workstations.
 - 2) Network connections.
 - 3) Building management panels.
 - 4) Controllers.
 - b. Device failure is annunciated to the operator.
7. Alarm Processing:
 - a. All system objects are configurable to "alarm in" and "alarm out" of normal state.
 - b. Configurable Objects:
 - 1) Alarm limits.
 - 2) Alarm limit differentials.
 - 3) States.
 - 4) Reactions for each object.
8. Alarm Messages:
 - a. Descriptor: English language.
 - b. Recognizable Features:
 - 1) Source.
 - 2) Location.
 - 3) Nature.
9. Configurable Alarm Reactions by Workstation and Time of Day:
 - a. Logging.
 - b. Starting programs.
 - c. Displaying messages.
 - d. Dialing out to remote locations.
 - e. Texting and emailing.
 - f. Providing audible annunciation.
 - g. Displaying specific system graphics.
10. Custom Trend Logs:
 - a. Definable for any data object in the system including interval, start time, and stop time.
 - b. Trend Data:
 - 1) Sampled and stored on the building controller panel.
 - 2) Archivable on hard disk.
 - 3) Retrievable for use in reports, spreadsheets and standard database programs.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 4) Archival on LAN accessible storage media including hard disk, Raid array drive, and virtual cloud environment.
11. Alarm and Event Log:
 - a. View all system alarms and change of states from any system location.
 - b. Events listed chronologically.
 - c. Operator with proper security acknowledges and clears alarms.
 - d. Alarms not cleared by operator are archived to the workstation hard disk.
12. Object, Property Status and Control:
 - a. Provide a method to view, edit if applicable, the status of any object and property in the system.
 - b. Status Available by the Following Methods:
 - 1) Property sheet.
 - 2) Slot sheet.
 - 3) Wire sheet.
 - 4) Relation sheet.
 - 5) Category sheet.
 - 6) Graphics.
 - 7) Custom Programs.
13. Reports and Logs:
 - a. Reporting Package:
 - 1) Allows operator to select, modify, or create reports.
 - 2) Definable as to data content, format, interval, and date.
 - 3) Exportable.
 - b. Real-time logs available by type or status such as alarm, lockout, normal, etc.
 - c. Stored on hard disk and readily accessible by standard software applications, including spreadsheets and word processing.
 - d. Set to be printed on operator command or specific time(s).
14. Reports:
 - a. Standard:
 - 1) Objects with current values.
 - 2) Current alarms not locked out.
 - 3) Disabled and overridden objects, points and SNVTs.
 - 4) Objects in manual or automatic alarm lockout.
 - 5) Objects in alarm lockout currently in alarm.
 - 6) Logs:
 - (a) Alarm History.
 - (b) System messages.
 - (c) System events.
 - (d) Trends.
 - b. Custom:
 - 1) Daily.
 - 2) Weekly.
 - 3) Monthly.
 - 4) Annual.
 - 5) Time and date stamped.
 - 6) Title.
 - 7) Facility name.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.06 CONTROLLER SOFTWARE

- A. All applications should reside and operate in the system controllers where standalone control is necessary and available. System level programming to be used when multiple controllers are needed for sequence implementation.
- B. System Security:
 - 1. User access secured via user passwords and user names.
 - 2. Passwords restrict user to the objects, applications, and system functions as assigned by the system manager.
 - 3. User Log On/Log Off attempts are recorded.
 - 4. Automatic Log Off occurs following the last keystroke after a user defined delay time.
- C. Object or Object Group Scheduling:
 - 1. Weekly Schedules Based on Separate, Daily Schedules:
 - a. Schedule is fully customizable (Boolean, float, enumerated, etc.).
 - b. Start/stop times adjustable for each group object.
 - c. All terminal devices (VAVs, FCUs, UHs, etc.) shall have the capability to be scheduled at Owner's direction.
- D. Provide standard application for equipment coordination and grouping based on function and location to be used for scheduling and other applications.
- E. Alarms:
 - 1. Binary object is set to alarm based on the operator specified state.
 - 2. Analog object to have high/low alarm limits.
 - 3. All alarming is capable of being automatically and manually disabled.
 - 4. Alarm Reporting:
 - a. Operator determines action to be taken for alarm event.
 - b. Alarms to be routed to appropriate email or text message.
- F. Maintenance Management: System can monitor equipment status and generates maintenance messages based upon user-designated run-time limits.
- G. Sequencing: Application software based upon specified sequences of operation in Section 230993.
- H. PID Control Characteristics:
 - 1. Direct or reverse action.
 - 2. Anti-windup.
 - 3. Calculated, time-varying, analog value, positions an output or stages a series of outputs.
 - 4. User selectable controlled variable, set-point, and PID gains.

2.07 HVAC CONTROL PROGRAMS

- A. General:
 - 1. Support Inch-pounds and SI (metric) units of measurement.
 - 2. Identify each HVAC Control system.
- B. Optimal Run Time:
 - 1. Base on occupancy schedules, outside air temperature, seasonal requirements, and interior room mass temperature.
 - 2. Control Summary:
 - a. Heating/cooling mode status.
 - b. Start/Stop times.
 - c. Occupancy and vacancy times.
 - 3. Mass temperature summary:
 - a. Mass temperature point type and ID.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- b. Desired and current mass temperature values.
- 4. HVAC point summary:
 - a. Control system identifier and status.
 - b. Point ID and status.
 - c. Outside air temperature point ID and status.
- C. Supply Air Reset:
 - 1. Monitor heating and cooling loads in building spaces, terminal reheat systems, both hot deck and cold deck temperatures on dual duct and multizone systems, single zone unit discharge temperatures.
 - 2. Adjust discharge temperatures to most energy efficient levels satisfying measured load by:
 - a. Raising cooling temperatures to highest possible value.
 - b. Reducing heating temperatures to lowest possible level.
 - 3. Control summary:
 - a. Supply air reset system status.
 - b. Heating and cooling loop.
 - c. High/low limits.
 - 4. Space load summary:
 - a. HVAC system status.
 - b. Heating/cooling loop status.
 - c. Space load point ID.
 - d. Current space load point value.
 - e. Calculated reset values.
 - f. Fan status point ID and status.
 - g. Control discharge temperature point ID and status.
- D. Enthalpy Switchover:
 - 1. Calculate outside and return air enthalpy using measured temperature and relative humidity; determine energy expended and control outside and return air dampers.
 - 2. Operator commands:
 - a. Define discharge controller parameters.
 - 3. Control summary:
 - a. Enthalpy switchover optimal system status.
 - b. Current return air enthalpy.
 - c. Current outside air enthalpy.
 - d. Enthalpy switchover dead band.
 - e. Status of damper mode switch.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that conditioned power supply is available to the control units and to the operator work station. Verify that field end devices, wiring, and pneumatic tubing is installed prior to installation proceeding.

3.02 INSTALLATION

- A. Install control units and other hardware in position on permanent walls where not subject to excessive vibration.
- B. Install software in control units and in operator work station. Implement all features of programs to specified requirements and appropriate to sequence of operation. Refer to Section 230993.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- C. Provide conduit and electrical wiring in accordance with Section 260583. Electrical material and installation shall be in accordance with appropriate requirements of .

3.03 MANUFACTURER'S FIELD SERVICES

- A. Start and commission systems. Allow sufficient time for start-up and commissioning prior to placing control systems in permanent operation.
- B. Provide basic operator training on sequence of operations, data display, alarm and status descriptors, requesting data, execution of commands and request of logs. Provide training on site.

3.04 DEMONSTRATION AND INSTRUCTIONS

- A. Demonstrate complete operating system to Owner.

3.05 MAINTENANCE

- A. See Section 017000 - Execution and Closeout Requirements, for additional requirements relating to maintenance service.
- B. Provide service and maintenance of energy management and control systems for one year from Date of Substantial Completion.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 230993
SEQUENCE OF OPERATIONS FOR HVAC CONTROLS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. This section defines the manner and method by which controls function. Requirements for each type of control system operation are specified. Equipment, devices, and system components required for control systems are specified in other sections.
- B. Sequence of operation for:
 - 1. Air terminal units.

1.02 RELATED REQUIREMENTS

- A. Section 019113 - General Commissioning Requirements: Commissioning requirements that apply to all types of work.
- B. Section 230913 - Instruments and Control Elements.
- C. Section 230923 - Direct-Digital Control System for HVAC.
- D. Section 262816.13 - Enclosed Circuit Breakers.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Sequence of Operation Documentation: Submit written sequence of operation for entire HVAC system and each piece of equipment.
 - 1. Preface: 1 or 2 paragraph overview narrative of the system describing its purpose, components and function.
 - 2. State each sequence in small segments and give each segment a unique number for referencing in Functional Test procedures; provide a complete description regardless of the completeness and clarity of the sequences specified in Contract Documents.

1.04 GENERAL INFORMATION

- A. Power Failure - Except for the equipment noted below, all supply, return, relief, exhaust, pumps, etc. shall stop on power failure. When power has been restored to normal for a minimum of two minutes, the mechanical equipment shall restart at 30-second intervals (adjustable) in a predetermined sequence.
- B. Schedule - Although specific set points, time periods and reset values are listed in the sequence of operation, all values shall be changeable through the Facility Management System console or portable operators' terminal. The initial occupied/unoccupied schedules shall be as designated by the owners representative.
- C. Point Database - Inputs and outputs required to meet the sequence of operation shall be provided, whether they are listed in the Input/Output schedule or not. All points listed in the Input/Output schedule shall also be provided.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 AIR TERMINAL UNITS

- A. VAV General Items
 - 1. Multiple Zone Control: Where a VAV box serves multiple zones, each zone should have a temperature sensor that can be used to average the temperatures of zones being served. This average temperature will be considered the zone temperature for control purposes. Unoccupied

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- areas (e.g. hallways, bathrooms, closets, etc.) served by the same box may be excluded from the requirement of temperature averaging. The controller shall monitor and report the temperature of each zone served with the value displayed on the graphical floor plan.
2. Analytics: All VAV controllers should employ Atkinson Modular Analytics (AMA) software as a means of performing ongoing VAV controller and equipment automated functional testing. A summary screen shall be included in the graphics package which lists the AMA testing results for all VAVs. This data shall be grouped by areas (e.g. area A, floor 2 South, etc.) where large numbers of VAV exist and not in one large list. Additionally, each VAV controller should incorporate a tagging structure (e.g. room, floor, air handler, transformer, etc.) in the BMS software to allow for higher level filtering and analysis.
 3. Temperature & Pressure Reset: All VAV DDC controllers shall have the ability to be included or excluded from system Discharge Air Temperature and Pressure resets for energy optimization.
 4. Zone Setpoints: The minimum dead band between occupied heating and cooling setpoints shall be 2 degF. The zone Heating and Cooling temperature setpoints as well as setpoint offset ranges should be set according to the following table:

	<u>IOS</u>	<u>OH</u>	<u>OC</u>	<u>OMM</u>	<u>UO</u>	<u>DB</u>	<u>UH</u>	<u>UC</u>
Classroom	72	70	74	68 / 76	+/- 2	4	68	78
Office & General Work	72	71	73	68 / 76	+/- 3	2	68	78
Lab	72	70	74	68 / 76	+/- 2	4	68	78
Lobby, Hall, Public	72	70	74	70 / 74	0	4	68	78
Auditorium	70	69	71	67 / 73	+/- 2	2	67	75
Critical	72	71	73	66 / 78	+/- 5	2	68	78

<u>abbreviation</u>	<u>description</u>
IOS	Initial Occupied Setpoint
OH	Occupied Heat Setpoint
OC	Occupied Cool Setpoint
OMM	Occupied Min / Max
UO	User Offset
DB	Deadband
UH	Unoccupied Heat Setpoint
UC	Unoccupied Cool Setpoint

5. Scheduling: Multiple BMS schedule options should be made available for VAV controllers using BYU's custom template. If a zone is occupied 24/7 it should resynchronize the primary and auxiliary dampers at least once per week.
6. Deadband Mode: When occupied and the zone temperature is between the heating and cooling zone temperature setpoints, or when unoccupied and the zone temperature is between the unoccupied heating and unoccupied cooling zone temperature setpoints, the box shall be in Deadband mode.
7. Cooling Mode: When occupied and the zone temperature is above the occupied zone cooling temperature setpoint, or when unoccupied and the zone temperature is above the unoccupied zone cooling temperature setpoint, the box shall be in Cooling mode.
8. Heating Mode: When occupied and the zone temperature is below the occupied zone heating temperature setpoint, or when unoccupied and the zone temperature is below the unoccupied zone heating temperature setpoint, the box shall be in Heating mode.
9. Start-up: When power is restored the VAV DDC controller should synchronize the primary and auxiliary dampers.
10. Warm-up: Morning Warm Up (MWU) mode should be enabled for the 1st hour of occupancy (adj) when OSA temperature is below 50 degF (adj) and the Return Air Temperature (RAT) of

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- the AHU unit serving the zones is below 67 degF (adj) with a 2 degF (adj) deadband. During MWU the OSA dampers of the AHU should be shut and the AHU should provide as warm of air as possible up to 75 degF (adj). During MWU all VAV boxes which have zone temperature (or average temperature) below the Heating setpoint should modulate the primary damper open to its cooling maximum ventilation setpoint (primary air is warm).
11. Occupancy Sensor: If the BMS system is occupied and a local occupancy sensor is used in conjunction with the BMS scheduling, the DDC controller should go into a Standby mode when motion is not detected. During Standby and in either Deadband or Heating modes, the local DDC controller shall modulate the primary damper to a fully closed position. During standby and in Cooling mode, follow the occupied cooling mode sequence of control. When occupancy is detected, the DDC controller will revert to the occupied mode. Where available standby setpoints should provide a wider deadband and be a minimum of +/- 1 (adj) degF offset from the occupied heating and cooling setpoints.
 12. CO2 Sensors: In zones where occupancy has high variability (e.g. conference room, classrooms, etc.) a CO2 sensor shall be used. The VAV controller shall compare the zone CO2 sensor to the CO2 set point (800 ppm – adj). When the CO2 rises above the CO2 set point the controller shall reset the minimum air flow ventilation set point up until it reaches that of the maximum cooling CFM. As the space CO2 falls below the CO2 set point the controller shall return the adjusted air flow set point to the original minimum air flow ventilation setting. The VAV controller shall modulate the damper to maintain the adjusted minimum air flow set point. The controller shall monitor and report the CO2 level of each zone served with the value displayed on the graphical floor plan.
 13. VOC Sensors: In zones where VOC concentrations may be elevated, a VOC sensor should be used. The DDC controller shall compare the zone VOC sensor to the VOC set point (40% – adj). When the VOC rises above the VOC set point the controller shall reset the minimum air flow ventilation set point up until it reaches that of the maximum cooling CFM. As the space VOC falls below the VOC set point the controller shall return the adjusted air flow set point to the original minimum air flow ventilation setting. The VAV controller shall modulate the damper to maintain the adjusted minimum air flow set point. The controller shall monitor and report the VOC level of each zone served with the value displayed on the graphical floor plan.
 14. Capacity control: The local VAV controller shall modulate the primary damper, auxiliary damper, reheat valve and / or auxiliary fan to a fully closed or off position if a load shed signal is received from the BMS system.
 15. Power outage: A VAV controller should be on normal power and not on emergency backup power unless called for by the specifying engineer. When power is lost all dampers should fail in place, the hot water valve should close, and the auxiliary fan should stop.
 16. Software Alarms & Histories:

	<u>PT</u>	<u>HT</u>	<u>CI</u>	<u>LCL</u>	<u>SCL</u>	<u>A</u> <u>L</u>	<u>SN</u>
Zone Air Temp	AI	Interval	10	3	36		SpcTemp
Zone Air Temp Setpoint	AV	Interval	10	3	36		SpcTempSp
Zone Occupancy Mode	MV	Interval	10	3	36		Occ
Air Damper Command	AV / AO	Interval	10	3	36		DmprPos
Discharge Air Flow	AI	Interval	10	3	36		DaFlow
Discharge Air Flow SP	AV	Interval	10	3	36		DaFlowSp
Hot Water Valve Command	AV / AO	Interval	10	3	36		HwVlvPos
Aux Air Damper Command	AV / AO	Interval	10	3	36		AuxDmprPos
Aux Discharge Air Flow	AI	Interval	10	3	36		AuxDaFlow
Aux Discharge Air Flow SP	AV	Interval	10	3	36		AuxDaFlowSp

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



<u>abbreviation</u>	<u>description</u>
PT	Point Type
HT	History Type
CI	Collection Interval
LCL	Local Collection Length
SCL	Supervisor Collection Length
AL	Alarm
SN	Software Name

B. Cooling Only VAV (VAVCO)

1. Occupied Mode: The occupancy of the zone shall be determined by the BMS or by a local override button (if applicable). When in Deadband or Heating modes, the local DDC controller shall modulate the primary damper to its minimum ventilation CFM setpoint. When in Cooling mode, the local DDC controller shall modulate the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100%.
2. Unoccupied Mode: When in Deadband or Heating modes, the local DDC controller shall modulate the primary damper to its fully closed position. When in Cooling mode, the local DDC controller shall modulate the primary damper open from its minimum to its maximum ventilation CFM setpoint as the cooling calculation ramps between 0 - 100%.

C. Reheat VAV (VAVR)

1. Occupied Mode: The occupancy of the zone shall be determined by the BMS or by a local override button (if applicable). When in Deadband, the local DDC controller shall modulate the primary damper to its minimum ventilation CFM setpoint and close the hot water reheat valve. When in Heating mode, the local DDC controller shall modulate open the hot water valve from 0 – 100% as the heating calculation rises from 0 – 50%, subject to discharge air temperature at or below 90 DegF. Once heating calculation reaches 50% then modulate open the primary damper from minimum to maximum heating ventilation CFM setpoint as the heating calculation rises from 50 – 100%. When in Cooling mode, the local DDC controller shall modulate the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100% and the reheat valve shall be closed.
2. Unoccupied Mode: When in Deadband mode, the local DDC controller shall modulate the primary damper and the reheat valve to a fully closed position. When in heating mode, follow the occupied heating sequence of control until zone is above the unoccupied heating setpoint. When in Cooling mode, the local DDC controller shall modulate the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100% and the reheat valve shall be closed.

D. Fan Powered VAV (VAVFP)

1. Occupied Mode: The occupancy of the zone shall be determined by the BMS or by a local override button (if applicable). When in Deadband, the local DDC controller shall modulate the primary damper to its minimum ventilation CFM setpoint, close the hot water reheat valve and stop the fan. When in Heating mode, the local DDC controller shall start the fan at minimum speed and modulate open the hot water valve from 0 – 100% as the heating calculation rises from 0 – 50%, subject to discharge air temperature at or below 90 DegF. Once heating calculation reaches 50% then modulate the speed of the fan from its minimum to maximum speed as the heating calculation rises from 50 – 100%. When in Cooling mode, the local DDC controller shall modulate the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100%, the fan shall be off, and the reheat valve shall be closed.
2. Unoccupied Mode: When in Deadband mode, the local DDC controller shall modulate the primary damper and the reheat valve to a fully closed position, and stop the fan. When in Heating mode, the local DDC controller shall start the fan at minimum speed and modulate open

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



the hot water valve from 0 – 100% as the heating calculation rises from 0 – 50%, subject to discharge air temperature at or below 90 DegF. Once heating calculation reaches 50% then modulate the speed of the fan from its minimum to maximum speed as the heating calculation rises from 50 – 100%. When in Cooling mode, the local DDC controller shall modulate the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100%, the fan shall be off, and the reheat valve shall be closed.

E. Dual Duct VAV (VAVDD)

1. Occupied Mode: The occupancy of the zone shall be determined by the BMS or by a local override button (if applicable). When in Deadband, the local DDC controller shall modulate the primary damper to its minimum ventilation CFM setpoint and the auxiliary damper closed. When in Heating mode, the local DDC controller shuts the primary damper and modulates the auxiliary damper open from its minimum to its maximum heating ventilation CFM setpoint as the heating calculation rises from 0 – 100%. When in Cooling mode, the local DDC controller shuts the auxiliary damper and modulates the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100%.
2. Unoccupied Mode: When in Deadband, the local DDC controller shall modulate the primary and auxiliary dampers closed. When in Heating mode, the local DDC controller shuts the primary damper and modulates the auxiliary damper open from its minimum to its maximum heating ventilation CFM setpoint as the heating calculation rises from 0 – 100%. When in Cooling mode, the local DDC controller shuts the auxiliary damper and modulates the primary damper open from its minimum to its maximum cooling ventilation CFM setpoint as the cooling calculation ramps between 0 - 100%.

F. Tracking VAV (VAVT)

1. All tracking VAVs (or slave VAVs) shall share zone temperature, temperature setpoints, heating and cooling demands. All DDC controllers will control damper, valve and fan outputs independently to meet shared setpoints.
2. All tracking VAVs should resynchronize the primary and auxiliary dampers at least once per week during off hours. If a large number of VAVTs will be synchronized, then split them into smaller groups to prevent duct pressurization issues.

G. Tracking Exhaust VAV (VAVTE)

1. All tracking Exhaust VAVs shall share airflow data so that the exhaust airflow is maintained at a specific CFM offset to the zone supply CFM. All DDC controllers will control damper, valve and fan outputs independently to meet shared setpoints.
2. All tracking Exhaust VAVs should resynchronize the primary dampers at least once per week during off hours. If a large number of VAVTEs will be synchronized, then split them into smaller groups to prevent duct pressurization issues.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 233100
HVAC DUCTS AND CASINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Metal ductwork.
- B. Nonmetal ductwork.
- C. Casing and plenums.
- D. Buried ductwork.
- E. Kitchen hood ductwork.
- F. Laboratory exhaust ductwork.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete.
- B. Section 078400 - Firestopping.
- C. Section 099113 - Exterior Painting: Weld priming, weather resistant, paint or coating.
- D. Section 099123 - Interior Painting: Weld priming, paint or coating.
- E. Section 114000 - Foodservice Equipment: Supply of kitchen range hoods for placement by this Section.
- F. Section 230130.51 - HVAC Air Duct Cleaning: Cleaning ducts after completion of installation.
- G. Section 230593 - Testing, Adjusting, and Balancing for HVAC.
- H. Section 230713 - Duct Insulation: External insulation and duct liner.
- I. Section 233300 - Air Duct Accessories.
- J. Section 233600 - Air Terminal Units.
- K. Section 233700 - Air Outlets and Inlets.

1.03 REFERENCE STANDARDS

- A. ASHRAE (FUND) - ASHRAE Handbook - Fundamentals; 2017.
- B. ASHRAE Std 126 - Method of Testing HVAC Air Ducts; 2016.
- C. ASTM A36/A36M - Standard Specification for Carbon Structural Steel; 2014.
- D. ASTM A240/A240M - Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications; 2016.
- E. ASTM A276/A276M - Standard Specification for Stainless Steel Bars and Shapes; 2017.
- F. ASTM A480/A480M - Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet, and Strip; 2017.
- G. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2015.
- H. ASTM A666 - Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2015.
- I. ASTM A1008/A1008M - Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable; 2016.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- J. ASTM A1011/A1011M - Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength; 2015.
- K. ASTM B209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2014.
- L. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- M. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009 (Reapproved 2016).
- N. ASTM E119 - Standard Test Methods for Fire Tests of Building Construction and Materials; 2016a.
- O. ASTM E2336 - Standard Test Methods for Fire Resistive Grease Duct Enclosure Systems; 2020.
- P. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2015.
- Q. ICC-ES AC106 - Acceptance Criteria for Predrilled Fasteners (Screw Anchors) in Masonry Elements; 2015.
- R. ICC-ES AC193 - Acceptance Criteria for Mechanical Anchors in Concrete Elements; 2015.
- S. ICC-ES AC308 - Acceptance Criteria for Post-Installed Adhesive Anchors in Concrete Elements; 2016.
- T. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.
- U. NFPA 90B - Standard for the Installation of Warm Air Heating and Air-Conditioning Systems; 2018.
- V. NFPA 96 - Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations; 2017.
- W. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005 (Rev. 2009).
- X. SMACNA (FGD) - Fibrous Glass Duct Construction Standards; 2003.
- Y. SMACNA (KVS) - Kitchen Ventilation Systems and Food Service Equipment Fabrication and Installation Guidelines; 2001.
- Z. SMACNA (LEAK) - HVAC Air Duct Leakage Test Manual; 2012, 2nd Edition.
- AA. UL 181 - Standard for Factory-Made Air Ducts and Air Connectors; current edition, including all revisions.
- AB. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.
- AC. UL 1978 - Grease Ducts; Current Edition, Including All Revisions.
- AD. UL 2221 - Tests of Fire Resistive Grease Duct Enclosure Assemblies; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data for duct materials, duct liner, and duct connections.
- C. Shop Drawings: Indicate duct fittings, particulars such as gages, sizes, welds, and configuration prior to start of work for all duct systems.
- D. Test Reports: Indicate pressure tests performed. Include date, section tested, test pressure, and leakage rate, following SMACNA (LEAK).
- E. Manufacturer's Installation Instructions: Indicate special procedures for glass fiber ducts.
- F. Project Record Documents: Record actual locations of ducts and duct fittings. Record changes in fitting location and type. Show additional fittings used.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.
- B. Installer Qualifications: Company specializing in performing the type of work specified in this section, with minimum five years of documented experience.

1.06 FIELD CONDITIONS

- A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers.
- B. Maintain temperatures within acceptable range during and after installation of duct sealants.

PART 2 PRODUCTS

2.01 DUCT ASSEMBLIES

- A. Regulatory Requirements: Construct ductwork to NFPA 90A, NFPA 90B, and NFPA 96 standards, as applicable.
- B. Ducts: Galvanized steel, unless otherwise indicated.
- C. Low Pressure Supply (Heating Systems): 2 inch w.g. pressure class, galvanized steel.
- D. Low Pressure Supply (System with Cooling Coils): 2 inch w.g. pressure class, galvanized steel.
- E. Buried Supply or Return: 2 inch w.g. pressure class, fiber glass reinforced plastic or Linear Low Density Polyethylene / High Density Polyethylene (EVALENE LLDPE/HDPE).
- F. Medium and High Pressure Supply: 6 inch w.g. pressure class, galvanized steel.
- G. Return and Relief: 1/2 inch w.g. pressure class, galvanized steel.
- H. General Exhaust: 1 inch w.g. pressure class, galvanized steel.
- I. Kitchen Cooking Hood Exhaust: 1 inch w.g. pressure class, stainless steel or un-galvanized steel.
 - 1. Construct of 16 gage, 0.0598 inch sheet steel using continuous external welded joints in rectangular sections.
 - 2. Construct of 18 gage, 0.0500 inch stainless steel using continuous external welded joints in rectangular sections.
- J. Dishwasher Exhaust: 1 inch w.g. pressure class, stainless steel.
 - 1. Construct of 18 gage, 0.0500 inch stainless steel using continuous external welded joints in rectangular sections.
- K. Grease Exhaust: 1 inch w.g. pressure class, stainless or un-galvanized steel.
 - 1. Construct of ASTM A1011/A1011M 16 gage un-galvanized steel.
 - 2. Construct of 18 gage, 0.0500 inch stainless steel.
 - 3. Construction:
 - a. Liquid tight with continuous external weld for all seams and joints.
 - b. Where ducts are not self-draining back to equipment, provide low point drain pocket with copper drain pipe to sanitary sewer.
 - 4. Access Doors:
 - a. Provide for duct cleaning inside horizontal duct at drain pockets, every 20 feet and at each change of direction.
 - b. Use same material and thickness as duct with gaskets and sealants rated 1500 degrees F for grease tight construction.
- L. Fume Hood Exhaust: 2 inch w.g. pressure class, galvanized steel.
- M. Outside Air Intake: 1/2 inch w.g. pressure class, galvanized steel.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- N. Combustion Air: 1/2 inch w.g. pressure class, galvanized steel.
- O. Evaporative Condenser Intake and Exhaust: 1/2 inch w.g. pressure class, galvanized steel.
- P. Emergency Generation Ventilation: 1/2 inch w.g. pressure class, galvanized steel.
- Q. Transfer Air and Sound Boots: 1/2 inch w.g. pressure class, Fibrous glass or sheet metal with acoustic lining.

2.02 MATERIALS

- A. Galvanized Steel for Ducts: Hot-dipped galvanized steel sheet, ASTM A653/A653M FS Type B, with G60/Z180 coating.
- B. Un-Galvanized Steel for Ducts: 1, Designation CS (commercial steel), cold-rolled.
- C. Stainless Steel for Ducts: 1, Type 304.
- D. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant.
 - 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrates, and recommended by manufacturer for pressure class of ducts.
 - 2. Surface Burning Characteristics: Flame spread index of zero and smoke developed index of zero, when tested in accordance with ASTM E84.
- E. Hanger Rod: ASTM A36/A36M; steel, galvanized; threaded both ends, threaded one end, or continuously threaded.
- F. Sheet Metal Strap.
- G. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."
- H. Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
 - 1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
 - 2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
 - 3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
 - 4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.
 - 5. Concrete Adhesive Type Anchors: Complying with ICC-ES AC308.
 - 6. Other Types: As required.

2.03 DUCTWORK FABRICATION

- A. Fabricate and support in accordance with SMACNA (DCS) and as indicated.
- B. No variation of duct configuration or size permitted except by written permission. Where permitted, size round duct installed in place of rectangular ducts in accordance with ASHRAE (FUND) Handbook - Fundamentals.
- C. Provide duct material, gages, reinforcing, and sealing for operating pressures indicated.
- D. Construct T's, bends, and elbows with radius of not less than 1-1/2 times width of duct on centerline, or where rectangular elbows are used, provide single width blade with trailing edge turning vanes of galvanized steel sheet metal.
- E. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever possible; maximum 30 degrees divergence upstream of equipment and 45 degrees convergence downstream.
- F. Fabricate continuously welded round and oval duct fittings in accordance with SMACNA (DCS).

2.04 MANUFACTURED DUCTWORK AND FITTINGS

- A. Flat Oval Ducts: Machine made from round spiral lock seam duct.
 - 1. Manufacture in accordance with SMACNA (DCS).

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2. Fittings: Manufacture at least two gages heavier metal than duct.
 3. Provide duct material, gages, reinforcing, and sealing for operating pressures indicated.
- B. Double Wall Insulated Flat Oval Ducts: Machine made from round spiral lock seam duct.
1. Manufacture in accordance with SMACNA (DCS).
 2. Fittings: Manufacture with solid inner wall.
 3. Duct inner wall: Perforated galvanized steel.
 4. Insulation:
 - a. Thickness: ___ inch fiberglass.
 - b. Insulation K Value: _____.
 - c. Insulation Density: _____.
- C. Double Wall Insulated Round Ducts: Round spiral lock seam duct with galvanized steel outer wall, perforated galvanized steel inner wall; fitting with solid inner wall.
1. Manufacture in accordance with SMACNA (DCS).
 2. Insulation:
 - a. Thickness: ___ inch.
 - b. Material: Fiberglass.
 - c. Insulation K Value: _____.
 - d. Insulation Density: _____.
- D. Double Wall Insulated Rectangular Ducts: Rectangular spiral lock seam duct with galvanized steel outer wall, perforated galvanized steel inner wall; fitting with solid inner wall.
1. Manufacture in accordance with SMACNA (DCS).
 2. Insulation:
 - a. Thickness: ___ inch.
 - b. Material: Fiberglass.
 - c. Insulation K Value: _____.
 - d. Insulation Density: _____.
- E. Spiral Ducts: Round spiral lock seam duct with galvanized steel outer wall.
1. Manufacture in accordance with SMACNA (DCS).
- F. Round Ducts: Round lock seam duct with galvanized steel outer wall.
1. Manufacture in accordance with SMACNA (DCS).
- G. Fiber Glass Reinforced Plastic (FRP) Ducts: Glass fiber reinforced plastic, minimum 3/16 inch wall thickness, for all direct-burial underground air duct systems.
1. Class 1 flame and smoke rating.
 2. Insulation: R-4 thru R-12 available.
 3. Manufacturers:
 - a. Spunstrand; Green Duct
 - b. Monoxivent; UnderDuct
 - c. Perry Fiberglass Products;
 - d. Substitutions: See Section 016000 - Product Requirements.
- H. Linear Low Density Polyethylene / High Density Polyethylene (EVALENE LLDPE/HDPE) Ducts: Self-insulated, direct-burial underground air duct system for supply air, outside air, return air, and relief air duct systems.
1. Manufacture in accordance with SMACNA (DCS).
 2. Fittings: Elbows, tees, wyes, reducers, boots, diffusers, plenums, endcaps, clamps and gaskets.
 3. Insulation: R-10 equivalent.
 4. Manufacturers:
 - a. AQC Industries; The BlueDuct

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- b. Substitutions: See Section 016000 - Product Requirements.
- I. Flexible Ducts: Woven and coated fiberglass liner permanently bonded to a helically wound coated or galvanized spring steel wire.
 - 1. Class 1.
 - 2. UL labeled.
 - 3. Insulation: Fiberglass insulation with aluminized polyester vapor barrier film.
 - 4. Pressure Rating: 16 inches WG positive for 4"-10" duct, 10 inches WG positive for 12"-16" duct, and 2 inches WG negative.
 - 5. Maximum Velocity Rating: 5500 fpm.
 - 6. Temperature Range: Minus 20 degrees F to 250 degrees F.
 - 7. Manufacturers:
 - a. Flexmaster U.S.A; 3M
 - b. Thermaflex; M-KC
 - c. Hart & Cooley, Inc; F294
 - d. Substitutions: See Section 016000 - Product Requirements.
- J. Transverse Duct Connection System: SMACNA "E" rated rigidly class connection, interlocking angle and duct edge connection system with sealant, gasket, cleats, and corner clips in accordance with SMACNA (DCS).
- K. Factory Fabricated Kitchen Cooking Hood and Grease Exhaust Duct Systems: Nominal 3 inches thick ceramic fiber insulation between 20 gage, 0.0375 inch, Type 304 stainless steel liner and 24 gage, 0.0239 inch aluminized steel sheet outer jacket.
 - 1. Tested and UL listed for use with commercial cooking equipment in accordance with NFPA 96.
 - 2. Certified for zero clearance to combustible material in accordance with:
 - a. UL 2221 with a 2 hour rating.
 - 3. Materials and construction of the modular sections and accessories to be in accordance with the terms of the following listings:
 - a. UL 1978.
 - b. UL 2221.
 - 4. Manufacturers:
 - a. AMPCO by Hart & Cooley, Inc.; Z-Clear
 - b. DuraVent; DuraZDuct (DIS3Z)
 - c. Security Chimneys International; Secure Duct (CIX3Z)
 - d. Selkirk Corporation; ZeroClear (IPS-Z3)
 - e. Substitutions: See Section 016000 - Product Requirements.
- L. Shop Fabricated Kitchen Cooking Hood and Grease Exhaust Ductwork: 16 gauge, 0.0598 inch sheet steel or 18 gauge, 0.0500 inch stainless steel constructed with a continuous, liquid-tight weld or braze on the external surface of all joints and seams.
 - 1. Fabricate in accordance with SMACNA (DCS), SMACNA (KVS), and NFPA 96.
 - 2. Grease duct shall be wrapped with International Mechanical Code (IMC) compliant duct insulation system to form a 2 hour rated firestop system.
 - 3. Duct wrap system certified for zero clearance to combustible material in accordance with:
 - a. ASTM E2336 Internal Grease Duct Test
 - 4. Manufacturers:
 - a. FyreWrap; Elite 1.5 Duct Insulation
 - b. 3M; Fire Barrier Duct Wrap 615+
 - c. Morgan ThermalCeramics; Pyroscat DuctWrap XL
 - d. Morgan ThermalCeramics; Duct Wrap 2x2+
 - e. Substitutions: See Section 016000 - Product Requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- M. Dishwasher Exhaust: Minimum 21 gage, 0.0344 inch thick, single wall, Type 304 stainless steel.
 - 1. Single wall, shop fabricated or factory built general use vent system.
 - 2. Designed, fabricated, and installed to be liquid tight preventing exhaust leakage into the building.
 - 3. Factory built system joints to be sealed during installation with factory supplied overlapping V-bands and sealant.
 - 4. Shop fabricated system joints shall be welded.
- N. Fume Hood Exhaust: Minimum 21 gage, 0.0344 inch thick, single wall, Type 304 stainless steel.
 - 1. Fabricate in accordance with ductwork manufacturer's instructions, test duct system to sustain positive and negative pressures in compliance with ASHRAE Std 126.
 - 2. Single wall, shop fabricated or factory built general use vent system.
 - 3. Designed, fabricated, and installed to be liquid tight preventing exhaust leakage into the building.
 - 4. Operating Range: -6 inch wg.
 - 5. Factory built system joints to be sealed during installation with factory supplied overlapping V-bands and sealant.
 - 6. Provide with factory fabricated and pressure tested access doors.
 - 7. Shop fabricated system joints shall be welded.

2.05 CASINGS

- A. Manufacturers:
 - 1. Semco;
 - 2. Commercial Acoustics;
 - 3. Substitutions: See Section 016000 - Product Requirements.
- B. General: Provide built up factory system as indicated on drawings for size, wall thickness, and as specified herein.
 - 1. Fabricate casings in accordance with SMACNA (DCS) and construct for operating pressures indicated.
 - 2. Where required by drawings, the plenum walls shall be installed on top of contractor provided concrete curbing to ensure a level surface for the walls to be installed on. The curbing shall be no less than 4" thick and 2" wider than the thickness of the walls that are to be installed on them. The curbing shall be installed with #4 rebar doveled into the floor with #4 rebar for pads 4" thick and #5 for pads that are 6" thick with a maximum of 16" center to center in a cross grid pattern. All curbs shall either be installed with chamfered edges or troweled edges to prevent chipping and cracking at the edges.
 - 3. Access doors shall be provided to service all internal components, where the plenum will allow. All access doors shall be large enough for a person to pass through the opening.
 - 4. The responsibility to provide a complete and operable plenum system lies with the installing sheet metal, or mechanical contractor. This contractor shall coordinate the efforts of the equipment suppliers, and subcontractors to insure that the final systems are complete and fully functional.
- C. Factory Fabricated Plenum Systems Construction:
 - 1. Plenum walls and ceilings shall be constructed with nominal thickness of 4" or 2" as required by drawings. Walls and ceilings shall be constructed with 18 gauge G90 galvanized exterior solid panels and 22 gauge 3/32" diameter holes on 3/16" staggered center spacing for the interior solid perforated panels. Internal panel reinforcements shall be role formed 16 gauge G90 galvanized steel and spaced with a maximum spacing of 24 inches. Perimeter and internal reinforcements shall be welded with the panels sheets to form a double wall insulated casing. Prior to the welding of the perforated panel the panel shall be filled with sound retarding and absorbing fill that shall be incombustible, inert, mildew-resistant, and vermin proof. The fill shall be slightly large and thicker than the inside void that it fills, no void shall be allowed. The face

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- panel shall be attached to plenum panel such that the inner liner is compressed and will hold it in position even in the presence of severe vibration from shipment, installation, or operation.
2. Door panels shall be of similar construction to standard panels. Doors shall be the same thickness as the plenum panels overlapping air/acoustical seals around the sill, jambs, and head. All doors shall be a minimum of 24" wide x 60" high unless otherwise specified on the drawings. Door frames shall be constructed of extruded aluminum or similar with gasketing around the frame. Face panel sheets shall be 20 gauge G90 galvanized steel on both sides of the door. All doors shall be installed such that the pressure created by the fan, or fans, shall close the door. All doors shall be provided with a minimum of 2 heavy duty hinges and two quick open latches. See drawings for doors that are to be provided with view windows. View windows shall be provided with two layer glass, one clear and one with wire reinforcement, view glass shall be 12"x12" unless the door isn't large enough, then an 8"x8" view glass shall be provided.
 3. Floor channels and panel connectors shall be 16 gauge G90 galvanized steel and roll formed. All panel accessories and trim shall be made of 18 gauge G90 galvanized steel furnished in standard lengths to be cut in the field as required. All openings for fans, coils, filters, duct connections, etc. shall be provided by the plenum wall manufacturer, all pipe and conduit penetrations shall be located and cut in the field and sealed air tight as per manufacturer's requirements. All fasteners shall be provided with the plenum wall system and shall be sized to withstand the air pressure force that the system shall be subjected to, #12x1" self-tapping hex head sheet metal screws located at 12" on centers shall be used as a minimum requirement.
- D. Factory Fabricated Plenum Systems Performance:
1. Acoustical panel ratings shall be determined by the dual reverberation room method in accordance with ASTM specifications E-90-81, E413-73, C423-81a, E795, or latest version thereof. The test set-up and procedure shall be such that all effects of flanking transmission, standing waves and test chamber sound absorption are eliminated. Data shall be presented on the submittals for tests conducted using current production materials and methods. The minimum allowable transmission loss of panels and components when tested in accordance with ASTM E-90-81 and E413-73, or latest version shall be as follows:

Transmission Loss In Decibels

Octave Band	2	3	4	5	6	7	
Frequency (Hz)	125	250	500	1000	2000	4000	STC
4" panel assembly	22	29	40	48	54	60	41
2" panel assembly	21	24	35	43	52	57	37

Sound Absorption Coefficients

Octave Band	2	3	4	5	6	7	
Frequency (Hz)	125	250	500	1000	2000	4000	STC
4" panel assembly	0.86	1.0	1.22	1.06	1.05	1.05	1.1
2" panel assembly	0.31	0.8	1.19	1.12	1.07	1.06	1.11

2.06 KITCHEN HOOD EXHAUST DUCTWORK

- A. Fabricate in accordance with ductwork manufacturer's installation instructions, SMACNA (DCS), SMACNA (KVS), and NFPA 96.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



PART 3 EXECUTION

3.01 INSTALLATION

- A. Install, support, and seal ducts in accordance with SMACNA (DCS).
- B. Install in accordance with manufacturer's instructions.
- C. During construction provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork system.
- D. Flexible Ducts: Connect to metal ducts with draw bands. No more than 24 inch long lengths of flexible ductwork allowed at each use.
- E. No spin-in duct fittings allowed. Use high efficiency take-offs or 45 degree take-offs only. Install high efficiency take-offs with 45 degree leg on upstream side of take-off.
- F. Kitchen Hood Exhaust: Provide residue traps at base of vertical risers with provisions for clean out.
- G. Grease Hood Exhaust: Duct shall slope back to hood or approved grease reservoir at a minimum slope of 1/4" per foot.
- H. Grease Duct Test: Prior to the use or concealment of any portion of a grease duct system, a leakage test and light test shall be performed by the contractor and witnessed by Owner's project manager, BYU Fire Marshall, and project commissioning agent. Ducts shall be considered to be concealed where installed in shafts or covered by coatings or wraps that prevent the ductwork from being visually inspected on all sides. The permit holder shall be responsible to provide the necessary equipment and perform the grease duct leakage test. A light test shall be performed to determine that all welded and brazed joints are liquid tight.
 - 1. A light test shall be performed by passing a lamp having a power rating not less than 100 watts equivalent, through the entire section of ductwork to be tested. The lamp shall be open so as to emit light equally in all directions perpendicular to the duct walls.
 - 2. A light test shall be performed for the entire duct system, including the hood-to-duct connection. The ductwork shall be permitted to be tested in sections, provided that every joint is tested.
 - 3. For listed factory-built grease ducts, this test shall be limited to duct joints assembled in the field and shall exclude factory welds.
- I. Underground Ducts: Slope to plenums or low pump out points at 1:500. Provide access doors for inspection.
- J. Duct sizes indicated are inside clear dimensions. For lined ducts, maintain sizes inside lining.
- K. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.
- L. Use crimp joints with or without bead for joining round duct with crimp in direction of air flow.
- M. Use double nuts and lock washers on threaded rod supports.
- N. Connect terminal units and diffusers to supply ducts directly, if possible. Where hard ducting connections are not possible, flexible duct shall be installed such that the center line of the terminal unit or diffuser inlet shall not be offset from the center line of the duct elbow by more than one duct radius. No flexible duct elbows allowed and do not use flexible duct to change direction.
- O. Set plenum doors 6 to 10 inches above floor. Arrange door swings so that fan static pressure holds door in closed position.
- P. At exterior wall louvers, seal duct to louver frame.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 233300
AIR DUCT ACCESSORIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Air turning vanes.
- B. Backdraft dampers.
- C. Combination fire and smoke dampers.
- D. Duct access doors.
- E. High efficiency take-offs with hand dampers.
- F. Hand dampers.
- G. Duct test holes.
- H. Fire dampers.
- I. Flexible duct connections.
- J. Smoke dampers.
- K. Variable control dampers.
- L. Miscellaneous products:
 - 1. Duct opening closure film.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 220548 - Vibration and Seismic Controls for Plumbing Piping and Equipment.
- C. Section 233100 - HVAC Ducts and Casings.
- D. Section 233600 - Air Terminal Units: Pressure regulating damper assemblies.
- E. Section 260583 - Wiring Connections: Electrical characteristics and wiring connections.

1.03 REFERENCE STANDARDS

- A. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.
- B. NFPA 92 - Standard for Smoke Control Systems; 2015.
- C. NFPA 96 - Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations; 2017.
- D. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005 (Rev. 2009).
- E. UL 33 - Safety Heat Responsive Links for Fire-Protection Service; Current Edition, Including All Revisions.
- F. UL 555 - Standard for Fire Dampers; Current Edition, Including All Revisions.
- G. UL 555S - Standard for Smoke Dampers; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide for shop fabricated assemblies including volume control dampers, duct access doors, and hardware used. Include electrical characteristics and connection requirements.
- C. Manufacturer's Installation Instructions: Provide instructions for fire dampers and combination fire and smoke dampers.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



D. Project Record Drawings: Record actual locations of access doors.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.
- B. Products Requiring Electrical Connection: Listed and classified by testing firm acceptable to the Authority Having Jurisdiction as suitable for the purpose specified and indicated.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Protect dampers from damage to operating linkages and blades. Store in clean, dry location.

PART 2 PRODUCTS

2.01 AIR TURNING DEVICES

- A. Manufacturers:
 - 1. Carlisle HVAC Products; Model DYN-O-RAIL, DYN-O-RAIL JR.
 - 2. Elgen Manufacturing, Inc; Model EVR-1
 - 3. Duro Dyne Corp; Model DHVR2, DHVR4
 - 4. Ductmate Industries, Inc.; MONOrail
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Multi-blade device with radius single wall blades aligned in short dimension of all square duct elbows; steel construction; turning vane spacing per SMACNA (DCS); each blade tack welded or crimped to the vane rail to prevent rattling.

2.02 BACKDRAFT DAMPERS

- A. Manufacturers:
 - 1. Greenheck Fan Corp.; _____
 - 2. Nailor Industries, Inc; _____
 - 3. Ruskin Company; _____
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Gravity Backdraft Dampers, Size 18 by 18 inches or Smaller, Furnished with Air Moving Equipment: Air moving equipment manufacturer's standard construction.
- C. Multi-Blade, Parallel Action Gravity Balanced Backdraft Dampers: Frame shall be .090" extruded aluminum wall thickness with mitered corners; blades shall be .050" extruded aluminum with extruded vinyl edge seals. Blade edge seals shall be mechanically locked into blade edge; adhesive type seals are unacceptable. Bearings shall be corrosion resistant synthetic and linkage shall be concealed in frame for low pressure drop and noise.; adjustment device to permit setting for varying differential static pressure.

2.03 COMBINATION FIRE AND SMOKE DAMPERS

- A. Manufacturers:
 - 1. Greenheck Fan Corp.; FSD-311
 - 2. NCA Manufacturing; FSD-AF-211
 - 3. Pottorff; FSD-151
 - 4. Ruskin Company; FSD60
- B. Fabricate in accordance with NFPA 90A, UL 555, UL 555S, and as indicated.
- C. Provide factory sleeve and collar for each damper.
- D. Multiple Blade Dampers: Galvanized hat-shaped steel channel frame; steel airfoil shaped double skin construction blades; silicone rubber blade edge seals; flexible compression jamb seals; stainless steel

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



bearings; leakage Class I; 4000 fpm velocity rating; damper and operator to be qualified for 350 degrees F temperature rating.

- E. Operators: UL listed and labelled spring return electric type suitable for 120 volts, single phase, 60 Hz. Locate damper operator on exterior of duct and link to damper operating shaft. Furnish and install a single pole switch to disconnect power, for testing and servicing.
- F. Electro Thermal Link: Cold or return air: Fusible link melting at 165 degrees F; hot air: Fusible link melting at 212 degrees F (100 degrees C); 120 volts, single phase, 60 Hz; UL listed and labeled.

2.04 DUCT ACCESS DOORS

- A. Manufacturers:
 - 1. Acudor Products Inc.; _____
 - 2. Elgen Manufacturing, Inc; _____
 - 3. Ductmate Industries, Inc.; _____
 - 4. Nailor Industries, Inc; _____
 - 5. Duro Dyne Corp.; _____
 - 6. SEMCO LLC; _____: www.semcohvac.com
 - 7. Substitutions: See Section 016000 - Product Requirements.
- B. Fabricate in accordance with SMACNA (DCS) and as indicated.
- C. Access doors with sheet metal screw fasteners are not acceptable.

2.05 HIGH EFFICIENCY TAKE-OFFS WITH MANUAL BALANCING DAMPERS

- A. Manufacturers:
 - 1. Sheet Metal Connectors, Inc.;
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Fabricated in accordance to SPIDA and SMACNA / ASHRAE Leakage Class 3 standards. Testing performed by ETL Testing lab.
- C. Fabricated from minimum 22 gauge galvanized steel (ASTM A653).
- D. 45 degree take-off angle design for optimal air flow.
- E. Supply with gasketed discharge connection.
- F. 1" wide flange with minimum 3/4" wide double faced adhesive gasket to assure tight seal and to hold the fitting securely in position during installation.
- G. 2" rod extension to extend damper handle location beyond duct insulation.
- H. Damper handle with locking hex or wing nut. Position of damper handle shall indicate damper setting.

2.06 MANUAL BALANCING DAMPERS

- A. Manufacturers:
 - 1. Greenheck;
 - 2. Ruskin;
 - 3. Pottorff;
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Frame: 20 gauge galvanized steel.
- C. Blades: 20 gauge galvanized steel.
- D. Control shafts and axles: 3/8" square plated steel, extended for stand-off.
- E. Bearings: Synthetic.
- F. 1 1/2" high stand-off bracket, minimum, with factory installed manual locking quadrant.
- G. Rated for maximum system velocity of 1500 fpm.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.07 DUCT TEST HOLES

- A. Temporary Test Holes: Cut or drill in ducts as required. Cap with neat patches, neoprene plugs, threaded plugs, or threaded or twist-on metal caps.

2.08 FIRE DAMPERS

- A. Manufacturers:
 - 1. Greenheck Fan Corp.; _____
 - 2. NCA Manufacturing; _____
 - 3. Pottorff; _____
 - 4. Ruskin Company; _____
- B. Fabricate in accordance with NFPA 90A and UL 555, and as indicated.
- C. Ceiling Dampers: Galvanized steel, 22 gage, 0.0299 inch frame and 16 gage, 0.0598 inch flap, two layers 0.125 inch ceramic fiber on top side and one layer on bottom side for round flaps, with locking clip.
- D. Horizontal Dampers: Galvanized steel, 22 gage, 0.0299 inch frame, stainless steel closure spring, and lightweight, heat retardant non-asbestos fabric blanket.
- E. Curtain Type Dampers: Galvanized steel with interlocking blades. Provide stainless steel closure springs and latches for horizontal installations. Configure with blades out of air stream except for 1.0 inch pressure class ducts up to 12 inches in height.
- F. Multiple Blade Dampers: 16 gage, 0.0598 inch galvanized steel frame and blades, oil-impregnated bronze or stainless steel sleeve bearings and plated steel axles, 1/8 by 1/2 inch plated steel concealed linkage, stainless steel closure spring, blade stops, and lock.
- G. Fusible Links: UL 33, separate at 160 degrees F with adjustable link straps for combination fire/balancing dampers.

2.09 FLEXIBLE DUCT CONNECTIONS

- A. Manufacturers:
 - 1. Carlisle HVAC Products
 - 2. Duro Dyne Corp.; _____
 - 3. Ductmate Industries, Inc.; _____
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Fabricate in accordance with SMACNA (DCS) and as indicated.
- C. Flexible Duct Connections: Fabric crimped into metal edging strip.
 - 1. Fabric: UL listed fire-retardant neoprene or hypalon coated woven glass fiber fabric to NFPA 90A, minimum density 30 oz per sq yd.
 - a. Net Fabric Width: Approximately 3.5 inch wide.
 - 2. Metal: 3 inches wide, 24 gage, 0.0239 inch thick galvanized steel.

2.10 SMOKE DAMPERS

- A. Manufacturers:
 - 1. Greenheck Fan Company; SMD-301:
 - 2. NCA Manufacturing; SSD-AF-201:
 - 3. Ruskin Company; SD60:
 - 4. PottorffSD-151:
- B. Fabricate in accordance with NFPA 90A and UL 555S, and as indicated.
- C. Dampers: Galvanized hat-shaped steel channel frame; 14-gauge steel airfoil shaped double skin construction blades; silicone rubber blade edge seals; flexible compression jamb seals; stainless steel bearings, leakage Class II; 4000 fpm velocity rating; damper and operator to be qualified for 350

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



degrees F temperature rating; damper and electric operator shall be normally closed.

2.11 VARIABLE CONTROL DAMPERS

- A. Manufacturers:
 - 1. Greenheck Fan Company;
 - 2. Ruskin Company;
 - 3. T.A. Morrison & Co. (Tamco);
- B. Fabricate in accordance with SMACNA (DCS) and as indicated.
- C. Variable Control Dampers:
 - 1. Dampers shall be supported, plenum openings shall be reinforced, the entire assembly shall be sturdy and operate smoothly; install parallel blade dampers to direct outside and return air into each other for mixing; use parallel blade dampers for outside air, return air, use opposed blade dampers for relief air, ventilation air, exhaust air, and supply air.
 - 2. Low leakage type with spring loaded side seals, inflatable butyl or neoprene fabric edge seals, bronze or Teflon bearings, reinforced extruded aluminum airfoil blades, aluminum frame. Action as indicated on drawings. Air leakage not to exceed 5 CFM per square foot at 4" upstream static pressure.
- D. Single Blade Dampers:
 - 1. Fabricate for duct sizes up to 6 by 30 inch.
 - 2. Blade: 24 gage, 0.0239 inch, minimum.
 - 3. Manufacturers:
 - a. Greenheck; VCD-43.
 - b. Ruskin; CD50.
 - c. Tamco; Series 1000.
- E. Multi-Blade Damper: Fabricate of opposed or parallel blade pattern with maximum blade sizes 8 by 60 inch. Maximum individual damper section height, 60". Maximum individual damper section width, 60".
 - 1. Blade: 18 gage, 0.0478 inch, minimum.
 - 2. Manufacturers:
 - a. Greenheck; VCD-43.
 - b. Ruskin; CD50.
 - c. Tamco; Series 1000.
- F. Quadrants:
 - 1. Provide locking, indicating quadrant regulators on single and multi-blade hand dampers.
 - 2. On insulated ducts, mount quadrant regulators on stand-off mounting brackets, bases, or adapters.
 - 3. Where rod lengths exceed 30 inches provide regulator at both ends.

2.12 MISCELLANEOUS PRODUCTS

- A. Duct Opening Closure Film: Mold-resistant, self-adhesive film to keep debris out of ducts during construction.
 - 1. Thickness: 2 mils.
 - 2. High tack water based adhesive.
 - 3. UV stable light blue color.
 - 4. Elongation Before Break: 325 percent, minimum.
 - 5. Manufacturers:
 - a. Carlisle HVAC Products; Dynair Duct Protection Film:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- b. Elgen Manufacturing; Shrink Wrap w/PSA.
- c. Substitutions: See Section 016000 - Product Requirements.

PART 3 EXECUTION

3.01 PREPARATION

- A. Verify that electric power is available and of the correct characteristics.
- B. Examine areas and conditions under which ductwork accessories will be installed. Do not proceed with work until conditions allow for contamination free duct installation.

3.02 INSTALLATION

- A. Install accessories in accordance with manufacturer's instructions, NFPA 90A, and follow SMACNA (DCS). Refer to Section 233100 for duct construction and pressure class.
- B. Provide backdraft dampers on exhaust fans or exhaust ducts nearest to outside and where indicated.
- C. Provide duct access doors for inspection, cleaning, and maintenance ahead of filters, coils, fans, and automatic dampers, and at fire dampers, combination fire and smoke dampers, and elsewhere as indicated. Provide for cleaning kitchen exhaust ducts in accordance with NFPA 96. Provide duct access door, of adequate size, for equipment requiring hand access or shoulder access, and as indicated. Review duct access door locations with Owner's Representative prior to fabrication.
- D. Provide fire dampers, combination fire and smoke dampers, and smoke dampers at locations indicated, where ducts and outlets pass through fire rated components, and where required by Authorities Having Jurisdiction. Install with required perimeter mounting angles, sleeves, breakaway duct connections, corrosion resistant springs, bearings, bushings and hinges.
- E. Install smoke dampers and combination smoke and fire dampers in accordance with NFPA 92.
- F. Demonstrate re-setting of fire dampers to Owner's representative.
- G. At fans and motorized equipment associated with ducts, provide flexible duct connections immediately adjacent to the equipment.
- H. Install turning vanes in square or rectangular 90 degree elbows in supply and exhaust air systems, and elsewhere as indicated.
- I. At equipment supported by vibration isolators, provide flexible duct connections immediately adjacent to the equipment.
 - 1. Refer to Section 230548.
- J. For fans developing static pressures of 5.0 inches and over, cover flexible connections with leaded vinyl sheet, held in place with metal straps.
- K. **Furnish and install manual balancing dampers on duct take-offs to diffusers, grilles, and registers on zones with multiple outlets.**

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 233600
AIR TERMINAL UNITS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Air terminal units.
 - 1. Single-duct, variable-volume units.
- B. Hot water reheat coil.
- C. Fan-powered units.
- D. Round terminal units.
 - 1. Single-duct, variable volume units.

1.02 RELATED REQUIREMENTS

- A. Section 230513 - Common Motor Requirements for HVAC Equipment.
- B. Section 230548 - Vibration and Seismic Controls for HVAC Piping and Equipment.
- C. Section 230913 - Instruments and Control Elements: Thermostats and actuators.
- D. Section 230923 - Direct-Digital Control System for HVAC.
- E. Section 230993 - Sequence of Operations for HVAC Controls.
- F. Section 232113 - Hydronic Piping: Connections to heating coils.
- G. Section 232114 - Hydronic Specialties: Connections to heating coils.
- H. Section 233100 - HVAC Ducts and Casings.
- I. Section 233300 - Air Duct Accessories.
- J. Section 233700 - Air Outlets and Inlets.
- K. Section 238200 - Convection Heating and Cooling Units: Air coils.
- L. Section 260583 - Wiring Connections: Electrical characteristics and wiring connections.

1.03 REFERENCE STANDARDS

- A. AHRI 410 - Forced-Circulation Air-Cooling and Air-Heating Coils; 2001 (R2011).
- B. AHRI 880 (I-P) - Performance Rating of Air Terminals; 2011 with Addendum 1.
- C. AHRI 885 - Procedure for Estimating Occupied Space Sound Levels in the Application of Air Terminals and Air Outlets; 2008 with Addendum 1.
- D. ASHRAE Std 52.2 - Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size; 2017.
- E. ASHRAE Std 62.1 - Ventilation for Acceptable Indoor Air Quality; 2016.
- F. ASHRAE Std 130 - Methods of Testing Air Terminal Units; 2016.
- G. ASTM A492 - Standard Specification for Stainless Steel Rope Wire; 1995 (Reapproved 2013).
- H. ASTM A603 - Standard Specification for Zinc-Coated Steel Structural Wire Rope; 1998 (Reapproved 2014).
- I. ASTM C1071 - Standard Specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material); 2016.
- J. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- K. ASTM E488/E488M - Standard Test Methods for Strength of Anchors in Concrete Elements; 2015.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- L. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.
- M. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- N. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.
- O. SMACNA (SRM) - Seismic Restraint Manual Guidelines for Mechanical Systems; Sheet Metal and Air Conditioning Contractors' National Association; 2008.
- P. UL 181 - Standard for Factory-Made Air Ducts and Air Connectors; current edition, including all revisions.
- Q. UL 94 - Tests for Flammability of Plastic Materials for Parts in Devices and Appliances; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Conduct a preinstallation meeting prior to the start of the work of this section; require attendance by all affected installers.
- B. Sequencing: Ensure that utility connections are achieved in an orderly and expeditious manner.
- C. Contractor shall provide a first installation of air terminal unit assembly and installation for owner's review. If both dual duct and vav reheat assemblies are used on project, a first installation shall be provided for each type of assembly. First installations, shall be reviewed and approved by owner's representative prior to any additional terminal unit assembly installations for project. After owner approval, all remaining terminal unit assembly installations shall meet standard of approved terminal assembly first installation.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide data indicating configuration, general assembly, and materials used in fabrication. Include catalog performance ratings that indicate air flow, static pressure, and NC designation.
- C. Shop Drawings: Indicate configuration, general assembly, and materials used in fabrication, of air terminal unit assembly. Drawings shall confirm spacing between face of coil and damper housing, as indicated in provided details.
- D. Certificates: Certify that coils are tested and rated in accordance with AHRI 410.
- E. Manufacturer's Installation Instructions: Indicate support and hanging details, installation instructions, recommendations, and service clearances required.
- F. Project Record Documents: Record actual locations of units and locations of access doors required for access of valving.
- G. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, maintenance and repair data, and parts lists.
- H. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.
- I. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- B. Product Listing Organization Qualifications: An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.
- C. Coordinate with Owner's commissioning representative, on first install, to confirm compliance of specification requirements.

1.07 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.

PART 2 PRODUCTS

2.01 AIR TERMINAL UNITS

- A. Manufacturers:
 - 1. Titus; _____
 - 2. Krueger; _____
 - 3. Price Industries, Inc; _____
- B. Basis of Design: Price Industries, Inc.
 - 1. Single-Duct Terminal Unit: SDV5000.
- C. Acoustic Performance Requirements:
 - 1. Use attenuation values found in appendix E of AHRI 885.
- D. General:
 - 1. Factory-assembled, variable volume air control terminal with damper assembly and flow sensor.
 - 2. AHRI 880 (I-P) rated.
- E. Unit Casing:
 - 1. Minimum 22 gage, 0.0299 inch galvanized steel.
 - a. Assembled with longitudinal lock seam construction.
 - b. Casing leakage to meet ASHRAE Std 130.
 - 2. Air Inlet Collar: Provide round, suitable for standard duct sizes 6" dia. and above.
 - 3. Unit Discharge: Rectangular, with slip-and-drive connections.
 - 4. Liner:
 - a. 1/2 inch thick, coated, fibrous-glass.
 - 1) Secure with adhesive.
 - 2) Coat edges exposed to airstream with NFPA 90A approved sealant.
 - 3) Insulation shall comply with the requirements of UL 181 (erosion), ASTM C1338 (fungi resistance), ASHRAE 62.1, and ASTM C1071, having a maximum flame/smoke spread of 25/50 for both the insulation and the adhesive when tested in accordance with ASTM E84.
- F. Damper Assembly:
 - 1. The damper assembly shall be minimum 18 gauge, galvanized steel with a solid shaft rotating in bearings.
 - 2. Provide integral position indicator or alternative method for indicating damper position over full range of 90 degrees. Shaft shall be clearly marked on the end to indicate damper position. The vav box shall incorporate mechanical stops to prevent over stroking of the damper and a synthetic seal to limit close-off leakage.
 - 3. The damper assembly shall incorporate a peripheral gasket on the damper blades for tight airflow shutoff.
 - 4. The air leakage past the closed damper shall not exceed two percent of unit maximum airflow at 3 inch wg inlet static pressure, tested in accordance with ASHRAE Std 130.
- G. Airflow Sensor:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1. The airflow sensor shall be a differential pressure airflow device measuring total and static pressures, and shall be factory mounted to the air inlet collar.
2. Plastic parts shall be fire-resistant, complying with UL 94.
3. Control tubing shall be protected by grommets at the wall of the airflow sensor's housing.
4. The airflow sensor signal accuracy shall be plus or minus five percent throughout terminal operating range.

2.02 HOT WATER REHEAT COIL

- A. Coil Construction:
1. Coil Casing: Minimum 22 gage, 0.0299 inch galvanized steel, casing size to match air terminal unit discharge with rectangular outlet, duct connection type. See installation notes and detail for approved installation location of coil.
 2. Coil Fins: Aluminum or aluminum plated 0.0045 inch fins, mechanically-bonded to seamless 0.50 by 0.016 inch copper tubes.
 - a. Fins to be formed in a high heat transfer sine wave configuration.
 - b. Two rows with ten fins-per-inch heating capacity density.
 3. Coil leak tested to minimum 300 psig.
 4. Base performance data on tests run in accordance with AHRI 410 and units to bear AHRI 410 label.

2.03 FAN-POWERED SERIES UNITS

- A. Manufacturers:
1. Krueger-HVAC; _____: www.krueger-hvac.com
 2. Price Industries, Inc; _____: www.priceindustries.com
 3. Titus.
 4. Substitutions: See Section 016000 - Product Requirements.
- B. General:
1. Factory-assembled and wired, AHRI 880 (I-P) rated, horizontal fan-powered terminal unit with blower, blower motor, mixing plenum, and primary air damper contained in a single unit housing.
- C. Unit Casing:
1. Minimum 22 gage, 0.0299 inch galvanized steel.
 2. Unit Discharge: Rectangular, suitable for flanged duct connection.
 3. Plenum Inlet: Filter rack with disposable filters.
 - a. 1 inch thick disposable fiberglass filters.
 - b. Minimum Efficiency Reporting Value (MERV): 8, when tested in accordance with ASHRAE Std 52.2.
 4. Acceptable Liners:
 - a. 1/2 inch thick, coated, fibrous-glass complying with ASTM C1071.
 - 1) Secure with adhesive.
 - 2) Coat edges exposed to airstream with NFPA 90A approved sealant.
 - 3) Cover liner with non-porous foil.
- D. Primary Air Damper Assembly:
1. Heavy-gauge, galvanized steel or extruded aluminum construction with solid shaft rotating in bearings.
 2. Provide indicator on damper shaft or alternative method for indicating damper position over full range of 90 degrees.
 3. Incorporate low leak (2 percent) damper blades for tight airflow shutoff.
 4. Fan(s): Forward curved, centrifugal type.
 5. Fan Motor:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- a. ECM (Electrically Commutated Motor):
 - 1) Brushless DC controlled by an integrated controller/inverter that operates the wound stator and senses rotor position to electrically commutate the stator.
 - 2) Designed to maintain a minimum of 70 percent efficiency over the entire operating range.
 - b. Fan motor shaft directly connected to fan and isolated from unit casing to prevent transmission of vibration.
- E. Electric Heating Coil:
- 1. Listed and provided by the terminal unit manufacturer.
 - 2. Coil Casing: Minimum 20 gauge, 0.0359 inch galvanized steel.
 - 3. Heating Elements: Open wire, nickel chrome, supported by ceramic insulators.
 - 4. Integral Control Panel: NEMA 250, Type 2 enclosure, with hinged access door for access to all controls and safety devices.
 - 5. Provide a primary automatic reset thermal cutout and differential pressure airflow switch for proof of airflow or electrical interlock to prevent heater operation when fan is not running.
 - 6. Provide the following additional components, mounted and/or wired within the control enclosure:
 - a. Door interlocking disconnect switch.
 - b. Fuse block.
 - 7. Provide SCR (Silicon Controlled Rectifier) controller.
- F. Hot Water Heating Coil:
- 1. Coil Casing: Minimum 22 gauge, 0.0299 inch galvanized steel, factory-installed on terminal unit with flanged discharge for attachment to downstream ductwork.
 - 2. Heavy-gauge aluminum fins, mechanically bonded to tubes.
 - 3. Copper Tubes: 0.016 inch minimum wall thickness with male solder header connections.
 - 4. Coil leak tested to minimum 305 psig.
 - 5. Base performance data on tests run in accordance with AHRI 410.
- G. Electrical Requirements:
- 1. Single-point power connection.
 - 2. Equipment wiring to comply with requirements of NFPA 70.

2.04 ROUND TERMINAL UNITS

- A. Manufacturers:
- 1. Titus; _____
 - 2. Krueger; _____
 - 3. Price Industries, Inc; _____
- B. Basis of Design: Price Industries, Inc.
- 1. General Supply/Exhaust Control Valve: RDV, (direct digital controls).
- C. General:
- 1. The terminal units shall be factory-assembled for variable air volume control with damper assembly and airflow sensor.
 - 2. AHRI 880 (I-P) rated and bearing the AHRI seal.
- D. Construction:
- 1. Casing: Minimum 20 gage, 0.0375 inch galvanized or zinc coated steel, meeting the requirements of NFPA 90A and UL 181.
 - 2. The damper assembly shall be 18 gauge galvanized steel with a solid shaft rotating in bearings.
 - 3. The damper shaft shall incorporate a visual position indicator etched into the end of the damper shaft to clearly indicate damper position over the full range of 90 degrees.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



4. The air terminal unit shall incorporate mechanical stops to prevent over stroking of the damper and shall incorporate a peripheral gasket on the damper blades for tight airflow shutoff.
 5. Air Inlet/Outlet: Suitable for standard duct sizes 6" dia. and above.
 6. Air leakage past the closed damper shall not exceed two percent of the unit maximum airflow at three inches water gauge inlet static pressure, tested in accordance with ASHRAE Std 130.
- E. Airflow Sensor:
1. The airflow sensor shall be a differential pressure airflow device measuring total and static pressures, and shall be factory mounted to the air inlet collar.
 2. Plastic parts shall be fire-resistant, complying with UL 94.
 3. Control tubing shall be protected by grommets at the wall of the airflow sensor's housing.
 4. The airflow sensor signal accuracy shall be plus or minus five percent throughout terminal operating range.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that conditions are suitable for installation.
- B. Verify that field measurements are as indicated on drawings.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install the inlets of air terminal units and air flow sensors a minimum of four duct diameters from elbows, transitions, and duct takeoffs.
- C. Sheet metal contractor shall remove and dispose of entire control box enclosure from all air terminal units prior to installation.
- D. Sheet metal contractor shall permanently cap or plug all air terminal box airflow sensor tubing except when controls contractor requires airflow sensor use.
- E. See drawings for vav box and reheat coil installation details and the size(s) and duct location(s) of all air terminal units.
- F. Install 12" section of ductwork between any air terminal units with reheat coils. Furnish and install a 9"x9" minimum duct access door with, two (2) cam lock latches, in bottom of duct to facilitate inspection and cleaning of reheat coil. Coordinate installation location of assemblies to facilitate inspection and cleaning.
- G. Install 12" long section of lined ductwork matching discharge size of air terminal box(es) or reheat coil whenever discharge duct size is smaller than the discharge size of air terminal box(es) or reheat coil.
- H. Provide ceiling access doors or locate units above easily removable ceiling components.
- I. Support air terminal units individually from structure with 22 gauge hanger strap in accordance with SMACNA (SRM). See Section 230548.
- J. Embed support anchors in concrete in accordance with ASTM E488/E488M.
- K. Do not support air terminal units and reheat coils from ductwork.
- L. Connect to ductwork in accordance with Section 233100.
- M. Provide 1 inch thick acoustically lined ductwork downstream of units.
- N. Verify that electric power is available and of the correct characteristics.
- O. Install reheat coil piping to provide thermal trap by rising supply/return pipes a minimum of 6" rise within three feet of unit.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3.03 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Test and inspect field-assembled components and equipment installation, including connections. Report results in writing.
 - 1. Leak Test:
 - a. After installation, fill water coils and test for leaks.
 - b. Repair leaks and retest until no leaks exist.
 - 2. Operational Test:
 - a. After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 - b. Test and adjust controls and safeties.
 - c. Replace damaged and malfunctioning controls and other equipment.
 - d. Remove and replace malfunctioning units and retest as specified above.

3.04 SCHEDULES - SEE DRAWINGS FOR SCHEDULES OF ALL AIR TERMINALS AND REHEAT COILS. END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



SECTION 233700
AIR OUTLETS AND INLETS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Diffusers.
- B. Critical Environment Laminar Flow Diffusers.
- C. Round ceiling diffusers.
- D. Slot ceiling diffusers.
- E. Registers/grilles.
 - 1. Floor-mounted, linear supply register/grilles.
- F. Door grilles.
- G. Louvers.
- H. Goosenecks.
- I. Gravity ventilators.

1.02 RELATED REQUIREMENTS

- A. Section 099123 - Interior Painting: Painting of ducts visible behind outlets and inlets.

1.03 REFERENCE STANDARDS

- A. AHRI 880 (I-P) - Performance Rating of Air Terminals; 2011 with Addendum 1.
- B. AMCA 500-L - Laboratory Methods of Testing Louvers for Rating; 2015.
- C. AMCA 511 - Certified Ratings Program for Air Control Devices; 2010.
- D. AMCA 550 - Test Method for High Velocity Wind Driven Rain Resistant Louvers; 2015.
- E. ASHRAE Std 70 - Method of Testing the Performance of Air Outlets and Inlets; 2006 (R2011).
- F. ASTM B221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2014.
- G. ASTM B221M - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2013.
- H. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- I. ISO 14644-1 - Cleanrooms and associated controlled environments - Part 1: Classification of air cleanliness by particle concentration; 2015.
- J. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.
- K. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.
- L. NFPA 90B - Standard for the Installation of Warm Air Heating and Air-Conditioning Systems; 2018.
- M. SMACNA (ASMM) - Architectural Sheet Metal Manual; 2012.
- N. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005 (Rev. 2009).

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide data for equipment required for this project. Review outlets and inlets as to size, finish, and type of mounting prior to submission.
- C. Project Record Documents: Record actual locations of air outlets and inlets.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



1.05 QUALITY ASSURANCE

- A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70.
- B. Test and rate louver performance in accordance with AMCA 500-L.
- C. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.
- D. Coordinate with Owner's commissioning representative, on first install, to confirm compliance of specification requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Diffusers and Grilles:
 - 1. Titus, a brand of Air Distribution Technologies;
 - 2. Hart & Cooley, Inc.;
 - 3. Price Industries;
 - 4. Krueger-HVAC, Division of Air System Components; _____
- B. Louvers:
 - 1. Greenheck Fan Corporation;
 - 2. Ruskin Company;
 - 3. Pottorff;
- C. Substitutions: See Section 016000 - Product Requirements.

2.02 ROUND CEILING DIFFUSERS

- A. Type: Round, adjustable horizontal discharge pattern, three cone diffuser to discharge air in 360 degree pattern.
- B. Fabrication: Steel with baked enamel finish.
- C. Connections: Round.
- D. Color: As indicated on drawings.
- E. Models:
 - 1. Titus No. TMR
 - 2. Hart & Cooley No. 20
 - 3. Price No. RCD
 - 4. Krueger No. RM1

2.03 SQUARE CEILING SUPPLY AIR DIFFUSERS - MODULAR T-BAR

- A. Type: Square, 24" x 24" module, border type for lay-in installation, removable plaque design for all neck sizes. Type as specified on drawings.
- B. Connections: Round.
- C. Frame: Provide inverted T-bar type as indicated on drawings.
- D. Fabrication: Steel with baked enamel finish.
- E. Color: As indicated on drawings.
- F. Accessories: Furnish diffuser with adjustable pattern controller, to adjust discharge pattern from horizontal to vertical, for diffusers installed 12 feet above finished floor and higher.
- G. Models:
 - 1. Titus No. OMNI
 - 2. Price No. SPD
 - 3. Krueger No. PLQ

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.04 SQUARE CEILING SUPPLY AIR DIFFUSERS - MODULAR SURFACE MOUNT

- A. Type: Square, full faced, 24" x 24" module, border type for surface installation, removable plaque design for all neck sizes. Type as specified on drawings.
- B. Connections: Round.
- C. Frame Provide surface mount type as indicated on drawings.
- D. Fabrication: Steel with baked enamel finish.
- E. Color: As indicated on drawings.
- F. Accessories: Furnish diffuser with adjustable pattern controller, to adjust discharge pattern from horizontal to vertical, for diffusers installed 12 feet above finished floor and higher.
- G. Models:
 - 1. Titus No. OMNI
 - 2. Price No. SPD
 - 3. Krueger No. PLQ

2.05 SQUARE AND RECTANGULAR SUPPLY AIR DIFFUSERS

- A. Type: Square or rectangular louvered face ceiling diffuser with square or rectangular neck, field removeable core, and with one-, two-, three-, or four-way horizontal discharge pattern.
- B. Connections: Square, rectangular, and transition piece for round.
- C. Frame: Provide surface mount type as indicated on drawings.
- D. Fabrication: Heavy gauge steel with baked enamel finish.
- E. Color: As indicated on drawings.
- F. Accessories: Furnish diffuser with moveable vanes, to adjust discharge pattern from horizontal to vertical, for diffusers installed 12 feet above finished floor and higher.
- G. Models:
 - 1. Titus No. TDC
 - 2. Hart & Cooley No. SRE
 - 3. Price No. SMD
 - 4. Krueger No. SHPC

2.06 CRITICAL ENVIRONMENT LAMINAR FLOW DIFFUSERS

- A. Type: Low velocity, non-aspirating, laminar flow, radial perforated face, 24" x 24" or 24" x 48" module sizes, border type for lay-in or surface mount, as per drawings.
- B. Connections: Round
- C. Frame: Steel, aluminum, or stainless steel, as per application, as specified by engineer.
- D. Face: Steel, aluminum, or stainless steel, as per application, as specified by engineer. Face shall be completely removable for cleaning, and shall have safety cables to prevent accidental falling or removal.
- E. Fabrication: Steel, aluminum, or stainless steel, pan and face as per application, as specified by engineer. Baked enamel finish.
- F. Color: As indicated on drawings.
- G. Models:
 - 1. Titus No. TLF
 - 2. Price No. LFD
 - 3. Krueger No. 5000

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



2.07 PERFORATED FACE RETURN AIR GRILLES - T-BAR

- A. Type: Perforated face, border type for lay-in installation.
- B. Frame: Inverted T-bar type, module sizes 12" x 24" or 24" x 24".
- C. Fabrication: Steel with steel frame and baked enamel finish.
- D. Color: As indicated on drawings.
- E. Models:
 - 1. Titus No. PAR
 - 2. Hart & Cooley No. PDF
 - 3. Price No. PFRF
 - 4. Krueger No. 1190

2.08 PERFORATED FACE RETURN AIR GRILLES - SURFACE MOUNT

- A. Type: Perforated face, border type for surface installation.
- B. Frame: Surface mount type, size as per drawings.
- C. Fabrication: Steel with steel frame and baked enamel finish.
- D. Color: As indicated on drawings.
- E. Models:
 - 1. Titus No. PAR
 - 2. Hart & Cooley No. PDF
 - 3. Price No. PFRF
 - 4. Krueger No. 1190

2.09 CEILING SLOT DIFFUSERS

- A. Type: Continuous, 1/2 in., 3/4 in., 1 in. wide slot, one - eight slots wide, and 1 1/2 in. or 2" in. wide slot, one - four slots wide, as per drawings.
- B. Fabrication: Extruded aluminum construction with factory baked enamel finish.
- C. Color: As indicated on the drawings.
- D. Frame: T-bar ceiling mounting or surface mounting with screw or concealed fastening, as per drawings.
- E. Plenum: Integral, galvanized steel, insulated.
- F. Accessories: Pattern controllers, concealed mounting brackets, mitered corners assemblies, blank offs, and alignment strips.
- G. Models:
 - 1. Titus No. ML
 - 2. Price No. SDS
 - 3. Krueger No. 1900

2.10 CEILING EGG CRATE EXHAUST GRILLES

- A. Type: Egg crate style face consisting of 1/2 by 1/2 by 1/2 inch grid core.
- B. Fabrication: Grid core consists of aluminum with mill aluminum finish.
- C. Color: As indicated on the drawings.
- D. Frame: The grille shall be suitable for surface or T-bar lay-in mounting, as specified on drawings, and shall have one of the following frame types:
 - 1. 1 1/4" flat face frame with countersunk screws for surface mounting
 - 2. 1 1/4" curved face frame with countersunk screws for surface mounting.
 - 3. Flat T-bar frame for T-bar mounting.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



4. Panel mount frame for T-bar mounting. The maximum grille size shall equal the module size minus four inches. The panel module size options for T-bar ceilings are:
 - a. 24 x 12 inches.
 - b. 24 x 24 inches.

- E. Models:
1. Titus No. 50F
 2. Price 80 Series
 3. Krueger No. EGC5

2.11 WALL SUPPLY GRILLES

- A. Type: Streamlined and individually adjustable blades, 3/4 inch minimum depth, 3/4 inch maximum spacing, horizontal face, double deflection.
- B. Frame: 1-1/4 inch margin with countersunk screw mounting and gasket.
- C. Fabrication: Steel with 1 - 1 1/2 inch minimum frames and 22 gage, 0.0299 inch minimum blades, with factory baked enamel finish.
- D. Color: As indicated on the drawings.
- E. Damper: Integral, gang-operated opposed blade type with removable key operator, operable from face. Included only when specified on drawings, by engineer.
- F. Models:
 1. Titus No. 300FL
 2. Price No. 520
 3. Krueger No. 880H
 4. Hart & Cooley No. 92HVO

2.12 WALL RETURN AND EXHAUST GRILLES

- A. Type: Streamlined and parallel fixed blades set at a 30 - 45 degree deflection to provide return or exhaust air with minimum see-through.
- B. Frame: 1-1/4 inch margin with countersunk screw mounting and gasket.
- C. Fabrication: Steel with 20 gage, 0.0359 inch minimum frames and 22 gage, 0.0299 inch minimum blades, with factory baked enamel finish.
- D. Color: As indicated on the drawings.
- E. Models:
 1. Titus No. 350RL
 2. Price No. 530
 3. Krueger No. S80
 4. Hart & Cooley 94A

2.13 LINEAR FLOOR SUPPLY REGISTERS/GRILLES

- A. Type: Streamlined blades with 0 or 15 degree deflection, 1/8 by 3/4 inch on 1/4 inch centers, assembled on expanded tubes mandrel construction.
- B. Frame: 1 - 1-1/4 inch heavy margin frame with countersunk screw mounting.
- C. Fabrication: Aluminum extrusions with factory baked enamel finish.
- D. Color: As indicated on the drawings.
- E. Damper: Integral opposed blade volume damper with screwdriver operator, operable from face.
- F. Models:
 1. Price No. LBPH, LBMH
 2. Krueger No. 1800

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



3. Shoemaker LF Series
4. Hart & Cooley No. 531

2.14 DOOR GRILLES

- A. Type: V-shaped louvers of 20 gage, 0.0359 inch thick steel, 1 inch deep on 1/2 inch centers.
- B. Frame: 20 gage, 0.0359 inch steel with auxiliary frame to give finished appearance on both sides of door, with factory prime coat finish.

2.15 LOUVERS

- A. General: AMCA rated drainable, stationary extruded aluminum weather louvers. Stationary louvers shall be sized to pass 1000 feet per minute velocity with less than 0.2" static pressure drop and shall carry less than 0.03 ounces of water per square foot when tested in accordance with AMCA Standard 500.
- B. Type: 4" or 6" deep, with integral gutters incorporated into blades, louver head, and jamb frames to drain water from louver.
- C. Fabrication: Louver blade and frame nominal wall thickness shall be 0.081" thick minimum, welded assembly, with factory clear anodized finish. Expanded, flattened aluminum bird screen in removable frame. All louvers shall be one piece.
- D. Color: Clear anodized finish, unless otherwise specified on drawings..
- E. Mounting: Contractor must coordinate louver size and flange type with structural and architectural openings to assure fit and appearance.
- F. Models:
 1. Ruskin No. ELF375DX or ELF6375DX
 2. Greenheck No. EDJ401 or EDJ601
 3. Pottorff No. EFJ-437-HP or EFJ-637-HP
 4. American Warming and Ventilating No. LE-23 or LE-33

2.16 GOOSENECKS

- A. Fabricate in accordance with SMACNA (DCS) of minimum 18 gage, 0.0598 inch galvanized steel.
- B. Mount on minimum 12 inch high curb base where size exceeds 9 by 9 inch.

2.17 GRAVITY VENTILATORS

- A. Hood Intake and Relief Gravity Ventilator:
 1. Manufacturers:
 - a. Twin City Fan & Blower; _____
 - b. Greenheck Fan Corporation; _____
 - c. Loren Cook Company; _____
 - d. Substitutions: See Section 016000 - Product Requirements.
 2. General:
 - a. Low silhouette for intake and relief applications with natural gravity or negative pressure system(s).
 - b. Performance ratings and factory testing to be in accordance with AMCA 511 and AMCA 550.
 - c. Suitable for non-ducted applications.
 - d. Equipment to bear permanently affixed manufacturer's nameplate listing model and serial number.
 3. Hood and Base:
 - a. Material: Galvanized steel.
 - b. Hood Construction: Precision formed, arched panels with interlocking seams.
 - c. Vertical End Panels: Fully locked into hood end panels.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- d. Curb Cap: Pre-punched mounting holes for installation.
 - 4. Bird screen:
 - a. Fabricate in accordance with ASTM B221 (ASTM B221M).
 - b. Construction: 1/2 inch Galvanized mesh.
 - c. Horizontally mounted across hood intake area.
 - 5. Hood Support: Galvanized steel construction and fastened so hood can be removed completely from the base or hinged open.
 - 6. Options/Accessories:
 - a. Roof Curbs:
 - 1) Flat Roofs:
 - (a) Welded, straight side, 24 inch high curb with flashing flange and wood nailer.
 - 2) Pitched Roofs: Welded, straight side, 24" high curb with flashing flange and wood nailer.
 - b. Curb Seal: Rubber seal between hood and roof curb.
 - c. Factory Finish: Baked enamel matching or complementing building colors.
 - d. Insect Screen:
 - 1) Fabricate in accordance with ASTM B221 (ASTM B221M).
 - 2) Construct of fine mesh aluminum.
 - 3) Fitted to top of the throat to prevent entry of insects.
 - e. Tie-Down Points: Aluminum brackets located on hood supports to secure fan in heavy wind applications.
- B. Spun Aluminum Intake and Relief Gravity Ventilator:
- 1. Manufacturers:
 - a. Twin City Fan & Blower; _____
 - b. Greenheck Fan Corporation; _____
 - c. Loren Cook Company; _____
 - d. Substitutions: See Section 016000 - Product Requirements.
 - 2. General:
 - a. Provide low silhouette configuration for intake and relief applications with natural gravity or negative pressure system.
 - b. Performance ratings and factory testing to be in accordance with AMCA 511 and AMCA 550.
 - c. Suitable for non-ducted applications.
 - d. Equipment to bear permanently affixed manufacturer's nameplate listing model and serial number.
 - 3. Hood:
 - a. Material: Aluminum.
 - b. Internal structure constructed of galvanized steel.
 - 4. Bird screen:
 - a. Fabricate in accordance with ASTM B221 (ASTM B221M).
 - b. Construction: 1/2 inch galvanized mesh.
 - c. Horizontally mounted across hood intake area.
 - 5. Housing:
 - a. Curb Cap:
 - 1) Type: No Hinged.
 - 2) Construction: Aluminum.
 - 3) Integral deep spun inlet venturi with pre-punched mounting holes to ensure correct attachment to roof.
 - b. Wind band:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 1) One piece spun aluminum construction with uniform, original material thickness throughout the housing.
 - 2) Include integral rolled bead for strength.
6. Options/Accessories:
- a. Roof Curbs:
 - 1) Flat Roofs:
 - (a) Welded, straight side, 24" high curb with flashing flange and wood nailer.
 - 2) Pitched Roofs: Welded, straight side, 24" high curb with flashing flange and wood nailer.
 - b. Curb Seal: Rubber seal between hood and roof curb.
 - c. Dampers:
 - 1) Type: Gravity.
 - 2) Factory designed to prevent outside air from entering back into building when fan is off.
 - 3) Balanced for minimal resistance to flow.
 - 4) Galvanized frames with pre-punched mounting holes.
 - d. Factory Finish: Baked enamel matching or complementing building colors.
 - e. Insect Screen:
 - 1) Fabricate in accordance with ASTM B221 (ASTM B221M).
 - 2) Fine mesh aluminum construction.
 - 3) Fitted to top of the throat to prevent entry of insects.
 - f. Tie-Down Points: Aluminum brackets located on hood supports to secure fan in heavy wind applications.
- C. Non-Powered Gravity Upblast Roof Ventilator:
1. Manufacturers:
 - a. Twin City Fan & Blower; _____
 - b. Greenheck Fan Corporation; _____
 - c. Loren Cook Company; _____
 - d. Substitutions: See Section 016000 - Product Requirements.
 2. General:
 - a. Discharge air directly away from the mounting surface.
 - b. Roof mounted applications designed for use as a weatherproof outlet on vertical, high velocity exhaust systems.
 - c. Performance ratings and factory testing to be in accordance with AMCA 511 and AMCA 550.
 3. Butterfly Dampers:
 - a. Material: Aluminum.
 - b. Designed to provide weather protection and prevent backdraft.
 - c. Blades with rubber seal.
 - d. Balanced for minimal resistance to flow.
 4. Wind band:
 - a. Construct from heavy gage, galvanized steel with reinforced and bolted seams.
 - b. Removable wind band to gain access through the butterfly dampers.
 - c. Directs exhaust air away from mounting surface.
 5. Curb Caps:
 - a. Aluminum construction.
 - b. Includes pre-punched mounting holes to ensure correct attachment to roof.
 6. Options/Accessories:
 - a. Curb Seal: Rubber seal between hood and roof curb.
 - b. Finish: Baked enamel matching or complementing building colors.
 - c. Roof Curbs:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



- 1) Flat Roofs:
 - (a) Welded, straight side, 24 inch high curb with flashing flange and wood nailer.
 - 2) Pitched Roofs: Welded, straight side, 24 inch high curb with flashing flange and wood nailer.
 - 3) Coating: Baked enamel matching or complementing building colors.
 - d. Tie-Down Points: Aluminum brackets located on hood supports to secure fan in heavy wind applications.
- D. Extruded Aluminum Intake and Relief Ventilator:
1. Manufacturers:
 - a. Twin City Fan & Blower; _____
 - b. Greenheck Fan Corporation; _____
 - c. Loren Cook Company; _____
 - d. Substitutions: See Section 016000 - Product Requirements.
 2. Construction:
 - a. Extruded aluminum louvers, 0.081 inch thick, mitered at corners and welded for maximum strength.
 - b. Removable Hood: 0.05 inch, reinforced and braced for extra strength.
 - c. Base: 0.08 inch aluminum with mitered corners and seams with continuous weld for strength and tightness.
 - d. Bird Screen Galvanized welded wire fabricated in accordance with ASTM B221 (ASTM B221M).
 - e. Performance ratings and factory testing to be in accordance with AMCA 511 and AMCA 550.
 3. Options/Accessories:
 - a. Insect screen fabricated in accordance with ASTM B221 (ASTM B221M).
 - b. Coatings: Protective.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Comply with SMACNA (ASMM) for flashing/counter-flashing of roof penetrations and supports for roof curbs and roof mounted equipment.
- C. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.
- D. Install diffusers to ductwork with air tight connection.
- E. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille and register assembly.

3.02 AIR OUTLET AND INLET SCHEDULE - SEE DRAWING SCHEDULES.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 000110
TABLE OF CONTENTS
ELECTRICAL SPECIFICATIONS**

SPECIFICATIONS

DIVISION 26 -- ELECTRICAL

- 260505 - Selective Demolition for Electrical
- 260529 – Hangers and supports for Electrical Systems
- 260533.16 - Boxes for Electrical Systems
- 260553 – Identification for Electrical Systems
- 260923 - Lighting Control Devices
- 262725 - Wiring Devices
- 265013 – Luminaire Schedule
- 265100 – Interior Lighting

DIVISION 28 -- ELECTRONIC SAFETY AND SECURITY

- 284050 - Conductors and Cables for Fire Detection and Alarm

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Downloaded from SpecLink: May 05, 2023

Signature & Date: _____



**SECTION 260505
SELECTIVE DEMOLITION FOR ELECTRICAL**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Electrical demolition.

1.02 RELATED REQUIREMENTS

- A. Section 017000 - Execution and Closeout Requirements: Additional requirements for alterations work.
- B. Section 028400 - Polychlorinate Biphenyl (PCB) Remediation: Removal of equipment and materials containing substances regulated under the Federal Toxic Substances Control Act (TSCA), including but not limited to those containing PCBs and mercury.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.

PART 2 PRODUCTS

2.01 MATERIALS AND EQUIPMENT

- A. Materials and equipment for patching and extending work: As specified in individual sections.
- B. Any existing equipment or materials to remain or be reused, shall meet current individual sections.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify field measurements and circuiting arrangements are as indicated.
- B. Verify that abandoned wiring and equipment serve only abandoned facilities.
- C. Demolition drawings are based on casual field observation and existing record documents.
- D. Report discrepancies to Owner and Owner's Construction Project Coordinator, before disturbing existing installation.
- E. Beginning of demolition means installer accepts existing conditions.

3.02 PREPARATION

- A. Disconnect electrical systems in walls, floors, and ceilings to be removed.
- B. Coordinate utility service outages with Owner and utility provider.
- C. Provide temporary wiring and connections to maintain existing systems in service during construction.
- D. When work must be performed on energized equipment or circuits, use personnel experienced in such operations, with appropriate safety equipment and practices.
- E. Existing Electrical Service: Maintain existing system in service until new system is complete and ready for service. Disable system only to make switchovers and connections. Minimize outage duration.
 - 1. Obtain permission from Owner at least 72 hours before partially or completely disabling system, unless otherwise indicated.
 - 2. Make temporary connections to maintain service in areas adjacent to work area as indicated.
- F. Existing Fire Alarm System: Maintain existing system in service until new system is accepted. Disable system only to make switchovers and connections. Minimize outage duration.
 - 1. Coordinate with Owner at least 72 hours before partially or completely disabling system.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



2. Make temporary connections to maintain service in areas adjacent to work area. In areas where fire alarm system is inoperable, provide fire watch per Division 28.
 3. For occupied buildings, provide a Fire Watch, per Section 284600, for all areas where the fire alarm detection and/or annunciation devices have been removed.
- G. Existing Telephone/Data System: Maintain existing system in service until new system is complete and ready for service. Disable system only upon the approval of the Owner's Office of Information Technology (OIT), to make switchovers and connections. Minimize outage duration.
1. Coordinate with Owner at least 72 hours before partially or completely disabling system.
 2. Notify Owner's Office of Information Technology (OIT) at least 24 hours before partially or completely disabling system.

3.03 DEMOLITION AND EXTENSION OF EXISTING ELECTRICAL WORK

- A. Contractor to perform work for removal of equipment and materials containing toxic substances, regulated under the Federal Toxic Substances Control Act (TSCA), in accordance with Section 028400 and applicable federal, state, and local regulations. Return equipment and materials to Owner's Chemical Management Building, for disposal by the Owner. Applicable equipment and materials include, but are not limited to:
1. PCB-containing electrical equipment, including transformers, capacitors, and switches.
 2. PCB- and DEHP-containing lighting ballasts.
 3. Mercury-containing lamps and tubes, including fluorescent lamps, high intensity discharge (HID), arc lamps, ultra-violet, high pressure sodium, mercury vapor, ignitron tubes, neon, and incandescent.
- B. Remove, relocate, and extend existing installations to accommodate new construction.
- C. Remove abandoned wiring to source of supply.
- D. Remove exposed abandoned conduit, including abandoned conduit above accessible ceiling finishes. Cut conduit flush with walls and floors, and patch surfaces.
- E. Disconnect abandoned outlets and remove devices. Remove abandoned outlets if conduit servicing them is abandoned and removed. Provide blank cover for abandoned outlets that are not removed.
- F. Disconnect and remove abandoned panelboards and distribution equipment.
- G. Disconnect and remove electrical devices and equipment serving utilization equipment that has been removed.
- H. Disconnect and remove abandoned luminaires. Remove brackets, stems, hangers, and other accessories, complete. Remove ballasts and lamps from light fixtures being abandoned. Place ballasts and lamps in Owner furnished barrels. Ballasts and lamps to be disposed of by the Owner.
- I. Repair adjacent construction and finishes damaged during demolition and extension work.
- J. Maintain access to existing electrical installations that remain active. Modify installation or provide access panel as appropriate.
- K. Protect existing electrical equipment and installations indicated to remain. If damaged or disturbed in the course of the Work, remove damaged portions and install new products of equal capacity, quality, and functionality.
- L. Accessible Work: Remove exposed electrical equipment and installations, indicated to be demolished, in their entirety.
- M. Abandoned Work: Cap raceways and patch surface to match existing finish.
- N. Remove demolished material from Project site.
- O. Remove, store, clean, reinstall, reconnect, and make operational components indicated for relocation.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- P. Extend existing installations using materials and methods compatible with existing electrical installations, or as specified.
- Q. In areas where the electrical panel feeds loads in areas not affected by this project, do not turn off circuit breakers until the entire circuit have been verified to not affect areas outside this project.

3.04 CLEANING AND REPAIR

- A. See Section 017419 - Construction Waste Management and Disposal for additional requirements.
- B. Clean and repair existing materials and equipment that remain or that are to be reused.
- C. Panelboards: Clean interior and exposed surfaces. Replace damaged circuit breakers and provide closure plates for vacant positions. Provide typed circuit directory showing revised circuiting arrangement.
- D. Luminaires: Remove existing luminaires for cleaning. Use mild detergent to clean all exterior and interior surfaces; rinse with clean water and wipe dry.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



SECTION 260529
HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Support and attachment components for equipment, conduit, cable, boxes, and other electrical work.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete: Concrete equipment pads.
- B. Section 055000 - Metal Fabrications: Materials and requirements for fabricated metal supports.
- C. Section 260533.13 - Conduit for Electrical Systems: Additional support and attachment requirements for conduits.
- D. Section 260536 - Cable Trays for Electrical Systems: Additional support and attachment requirements for cable tray.
- E. Section 260533.16 - Boxes for Electrical Systems: Additional support and attachment requirements for boxes.
- F. Section 260548 - Vibration and Seismic Controls for Electrical Systems.
- G. Section 262513 - Low-Voltage Busways: Additional support and attachment requirements for busway.
- H. Section 265100 - Interior Lighting: Additional support and attachment requirements for interior luminaires.
- I. Section 265113 - Luminaires, Ballasts, and Drivers: Additional support and attachment requirements for luminaires.
- J. Section 265600 - Exterior Lighting: Additional support and attachment requirements for exterior luminaires.

1.03 REFERENCE STANDARDS

- A. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- B. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2016a.
- C. ASTM B633 - Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel; 2015.
- D. MFMA-4 - Metal Framing Standards Publication; 2004.
- E. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- F. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. UL 5B - Strut-Type Channel Raceways and Fittings; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate sizes and arrangement of supports and bases with the actual equipment and components to be installed.
 - 2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 - 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



4. Coordinate the arrangement of supports with ductwork, piping, equipment and other potential conflicts installed under other sections or by others.
5. Notify Architect and Owner's Construction Project Coordinator, of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

B. Sequencing:

1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for metal channel (strut) framing systems, non-penetrating rooftop supports, and post-installed concrete and masonry anchors.
- C. Shop Drawings: Include details for fabricated hangers and supports where materials or methods other than those indicated are proposed for substitution.
- D. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

1.06 QUALITY ASSURANCE

- A. Comply with NFPA 70.
- B. Comply with applicable building code.
- C. Maintain at the project site a copy of each referenced document that prescribes execution requirements.
- D. Installer Qualifications for Powder-Actuated Fasteners (when specified): Certified by fastener system manufacturer with current operator's license.
- E. Product Listing Organization Qualifications: An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 SUPPORT AND ATTACHMENT COMPONENTS

- A. General Requirements:
 1. Provide all required hangers, supports, anchors, fasteners, fittings, accessories, and hardware as necessary for the complete installation of electrical work.
 2. Provide products listed, classified, and labeled as suitable for the purpose intended, where applicable.
 3. Where support and attachment component types and sizes are not indicated, select in accordance with manufacturer's application criteria as required for the load to be supported _____. Include consideration for vibration, equipment operation, and shock loads where applicable.
 4. Do not use products for applications other than as permitted by NFPA 70 and product listing.
 5. Do not use wire, chain, perforated pipe strap, or wood for permanent supports unless specifically indicated or permitted.
 6. Steel Components: Use corrosion resistant materials suitable for the environment where installed.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- a. Indoor Dry Locations: Use zinc-plated steel or approved equivalent unless otherwise indicated.
 - b. Outdoor and Damp or Wet Indoor Locations: Use galvanized steel, stainless steel, or approved equivalent unless otherwise indicated.
 - c. Zinc-Plated Steel: Electroplated in accordance with ASTM B633.
 - d. Galvanized Steel: Hot-dip galvanized after fabrication in accordance with ASTM A123/A123M or ASTM A153/A153M.
- B. Materials for Metal Fabricated Supports: Comply with Section 055000.
- C. Conduit and Cable Supports: Straps, clamps, etc. suitable for the conduit or cable to be supported.
- 1. Conduit Straps: One-hole or two-hole type; steel.
 - 2. Conduit Clamps: Bolted type unless otherwise indicated.
 - 3. Use of cable/conduit clips (batwings) are not an approved method for conduit supports.
- D. Outlet Box Supports: Hangers, brackets, etc. suitable for the boxes to be supported.
- E. Metal Channel (Strut) Framing Systems: Factory-fabricated continuous-slot metal channel (strut) and associated fittings, accessories, and hardware required for field-assembly of supports.
- 1. Comply with MFMA-4.
 - 2. Channel (Strut) Used as Raceway (only where specifically indicated): Listed and labeled as complying with UL 5B.
 - 3. Channel Material:
 - a. Indoor Dry Locations: Use galvanized steel.
 - b. Outdoor and Damp or Wet Indoor Locations: Use galvanized steel.
 - 4. Minimum Channel Thickness: Steel sheet, 12 gage, 0.1046 inch.
 - 5. Minimum Channel Dimensions: 1-5/8 inch width by 13/16 inch height.
 - 6. Minimum Channel Length 24 inches.
 - 7. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation; _____: www.cooperindustries.com
 - b. Thomas & Betts Corporation; _____: www.tnb.com
 - c. Unistrut, a brand of Atkore International Inc; _____: www.unistrut.com
 - d. nVent/Caddy.
- F. Hanger Rods: Threaded zinc-plated steel unless otherwise indicated.
- 1. Minimum Size, Unless Otherwise Indicated or Required:
 - a. Equipment Supports: Hanger rods per equipment manufacturers recommendations or per the recommendations of a licensed structural engineer.
 - b. Busway Supports: Hanger rods per equipment manufacturers recommendations or per the recommendations of a licensed structural engineer.
 - c. Single Conduit up to 1 inch (27 mm) trade size: 1/4 inch diameter.
 - d. Single Conduit larger than 1 inch (27 mm) trade size: 3/8 inch diameter.
 - e. Trapeze Support for Multiple Conduits: 3/8 inch diameter.
 - f. Outlet Boxes: 1/4 inch diameter.
 - g. Luminaires: 1/4 inch diameter.
- G. Non-Penetrating Rooftop Supports for Low-Slope Roofs: Steel pedestals with thermoplastic or rubber bases that rest on top of roofing membrane, not requiring any attachment to the roof structure and not penetrating the roofing assembly, with support fixtures as specified.
- 1. Base Sizes: As required to distribute load sufficiently to prevent indentation of roofing assembly.
 - 2. Attachment/Support Fixtures: As recommended by manufacturer, same type as indicated for equivalent indoor hangers and supports.
 - 3. Mounting Height: Provide minimum clearance of 2" inches under supported component to top of roofing.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 4. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation; _____: www.cooperindustries.com
 - b. Erico International Corporation; _____: www.erico.com
 - c. Unistrut, a brand of Atkore International Inc: www.unistrut.com

H. Anchors and Fasteners:

- 1. Unless otherwise indicated and where not otherwise restricted, use the anchor and fastener types indicated for the specified applications.
- 2. Concrete: Use preset concrete inserts, expansion anchors, or screw anchors.
- 3. Solid or Grout-Filled Masonry: Use expansion anchors or screw anchors.
- 4. Hollow Masonry: Use toggle bolts.
- 5. Hollow Stud Walls: Use toggle bolts.
- 6. Steel: Use beam clamps, machine bolts, or welded threaded studs.
- 7. Sheet Metal: Use sheet metal screws.
- 8. Wood: Use wood screws.
- 9. Plastic and lead anchors are permitted.
- 10. Powder-actuated fasteners are permitted.
 - a. Use only threaded studs; do not use pins.
- 11. Hammer-driven anchors and fasteners are permitted..
 - a. Nails are permitted for attachment of nonmetallic boxes to wood frame construction (when specified).
 - b. Staples are permitted for attachment of nonmetallic-sheathed cable to wood frame construction (when specified).
- 12. Preset Concrete Inserts: Continuous metal channel (strut) and spot inserts specifically designed to be cast in concrete ceilings, walls, and floors.
 - a. Comply with MFMA-4.
 - b. Channel Material: Use galvanized steel.
 - c. Minimum Channel Thickness: Steel sheet, 12 gage, 0.1046 inch minimum base metal thickness.
 - d. Manufacturer: Same as manufacturer of metal channel (strut) framing system.
- 13. Post-Installed Concrete and Masonry Anchors: Evaluated and recognized by ICC Evaluation Service, LLC (ICC-ES) for compliance with applicable building code.
- 14. Manufacturers - Mechanical Anchors:
 - a. Hilti, Inc; _____: www.us.hilti.com
 - b. ITW Red Head, a division of Illinois Tool Works, Inc; _____: www.itwredhead.com
 - c. Powers Fasteners, Inc; _____: www.powers.com
 - d. Simpson Strong-Tie Company Inc; _____: www.strongtie.com
 - e. Substitutions: See Section 016000 - Product Requirements.
- 15. Manufacturers - Powder-Actuated Fastening Systems:
 - a. Hilti, Inc; _____: www.us.hilti.com
 - b. ITW Ramset, a division of Illinois Tool Works, Inc; _____: www.ramset.com
 - c. Powers Fasteners, Inc; _____: www.powers.com
 - d. Simpson Strong-Tie Company Inc; _____: www.strongtie.com

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive support and attachment components.
- C. Verify that conditions are satisfactory for installation prior to starting work.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
- D. Unless specifically indicated or approved by Architect, do not provide support from suspended ceiling support system or ceiling grid.
- E. Unless specifically indicated or approved by Architect, do not provide support from metal roof deck.
- F. Do not penetrate or otherwise notch or cut structural members without approval of Structural Engineer.
- G. Provide required vibration isolation and/or seismic controls in accordance with Section 260548.
- H. Field-Welding (where approved by Architect): Comply with Section 055000.
- I. Equipment Support and Attachment:
 - 1. Use metal fabricated supports or supports assembled from metal channel (strut) to support equipment as required.
 - 2. Use metal channel (strut) secured to studs to support equipment surface-mounted on hollow stud walls when wall strength is not sufficient to resist pull-out.
 - 3. Use metal channel (strut) to support surface-mounted equipment in wet or damp locations to provide space between equipment and mounting surface.
 - 4. Unless otherwise indicated, mount floor-mounted equipment on properly sized 4 inch high concrete pad constructed in accordance with Section 033000.
 - 5. Securely fasten floor-mounted equipment. Do not install equipment such that it relies on its own weight for support.
- J. Conduit Support and Attachment: Also comply with Section 260533.13.
- K. Cable Tray Support and Attachment: Also comply with Section 260536.
- L. Box Support and Attachment: Also comply with Section 260533.16.
- M. Busway Support and Attachment: Also comply with Section 262513.
- N. Interior Luminaire Support and Attachment: Also comply with Section 265100.
- O. Exterior Luminaire Support and Attachment: Also comply with Section 265600.
- P. Preset Concrete Inserts: Use manufacturer provided closure strips to inhibit concrete seepage during concrete pour.
- Q. Secure fasteners according to manufacturer's recommended torque settings.
- R. Remove temporary supports.
- S. Identify independent electrical component support wires above accessible ceilings (only where specifically indicated or permitted) with color distinguishable from ceiling support wires in accordance with NFPA 70.
- T. Multiple Raceway trapeze-type support structure minimum width shall be 24 inches, unless specified otherwise. For shorter widths, obtain permission from the Owners engineer, prior to installation. Sized support structure so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.

3.03 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect support and attachment components for damage and defects.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- C. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.
- D. Correct deficiencies and replace damaged or defective support and attachment components.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



SECTION 260533.16
BOXES FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Outlet and device boxes up to 100 cubic inches, including those used as junction and pull boxes.
- B. Cabinets and enclosures, including junction and pull boxes larger than 100 cubic inches.
- C. Boxes and enclosures for integrated power, data, and audio/video.
- D. Boxes for hazardous (classified) locations.
- E. Floor boxes.
- F. Underground boxes/enclosures.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete.
- B. Section 078400 - Firestopping.
- C. Section 083100 - Access Doors and Panels: Panels for maintaining access to concealed boxes.
- D. Section 260526 - Grounding and Bonding for Electrical Systems.
- E. Section 260529 - Hangers and Supports for Electrical Systems.
- F. Section 260533.13 - Conduit for Electrical Systems:
 - 1. Conduit bodies and other fittings.
 - 2. Additional requirements for locating boxes to limit conduit length and/or number of bends between pulling points.
- G. Section 260533.23 - Surface Raceways for Electrical Systems:
 - 1. Accessory boxes designed specifically for surface raceway systems.
- H. Section 260539 - Underfloor Raceways for Electrical Systems:
- I. Section 260553 - Identification for Electrical Systems: Identification products and requirements.
- J. Section 260916 - Electrical Controls and Relays.
- K. Section 262725 - Wiring Devices:
 - 1. Wall plates.
 - 2. Floor box service fittings.
 - 3. Poke-through assemblies.
 - 4. Access floor boxes.
 - 5. Additional requirements for locating boxes for wiring devices.
- L. Section 262813 - Fuses: Spare fuse cabinets.
- M. Section 271005 - Structured Cabling for Voice and Data - Inside-Plant: Additional requirements for communications systems boxes.
- N. Section 337119 - Electrical Underground Ducts, Ductbanks, and Manholes: Concrete manholes for electrical systems.

1.03 REFERENCE STANDARDS

- A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- B. NECA 130 - Standard for Installing and Maintaining Wiring Devices; 2010.
- C. NEMA FB 1 - Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; 2014.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- D. NEMA OS 1 - Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports; 2013.
- E. NEMA OS 2 - Nonmetallic Outlet Boxes, Device Boxes, Covers and Box Supports; 2013.
- F. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.
- G. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- H. SCTE 77 - Specification for Underground Enclosure Integrity; 2013.
- I. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.
- J. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.
- K. UL 508A - Industrial Control Panels; Current Edition, Including All Revisions.
- L. UL 514A - Metallic Outlet Boxes; Current Edition, Including All Revisions.
- M. UL 514C - Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers; Current Edition, Including All Revisions.
- N. UL 1203 - Explosion-Proof and Dust-Ignition-Proof Electrical Equipment for Use in Hazardous (Classified) Locations; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate the work with other trades to avoid placement of ductwork, piping, equipment, or other potential obstructions within the dedicated equipment spaces and working clearances for electrical equipment required by NFPA 70.
 - 2. Coordinate arrangement of electrical equipment with the dimensions and clearance requirements of the actual equipment to be installed.
 - 3. Coordinate minimum sizes of boxes with the actual installed arrangement of conductors, clamps, support fittings, and devices, calculated according to NFPA 70.
 - 4. Coordinate minimum sizes of pull boxes with the actual installed arrangement of connected conduits, calculated according to NFPA 70.
 - 5. Coordinate the placement of boxes with millwork, furniture, devices, equipment, etc. installed under other sections or by others.
 - 6. Coordinate the work with other trades to preserve insulation integrity.
 - 7. Coordinate the work with other trades to provide walls suitable for installation of flush-mounted boxes where indicated.
 - 8. Notify Architect and Owner's Construction Project Coordinator, of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for cabinets and enclosures, boxes for hazardous (classified) locations, floor boxes, and underground boxes/enclosures.
 - 1. Underground Boxes/Enclosures: Include reports for load testing in accordance with SCTE 77 certified by a professional engineer or an independent testing agency upon request.
- C. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- D. Project Record Documents: Record actual locations for outlet and device boxes, junction boxes, pull boxes, cabinets and enclosures, floor boxes, and underground boxes/enclosures.
- E. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
 - 2. Keys for Lockable Enclosures: Two of each different key.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.
- B. Maintain at the project site a copy of each referenced document that prescribes execution requirements.
- C. Product Listing Organization Qualifications: An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 BOXES

- A. General Requirements:
 - 1. Do not use boxes and associated accessories for applications other than as permitted by NFPA 70 and product listing.
 - 2. Provide all boxes, fittings, supports, and accessories required for a complete raceway system and to accommodate devices and equipment to be installed.
 - 3. Provide products listed, classified, and labeled as suitable for the purpose intended.
 - 4. Where box size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
 - 5. Provide grounding terminals within boxes where equipment grounding conductors terminate.
- B. Outlet and Device Boxes Up to 100 cubic inches, Including Those Used as Junction and Pull Boxes:
 - 1. Use sheet-steel boxes for dry locations unless otherwise indicated or required.
 - 2. Use cast iron boxes or cast aluminum boxes for damp or wet locations unless otherwise indicated or required; furnish with compatible weatherproof gasketed covers.
 - 3. Use cast iron boxes or cast aluminum boxes where exposed galvanized steel rigid metal conduit or exposed intermediate metal conduit (IMC) is used.
 - 4. Use suitable concrete type boxes where flush-mounted in concrete.
 - 5. Use suitable masonry type boxes where flush-mounted in masonry walls.
 - 6. Use raised covers suitable for the type of wall construction and device configuration where required.
 - 7. Use shallow boxes where required by the type of wall construction.
 - 8. Do not use "through-wall" boxes designed for access from both sides of wall.
 - 9. Sheet-Steel Boxes: Comply with NEMA OS 1, and list and label as complying with UL 514A.
 - 10. Cast Metal Boxes: Comply with NEMA FB 1, and list and label as complying with UL 514A; furnish with threaded hubs.
 - 11. Nonmetallic Boxes: Comply with NEMA OS 2, and list and label as complying with UL 514C.
 - 12. Boxes for Supporting Luminaires and Ceiling Fans: Listed as suitable for the type and weight of load to be supported; furnished with fixture stud to accommodate mounting of luminaire where required. For light fixtures 50 pounds and heavier, provide boxes rated at 150% of fixture weight.
 - 13. Boxes for Ganged Devices: Use multigang boxes of single-piece construction. Do not use field-connected gangable boxes unless specifically indicated or permitted.
 - 14. Minimum Box Size, Unless Otherwise Indicated:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- a. Wiring Devices (Other Than Communications Systems Outlets): 4 inch square by 2-1/8 inch deep (100 by 54 mm) trade size.
- b. Communications Systems Outlets: Comply with Section 271005.
- c. Ceiling Outlets: 4 inch octagonal or square by 2-1/8 inch deep (100 by 54 mm) trade size.
- 15. Wall Plates: Comply with Section 262725.
- 16. Manufacturers:
 - a. Cooper Crouse-Hinds, a division of Eaton Corporation; _____: www.cooperindustries.com
 - b. Hubbell Incorporated; Bell Products; _____: www.hubbell-rtb.com
 - c. Hubbell Incorporated; RACO Products; _____: www.hubbell-rtb.com
 - d. O-Z/Gedney, a brand of Emerson Industrial Automation; _____: www.emersonindustrial.com
 - e. Thomas & Betts Corporation; _____: www.tnb.com
 - f. Bowers.
 - g. Substitutions: See Section 016000 - Product Requirements.
- C. Cabinets and Enclosures, Including Junction and Pull Boxes Larger Than 100 cubic inches:
 - 1. Comply with NEMA 250, and list and label as complying with UL 50 and UL 50E, or UL 508A.
 - 2. NEMA 250 Environment Type, Unless Otherwise Indicated:
 - a. Indoor Clean, Dry Locations: Type 1, painted steel.
 - b. Outdoor Locations: Type 4, painted steel.
 - 3. Junction and Pull Boxes Larger Than 100 cubic inches:
 - a. Provide screw-cover or hinged-cover enclosures unless otherwise indicated.
 - b. Boxes 6 square feet and Larger: Provide hinged-cover enclosures, unless otherwise indicated.
 - 4. Cabinets and Hinged-Cover Enclosures, Other Than Junction and Pull Boxes:
 - a. Provide lockable hinged covers, all locks keyed alike unless otherwise indicated.
 - b. Back Panels: Painted steel, removable.
 - c. Terminal Blocks: For low voltage controls, provide voltage/current ratings and terminal quantity suitable for purpose indicated, with 25 percent spare terminal capacity. Terminal blocks not permitted for Class 1 wiring. Class 1 wiring to utilize wirenut termination methods.
 - 5. Finish for Painted Steel Enclosures: Manufacturer's standard grey unless otherwise indicated.
 - 6. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation; _____: www.cooperindustries.com
 - b. Hoffman, a brand of Pentair Technical Products; _____: www.hoffmanonline.com
 - c. Hubbell Incorporated; Wiegmann Products; _____: www.hubbell-wiegmann.com
- D. Boxes and Enclosures for Integrated Power, Data, and Audio/Video: Size and configuration as indicated or as required with partitions to separate services; field-connected gangable boxes may not be used.
 - 1. See Section 271005.
- E. Boxes for Hazardous (Classified) Locations: Listed and labeled as complying with UL 1203 for the classification of the installed location.
 - 1. Manufacturers:
 - a. Appleton, a brand of Emerson Industrial Automation; _____: www.emersonindustrial.com
 - b. Cooper Crouse-Hinds, a division of Eaton Corporation; _____: www.cooperindustries.com
 - c. Hubbell Incorporated; Killark Products; _____: www.hubbell-killark.com
 - d. Substitutions: See Section 016000 - Product Requirements.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- F. Floor Boxes:
 - 1. Description: Floor boxes compatible with floor box service fittings provided in accordance with Section 262725; with partitions to separate multiple services; furnished with all components, adapters, and trims required for complete installation.
 - 2. Metallic Floor Boxes: Fully adjustable (with integral means for leveling adjustment prior to and after concrete pour).
 - 3. Manufacturer: Same as manufacturer of floor box service fittings.
- G. Underground Boxes/Enclosures:
 - 1. See Section 337119 for underground boxes and enclosures.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive boxes.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install boxes in accordance with NECA 1 (general workmanship) and, where applicable, NECA 130, including mounting heights specified in those standards where mounting heights are not indicated.
- C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.
- D. Provide separate boxes for emergency power and normal power systems.
- E. Unless otherwise indicated, provide separate boxes for line voltage and low voltage systems.
- F. Flush-mount boxes in finished areas unless specifically indicated to be surface-mounted.
- G. Unless otherwise indicated, boxes may be surface-mounted where exposed conduits are indicated or permitted.
- H. Box Locations:
 - 1. Locate boxes to be accessible. Provide access panels in accordance with Section 083100 as required where approved by the Architect.
 - 2. Unless dimensioned, box locations indicated are approximate.
 - 3. Locate boxes as required for devices installed under other sections or by others.
 - a. Switches, Receptacles, and Other Wiring Devices: Comply with Section 262725.
 - b. Communications Systems Outlets: Comply with Section 271005.
 - 4. Locate boxes so that wall plates do not span different building finishes.
 - 5. Locate boxes so that wall plates do not cross masonry joints.
 - 6. Unless otherwise indicated, where multiple outlet boxes are installed at the same location at different mounting heights, install along a common vertical center line.
 - 7. Do not install flush-mounted boxes on opposite sides of walls back-to-back. Provide minimum 6 inches horizontal separation unless otherwise indicated.
 - 8. Acoustic-Rated Walls: Do not install flush-mounted boxes on opposite sides of walls back-to-back; provide minimum 24 inches horizontal separation.
 - 9. Fire Resistance Rated Walls: Install flush-mounted boxes such that the required fire resistance will not be reduced.
 - a. Do not install flush-mounted boxes on opposite sides of walls back-to-back; provide minimum 24 inches separation where wall is constructed with individual noncommunicating stud cavities or protect both boxes with listed putty pads.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- b. Do not install flush-mounted boxes with area larger than 16 square inches or such that the total aggregate area of openings exceeds 100 square inches for any 100 square feet of wall area.
- 10. Locate junction and pull boxes as indicated, as required to facilitate installation of conductors, and to limit conduit length and/or number of bends between pulling points in accordance with Section 260533.13.
- 11. Locate junction and pull boxes in the following areas, unless otherwise indicated or approved by the Architect:
 - a. Concealed above accessible suspended ceilings.
 - b. Within joists in areas with no ceiling.
 - c. Electrical rooms.
 - d. Mechanical equipment rooms.
- I. Box Supports:
 - 1. Secure and support boxes in accordance with NFPA 70 and Section 260529 using suitable supports and methods approved by the authority having jurisdiction.
 - 2. Provide independent support from building structure except for cast metal boxes (other than boxes used for fixture support) supported by threaded conduit connections in accordance with NFPA 70. Do not provide support from piping, ductwork, or other systems.
 - 3. Installation Above Suspended Ceilings: Do not provide support from ceiling grid or ceiling support system.
 - 4. Use far-side support to secure flush-mounted boxes supported from single stud in hollow stud walls. Repair or replace supports for boxes that permit excessive movement.
- J. Install boxes plumb and level.
- K. Flush-Mounted Boxes:
 - 1. Install boxes in noncombustible materials such as concrete, tile, gypsum, plaster, etc. so that front edge of box or associated raised cover is not set back from finished surface more than 1/4 inch or does not project beyond finished surface.
 - 2. Install boxes in combustible materials such as wood so that front edge of box or associated raised cover is flush with finished surface.
 - 3. Repair rough openings around boxes in noncombustible materials such as concrete, tile, gypsum, plaster, etc. so that there are no gaps or open spaces greater than 1/8 inch at the edge of the box.
- L. Floor-Mounted Cabinets: Mount on properly sized 3 inch high concrete pad constructed in accordance with Section 033000.
- M. Install boxes as required to preserve insulation integrity.
- N. Metallic Floor Boxes: Install box level at the proper elevation to be flush with finished floor.
- O. Nonmetallic Floor Boxes: Cut box flush with finished floor after concrete pour.
- P. Install permanent barrier between ganged wiring devices when voltage between adjacent devices exceeds 300 V.
- Q. Install firestopping to preserve fire resistance rating of partitions and other elements, using materials and methods specified in Section 078400.
- R. Close unused box openings.
- S. Install blank wall plates on junction boxes and on outlet boxes with no devices or equipment installed or designated for future use.
- T. Provide grounding and bonding in accordance with Section 260526.
- U. Identify boxes in accordance with Section 260553.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3.03 CLEANING

- A. Clean interior of boxes to remove dirt, debris, plaster and other foreign material.

3.04 PROTECTION

- A. Immediately after installation, protect boxes from entry of moisture and foreign material until ready for installation of conductors.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



SECTION 260553
IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Electrical identification requirements.
- B. Identification nameplates and labels.
- C. Wire and cable markers.
- D. Voltage markers.
- E. Underground warning tape.
- F. Floor marking tape.
- G. Warning signs and labels.
- H. Identification for conductors.
- I. Identification for raceways.
- J. Circuit identification of wiring devices.
- K. Handicapped door operators.
- L. Instruction signs.

1.02 RELATED REQUIREMENTS

- A. Section 099113 - Exterior Painting.
- B. Section 099123 - Interior Painting.
- C. Section 260513 - Medium-Voltage Cables.
- D. Section 260519 - Low-Voltage Electrical Power Conductors and Cables: Color coding for power conductors and cables 600 V and less; vinyl color coding electrical tape.
- E. Section 260519.13 - Undercarpet Electrical Power Cables.
- F. Section 260526 - Grounding and Bonding for Electrical Systems.
- G. Section 260533.13 - Conduit for Electrical Systems.
- H. Section 260536 - Cable Trays for Electrical Systems: Additional identification requirements for cable tray systems.
- I. Section 260573 - Power System Studies: Arc flash hazard warning labels.
- J. Section 262300 - Low-Voltage Switchgear: Factory-installed mimic bus.
- K. Section 262725 - Wiring Devices: Electrical power devices.
- L. Section 262713 - Electricity Metering: Metering for main service entrance gear.
- M. Section 271005 - Structured Cabling for Voice and Data - Inside-Plant: Identification for communications cabling and devices.
- N. Section 284050 - Conductors and Cables for Fire Detection and Alarm.
- O. Section 285600 - Fire Detection and Alarm.
- P. Section 337900 - Site Grounding.

1.03 REFERENCE STANDARDS

- A. ANSI Z535.2 - American National Standard for Environmental and Facility Safety Signs; 2011.
- B. ANSI Z535.4 - American National Standard for Product Safety Signs and Labels; 2011.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- C. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- D. NFPA 70E - Standard for Electrical Safety in the Workplace; 2017.
- E. UL 969 - Marking and Labeling Systems; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Verify final designations for equipment, systems, and components to be identified prior to fabrication of identification products.
- B. Sequencing:
 - 1. Do not conceal items to be identified, in locations such as above suspended ceilings, until identification products have been installed.
 - 2. Do not install identification products until final surface finishes and painting are complete.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittals procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for each product.
- C. Shop Drawings: Provide schedule of items to be identified indicating proposed designations, materials, legends, and formats.
- D. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation and installation of product.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

1.07 FIELD CONDITIONS

- A. Do not install adhesive products when ambient temperature is lower than recommended by manufacturer.
- B. Coordinate installation of labels, marking, stickers, etc., on devices, conduit, equipment, conductors, etc., after installation and painting phases are complete.

PART 2 PRODUCTS

2.01 IDENTIFICATION REQUIREMENTS

- A. Existing Work: Unless specifically excluded, identify existing elements to remain that are not already identified in accordance with specified requirements.
- B. Identification for Equipment:
 - 1. Use identification nameplate to identify each piece of electrical distribution and control equipment and associated sections, compartments, and components.
 - a. Switchgear, 600V or less.
 - 1) Identify ampere rating.
 - 2) Identify voltage and phase.
 - 3) Use identification nameplate to identify main and tie devices.
 - 4) Use identification nameplate to identify load(s) served for each branch device. Identify spares and spaces. Provide engraved micarta nameplates for all circuit breakers. Black face with white engraved letters.
 - 5) See Section 262300 for factory-installed mimic bus.
 - b. MV Switchgear, Isolation Switches and Dead Break Junctions (DBJ), over 600V.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 1) Use identification nameplate to identify switchgear, isolation switches and dead break junction name.
 - 2) Use identification nameplate to identify name for each switchgear, isolation switches and dead break junction, switched or non-switched way.
 - 3) Provide self-adhesive vinyl labels.
 - 4) Labels shall be black text on a yellow background.
 - 5) Text for switch name shall be 1" high.
 - 6) Text for each switched/non-switched way shall be 3/8" high.
- c. Switchboards:
- 1) Identify ampere rating.
 - 2) Identify voltage and phase.
 - 3) Identify power source and circuit number. Include location when not within sight of equipment.
 - 4) Use identification nameplate to identify main overcurrent protective device.
 - 5) Use identification nameplate to identify load(s) served for each branch device. Identify spares and spaces. Provide engraved micarta nameplates for all circuit breakers. Black face with white engraved letters.
- d. Motor Control Centers:
- 1) Identify ampere rating.
 - 2) Identify voltage and phase.
 - 3) Identify power source and circuit number. Include location when not within sight of equipment.
 - 4) Use identification nameplate to identify main overcurrent protective device or incoming section.
 - 5) Use identification nameplate to identify load(s) served for each branch device. Identify spares and spaces. Provide engraved micarta nameplates for all circuit breakers. Black face with white engraved letters.
- e. Panelboards:
- 1) Identify ampere rating.
 - 2) Identify voltage and phase.
 - 3) Identify power source and circuit number. Include location when not within sight of equipment.
 - 4) Use typewritten circuit directory to identify load(s) served for panelboards with a door. Identify spares and spaces using pencil.
 - 5) Provide engraved micarta nameplate to identify panel. Black face with white engraved letters.
- f. Transformers, 600 V and less:
- 1) Identify power source and circuit number. Include location when not within sight of equipment.
 - 2) Identify load(s) served. Include location when not within sight of equipment.
- g. Transformers, over 600V.
- 1) Use identification nameplate to identify transformer name.
 - 2) Provide self-adhesive vinyl labels.
 - 3) Labels shall be black text on a yellow background.
 - 4) Text shall be 1.5" high.
- h. Enclosed switches, circuit breakers, motor controllers, and variable frequency drives (VFDs):
- 1) Identify voltage and phase.
 - 2) Identify power source and circuit number. Include location when not within sight of equipment.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 3) Identify load(s) served. Include location when not within sight of equipment.
- i. Enclosed Enclosures and Electrical Cabinets:
 - 1) Identify voltage and phase.
 - 2) Identify power source and circuit number. Include location when not within sight of equipment.
 - 3) Where enclosure serves electrical equipment, identify load(s) served. Include location when not within sight of equipment.
- j. Enclosed Push Button Stations:
 - 1) Identify voltage and phase.
 - 2) Identify power source and circuit number. Include location when not within sight of equipment.
 - 3) Where enclosure serves electrical equipment, identify load(s) served. Include location when not within sight of equipment.
- k. Busway:
 - 1) Identify ampere rating.
 - 2) Identify voltage and phase.
 - 3) Identify power source and circuit number. Include location when not within sight of equipment.
 - 4) Provide identification at maximum intervals of 12 feet for horizontal busway. For vertical busway, identify on each floor.
 - 5) Use identification nameplate to identify load(s) served for each plug-in unit. Include location when not within sight of equipment.
- l. Access Doors and panels that conceal electrical items:
 - 1) Identify equipment behind access door or panel.
 - 2) Identify power source and circuit number.
- m. Time Switches:
 - 1) Identify load(s) served and associated circuits controlled. Include location.
 - 2) Identify power source and circuit number.
- n. Enclosed Contactors:
 - 1) Identify ampere rating.
 - 2) Identify voltage and phase.
 - 3) Identify configuration, electrically or mechanically held.
 - 4) Identify coil voltage.
 - 5) Identify load(s) and associated circuits controlled. Include location.
 - 6) Identify power source and circuit number.
- o. Emergency system boxes and enclosures:
 - 1) Identify input and output voltage and phase.
 - 2) Identify power source and circuit number for normal power source. Include location when not within sight of equipment.
 - 3) Identify load(s) served. Include location.
- p. Centralized Emergency Lighting Inverters, and Battery Racks:
 - 1) Identify input and output voltage and phase.
 - 2) Identify power source and circuit number for normal power source. Include location when not within sight of equipment.
 - 3) Identify load(s) served. Include location.
- q. Emergency Generators and Transfer Switches:
 - 1) Identify voltage, amperage and phase for transfer switches.
 - 2) Identify voltage, amperage, kilo-watt (KW), kilo-volt-amp (KVA) and phase for emergency generators.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 3) Identify power source and circuit number for both normal power source and standby power source. Include location when not within sight of equipment.
- 4) Identify load(s) served. Include location when not within sight of equipment.
- 5) Identify short circuit current rating based on the specific overcurrent protective device type and settings protecting the generator and transfer switch.
- r. Uninterruptable Power Supply (UPS):
 - 1) Identify voltage, amperage, kilo-watt (KW), kilo-volt-amp (KVA) and phase.
 - 2) Identify power source and circuit number for both normal power source and UPS power source. Include location when not within sight of equipment.
 - 3) Identify load(s) served. Include location when not within sight of equipment.
 - 4) Identify short circuit current rating based on the specific overcurrent protective device type and settings protecting the UPS.
- s. Electricity Meters:
 - 1) Identify load(s) metered.
2. Service Equipment:
 - a. Use identification nameplate to identify each service disconnecting means.
 - b. For buildings or structures supplied by more than one service, or any combination of branch circuits, feeders, and services, use identification nameplate or means of identification acceptable to Owner's Construction Coordinator, at each service disconnecting means to identify all other services, feeders, and branch circuits supplying that building or structure. Verify format and descriptions with Owner Construction Coordinator. Provide engraved micarta nameplates for all circuit breakers. Black face with white engraved letters.
3. Emergency System Equipment:
 - a. Use identification nameplate or voltage marker to identify emergency system equipment in accordance with NFPA 70.
 - b. Use identification nameplate at each piece of service equipment to identify type and location of on-site emergency power sources. Provide engraved micarta nameplates for all circuit breakers. Red face with white engraved letters.
 - c. Use identification label to identify emergency operating instructions for emergency system equipment.
4. Use voltage marker to identify highest voltage present for each piece of electrical equipment.
5. Use identification nameplate to identify switchboards and panelboards utilizing a high leg delta system in accordance with NFPA 70.
6. Use identification nameplate to identify disconnect location for equipment with remote disconnecting means.
7. Use identification label or handwritten text using indelible marker on inside of door at each fused switch to identify required NEMA fuse class and size.
8. Use identification label or handwritten text using indelible marker on inside of door at each motor controller to identify nameplate horsepower, full load amperes, code letter, service factor, voltage, and phase of motor(s) controlled.
9. Use identification label to identify overcurrent protective devices for branch circuits serving fire alarm circuits. Identify with text "FIRE ALARM CIRCUIT".
10. Use field-painted floor markings, floor marking tape, or warning labels to identify required equipment working clearances where indicated or where required by the authority having jurisdiction.
 - a. Field-Painted Floor Markings: Alternating black and white stripes, 3 inches wide, painted in accordance with Section 099123 and 099113.
11. Available Fault Current Documentation: Use identification label to identify the available fault current and date calculations were performed at locations requiring documentation by NFPA 70, including but not limited to the following.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- a. Service equipment.
 - b. Industrial control panels.
 - c. Motor control centers.
 - d. Elevator control panels.
 - e. Industrial machinery.
12. Arc Flash Hazard Warning Labels: Comply with Section 260573.
13. Use warning signs to identify electrical hazards for entrances to all rooms and other guarded locations that contain exposed live parts operating at 600 V nominal or less with the word message "DANGER; Electrical hazard; Authorized personnel only" or approved equivalent.
14. Use warning signs to identify electrical hazards for entrances to all buildings, vaults, rooms, or enclosures containing exposed live parts or exposed conductors operating at over 600 V nominal with the word message "DANGER; HIGH VOLTAGE; KEEP OUT".
15. Use warning labels to identify electrical hazards for equipment, compartments, and enclosures containing exposed live parts or exposed conductors operating at over 600 V nominal with the word message "DANGER; HIGH VOLTAGE; KEEP OUT".
16. Use warning labels, identification nameplates, or identification labels to identify electrical hazards for equipment where multiple power sources are present with the word message "DANGER; Hazardous voltage; Multiple power sources may be present; Disconnect all electric power including remote disconnects before servicing" or approved equivalent.
- C. Identification for Conductors and Cables:
- 1. Identification for Communications Conductors and Cables: Comply with Section 271005.
 - 2. Color Coding for Power Conductors and Cables, 600V or Less:
 - a. Color Code:
 - 1) 480Y277 V, 3 Phase, 4 Wire System:
 - (a) Phase A: Brown.
 - (b) Phase B: Orange.
 - (c) Phase C: Yellow.
 - (d) Neutral/Grounded:
 - (1) Phase A: Gray with Brown stripe.
 - (2) Phase B: Gray with Orange stripe.
 - (3) Phase C: Gray with Yellow stripe.
 - 2) 208Y120 V, 3 Phase, 4 Wire System:
 - (a) Phase A: Black.
 - (b) Phase B: Red.
 - (c) Phase C: Blue.
 - (d) Neutral/Grounded:
 - (1) Phase A: White with Black stripe.
 - (2) Phase B: White with Red stripe.
 - (3) Phase C: White with Blue stripe.
 - 3) 240/120 V (High-Leg) Delta: 3 Phase, 4 Wire System:
 - (a) Phase A: Black.
 - (b) Phase B: (High Leg): Orange.
 - (c) Phase C: Blue.
 - (d) Neutral/Grounded:
 - (1) Phase A: White with Black stripe.
 - (2) Phase C: White with Blue stripe.
 - 4) 240/120 V, 1 Phase, 3 Wire System:
 - (a) Phase A: Black.
 - (b) Phase B: Red.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- (c) Neutral/Grounded:
 - (1) Phase A: White with Black stripe.
 - (2) Phase B: White with Red stripe.
 - 5) Equipment Ground, All Systems: Green.
 - 6) Isolated Ground, All Systems: Green with yellow stripe.
 - 7) Travelers for 3-Way and 4-Way Switching: Pink and Purple.
 - b. Color shall be factory applied or field applied for sizes larger than No. 8 AWG
3. Labeling and Color-Coding for Power Conductors/Cables over 600 V:
- a. Color Code:
 - 1) 12,4700Y/7200 V, 3 Phase, 3 and 4 Wire Systems:
 - (a) Phase A: Orange.
 - (b) Phase B: Red.
 - (c) Phase C: Blue.
 - (d) Neutral/Grounded: White.
 - 2) 4,160Y/2400 V, 3 Phase, 3 and 4 Wire Systems:
 - (a) Phase A: Orange.
 - (b) Phase B: Red.
 - (c) Phase C: Blue.
 - (d) Neutral/Grounded: White.
 - b. Power Conductor Identification, More than 600 V: For conductors in vaults, pull and junction boxes, manholes, handholes, MV switches, transformers, and all other areas where conductors are exposed to view; use color-coded adhesive tape to identify all cables.
 - 1) Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns a minimum distance of 12 inches from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.
 - c. Power Feeders Identification, More than 600 V. Identify each set of MV feeders.
 - 1) Provide an engraved micarta label for each set of feeder. Provide labeling at all locates described below:
 - (a) Provide label at all terminations to switches.
 - (b) provide labeling where feeders enter/exit all man holes, hand holes and vaults.
 - (c) Do not provide labeling where feeders terminate at a transformer.
 - (d) Attach label to feeders with an UV-Stabilized Cable Ties. See Cable Ties section below for additional information.
 - 2) Labeling text shall include the following:
 - (a) Labels shall be white text on a black background.
 - (b) Text shall be 3/8" high.
 - (c) Text shall include the termination point of each end of the feeder, the vault name, switch name; and on which switch, the feeders are terminated.
4. Use identification label to identify color code for ungrounded and grounded power conductors and cables, at each piece of feeder or branch-circuit distribution equipment.
5. For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
6. Use wire and cable markers to identify circuit number or other designation indicated for power, control, and instrumentation conductors and cables at the following locations:
- a. At each source and load connection.
 - b. Within boxes when more than one circuit is present.
 - c. Within equipment enclosures when conductors and cables enter or leave the enclosure.
 - d. In cable tray, at maximum intervals of 20 feet.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



7. Use wire and cable markers to identify connected grounding electrode system components for grounding electrode conductors.
 8. Use underground warning tape to identify direct buried cables.
 9. Multiple Power or Lighting Circuits in the Same Enclosure: Identify each conductor with source, voltage, circuit number, and phase. Use color-coding to identify circuits' voltage and phase.
 10. Multiple Control and Communication Circuits in the Same Enclosure: Identify each conductor by its system and circuit designation. Use a consistent system of tags, color-coding, or cable marking tape.
- D. Identification for Raceways and Boxes. For all raceways, 600v and less:
1. Use paint identification to identify the system cables/conductors, inside the conduit.
 2. Use color-coded paint to identify all, accessible and inaccessible, conduits as follows:
 3. Paint all conduit fittings.
 - a. Paint the exterior of pull and junction boxes. Paint the exterior of all box covers.
 - b. Paint conduit as it enters/exits wall and floors.
 - c. In congested areas, paint bands at 5 foot intervals.
 - d. Only paint boxes dimensions that are 12" by 12" and smaller.
 - e. Color Code:
 - 1) Fire-Alarm System: Red.
 - 2) Fire-Suppression Supervisory and Control System: Red and Yellow.
 - 3) Security System: Purple
 - 4) Mechanical and Electrical Supervisory System: Green and Blue.
 - 5) Telecommunications System: Blue
 - 6) Emergency/UPS power system: Yellow.
 - 7) 277/480 volts system: Brown.
 - 8) 120/208 volts system: Black.
 - 9) Clocks & Bells: Orange.
 - 10) Sound System: Green.
 - 11) Traveler (switch to light or switch to switch) 120 volts: Pink and Black.
 - 12) Traveler (switch to light or switch to switch) 277 volts: Pink and Brown.
 - 13) Lighting control and dimmers systems: White.
 - 14) Field-Painting: Comply with Section 099123 and 099113.
 4. Use underground warning tape to identify underground raceways and duct banks.
 5. For all pull and junction boxes, write the source panel and circuit number on the the inside box cover, with a permanent, waterproof type marker.
 6. Conductors to Be Extended in the Future: Attach write-on tags to raceways and list source.
- E. Identification for Raceways. For all raceways, over 600v:
1. Install self-adhesive labels on 10-foot centers over the full length of the raceway or duct. The labels shall read "DANGER - HIGH VOLTAGE".
 2. Apply to the following finished surfaces:
 - a. Floor surface directly above conduits running beneath and within 12 inches of a floor that is in contact with earth or is framed above unexcavated space.
 - b. Wall surfaces directly external to raceways concealed within wall.
 - c. Accessible surfaces of concrete envelope around raceways in vertical shafts, exposed in the building, or concealed above suspended ceilings.
- F. Identification for Cable Tray Conductors: Comply with Section 260536.
1. Use color-coded bands to identify conductors at maximum intervals of 10 feet.
 - a. Color-Coded Bands: Use vinyl color coding electrical tape to mark bands 1/2 inch(es) wide.
 - 1) Color Code:
 - (a) Fire-Alarm System: Red.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- (b) Fire-Suppression Supervisory and Control System: Red and Yellow.
 - (c) Security System: Purple
 - (d) Mechanical and Electrical Supervisory System: Green and Blue.
 - (e) Telecommunications System: Blue
 - (f) Emergency/UPS power system: Yellow.
 - (g) 277/480 volts system: Brown.
 - (h) 120/208 volts system: Black.
 - (i) Clocks & Bells: Orange.
 - (j) Sound System: Green.
 - (k) Traveler (switch to light or switch to switch) 120 volts: Pink and Black.
 - (l) Traveler (switch to light or switch to switch) 277 volts: Pink and Brown.
 - (m) Lighting control and dimmers systems: White.
- 2) Field-Painting: Comply with Section 099123 and 099113.
 - 3) Vinyl Color Coding Electrical Tape: Comply with Section 260519.
- 2. Use identification labels, handwritten text using indelible marker, or plastic marker tags to identify circuits enclosed for accessible conduits at wall penetrations, at floor penetrations, at roof penetrations, and at equipment terminations when source is not within sight.
 - 3. Use identification labels, handwritten text using indelible marker, or plastic marker tags to identify spare conduits at each end. Identify purpose and termination location.
- G. Identification for Devices:
- 1. Identification for Communications Devices: Comply with Section 271005.
 - 2. Identification for Fire Alarm Equipment and Devices: Comply with Section 284600.
 - 3. Wiring Device and Wallplate Finishes: Comply with Section 262725.
 - 4. Use identification label or engraved wallplate to identify serving branch circuit for all receptacles.
 - 5. Use identification label or engraved wallplate to identify load controlled for wall-mounted control devices controlling loads that are not visible from the control location and for multiple wall-mounted control devices installed at one location.
 - 6. Use identification label to identify receptacles protected by upstream GFI protection, where permitted.
- H. Identification in Tunnels/Vaults:
- 1. Where ductbanks enter/exit vaults and tunnels, label the origination point of all conduits. ie., vaults, tunnels building, etc.

2.02 IDENTIFICATION NAMEPLATES AND LABELS

- A. Identification Nameplates:
- 1. Manufacturers:
 - a. Brimar Industries, Inc: www.brimar.com
 - b. Kolbi Pipe Marker Co; _____: www.kolbipipemarkers.com
 - c. Seton Identification Products; _____: www.seton.com
 - d. Substitutions: See Section 016000 - Product Requirements.
 - 2. Materials:
 - a. Indoor Clean, Dry Locations: Use plastic nameplates.
 - b. Outdoor Locations: Use plastic, stainless steel, or aluminum nameplates suitable for exterior use.
 - 3. Plastic Nameplates: Two-layer or three-layer laminated acrylic or electrically non-conductive phenolic with beveled edges; minimum thickness of 1/16 inch; engraved text.
 - a. Exception: Provide minimum thickness of 1/8 inch when any dimension is greater than 4 inches.
 - 4. Stainless Steel Nameplates: Minimum thickness of 1/32 inch; engraved or laser-etched text.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



5. Aluminum Nameplates: Anodized; minimum thickness of 1/32 inch; engraved or laser-etched text.
 6. Mounting Holes for Mechanical Fasteners: Two, centered on sides for sizes up to 1 inch high; Four, located at corners for larger sizes.
- B. Identification Labels:
1. Manufacturers:
 - a. Brady Corporation; _____: www.bradyid.com
 - b. Brother International Corporation: www.brother-usa.com
 - c. Panduit Corp: www.panduit.com
 - d. Substitutions: See Section 016000 - Product Requirements.
 2. Materials: Use self-adhesive laminated plastic labels; UV, chemical, water, heat, and abrasion resistant.
 3. Text: Use factory pre-printed or machine-printed text. Do not use handwritten text unless otherwise indicated.
- C. Format for Equipment Identification:
1. Minimum Size: 1 inch by 2.5 inches.
 2. Legend:
 - a. Equipment designation or other approved description.
 3. Text: All capitalized unless otherwise indicated.
 4. Minimum Text Height:
 - a. System Designation: 1 inch.
 - b. Equipment Designation: 1/2 inch.
 - c. Other Information: 1/4 inch.
 - d. Exception: Provide minimum text height of 1 inch for equipment located more than 10 feet above floor or working platform.
 5. Color:
 - a. Normal Power System: White text on black background.
 - b. Emergency Power System: White text on red background.
 - c. Fire Alarm System: White text on red background.
- D. Format for General Information and Operating Instructions:
1. Minimum Size: 1 inch by 2.5 inches.
 2. Legend: Include information or instructions indicated or as required for proper and safe operation and maintenance.
 3. Text: All capitalized unless otherwise indicated.
 4. Minimum Text Height: 1/4 inch.
 5. Color: Black text on white background unless otherwise indicated.
 - a. Exceptions:
 - 1) Provide white text on red background for general information or operational instructions for emergency systems.
 - 2) Provide white text on red background for general information or operational instructions for fire alarm systems.
- E. Format for Caution and Warning Messages:
1. Minimum Size: 2 inches by 4 inches.
 2. Legend: Include information or instructions indicated or as required for proper and safe operation and maintenance.
 3. Text: All capitalized unless otherwise indicated.
 4. Minimum Text Height: 1/2 inch.
 5. Color: Black text on yellow background unless otherwise indicated.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- F. Format for Receptacle Identification:
 - 1. Minimum Size: 3/8 inch by 1.5 inches.
 - 2. Legend: Power source and circuit number or other designation indicated.
 - a. Include voltage and phase for other than 120 V, single phase circuits.
 - 3. Text: All capitalized unless otherwise indicated.
 - 4. Label Type: Machine printed, pressure-sensitive adhesive labels.
 - 5. Minimum Text Height: 3/16 inch.
 - 6. Color: Black text on clear background.
- G. Format for Control Device Identification:
 - 1. Minimum Size: 3/8 inch by 1.5 inches.
 - 2. Legend: Load controlled or other designation indicated.
 - 3. Text: All capitalized unless otherwise indicated.
 - 4. Minimum Text Height: 3/16 inch.
 - 5. Color: Black text on clear background.
- H. Format for Fire Alarm Device Identification:
 - 1. See Section 284600 - Fire Detection and Alarm, for identification of fire alarm devices and equipment.

2.03 WIRE AND CABLE MARKERS

- A. Manufacturers:
 - 1. Brady Corporation; _____: www.bradyid.com
 - 2. HellermannTyton; _____: www.hellermannntyton.com
 - 3. Panduit Corp: www.panduit.com
 - 4. _____
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Markers for Conductors and Cables: Use wrap-around self-adhesive vinyl cloth, wrap-around self-adhesive vinyl self-laminating, heat-shrink sleeve, plastic sleeve, plastic clip-on, or vinyl split sleeve type markers suitable for the conductor or cable to be identified.
- C. Markers for Conductor and Cable Bundles: Use plastic marker tags secured by nylon cable ties.
- D. Legend: Power source and circuit number or other designation indicated.
- E. Text: Use factory pre-printed or machine-printed text, all capitalized unless otherwise indicated.
- F. Minimum Text Height: 1/8 inch.
- G. Color: Black text on white background unless otherwise indicated.

2.04 VOLTAGE MARKERS

- A. Manufacturers:
 - 1. Brady Corporation; _____: www.bradyid.com
 - 2. Brimar Industries, Inc: www.brimar.com
 - 3. Seton Identification Products; _____: www.seton.com
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Markers for Conduits: Use factory pre-printed self-adhesive vinyl type markers.
- C. Markers for Boxes and Equipment Enclosures: Use factory pre-printed self-adhesive vinyl type markers.
- D. Minimum Size:
 - 1. Markers for Equipment: 1 1/8 by 4 1/2 inches.
 - 2. Markers for Conduits: As recommended by manufacturer for conduit size and voltage to be identified.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3. Markers for Pull Boxes: 1 1/8 by 4 1/2 inches.
4. Markers for Junction Boxes: 1/2 by 2 1/4 inches.

E. Legend:

1. Markers for Voltage Identification: Highest voltage present.
2. Markers for System Identification:
 - a. Emergency Power System: Text "EMERGENCY".
 - b. Communication and fiber optic cables: Text "COMMUNICATION".

F. Color: Black text on orange background unless otherwise indicated.

2.05 UNDERGROUND WARNING TAPE

A. Manufacturers:

1. Brady Corporation; _____: www.bradyid.com
2. Brimar Industries, Inc: www.brimar.com
3. L.H. Dottie.
4. Seton Identification Products; _____: www.seton.com
5. Thomas & Betts - USA.
6. Substitutions: See Section 016000 - Product Requirements.

B. Materials: Use foil-backed detectable type polyethylene tape suitable for direct burial, unless otherwise indicated.

C. Foil-backed Detectable Type Tape: 6 inches wide, with minimum thickness of 5 mil, unless otherwise required for proper detection.

D. Legend: Type of service, continuously repeated over full length of tape.

E. Color:

1. Tape for Buried Power Lines: Black text on red background.
2. Tape for Buried Communication, Alarm, and Signal Lines: Black text on orange background.

2.06 FLOOR MARKING TAPE

A. Manufacturers:

1. Brady Corporation; _____: www.bradyid.com
2. Brimar Industries, Inc: www.brimar.com
3. Seton Identification Products; _____: www.seton.com
4. Substitutions: See Section 016000 - Product Requirements.

B. Floor Marking Tape for Equipment Working Clearance Identification: Self-adhesive vinyl or polyester tape with overlamine, 3 inches wide, with alternating black and white stripes.

2.07 CABLE TIES:

A. General Purpose Cable Ties: Fungus Inert, Self Extinguishing, One Piece, Self Locking, Nylon:

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black except where used for color-coding.

B. UV-Stabilized Cable Ties: Fungus inert, designed for continuous exposure to exterior sunlight, self extinguishing, one piece, self locking, nylon:

1. Minimum Width: 3/16 inch.
2. For MV cabling, provide 1/4 inch or larger cable ties.
3. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
4. Temperature Range: Minus 40 to plus 185 deg F.
5. Color: Black.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- C. Plenum-Rated Cable Ties: Self extinguishing, UV stabilized, one piece, self locking:
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 7000 psi.
 - 3. UL 94 Flame Rating: 94V-0.
 - 4. Temperature Range: Minus 50 to plus 284 deg F.
 - 5. Color: Black.
- D. Use general-purpose type cable ties, with the following exceptions:
 - 1. Exterior: UV-stabilized nylon.
 - 2. Areas of Environmental Air: Plenum rated.

2.08 WARNING SIGNS AND LABELS

- A. Manufacturers:
 - 1. Brimar Industries, Inc: www.brimar.com
 - 2. Clarion Safety Systems, LLC; _____: www.clarionsafety.com
 - 3. Seton Identification Products; _____: www.seton.com
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Comply with ANSI Z535.2 or ANSI Z535.4 as applicable.
- C. Warning Signs:
 - 1. Materials:
 - a. Indoor Dry, Clean Locations: Use factory pre-printed rigid plastic or self-adhesive vinyl signs.
 - b. Outdoor Locations: Use factory pre-printed rigid aluminum or rigid plastic signs.
 - 2. Rigid Signs: Provide four mounting holes at corners for mechanical fasteners.
 - 3. Minimum Size: 7 by 10 inches unless otherwise indicated.
- D. Warning Labels:
 - 1. Materials: Use factory pre-printed or machine-printed self-adhesive polyester or self-adhesive vinyl labels; UV, chemical, water, heat, and abrasion resistant; produced using materials recognized to UL 969.
 - a. Do not use labels designed to be completed using handwritten text.
 - 2. Machine-Printed Labels: Use thermal transfer process printing machines and accessories recommended by label manufacturer.
 - 3. Minimum Size: 2 by 4 inches unless otherwise indicated.

2.09 HANDICAPPED DOOR OPERATORS

- A. Provide labeling for maintenance workers inside of accessible panels. Labeling shall include the following:
 - 1. Identify location of panel feeding door operator.
 - 2. Identify panel name and circuit number.

PART 3 EXECUTION

3.01 PREPARATION

- A. Clean surfaces to receive adhesive products according to manufacturer's instructions.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Use consistent naming designations, throughout project.
- C. Install identification products to be plainly visible for examination, adjustment, servicing, and maintenance. Do not install where label will interfere with maintenance and operation of equipment. Unless otherwise indicated, locate products as follows:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



1. Surface-Mounted Equipment: Enclosure front.
2. Flush-Mounted Equipment: Inside of equipment door.
3. Free-Standing Equipment: Enclosure front; also enclosure rear for equipment with rear access.
4. Elevated Equipment: Legible from the floor or working platform.
5. Branch Devices: Adjacent to device.
6. Interior Components: Legible from the point of access.
7. Conduits: Legible from the floor.
8. Boxes: Outside face of cover.
9. Conductors and Cables: Legible from the point of access.
10. Devices: Outside face of cover.

D. Labeling of conduits and cables in Tunnels:

1. Install labels where upon conduits/cables enter and exit from tunnel. Label every 10 feet, thereafter.

E. Install identification products centered, level, and parallel with lines of item being identified.

F. Secure nameplates to exterior surfaces of enclosures using stainless steel screws and to interior surfaces using self-adhesive backing or epoxy cement.

G. Install self-adhesive labels and markers to achieve maximum adhesion, with no bubbles or wrinkles and edges properly sealed.

H. Install underground warning tape above buried lines with one tape per trench at 3 inches below finished grade.

I. Secure rigid signs using stainless steel screws.

J. Mark all handwritten text, where permitted, to be neat and legible.

3.03 UNDERGROUND WARNING TAPE:

A. Install continuous, underground-line warning tape. Locate directly above duct bank.

B. Locate warning tape at 6 to 8 inches, below finished grade.

3.04 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements, for additional requirements.

B. Replace self-adhesive labels and markers that exhibit bubbles, wrinkles, curling or other signs of improper adhesion.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



SECTION 260923
LIGHTING CONTROL DEVICES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Occupancy Sensors.
- B. Dimming Occupancy Sensors.
- C. Time switches.
- D. In-wall interval timers.
- E. Outdoor lighting controls.
- F. Lighting contactors.
- G. Control accessories.

1.02 RELATED REQUIREMENTS

- A. Section 260526 - Grounding and Bonding for Electrical Systems.
- B. Section 260529 - Hangers and Supports for Electrical Systems.
- C. Section 260533.16 - Boxes for Electrical Systems.
- D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.
- E. Section 260573 - Power System Studies.
- F. Section 260923 - Modular Lighting Control Systems
- G. Section 262725 - Wiring Devices: Devices for manual control of lighting, including wall switches.
 - 1. Includes finish requirements for wall controls specified in this section.
 - 2. Includes accessory receptacles, switches, dimmers and wall plates, to match lighting controls specified in this section.
- H. Section 262813 - Fuses.
- I. Section 262913 - Enclosed Controllers : General purpose contactors.
- J. Section 265100 - Interior Lighting.
- K. Section 265113 - Luminaires, Ballasts, and Drivers.
- L. Section 265561 - Theatrical Lighting: Controls for stage lighting units.
- M. Section 265600 - Exterior Lighting.

1.03 REFERENCE STANDARDS

- A. 47 CFR 15 - Radio Frequency Devices; current edition.
- B. ANSI C136.10 - American National Standard for Roadway and Area Lighting Equipment - Locking-Type Photocontrol Devices and Mating Receptacles - Physical and Electrical Interchangeability and Testing; 2010.
- C. ANSI C136.24 - American National Standard for Roadway and Area Lighting Equipment - Nonlocking (Button) Type Photocontrols; 2004 (R2010).
- D. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- E. NECA 130 - Standard for Installing and Maintaining Wiring Devices; 2010.
- F. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.
- G. NEMA 410 - Performance Testing for Lighting Controls and Switching Devices with Electronic Drivers and Discharge Ballasts; 2015.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- H. NEMA ICS 2 - Industrial Control and Systems Controllers, Contactors and Overload Relays Rated 600 Volts; 2000, with Errata (2008).
- I. NEMA ICS 5 - Industrial Control and Systems: Control Circuit and Pilot Devices; 2017.
- J. NEMA ICS 6 - Industrial Control and Systems: Enclosures; 1993 (Reaffirmed 2016).
- K. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- L. UL 773 - Plug-in, Locking Type Photocontrols for Use with Area Lighting; Current Edition, Including All Revisions.
- M. UL 773A - Nonindustrial Photoelectric Switches for Lighting Control; Current Edition, Including All Revisions.
- N. UL 916 - Energy Management Equipment; Current Edition, Including All Revisions.
- O. UL 917 - Clock-Operated Switches; Current Edition, Including All Revisions.
- P. UL 1472 - Solid-State Dimming Controls; Current Edition, Including All Revisions.
- Q. UL 60947-1 - Low-Voltage Switchgear and Controlgear - Part 1: General Rules; Current Edition, Including All Revisions.
- R. UL 60947-4-1 - Low-Voltage Switchgear and Controlgear - Part 4-1: Contactors and Motor-starters - Electromechanical Contactors and Motor-starters; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate the placement of lighting control devices with millwork, furniture, equipment, etc. installed under other sections or by others.
 - 2. Coordinate the placement of wall switch occupancy sensors with actual installed door swings.
 - 3. Coordinate the placement of occupancy sensors with millwork, furniture, equipment or other potential obstructions to motion detection coverage installed under other sections or by others.
 - 4. Coordinate the placement of photo sensors for daylighting controls with windows, skylights, and luminaires to achieve optimum operation. Coordinate placement with ductwork, piping, equipment, or other potential obstructions to light level measurement installed under other sections or by others.
 - 5. Notify Architect and Owner's Construction Project Coordinator, of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.
- B. Sequencing:
 - 1. Do not install lighting control devices until final surface finishes and painting are complete.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Include ratings, configurations, standard wiring diagrams, dimensions, colors, service condition requirements, and installed features.
 - 1. Occupancy Sensors: Include detailed motion detection coverage range diagrams.
- C. Shop Drawings:
 - 1. Occupancy Sensors: Provide lighting plan indicating location, model number, and orientation of each occupancy sensor and associated system component.
 - 2. Daylighting Controls: Provide lighting plan indicating location, model number, and orientation of each photo sensor and associated system component.
- D. Field Quality Control Reports.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- E. **Manufacturer's Installation Instructions:** Include application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
- F. **Operation and Maintenance Data:** Include detailed information on device programming and setup.
- G. **Maintenance Materials:** Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
- H. **Project Record Documents:** Record actual installed locations and settings for lighting control devices.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.
- B. Maintain at the project site a copy of each referenced document that prescribes execution requirements.
- C. **Manufacturer Qualifications:** Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- D. **Product Listing Organization Qualifications:** An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.

1.07 DELIVERY, STORAGE, AND PROTECTION

- A. Store products in a clean, dry space in original manufacturer's packaging in accordance with manufacturer's written instructions until ready for installation.

1.08 FIELD CONDITIONS

- A. Maintain field conditions within manufacturer's required service conditions during and after installation.

1.09 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Provide five year manufacturer warranty for all occupancy sensors.
- C. Provide five year manufacturer warranty for utility grade locking receptacle-mounted outdoor photo controls.
- D. Provide two year manufacturer warranty for all daylighting controls.

PART 2 PRODUCTS

2.01 LIGHTING CONTROL DEVICES - GENERAL REQUIREMENTS

- A. Provide products listed, classified, and labeled as suitable for the purpose intended.
- B. Unless specifically indicated to be excluded, provide all required conduit, wiring, connectors, hardware, components, accessories, etc. as required for a complete operating system.
- C. **Products for Switching of Electronic Ballasts/Drivers:** Tested and rated to be suitable for peak inrush currents specified in NEMA 410.

2.02 OCCUPANCY SENSORS

- A. **Manufacturers (non-dimming):**
 - 1. Hubbell Incorporated: www.hubbell.com
 - 2. Sensor Switch Inc: www.sensorswitch.com
 - 3. WattStopper: www.wattstopper.com
 - 4. **Source Limitations:** Furnish products produced by a single manufacturer and obtained from a single supplier.
- B. All Occupancy Sensors:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



1. Description: Factory-assembled commercial specification grade devices for indoor use capable of sensing both major motion, such as walking, and minor motion, such as small desktop level movements, according to published coverage areas, for automatic control of load indicated.
 2. Sensor Technology:
 - a. Passive Infrared/Ultrasonic Dual Technology Occupancy Sensors: Designed to detect occupancy using a combination of both passive infrared and ultrasonic technologies.
 - b. Passive Infrared/Acoustic Dual Technology Occupancy Sensors: Designed to detect occupancy using a combination of both passive infrared and audible sound sensing technologies.
 3. Provide LED to visually indicate motion detection with separate color LEDs for each sensor type in dual technology units.
 4. Operation: Unless otherwise indicated, occupancy sensor to turn load on when occupant presence is detected and to turn load off when no occupant presence is detected during an adjustable turn-off delay time interval.
 5. Dual Technology Occupancy Sensors: Field configurable turn-on and hold-on activation with settings for activation by either or both sensing technologies.
 6. Passive Infrared Lens Field of View: Field customizable by addition of factory masking material, adjustment of integral blinders, or similar means to block motion detection in selected areas.
 7. Turn-Off Delay: Field adjustable, with time delay settings up to 30 minutes.
 8. Sensitivity: Field adjustable.
 9. Adaptive Technology: Field selectable; capable of self-adjusting sensitivity and time delay according to conditions.
 10. Integral Photocell: For field selectable and adjustable inhibition of automatic turn-on of load when ambient lighting is above the selected level.
 11. Compatibility (Non-Dimming Sensors): Suitable for controlling incandescent lighting, low-voltage lighting with electronic and magnetic transformers, fluorescent lighting with electronic and magnetic ballasts, and fractional motor loads, with no minimum load requirements.
 12. Load Rating for Line Voltage Occupancy Sensors: As required to control the load indicated on drawings.
 13. Isolated Relay for Low Voltage Occupancy Sensors: SPDT dry contacts, ratings as required for interface with system indicated. When specified on contract documents.
 14. Where wired sensors are indicated, wireless sensors are not acceptable without prior approval of Architect.
- C. Wall Switch Occupancy Sensors:
1. All Wall Switch Occupancy Sensors:
 - a. Description: Occupancy sensors designed for installation in standard wall box at standard wall switch mounting height with a field of view of 180 degrees, integrated manual control capability, and no leakage current to load in off mode.
 - b. Unless otherwise indicated or required to control the load indicated on drawings, provide line voltage units with self-contained relay.
 - c. Where indicated, provide two-circuit units for control of two separate lighting loads, with separate manual controls and separately programmable operation for each load.
 - d. Operation: Field selectable to operate either as occupancy sensor (automatic on/off) or as vacancy sensor (manual-on/automatic off).
 - e. Manual-Off Override Control: When used to turn off load while in automatic-on mode, unit to revert back to automatic mode after no occupant presence is detected during the delayed-off time interval.
 - f. Finish: Match finishes specified for wiring devices in Section 262725, unless otherwise indicated.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- g. Provide vandal resistant lenses for passive infrared (PIR) and dual technology wall switch occupancy sensors where indicated.
- 2. **Passive Infrared/Ultrasonic Dual Technology Wall Switch Occupancy Sensors:** Capable of detecting motion within an area of 900 square feet.
- D. **Wall Dimmer Occupancy Sensors:**
 - 1. **General Requirements:**
 - a. **Description:** Occupancy sensors designed for installation in standard wall box at standard wall switch mounting height with a field of view of 180 degrees, integrated dimming control capability, and no leakage current to load in off mode.
 - b. **Operation:** Field selectable to operate either as occupancy sensor (automatic on/off) or as vacancy sensor (manual-on/automatic off).
 - c. **Manual-Off Override Control Capability:** When used to turn off load while in automatic-on mode, unit to revert back to automatic mode after no occupant presence is detected during the delayed-off time interval.
 - d. **Dimmer:** Solid-state with continuous full-range even control following square law dimming curve, integral radio frequency interference filtering, power failure preset memory, air gap switch accessible without removing wall plate, and listed as complying with UL 1472; type and rating suitable for load controlled.
 - e. Provide field adjustable dimming preset for occupied state.
 - f. Provide fade-to-off operation to notify occupant of impending load turn-off.
 - g. **Finish:** Match finishes specified for wiring devices in Section 262725, unless otherwise indicated.
- E. **Ceiling Mounted Occupancy Sensors:**
 - 1. **All Ceiling Mounted Occupancy Sensors:**
 - a. **Description:** Low profile occupancy sensors designed for ceiling installation.
 - b. Unless otherwise indicated or required to control the load indicated on the drawings, provide line voltage units with self-contained relay, or low voltage units, for use with separate compatible accessory power packs.
 - c. **Finish:** White unless otherwise indicated.
 - 2. **Passive Infrared/Ultrasonic Dual Technology Wall Mounted Occupancy Sensors:**
 - a. **Standard Range Sensors:** Capable of detecting motion within an area of 450 square feet at a mounting height of 9 feet, with a field of view of 360 degrees.
 - 1) **Products:**
 - (a) Wattstopper, DW-311.
 - 3. **Passive Infrared/Ultrasonic Dual Technology Ceiling Mounted Occupancy Sensors:**
 - a. **Standard Range Sensors:** Capable of detecting motion within an area of 450 square feet at a mounting height of 9 feet, with a field of view of 360 degrees.
 - 1) **Products:**
 - (a) Wattstopper, DT-355 series
- F. **Power Packs for Low Voltage Occupancy Sensors:**
 - 1. **Description:** Plenum rated, self-contained low voltage class 2 transformer and relay compatible with specified low voltage occupancy sensors for switching of line voltage loads.
 - 2. Provide quantity and configuration of power and slave packs with all associated wiring and accessories as required to control the load indicated on drawings.
 - 3. **Input Supply Voltage:** Dual rated for 120/277 V ac.
 - 4. **Load Rating:** As required to control the load indicated on drawings.
- G. **Accessories:**
 - 1. Provide heavy duty coated steel wire protective guards compatible with specified occupancy sensors where indicated.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



2.03 TIME SWITCHES

A. Manufacturers:

1. Tork, a division of NSI Industries LLC; _____: www.tork.com
 - a. Product: #7200ZL series.

B. Electromechanical Time Switches:

1. Description: Factory-assembled controller with motor-operated timing dial mechanism and adjustable trippers for setting on/off operations, listed and labeled as complying with UL 917.
2. Program Capability:
 - a. Astronomic Time Switches: With same schedule for each day of the week and skip-a-day feature to omit selected days with automatic adjustment for seasonal changes in sunrise and sunset times.
3. Schedule Capacity:
 - a. 24-Hour Time Switches: Accommodating not less than 12 pairs of selected on/off operations per day.
 - b. Astronomic Time Switches: Capable of turning load on at sunset and off at either sunrise or selected fixed time.
4. Provide spring reserve backup to maintain clock during power outage.
5. Manual override: Capable of overriding current schedule both permanently and temporarily until next scheduled event.
6. Input Supply Voltage: As indicated on the drawings.
7. Output Switch Configuration: As required to control the load indicated on drawings.
8. Output Switch Contact Ratings: As required to control the load indicated on drawings.
9. Provide lockable enclosure; environmental type per NEMA 250 as specified for the following installation locations:
 - a. Indoor clean, dry locations: Type 1.
 - b. Outdoor locations: Type 3R.
10. Provide flush-mounted unit where indicated, where mounted in public areas, or where mounted adjacent to flush-mounted equipment.

2.04 IN-WALL INTERVAL TIMERS

A. Manufacturers:

1. Intermatic, Inc; _____: www.intermatic.com
2. Tork, a division of NSI Industries LLC; _____: www.tork.com

B. Spring Wound In-Wall Interval Timers:

1. Description: Factory-assembled controller with mechanical spring wound timing mechanism requiring no electricity to operate; suitable for mounting in standard wall box; rotary control operator with matching wall plate factory marked with time interval units; listed and labeled as complying with UL 916 or UL 917.
2. Program Capability: Designed to turn load off at end of preset time interval.
3. Time Interval: User selectable from zero up to 2 hours.
4. Switch Configuration: SPST.
5. Contact Ratings: As required to control the load indicated on drawings.
6. Contact Ratings:

2.05 LIGHTING CONTACTORS

A. Manufacturers:

1. Rockwell Automation Inc; Allen-Bradley Products; _____: ab.rockwellautomation.com
2. Schneider Electric; Square D Products; _____: www.schneider-electric.us
3. Siemens Industry, Inc; _____: www.usa.siemens.com

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 4. Substitutions: See Section 016000 - Product Requirements.
- B. Description: Magnetic lighting contactors complying with NEMA ICS 2, and listed and labeled as complying with UL 60947-1 and UL 60947-4-1; noncombination type unless otherwise indicated; ratings, configurations and features as indicated on the drawings.
- C. Short Circuit Current Rating:
 - 1. Provide contactors with listed short circuit current rating not less than the available fault current at the installed location as determined by short circuit study performed in accordance with Section 260573.
- D. Enclosures:
 - 1. Comply with NEMA ICS 6.
 - 2. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
 - a. Indoor Clean, Dry Locations: Type 1 or Type 12.
 - b. Outdoor Locations: Type 3R or Type 4.
 - 3. Finish: Manufacturer's standard unless otherwise indicated.

2.06 CONTROL ACCESSORIES

- A. Auxiliary Contacts:
 - 1. Comply with NEMA ICS 5.
 - 2. Provide number and type of contacts indicated or required to perform necessary functions, including holding (seal-in) circuit and interlocking, plus one normally open (NO) and one normally closed (NC) spare contact for each lighting contactor, minimum.
- B. Pilot Devices:
 - 1. Comply with NEMA ICS 5; heavy-duty type.
 - 2. Nominal Size: 30 mm.
 - 3. Pushbuttons: Unless otherwise indicated, provide momentary, non-illuminated type with flush button operator; normally open or normally closed as indicated or as required.
 - 4. Selector Switches: Unless otherwise indicated, provide maintained, non-illuminated type with knob operator; number of switch positions as indicated or as required.
 - 5. Indicating Lights: Push-to-test type unless otherwise indicated.
 - 6. Provide LED lamp source for indicating lights and illuminated devices.
- C. Control and Timing Relays:
 - 1. Comply with NEMA ICS 5.
 - 2. Provide number and type of relays indicated or required to perform necessary functions.
 - 3. Timing Relays: Electronic.
 - a. Adjustable Timing Range: As indicated on drawings.
- D. Fire-Rated Device Enclosures:
 - 1. Manufacturers:
 - a. Fire Rated Product Specialties Corp; _____: www.frpsonline.com
 - b. Substitutions: See Section 016000 - Product Requirements.
 - 2. Provide as required to preserve fire resistance rating of building elements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate devices and conductors in accordance with NFPA 70.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- C. Verify that openings for outlet boxes are neatly cut and will be completely covered by devices or wall plates.
- D. Verify that final surface finishes are complete, including painting.
- E. Verify that branch circuit wiring installation is completed, tested, and ready for connection to lighting control devices.
- F. Verify that the service voltage and ratings of lighting control devices are appropriate for the service voltage and load requirements at the location to be installed.
- G. Verify that conditions are satisfactory for installation prior to starting work.

3.02 PREPARATION

- A. Provide extension rings to bring outlet boxes flush with finished surface.
- B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.03 INSTALLATION

- A. Install lighting control devices in accordance with NECA 1 (general workmanship) and, where applicable, NECA 130, including mounting heights specified in those standards unless otherwise indicated.
- B. Coordinate locations of outlet boxes provided under Section 260533.16 as required for installation of lighting control devices provided under this section.
 - 1. Mounting Heights: Unless otherwise indicated, as follows:
 - a. Wall Switch Occupancy Sensors: 48 inches above finished floor.
 - 2. Orient outlet boxes for vertical installation of lighting control devices unless otherwise indicated.
 - 3. Locate wall switch occupancy sensor on strike side of door. Where locations are indicated otherwise, notify Architect to obtain direction prior to proceeding with work.
- C. Install lighting control devices in accordance with manufacturer's instructions.
- D. Unless otherwise indicated, connect lighting control device grounding terminal or conductor to branch circuit equipment grounding conductor and to outlet box with bonding jumper.
- E. Install lighting control devices plumb and level, and held securely in place.
- F. Where required and not furnished with lighting control device, provide wall plate in accordance with Section 262725.
- G. Provide required supports in accordance with Section 260529.
- H. Where applicable, install lighting control devices and associated wall plates to fit completely flush to mounting surface with no gaps and rough opening completely covered without strain on wall plate. Repair or reinstall improperly installed outlet boxes or improperly sized rough openings. Do not use oversized wall plates in lieu of meeting this requirement.
- I. Identify lighting control devices in accordance with Section 260553.
- J. Occupancy Sensor Locations:
 - 1. Location Adjustments: Within the design intent, reasonably minor adjustments to locations may be made in order to optimize coverage and avoid conflicts or problems affecting coverage.
 - 2. Locate dual technology passive infrared/ultrasonic occupancy sensors a minimum of 4 feet from air supply ducts or other sources of heavy air flow and as per manufacturer's recommendations, in order to minimize false triggers.
- K. Unless otherwise indicated, install power packs for lighting control devices above accessible ceiling or above access panel in inaccessible ceiling near the sensor location.
- L. Where indicated, install separate compatible wall switches for manual control interface with lighting control devices or associated power packs.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- M. Unless otherwise indicated, install switches on load side of power packs so that switch does not turn off power pack.
- N. Where indicated or required, provide cabinet or enclosure in accordance with Section 260533.16 for mounting of lighting control device system components.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect each lighting control device for damage and defects.
- C. Test occupancy sensors to verify proper operation, including time delays and ambient light thresholds where applicable. Verify optimal coverage for entire room or area.
- D. Test time switches to verify proper operation.
- E. Correct wiring deficiencies and replace damaged or defective lighting control devices.

3.05 ADJUSTING

- A. Adjust devices and wall plates to be flush and level.
- B. Adjust occupancy sensor settings to minimize undesired activations while optimizing energy savings, and to achieve desired function as indicated or as directed by Architect.
- C. Adjust position of directional occupancy sensors and outdoor motion sensors to achieve optimal coverage as required.
- D. Where indicated or as directed by Architect, install factory masking material or adjust integral blinders on dual technology occupancy sensor lenses to block undesired motion detection.
- E. Adjust time switch settings to achieve desired operation schedule as indicated or as directed by Architect.

3.06 CLEANING

- A. Clean exposed surfaces to remove dirt, paint, or other foreign material and restore to match original factory finish.
- B. Clean inside of boxes and control enclosures, prior to installing devices, equipment, etc.

3.07 COMMISSIONING

- A. See Section 019113 - General Commissioning Requirements for commissioning requirements.

3.08 CLOSEOUT ACTIVITIES

- A. See Section 017800 - Closeout Submittals, for closeout submittals.
- B. See Section 017900 - Demonstration and Training, for additional requirements.
- C. Demonstration: Demonstrate proper operation of lighting control devices to Architect, and correct deficiencies or make adjustments as directed.
- D. Training: Train Owner's personnel on operation, adjustment, programming, and maintenance of lighting control devices.
 - 1. Use operation and maintenance manual as training reference, supplemented with additional training materials as required.
 - 2. Provide minimum of two hours of training.
 - 3. Instructor: Qualified contractor familiar with the project and with sufficient knowledge of the installed lighting control devices.
 - 4. Location: At project site.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



SECTION 262725 WIRING DEVICES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Wall switches.
- B. Receptacles.
- C. Wall plates.
- D. Poke-through assemblies.

1.02 RELATED REQUIREMENTS

- A. Section 096900 - Access Flooring.
- B. Section 260519 - Low-Voltage Electrical Power Conductors and Cables: Manufactured wiring systems for use with access floor boxes with compatible pre-wired connectors.
- C. Section 260526 - Grounding and Bonding for Electrical Systems.
- D. Section 260533.16 - Boxes for Electrical Systems.
- E. Section 260533.23 - Surface Raceways for Electrical Systems: Surface raceway systems, including multioutlet assemblies.
- F. Section 260539 - Underfloor Raceways for Electrical Systems.
- G. Section 260553 - Identification for Electrical Systems: Identification products and requirements.
- H. Section 260583 - Wiring Connections: Cords and plugs for equipment.
- I. Section 260923 - Lighting Control Devices: Devices for automatic control of lighting, including occupancy sensors.
- J. Section 260936 - Modular Lighting Control Systems: Lighting controls, to match accessory receptacles and wallplates specified in this section.
- K. Section 262723 - Indoor Service Poles.
- L. Section 262913 - Enclosed Controllers: Manual motor starters and horsepower rated motor-starting switches without overload protection.
- M. Section 271005 - Structured Cabling for Voice and Data - Inside-Plant: Voice and data jacks.

1.03 REFERENCE STANDARDS

- A. FS W-C-596 - Connector, Electrical, Power, General Specification for, Revision H, 2014.
- B. FS W-S-896 - Switches, Toggle (Toggle and Lock), Flush-mounted (General Specification); Revision G, 2014.
- C. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- D. NECA 130 - Standard for Installing and Maintaining Wiring Devices; 2010.
- E. NEMA WD 1 - General Color Requirements for Wiring Devices; 1999 (R2015).
- F. NEMA WD 6 - Wiring Devices - Dimensional Specifications; 2016.
- G. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- H. UL 20 - General-Use Snap Switches; Current Edition, Including All Revisions.
- I. UL 498 - Attachment Plugs and Receptacles; Current Edition, Including All Revisions.
- J. UL 514D - Cover Plates for Flush-Mounted Wiring Devices; Current Edition, Including All Revisions.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- K. UL 943 - Ground-Fault Circuit-Interrupters; Current Edition, Including All Revisions.
- L. UL 1310 - Class 2 Power Units; Current Edition, Including All Revisions.
- M. UL 1449 - Standard for Surge Protective Devices; Current Edition, Including All Revisions.
- N. UL 1472 - Solid-State Dimming Controls; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate the placement of outlet boxes with millwork, furniture, equipment, etc. installed under other sections or by others.
 - 2. Coordinate wiring device ratings and configurations with the electrical requirements of actual equipment to be installed.
 - 3. Coordinate the placement of outlet boxes for wall switches with actual installed door swings.
 - 4. Coordinate the installation and preparation of uneven surfaces, such as split face block, to provide suitable surface for installation of wiring devices.
 - 5. Coordinate the core drilling of holes for poke-through assemblies with the work covered under other sections.
 - 6. Notify Architect and Owner's project coordinator, of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.
- B. Sequencing:
 - 1. Do not install wiring devices until final surface finishes and painting are complete.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's catalog information showing dimensions, colors, and configurations.
 - 1. Surge Protection Receptacles: Include surge current rating, voltage protection rating (VPR) for each protection mode, and diagnostics information.
- C. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
- D. Operation and Maintenance Data:
 - 1. GFCI Receptacles: Include information on status indicators.
 - 2. Surge Protection Receptacles: Include information on status indicators.
- E. Project Record Documents: Record actual installed locations of wiring devices.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 - Product Requirements, for additional provisions.
 - 2. Screwdrivers for Tamper-Resistant Screws: Two for each type of screw.
 - 3. Extra Keys for Locking Switches: Two of each type.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.
- B. Maintain at the project site a copy of each referenced document that prescribes execution requirements.
- C. Products: Listed, classified, and labeled as suitable for the purpose intended.
- D. Product Listing Organization Qualifications: An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



1.07 DELIVERY, STORAGE, AND PROTECTION

- A. Store in a clean, dry space in original manufacturer's packaging until ready for installation.

PART 2 PRODUCTS

2.01 WIRING DEVICE APPLICATIONS

- A. Provide wiring devices suitable for intended use and with ratings adequate for load served.
- B. For single receptacles installed on an individual branch circuit, provide receptacle with ampere rating not less than that of the branch circuit.
- C. Provide weather resistant GFCI receptacles with specified weatherproof covers for receptacles installed outdoors or in damp or wet locations.
- D. Provide tamper resistant receptacles for receptacles installed in dwelling units and children areas.
- E. Provide GFCI protection for receptacles installed within 6 feet of sinks.
- F. Provide GFCI protection for receptacles installed in kitchens.
- G. Provide GFCI protection for receptacles serving electric drinking fountains.
- H. Unless noted otherwise, do not use combination switch/receptacle devices.

2.02 WIRING DEVICE FINISHES

- A. Provide wiring device finishes as described below unless otherwise indicated.
- B. Wiring Devices, Unless Otherwise Indicated: Gray with stainless steel wall plate.
- C. Wiring Devices Installed in Finished Spaces: Gray with stainless steel wall plate.
- D. Wiring Devices Installed in Unfinished Spaces: Gray with galvanized steel wall plate.
- E. Wiring Devices Installed in Wet or Damp Locations: Gray with specified weatherproof cover.
- F. Wiring Devices Installed in ceilings: White with stainless steel wall plate, except for surge protection receptacles.
- G. Isolated Ground Convenience Receptacles: Orange with a stainless steel cover plate.
- H. Surge Protection Receptacles: Blue with a stainless steel cover plate.
- I. Wiring Devices Connected to Emergency Power: Red with wall plate as specified for wiring devices connected to normal power, but engraved "Emergency".
- J. Clock Hanger Receptacles: Gray with stainless steel wall plate.

2.03 WALL SWITCHES

- A. Manufacturers:
 - 1. Hubbell Incorporated; _____: www.hubbell.com
 - 2. Leviton Manufacturing Company, Inc; _____: www.leviton.com
 - 3. Pass & Seymour, a brand of Legrand North America, Inc; _____: www.legrand.us
- B. Wall Switches - General Requirements: AC only, quiet operating, extra heavy duty industrial grade, switches with silver alloy contacts, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 20 and where applicable, FS W-S-896; types as indicated on the drawings.
 - 1. Wiring Provisions: Terminal screw actuated binding clamp for back and side wiring with separate ground terminal screw.
- C. Standard Wall Switches: Industrial specification grade, 20 A, 120/277 V with standard toggle type switch actuator and maintained contacts; single pole single throw, double pole single throw, three way, or four way as indicated on the drawings.
 - 1. Products:
 - a. Hubbell,

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- b. Leviton,
 - c. Pass & Seymour,
- D. Lighted Wall Switches: Industrial specification grade, 20 A, 120/277 V with clear illuminated standard toggle type switch actuator and maintained contacts; illuminated with load off, single pole single throw, double pole single throw, three way, or four way as indicated on the drawings.
- 1. Products:
 - a. Hubbell,
 - b. Leviton,
 - c. Pass & Seymour,
- E. Pilot Light Wall Switches: Industrial specification grade, 20 A, 120/277 V with clear illuminated standard toggle type switch actuator and maintained contacts; illuminated with load on; single pole single throw, double pole single throw, three way, or four way as indicated on the drawings.
- 1. Products:
 - a. Hubbell,
 - b. Leviton,
 - c. Pass & Seymour,
 - d. _____
- F. Locking Wall Switches: Industrial specification grade, 20 A, 120/277 V with lever type keyed switch actuator and maintained contacts; switches keyed alike; single pole single throw, double pole single throw, three way, or four way as indicated on the drawings.
- 1. Products:
 - a. Hubbell,
 - b. Leviton,
 - c. Pass & Seymour,
- G. Momentary Contact Wall Switches: Industrial specification grade, 20 A, 120/277 V with toggle type three position switch actuator and momentary contacts; single pole double throw, off with switch actuator in center position.
- 1. Products:
 - a. Hubbell,
 - b. Leviton,
 - c. Pass & Seymour,
- H. Locking Momentary Contact Wall Switches: Industrial specification grade, 20 A, 120/277 V with lever type keyed three position switch actuator and momentary contacts; switches keyed alike; single pole double throw, off with switch actuator in center position.
- 1. Products:
 - a. Hubbell,
 - b. Leviton,
 - c. Pass & Seymour,

2.04 RECEPTACLES

- A. Manufacturers:
- 1. Hubbell Incorporated; _____: www.hubbell.com
 - 2. Leviton Manufacturing Company, Inc; _____: www.leviton.com
 - 3. Pass & Seymour, a brand of Legrand North America, Inc; _____: www.legrand.us
 - 4. Source Limitations: Where wall controls are furnished as part of lighting control system, provide accessory matching receptacles and wallplates by the same manufacturer in locations indicated.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- B. Receptacles - General Requirements: Self-grounding, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 498, and where applicable, FS W-C-596; types as indicated on the drawings.
1. Wiring Provisions: Terminal screw actuated binding clamp for back wiring with separate ground terminal screw.
 2. NEMA configurations specified are according to NEMA WD 6.
 3. Hospital Grade Receptacles: Listed as complying with UL 498 Supplement SD, with green dot hospital grade mark on device face.
- C. Convenience Receptacles:
1. Standard Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R; single or duplex as indicated on the drawings.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
 2. Automatically Controlled Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R; controlled receptacle marking on device face per NFPA 70; single or duplex as indicated on the drawings.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
 3. Isolated Ground Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R, with ground contacts isolated from mounting strap; isolated ground triangle mark on device face; single or duplex as indicated on the drawings.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
 4. Weather Resistant Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R, listed and labeled as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations; single or duplex as indicated on the drawings.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
 5. Tamper Resistant Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R, listed and labeled as tamper resistant type; single or duplex as indicated on the drawings.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
 - 4) _____
 6. Tamper Resistant and Weather Resistant Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R, listed and labeled as tamper resistant type and as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations; single or duplex as indicated on the drawings.
 - a. Products:
 - 1) Hubbell,

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 2) Leviton,
- 3) Pass & Seymour,

D. GFCI Receptacles:

- 1. GFCI Receptacles - General Requirements: Self-testing, with feed-through protection and light to indicate ground fault tripped condition and loss of protection; listed as complying with UL 943, class A.
 - a. Provide test and reset buttons of same color as device.
- 2. Standard GFCI Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
- 3. Weather Resistant GFCI Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style, listed and labeled as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
 - 4) _____
 - 5) _____
- 4. Tamper Resistant GFCI Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style, listed and labeled as tamper resistant type.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
- 5. Tamper Resistant and Weather Resistant GFCI Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style, listed and labeled as tamper resistant type and as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,

E. USB Charging Devices:

- 1. USB Charging Devices - General Requirements: Listed as complying with UL 1310.
 - a. Charging Capacity - Two-Port Devices: 2.1 A, minimum.
 - b. Charging Capacity - Four-Port Devices: 4.2 A, minimum.
- 2. USB Charging/Tamper Resistant Receptacle Combination Devices: Two-port (Type A) USB charging device and receptacle, commercial specification grade, duplex, 20A, 125V, NEMA 5-20R, listed and labeled as tamper resistant type; rectangular decorator style.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,
- 3. USB Charging Noncombination Devices: Four-port (Type A); rectangular decorator style.
 - a. Products:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 1) Hubbell,
- 2) Leviton,
- 3) Pass & Seymour,
- 4) _____.

F. Surge Protection Receptacles:

1. Surge Protection Receptacles - General Requirements: Listed and labeled as complying with UL 1449, Type 2 or 3.
 - a. Energy Dissipation: Not less than 240 J per mode.
 - b. Protected Modes: L-N, L-G, N-G.
 - c. UL 1449 Voltage Protection Rating (VPR): Not more than 700 V for L-N, L-G modes and 1200 V for N-G mode.
 - d. Diagnostics:
 - 1) Visual Notification: Provide indicator light to report functional status of surge protection.
2. Standard Surge Protection Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style.
 - a. Products:
 - 1) Hubbell,
 - 2) Leviton,
 - 3) Pass & Seymour,

G. Clock Hanger Receptacles: See Section 275313 for additional information.

2.05 WALL PLATES

A. Manufacturers:

1. Hubbell Incorporated; _____: www.hubbell-wiring.com
2. Leviton Manufacturing Company, Inc; _____: www.leviton.com
3. Pass & Seymour, a brand of Legrand North America, Inc; _____: www.legrand.us
4. Source Limitations: Where wall controls are furnished as part of lighting control system, provide accessory matching receptacles and wallplates by the same manufacturer in locations indicated.

B. Wall Plates: Comply with UL 514D.

1. Configuration: One piece cover as required for quantity and types of corresponding wiring devices.
2. Size: Standard; _____.
3. Screws: Metal with slotted heads finished to match wall plate finish.

C. Stainless Steel Wall Plates: Brushed satin finish, 0.032 inch thick, Type 302/304 stainless steel.

D. Galvanized Steel Wall Plates: Rounded corners and edges, with corrosion resistant screws.

E. Weatherproof Covers for Damp Locations: Gasketed, cast aluminum, with self-closing hinged cover and corrosion-resistant screws; listed as suitable for use in wet locations with cover closed.

F. Weatherproof Covers for Wet Locations: Gasketed, cast aluminum, with hinged lockable cover and corrosion-resistant screws; listed as suitable for use in wet locations while in use with attachment plugs connected and identified as extra-duty type.

2.06 FLOOR BOX SERVICE FITTINGS

A. Manufacturers:

1. Hubbell Incorporated; _____: www.hubbell.com
2. Thomas & Betts Corporation; _____: www.tnb.com
3. Wiremold, a brand of Legrand North America, Inc; _____: www.legrand.us

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- B. Description: Service fittings compatible with floor boxes provided under Section 260533.16 with components, adapters, and trims required for complete installation.
- C. Above-Floor Service Fittings:
 - 1. Coverplate configuration as shown on the drawings.
 - 2. Single Service Pedestal Furniture Feed:
 - 3. Dual Service Pedestal Combination Outlets:
 - a. Provide barrier to separate line and low voltage compartments.
- D. Flush Floor Service Fittings:
 - 1. Single Service Flush Convenience Receptacles:
 - a. Cover: Round.
 - b. Configuration: One standard convenience duplex receptacle(s) with duplex flap opening(s).
 - 2. Single Service Flush Communications Outlets:
 - a. Cover: Round.
 - b. Configuration: As shown on the drawings.
 - c. Voice and Data Jacks: As specified in Section 271005.
 - 3. Single Service Flush Furniture Feed:
 - a. Cover: Round.
 - b. Configuration: One 2-1/8 inch by 3/4 inch combination threaded opening(s).
 - 4. Dual Service Flush Combination Outlets:
 - a. Cover: Round.
 - b. Configuration:
 - 1) Power: One standard convenience duplex receptacle(s) with duplex flap opening(s).
 - 2) Voice and Data Jacks: As specified in Section 271005.
 - 5. Dual Service Flush Furniture Feed:
 - a. Cover: Round.
 - b. Configuration:
 - 1) Power: One 2-1/8 inch by 3/4 inch combination threaded opening(s).
 - 2) Communications: One 2-1/8 inch by 1 inch combination threaded opening(s).
 - 6. Accessories:
 - a. Tile Rings: Finish to match covers; configuration as required to accommodate specified covers.
 - b. Carpet Flanges: Finish to match covers; configuration as required to accommodate specified covers.

2.07 POKE-THROUGH ASSEMBLIES

- A. Manufacturers:
 - 1. Hubbell Incorporated; _____; www.hubbell.com
 - 2. Thomas & Betts Corporation; _____; www.tnb.com
 - 3. Wiremold, a brand of Legrand North America, Inc; _____; www.legrand.us
 - 4. Substitutions: See Section 016000 - Product Requirements.
- B. Description: Assembly comprising floor service fitting, poke-through component, fire stops and smoke barriers, and junction box for conduit termination; fire rating listed to match fire rating of floor and suitable for floor thickness where installed.
- C. Above-Floor Service Fittings:
 - 1. Single Service Pedestal Convenience Receptacles:
 - a. Configuration: One standard convenience duplex receptacle.
 - 2. Single Service Pedestal Communications Outlets:
 - a. Configuration: One 1 inch bushed opening.
 - b. Voice and Data Jacks: As specified in Section 271005.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3. Single Service Pedestal Furniture Feed:
 - a. Configuration: One 3/4 inch knockout.
 4. Dual Service Pedestal Combination Outlets:
 - a. Configuration:
 - 1) Power: One standard convenience duplex receptacle.
 - 2) Communications: One 1 inch bushed opening.
 - 3) Voice and Data Jacks: As specified in Section 271005.
 - b. Provide barrier to separate line and low voltage compartments.
- D. Flush Floor Service Fittings:
1. Single Service Flush Convenience Receptacles:
 - a. Configuration: One standard convenience duplex receptacle(s) with duplex flap opening(s).
 2. Single Service Flush Communications Outlets:
 - a. Configuration: _____.
 - b. Voice and Data Jacks: As specified in Section 271005.
 3. Single Service Flush Furniture Feed:
 - a. Configuration: One 2 inch by 1-1/4 inch combination threaded opening(s).
 4. Dual Service Flush Combination Outlets:
 - a. Cover: Hinged door(s).
 - b. Configuration:
 - 1) Power: One standard convenience duplex receptacle(s).
 - 2) Communications: _____.
 - 3) Voice and Data Jacks: As specified in Section 271005.
 5. Dual Service Flush Furniture Feed:
 - a. Configuration:
 - 1) Power: One 3/4 inch threaded opening(s).
 - 2) Communications: One 1-1/4" threaded opening(s).
 6. Accessories:
 - a. Closure Plugs: Size and fire rating as required to seal unused core hole and maintain fire rating of floor.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate devices and conductors in accordance with NFPA 70.
- C. Verify that wall openings are neatly cut and will be completely covered by wall plates.
- D. Verify that final surface finishes are complete, including painting.
- E. Verify that floor boxes are adjusted properly.
- F. Verify that branch circuit wiring installation is completed, tested, and ready for connection to wiring devices.
- G. Verify that core drilled holes for poke-through assemblies are in proper locations.
- H. Verify that openings in access floor are in proper locations.
- I. Verify that conditions are satisfactory for installation prior to starting work.

3.02 PREPARATION

- A. Provide extension rings to bring outlet boxes flush with finished surface.
- B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3.03 INSTALLATION

- A. Perform work in accordance with NECA 1 (general workmanship) and, where applicable, NECA 130, including mounting heights specified in those standards unless otherwise indicated.
- B. Coordinate locations of outlet boxes provided under Section 260533.16 as required for installation of wiring devices provided under this section.
 - 1. Mounting Heights: Unless otherwise indicated, as follows:
 - a. Wall Switches: 48 inches above finished floor.
 - b. Receptacles: 18 inches above finished floor or 6 inches above counter.
 - c. All box height measurements are to the top of the box.
 - 2. Orient outlet boxes for vertical installation of wiring devices unless otherwise indicated.
 - 3. Where multiple receptacles or wall switches are installed at the same location and at the same mounting height, gang devices together under a common wall plate.
 - 4. Locate wall switches on strike side of door with edge of wall plate 8 inches from edge of door frame. Where locations are indicated otherwise, notify Architect to obtain direction prior to proceeding with work.
 - 5. Locate receptacles for electric drinking fountains concealed behind drinking fountain according to manufacturer's instructions.
- C. Install wiring devices in accordance with manufacturer's instructions.
- D. Install permanent barrier between ganged wiring devices when voltage between adjacent devices exceeds 300 V.
- E. Where required, connect wiring devices using pigtails not less than 12 inches long. Do not connect more than one conductor to wiring device terminals.
- F. Connect wiring devices by inserting conductors into back of device and tightening to proper torque specified by the manufacturer. Where present, do not use push-in pressure terminals that do not rely on screw-actuated binding.
- G. Unless otherwise indicated, connect wiring device grounding terminal to branch circuit equipment grounding conductor and to outlet box with bonding jumper.
- H. For isolated ground receptacles, connect wiring device grounding terminal only to identified branch circuit isolated equipment grounding conductor. Do not connect grounding terminal to outlet box or normal branch circuit equipment grounding conductor.
- I. Provide GFCI receptacles with integral GFCI protection at each location indicated. Do not use feed-through wiring to protect downstream devices.
- J. Where split-wired duplex receptacles are indicated, remove tabs connecting top and bottom receptacles.
- K. Install wiring devices plumb and level with mounting yoke held rigidly in place.
- L. Install wall switches with OFF position down.
- M. Install vertically mounted receptacles with grounding pole on top and horizontally mounted receptacles with grounding pole on left.
- N. Install wall plates to fit completely flush to wall with no gaps and rough opening completely covered without strain on wall plate. Repair or reinstall improperly installed outlet boxes or improperly sized rough openings. Do not use oversized wall plates in lieu of meeting this requirement.
- O. Install blank wall plates on junction boxes and on outlet boxes with no wiring devices installed or designated for future use.
- P. Identify wiring devices and circuiting, in accordance with Section 260553.
- Q. Install poke-through closure plugs in each unused core holes to maintain fire rating of floor.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect each wiring device for damage and defects.
- C. Operate each wall switch, wall dimmer, and fan speed controller with circuit energized to verify proper operation.
- D. Test each receptacle to verify operation and proper polarity.
- E. Test each GFCI receptacle for proper tripping operation according to manufacturer's instructions.
- F. Inspect each surge protection receptacle to verify surge protection is active.
- G. Correct wiring deficiencies and replace damaged or defective wiring devices.

3.05 ADJUSTING

- A. Adjust devices and wall plates to be flush and level.

3.06 CLEANING

- A. Clean exposed surfaces to remove dirt, paint, or other foreign material and restore to match original factory finish.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



**SECTION 265013
LUMINAIRE SCHEDULE**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Specific requirements for individual luminaire types.

1.02 RELATED REQUIREMENTS

- A. Section 265100 - Interior Lighting: General requirements applicable to products specified in this section.
- B. Section 265537 - Obstruction and Landing Lights: General requirements applicable to products specified in this section.
- C. Section 265561 - Theatrical Lighting: General requirements applicable to products specified in this section.
- D. Section 265600 - Exterior Lighting: General requirements applicable to products specified in this section.

1.03 REFERENCE STANDARDS

- A. ANSI C136.10 - American National Standard for Roadway and Area Lighting Equipment - Locking-Type Photocontrol Devices and Mating Receptacles - Physical and Electrical Interchangeability and Testing; 2010.
- B. IES RP-8 - Roadway Lighting; 2014.

PART 2 PRODUCTS

2.01 LUMINAIRE TYPES

- A. Furnish products as specified below.
- B. Recessed Troffer.
 - 1. Products:
 - a. Lithonia Lighting.
 - 1) 2BLTBA Series
 - b. Phillips Lighting.
 - 1) FluxGrid Series
 - c. Columbia Lighting
 - 1) LCAT Series
 - d. Deco Lighting
 - 1) GO-LED Series
 - e. Eaton
 - 1) 22/24CZ
 - f. No substitutions permitted.
 - 2. Housing: Steel, painted white.
 - 3. Nominal Size: 1x4 ft, 2x2 ft and 2x4 ft.
 - 4. LED light source: 4000K (80 CRI), 3500K (80 and 90 CRI), 4000K (90 CRI) and 5000K (80 and 90 CRI) may be used only upon approval by the Owner.
 - 5. Light Output:
 - a. Lithonia:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 20L, 30L, 40L, 48L and 60L.
 - (b) 2 x 2 foot fixture: 20L, 33L and 40L.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- (c) 2 x 4 foot fixture: 30L, 40L, 48L, 60L and 72L.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - b. Phillips:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 38L, 45L and 41B.
 - (b) 2 x 2 foot fixture: 38L, 38B and 47L.
 - (c) 2 x 4 foot fixture: 42B, 43L, 48L, 5L and 74L.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) 30L (2 x 4 foot fixture) and 38L (2 x 4 foot fixture).
 - c. Deco:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 x 2 foot fixture: 2340, 3250 and 4410.
 - (b) 2 x 4 foot fixture: 3500, 4280 and 5800
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - d. Eaton
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 20, 25, 29, 35, 39, 44
 - (b) 2 x 2 foot fixture: 20, 24, 32, 39, 44
 - (c) 2 x 4 foot fixture: 30, 35, 40, 45, 50, 55, 60, 65
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - 6. Diffuser: Diffuse and ribbed.
 - a. Lithonia: "ADP", Curved, linear prisms.
 - b. Philips: "D", Diffuse, Ribbed.
 - c. Columbia: "R", Rectangular, linear prisms.
 - d. Deco: "N" Architectural Narrow Lens
 - e. Eaton: "blank", Ribbed, frosted acrylic
 - 7. Voltage: Universal 120-277 V.
 - 8. LED drivers: Provide LED drivers as recommended by the manufacturer.
 - 9. Dimming Options: Provide 0-10v dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 - 10. Provide emergency power supply unit in luminaires designated with "EM" on the drawings.
 - a. Emergency battery packs are only permitted where no generator or inverter power is available.
 - 11. Mounting: Lay-in, grid ceiling.
- C. Flat Panel LED
- 1. Products:
 - a. Lithonia
 - 1) EPANL Series
 - b. Komee
 - 1) KMLP Series
 - c. Philips
 - 1) FXP Series

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- d. Metalux
 - 1) FP Series
 - e. Deco
 - 1) CFP Series
 - f. Sylvania
 - 1) PanelF1A Series
 - g. RAB
 - 1) EZPAN
 - h. No substitutions permitted.
2. Housing: Aluminum bezel with steel back plate.
3. Nominal Size: 1'x4', 2'x2', and 2'x4'
4. LED light source: 4000K (80 CRI)
5. Light Output:
- a. Lithonia:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 1500L, 3000L, 4000L, 4800L, 6000L
 - (b) 2 x 2 foot fixture: 2000L, 3400L, 4000L, 4800L
 - (c) 2 x 4 foot fixture: 3000L, 4000L, 4800L, 5400L, 6000L, 6800L
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - b. Phillips:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 x 2 foot fixture: 3800L
 - (b) 2 x 4 foot fixture: 4200L
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - c. Komee:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 x 2 foot fixture: 4160L, 4800L
 - (b) 2 x 4 foot fixture: 6500L, 6700L
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - d. Metalux:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 3176L, 4389L
 - (b) 2 x 2 foot fixture: 2551L, 3560L, 4567L
 - (c) 2 x 4 foot fixture: 3608L, 4858L, 6611L
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - e. Deco
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 30, 35
 - (b) 2 x 2 foot fixture: 30, 35
 - (c) 2 x 4 foot fixture: 30, 35

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - f. Sylvania
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 3300
 - (b) 2 x 2 foot fixture: 3500
 - (c) 2 x 4 foot fixture: 3300, 4200
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - g. RAB
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 x 2 foot fixture: 3000, 4135
 - (b) 2 x 4 foot fixture: 4286, 5902
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - 6. Diffuser: Satin white lens
 - 7. Voltage: Universal 120-277 V.
 - 8. LED drivers: Provide LED drivers as recommended by the manufacturer.
 - 9. Dimming Options: Provide 0-10V, 1% dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 - 10. Provide emergency power supply unit in luminaires designated with "EM" on the drawings.
 - a. Emergency battery packs are only permitted where generator or inverter power is not available.
 - 11. Provide with the following features/accessories:
 - a. Surfacemount troffer kit
 - 12. Mounting: Lay-in, grid ceiling.
- D. Linear Suspended Pendant (rectangular 7" x 2" nominal, up/down light)
- 1. Products:
 - a. Litecontrol
 - 1) SAE 104 Series
 - b. Lithonia Lighting
 - 1) GRAD Series
 - c. Ledalite
 - 1) 7406 Series
 - d. Corelite
 - 1) J2 Series
 - e. Substitutes not permitted.
 - 2. Housing: Steel, painted white.
 - 3. Maximum Section Length in Row: 8 feet.
 - 4. LED light source: 4000K color temperature.
 - 5. Light Output: 1300 Lumens/ft (nominal)
 - 6. CRI: 80min.
 - 7. Distribution: 20% Up, 80% Down
 - 8. Voltage: Universal 120-277 V.
 - 9. LED drivers: Provide LED drivers as recommended by the manufacturer.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



10. Dimming Options: Provide 0-10V (1%) dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 11. Provide with the following features/accessories:
 - a. Dust cover.
 12. Mounting: Suspended.
- E. Linear Suspended Pendant (Square 4" x 4" nominal, down light)
1. Products:
 - a. Prudential
 - 1) P40 Series
 - b. Pinnacle
 - 1) EDGE EX4 Series
 - c. Substitutes not permitted.
 2. Housing: Aluminum, painted white.
 3. Maximum Section Length in Row: 8 feet.
 4. LED light source: 4000K color temperature.
 5. Light Output: 394 Lumens/ft (nominal)
 6. CRI: 80min.
 7. Distribution: 100% down
 8. Lens: Satine
 9. Voltage: Universal 120-277 V.
 10. LED drivers: Provide LED drivers as recommended by the manufacturer.
 11. Dimming Options: Provide 0-10V (1%) dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 12. Mounting: Suspended.
- F. General purpose strip.
1. Products:
 - a. Philips Lighting.
 - 1) Fluxstream Series.
 - b. Lithonia.
 - 1) ZL1D Series.
 - c. Metalux.
 - 1) 4SNLED Series.
 - d. Deco Lighting
 - 1) DACH-LED Series.
 - e. Substitutes not permitted.
 2. Housing: Steel, painted white.
 3. Nominal Length: 4 feet.
 4. LED light source: 4000K.
 5. Light Output:
 - a. Phillips:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 foot fixture: 20L and 30L.
 - (b) 3 foot fixture: 30L.
 - (c) 4 foot fixture: 30L, 40L 55L and 70L.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - b. Lithonia:
 - 1) The following lumen configurations are recommended by the owner:

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- (a) 2 foot fixture: 2500LM and 3500LM.
 - (b) 4 foot fixture: 3000LM, 5000LM and 7000LM.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - c. Metalux:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 foot fixture: 20SL and 30SL.
 - (b) 4 foot fixture: 30SL, 41SL, and 50SL.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - d. Deco:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 foot fixture: 2350.
 - (b) 4 foot fixture: 2560, 4550, 5980.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - e. Sylvania:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 2 foot fixture: 1900.
 - (b) 4 foot fixture: 4000, 6200.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 - 6. Reflector: None.
 - 7. Lens: Frosted acrylic.
 - 8. Voltage: Universal 120-277 V.
 - 9. LED drivers: Provide LED drivers as recommended by the manufacturer.
 - 10. Dimming Options: Provide 0-10v dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 - 11. Provide emergency power supply unit in luminaires designated with "EM" on the drawings.
 - a. Emergency battery packs are only permitted where not generator or inverter power is available.
 - 12. Provide with the following features/accessories:
 - a. Fusing: Fast blow type.
 - b. Wireguard(s), where installed in areas where fixture may be damaged.
 - 13. Mounting: Surface, Ceiling or Suspended.
- G. Vapor Tight Luminaire
- 1. Products:
 - a. Philips Lighting
 - 1) V3W Series
 - b. Lithonia Lighting
 - 1) VAP Series
 - c. Eaton
 - 1) 4VT3
 - d. Substitutes not permitted.
 - 2. Housing: Frosted polycarbonate with closed-cell gasket, wet location listed.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



3. Lens: Clear Polycarbonate.
 4. Nominal Length: 4 feet.
 5. LED light source: 4000K, 80 CRI.
 6. Light Output:
 - a. Lithonia
 - 1) 4000, 6000, 8000, 12000, and 15000 lumens
 - b. Philips
 - 1) 3500, 4300, 5100, 7000, 8000, and 10000 lumens
 - c. Eaton
 - 1) 4000, 6000 and 80000 lumens
 - d. The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - 1) No lumen packages not permitted at this time.
 7. Reflector: None.
 8. Voltage: Universal 120-277 V.
 9. LED drivers: Provide LED drivers as recommended by the manufacturer.
 10. Dimming Options: Provide 0-10v dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 11. Mounting: Surface, Ceiling or Suspended. _____.
- H. Food Processing Troffers
1. Products:
 - a. Kurtzon.
 - 1) FP Series.
 - b. No substitutions permitted.
 2. Listing: NSF2, IP66, ETL
 3. Housing: Steel, painted white.
 4. Nominal Size: 1x4 ft, 2x2 ft and 2x4 ft.
 5. LED light source: 4000K (80 CRI). 3500K (80 and 90 CRI), 4000K (90 CRI) and 5000K (80 and 90 CRI) may be used only upon approval by the Owner.
 6. Light Output:
 - a. Kurtzon:
 - 1) The following lumen configurations are recommended by the owner:
 - (a) 1 x 4 foot fixture: 20L, 30L, 40L, 48L and 60L.
 - (b) 2 x 2 foot fixture: 20L, 33L and 40L.
 - (c) 2 x 4 foot fixture: 30L, 40L, 48L, 60L and 72L.
 - 2) The following lumen configurations are not recommended due to additional cost and delay in shipping:
 - (a) No lumen packages not permitted at this time.
 7. Door: Steel, flush, white. Bottom access. Gasketed.
 8. Lens: P12 prismatic pattern inverted, 0.135" virgin acrylic, gasketed.
 9. Voltage: Universal 120-277 V.
 10. LED drivers: Provide LED drivers as recommended by the manufacturer.
 11. Dimming Options: Provide 0-10v dimming options for all fixtures. Other dimming options are not permitted, unless directed by the Owner.
 12. Provide emergency power supply unit in luminaires designated with "EM" on the drawings.
 - a. Operate two lamp(s) at a minimum of 1350 lumens unless otherwise indicated with indicated illumination evenly divided between the lamps.
 - b. Emergency battery packs are only permitted where not generator or inverter power is available.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- 13. Provide with the following features/accessories:
 - a. Fusing: Fast blow type.
- 14. Mounting: Lay-in, grid ceiling.
- I. Recessed compact downlight.
 - 1. Products:
 - a. Gotham Lighting:
 - 1) Incito Series.
 - 2) EVO Series.
 - b. Prescolite:
 - 1) LF6SL Series.
 - c. Lightolier:
 - 1) EasyLyte or LyteProfileSeries
 - d. Halo:
 - 1) HC6 Series
 - e. No Substitutes permitted.
 - 2. Reflector Finish: Semi-specular, clear.
 - 3. Trim: Match reflector finish.
 - 4. Voltage: Universal 120-277 V.
 - 5. Provide emergency power supply unit in luminaires designated with "EM" on the drawings.
 - 6. Provide sloped ceiling adapters suitable for the installed location where required.
 - 7. Provide with the following features/accessories:
 - a. Fusing.
 - 8. Mounting: Recessed.
 - 9. Listings:
 - a. Non-IC Rated: Not suitable for direct contact with insulation and combustible materials.
- J. Exit sign.
 - 1. Products:
 - a. Dual-Lite.
 - 1) Generator/Inverter Power Operation:
 - (a) Single face #SESGW
 - (b) Double face #SEDGW
 - 2) Emergency Battery Operation:
 - (a) Single face #SESGWE
 - (b) Double face #SEDGWE
 - b. No alternate manufacturers permitted.
 - 2. Lamps: LED.
 - 3. Housing: Die cast aluminum.
 - 4. Finish: White.
 - 5. Mounting Type: Universal.
 - 6. Number of Faces: As specified.
 - 7. Letter Color: Green.
 - 8. Emergency Operation: For use only where generator or inverter power is not available..
 - a. Battery: Nickel cadmium.
 - b. Only permitted in areas where no generator or inverter power is available.
 - 9. Voltage: Dual 120/277 V.
 - 10. Mounting:
 - a. Ceiling-mounted: _____.
 - b. Wall-mounted: _____.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



K. High bay luminaire.

1. Products:
 - a. GE Lighting.
 - 1) Albeo #ABV3 series
 - b. Lithonia.
 - 1) I-beam, LBG
 - c. Metalux
 - 1) OHB Series

L. Under counter lighting.

1. Products:
 - a. H.E. Williams.
 - 1) 1SF Series.
 - b. Nora Lighting.
 - 1) NUD-88 Series
 - c. EELP
 - 1) VLUC Series.
 - d. Eaton
 - 1) HU30
 - e. Housing: Steel, painted white.
 - f. Correlated Color Temperature: 4,100 K.
 - g. Voltage: Universal 120-277 V.
 - h. Provide with the following features/accessories:
 - 1) Built-in on/off rocker switch
 - 2) End to end connectors
 - i. Mounting: Surface mount to bottom of cabinet.

M. Tape Light

1. Products
 - a. Sylvania Osram
 - b. Q-Tran

N. Wall mounted strip

1. Products
 - a. Lithonia Lighting
 - 1) #WL4 Series
 - b. Philips Lighting
 - 1) Fluxstream #FSW Series

O. Wall wash linear

1. Products
 - a. ELP
 - 1) AKTB LED Series

P. Track Lighting

1. Products
 - a. Track
 - 1) Halo
 - (a) L650 Series
 - 2) LSI (Lighting Services Inc.)
 - (a) Surface Track (120V).
 - b. Heads
 - 1) Philips Lightolier

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- (a) Corepro Mini Cylinder Series, #LT-H-08--
 - (1) Beam spread, CRI/CCT, and finish color to be determined per project.
- 2) LSI (Lighting Services Inc.)
 - (a) LED light sourced track heads.
- 3) Halo
 - (a) L808

Q. Pole-mounted LED area Luminaire.

- 1. Configuration: As required for proper illumination per Illumination Engineering Society of North America (IESNA).
- 2. Luminaire (Fixture Heads):
 - a. Products:
 - 1) Kim Lighting
 - 2) Substitutions are not permitted.
 - b. Housing: Aluminum.
 - c. Finish: Painted
 - 1) Academic Campus Areas: Custom Color "CC" - PMS 462 Gloss Brown.
 - 2) Heritage Housing Areas: Custom Color "CC" - RAL 7008.
 - d. Luminaire Head Shape: Rectilinear.
 - e. Illumination Source LED.
 - f. Shielding: Flat glass lens.
 - g. Lighting Distribution per IES RP-8:
 - 1) Lateral Distribution: Types II, III, IV and V.
 - 2) Cutoff Category: Full cutoff.
 - h. Voltage: Multi-tap 120/208/240/277 V.
 - i. Driver: Provide LED driver per manufacturer's recommendations.
 - j. Pole Mounting: Standard arm suitable for mounting on specified pole, finish to match luminaire.
 - k. Building/Wall Mounting: Standard arm suitable for wall-mounting.
 - l. Provide with the following features/accessories:
 - 1) Fusing.
 - 2) Integral locking receptacle for photo control complying with ANSI C136.10.
 - 3) House-side shield, external, if required for critical areas.
 - m. Listings:
 - 1) Suitable for wet locations.
- 3. Pole:
 - a. Products:
 - 1) Kim Lighting:
 - (a) Roadway and Parking Areas: #PAR25-6188.
 - (b) Walkways and Sidewalks: #PAR14-4188.
 - (c) License Plate Readers: #PRA12-6250.
 - 2) Substitutions are not permitted.
 - b. Material: Aluminum.
 - c. Shape: Round straight.
 - d. Finish: Match luminaire finish.
 - e. Mounting Height: _____. Height dictated by area of use, described above.
 - f. Mounting: _____. Mount on Owner standard concrete base.
 - g. Provide with the following features/accessories:
 - 1) Top cap.
 - 2) Handhole, per manufacture size.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 3) Anchor base cover.
- 4) Provision for pole-mounted weatherproof GFI receptacle, where indicated on the drawings.
4. Type Pole Mounted LED Flood/Spot Lights: _____.
 - a. Configuration: Single Luminaire(s) orientation as shown on Drawings.
 - b. Luminaire(s):
 - 1) Products:
 - 2) Kim Lighting.
 - 3) Housing: Aluminum.
 - 4) Finish: Match pole light color. .
 - 5) Illumination Source: LED.
 - 6) Shielding: Flat glass lens.
 - 7) Lighting Distribution: As shown on Drawings. .
 - 8) Voltage: Multi-tap 120/208/240/277 V.
 - 9) Driver: Provide LED driver per manufacturer's recommendations.
 - 10) Mounting Provision: Yoke mount.
 - 11) Mounting: Pole-top bracket suitable for mounting on specified pole, finish to match pole.
 - 12) Provide with the following features/accessories:
 - (a) Fusing.
 - (b) Integral locking receptacle for photo control complying with ANSI C136.10.
 - 13) Listings:
 - (a) Suitable for wet locations.

R. Wall-mounted Exterior LED luminaire.

1. Products:
 - a. Kim:
 - 1) Wall Director - Small: #WD14 Series:
 - 2) Wall Director - Large: #WD18 Series:
 - b. Sylvania:
 - 1) Small Wall Pack: #SMWL-1N-015-UNV-7-50-NC-BZ.
 - 2) Medium Wall Pack: #WALPAK-(Generation)-(Wattage)-UNV-7-NC-BZ-(Options).
 - (a) Generation: 1N, 2N or 3N.
 - (b) Wattage: 030 (30 watts), 050 (50 watts), 075 (75 watts), 105 (105 watts).
 - (c) Options: P (Photocontrol); (E) Emergency Battery Pack.
 - c. Eaton
 - 1) Medium Wall Pak: DPMLLED
 - (a) Options: P (Photocontrol)
2. Substitutions not permitted.
3. Housing: Aluminum.
4. Finish: Color by Architect. _____.
5. Shape: Rectangular.
6. Lamp: _____.
7. Shielding: Clear tempered glass lens.
8. Lighting Distribution:
 - a. Lateral Distribution: Forward throw.
 - b. Cutoff Category: Full cutoff.
9. Voltage: Multi-tap 120/208/240/277 V.
10. Driver: Provide LED driver per manufacturer's recommendations.
11. Mounting: _____ Surface mount on building/structure.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



12. Provide emergency power supply unit in luminaires designated with "EM" on the drawings.
 13. Provide with the following features/accessories:
 - a. Wireguard as specified on Drawings.
 14. Listings:
 - a. Suitable for wet locations.
- S. LED Bollard Luminaire.
1. Products:
 - a. Philips Lighting, "BRM832".
 - b. Substitutions not permitted.
 2. Housing: Aluminum.
 3. Finish: _____.
 - a. Academic Campus Areas: Custom Color "CC" - PMS 462 Gloss Brown.
 - b. Heritage Housing Areas: Standard Color - "BZ" (Bronze).
 - c. Athletic Areas: Custom Color "CC" - RAL 5002.
 4. Shape: Round.
 5. Nominal Size: 8 inches (diameter).
 6. Nominal Height: "42" - 42 inches high.
 7. Illumination Characteristics: _____.
 - a. Quantity of LEDs: "108L" - 36 led's per louver with 360 degree distribution.
 - b. LED Drive Current: "58" - 58 mA drive current.
 - c. LED Color Generation: "CW-G2" - Cool White, 5000K, 70 CRI, Generation 2.
 8. Surge Protection: 10 kA (Standard Option).
 9. Lighting Distribution: Symmetrical.
 10. Voltage: Multi-tap 120/208/240/277 V.
 11. Mounting: Mount on Owner approved concrete base..
 12. Provide with the following features/accessories:
 - a. Fusing.
 - b. Anchor bolts.
 - c. _____.
 13. Listings:
 - a. Suitable for wet locations.
 - b. _____.
 14. _____.
- T. Light Fixture manufacturers NOT permitted on campus.
1. Spectrum Lighting. All light fixtures manufactured by Spectrum Lighting.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



SECTION 265100 INTERIOR LIGHTING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Interior luminaires.
- B. Emergency lighting units.
- C. Exit signs.
- D. Ballasts and drivers.
- E. Emergency power supply units.
- F. Lamps.
- G. LED retrofit luminaire conversion kits.
- H. Luminaire accessories.

1.02 RELATED REQUIREMENTS

- A. Section 260529 - Hangers and Supports for Electrical Systems.
- B. Section 260533.16 - Boxes for Electrical Systems.
- C. Section 260548 - Vibration and Seismic Controls for Electrical Systems.
- D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.
- E. Section 260923 - Lighting Control Devices: Automatic controls for lighting including occupancy sensors, outdoor motion sensors, time switches, outdoor photo controls, and daylighting controls.
- F. Section 262725 - Wiring Devices: Manual wall switches and wall dimmers.
- G. Section 265013 - Luminaire Schedule.

1.03 REFERENCE STANDARDS

- A. ANSI C82.11 - American National Standard for Lamp Ballasts - High Frequency Fluorescent Lamp Ballasts - Supplements; 2011.
- B. IEC 60529 - Degrees of Protection Provided by Enclosures (IP Code); 2013-08, with 2015 Corrigendum.
- C. IEEE C62.41.2 - Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and less) AC Power Circuits; 2002 (Cor 1, 2012).
- D. IES LM-63 - IESNA Standard File Format for Electronic Transfer of Photometric Data and Related Information; 2002 (Reaffirmed 2008).
- E. IESNA LM-63 - ANSI Approved Standard File Format for Electronic Transfer of Photometric Data and Related Information; 2002 (Reaffirmed 2008).
- F. IES LM-79 - Approved Method: Electrical and Photometric Measurements of Solid-State Lighting Products; 2008.
- G. IES LM-80 - Approved Method: Measuring Luminous Flux and Color Maintenance of LED Packages, Arrays, and Modules; 2015.
- H. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- I. NECA/IESNA 500 - Standard for Installing Indoor Commercial Lighting Systems; 2006.
- J. NECA/IESNA 502 - Standard for Installing Industrial Lighting Systems; 2006.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- K. NEMA 410 - Performance Testing for Lighting Controls and Switching Devices with Electronic Drivers and Discharge Ballasts; 2015.
- L. NEMA LE 4 - Recessed Luminaires, Ceiling Compatibility; 2012.
- M. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- N. NFPA 101 - Life Safety Code; 2015.
- O. UL 844 - Luminaires for Use in Hazardous (Classified) Locations; Current Edition, Including All Revisions.
- P. UL 924 - Emergency Lighting and Power Equipment; Current Edition, Including All Revisions.
- Q. UL 935 - Fluorescent-Lamp Ballasts; Current Edition, Including All Revisions.
- R. UL 1598 - Luminaires; Current Edition, Including All Revisions.
- S. UL 1598C - Light-Emitting Diode (LED) Retrofit Luminaire Conversion Kits; Current Edition, Including All Revisions.
- T. UL 8750 - Light Emitting Diode (LED) Equipment for Use in Lighting Products; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate the installation of luminaires with mounting surfaces installed under other sections or by others. Coordinate the work with placement of supports, anchors, etc. required for mounting. Coordinate compatibility of luminaires and associated trims with mounting surfaces at installed locations.
 - 2. Coordinate the placement of luminaires with structural members, ductwork, piping, equipment, diffusers, fire suppression system components, and other potential conflicts installed under other sections or by others.
 - 3. Coordinate the placement of exit signs with furniture, equipment, signage or other potential obstructions to visibility installed under other sections or by others.
 - 4. Notify Architect and Owner's Construction Project Coordinator, of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings:
 - 1. Indicate dimensions and components for each luminaire that is not a standard product of the manufacturer.
 - 2. Provide photometric calculations where luminaires are proposed for substitution upon request.
- C. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, installed accessories, and ceiling compatibility; include model number nomenclature clearly marked with all proposed features.
 - 1. LED Luminaires:
 - 2. Ballasts/Drivers: Include wiring diagrams and list of compatible lamp configurations.
 - 3. Lamps: Include rated life, color temperature, color rendering index (CRI), and initial and mean lumen output.
 - 4. Emergency Power Supply Unit: Include list of compatible lamp configurations and associated lumen output.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- 5. LED Retrofit Luminaire Conversion Kits: Include list of compatible luminaires and/or criteria for compatibility.
- D. Certificates for Dimming Drivers: Manufacturer's documentation of compatibility with dimming controls to be installed.
- E. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
- F. Operation and Maintenance Data: Instructions for each product including information on replacement parts.
- G. Project Record Documents: Record actual connections and locations of luminaires and any associated remote components.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

1.07 DELIVERY, STORAGE, AND PROTECTION

- A. Receive, handle, and store products according to NECA/IESNA 500 (commercial lighting), NECA/IESNA 502 (industrial lighting), and manufacturer's written instructions.
- B. Keep products in original manufacturer's packaging and protect from damage until ready for installation.

1.08 FIELD CONDITIONS

- A. Maintain field conditions within manufacturer's required service conditions during and after installation.

1.09 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Provide five year manufacturer warranty for all LED luminaires, including drivers.

PART 2 PRODUCTS

2.01 LUMINAIRE TYPES

- A. Furnish products as indicated in luminaire schedule included on the drawings.
- B. Substitutions: See Section 016000 - Product Requirements, except where individual luminaire types are designated with substitutions not permitted.

2.02 LUMINAIRES

- A. Provide products that comply with requirements of NFPA 70.
- B. Provide products that are listed and labeled as complying with UL 1598, where applicable.
- C. Provide products listed, classified, and labeled as suitable for the purpose intended.
- D. Provide products complying with Federal Energy Management Program (FEMP) requirements.
- E. Unless otherwise indicated, provide complete luminaires including lamp(s) and all sockets, ballasts, reflectors, lenses, housings and other components required to position, energize and protect the lamp and distribute the light.
- F. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, hardware, supports, trims, accessories, etc. as necessary for a complete operating system.
- G. Provide products suitable to withstand normal handling, installation, and service without any damage, distortion, corrosion, fading, discoloring, etc.
- H. Recessed Luminaires:
 - 1. Ceiling Compatibility: Comply with NEMA LE 4.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



2. Luminaires Recessed in Insulated Ceilings: Listed and labeled as IC-rated, suitable for direct contact with insulation and combustible materials.
3. Luminaires Recessed in Sloped Ceilings: Provide suitable sloped ceiling adapters.
- I. Hazardous (Classified) Location Luminaires: Listed and labeled as complying with UL 844 for the classification of the installed location.
- J. Fluorescent Luminaires:
 1. Provide ballast disconnecting means complying with NFPA 70 where required.
- K. LED Luminaires:
 1. Components: UL 8750 recognized or listed as applicable.
 2. Tested in accordance with IES LM-79 and IES LM-80.
 3. LED Estimated Useful Life: Minimum of 50,000 hours at 70 percent lumen maintenance, calculated based on IES LM-80 test data.
- L. LED Tape Lighting Systems: Provide all power supplies, drivers, cables, connectors, channels, covers, mounting accessories, and interfaces as necessary to complete installation.
 1. LED Tape - General Requirements:
 - a. Listed.
 - b. Designed for field cutting in accordance with listing.
 - c. Wet Location Applications: IEC 60529, IP 68 (waterproof) rated.
- M. Track Lighting Systems: Provide track compatible with specified track heads, with all connectors, power feed fittings, dead ends, hangers and canopies as necessary to complete installation.
- N. Luminaires Mounted in Continuous Rows: Provide quantity of units required for length indicated, with all accessories required for joining and aligning.

2.04 EXIT SIGNS

- A. Description: Internally illuminated exit signs with LEDs unless otherwise indicated; complying with NFPA 101 and all applicable state and local codes, and listed and labeled as complying with UL 924.
 1. Number of Faces: Single or double as indicated or as required for the installed location.
 2. Directional Arrows: As indicated or as required for the installed location.
- B. Self-Powered Exit Signs:
 1. Operation: Upon interruption of normal power source or brownout condition exceeding 20 percent voltage drop from nominal, solid-state control automatically switches connected lamps to integral battery power for minimum of 90 minutes of rated emergency illumination, and automatically recharges battery upon restoration of normal power source.
 2. Battery: Sealed maintenance-free nickel cadmium unless otherwise indicated.
 3. Diagnostics: Provide power status indicator light and accessible integral test switch to manually activate emergency operation.
 4. Provide low-voltage disconnect to prevent battery damage from deep discharge.
- C. Photoluminescent Exit Signs: Powder-coated sheet aluminum with photoluminescent pigmented material, are not permitted for use on this project.
- D. Accessories:
 1. Provide compatible accessory high impact polycarbonate vandal shields where indicated.
 2. Provide compatible accessory wire guards where indicated.

2.05 BALLASTS AND DRIVERS

- A. Ballasts/Drivers - General Requirements:
 1. Provide drivers based upon luminaire manufacture's recommendations.
 2. Provide ballasts containing no polychlorinated biphenyls (PCBs).

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



3. Minimum Efficiency/Efficacy: Provide ballasts complying with all current applicable federal and state ballast efficiency/efficacy standards.
 4. Electronic Ballasts/Drivers: Inrush currents not exceeding peak currents specified in NEMA 410.
- B. Dimmable LED Drivers:
1. Dimming Range: Continuous dimming from 100 percent to five percent relative light output unless dimming capability to lower level is indicated, without flicker.
 2. Control Compatibility: Fully compatible with the dimming controls to be installed.
 - a. Lighting Controls: See Section 260923.
 - b. Lighting Control Systems: See Section 260936.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate conductors in accordance with NFPA 70.
- C. Verify that suitable support frames are installed where required.
- D. Verify that branch circuit wiring installation is completed, tested, and ready for connection to luminaires.
- E. Verify that conditions are satisfactory for installation prior to starting work.

3.02 PREPARATION

- A. Provide extension rings to bring outlet boxes flush with finished surface.
- B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.03 INSTALLATION

- A. Coordinate locations of outlet boxes provided under Section 260533.16 as required for installation of luminaires provided under this section.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Install products in accordance with manufacturer's instructions.
- D. Install luminaires securely, in a neat and workmanlike manner, as specified in NECA 500 (commercial lighting) and NECA 502 (industrial lighting).
- E. Provide required support and attachment in accordance with Section 260529.
- F. Provide required seismic controls in accordance with Section 260548.
- G. Install luminaires plumb and square and aligned with building lines and with adjacent luminaires.
- H. Suspended Ceiling Mounted Luminaires:
 1. Do not use ceiling tiles to bear weight of luminaires.
 2. Do not use ceiling support system to bear weight of luminaires unless ceiling support system is certified as suitable to do so.
 3. Fixture length shall not exceed 12 ft.
 4. Secure surface-mounted, recessed, and pendant-mounted luminaires to framing members or to building structure.
 5. Secure lay-in luminaires to ceiling support channels using listed safety clips at four corners.
 6. In addition to ceiling support wires, provide two galvanized steel safety wire(s), minimum 12 gage, connected from opposing corners of each recessed luminaire to building structure.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



7. See appropriate Division 9 section where suspended grid ceiling is specified for additional requirements.
- I. Recessed Luminaires:
 1. Install trims tight to mounting surface with no visible light leakage.
 2. Non-IC Rated Luminaires: Maintain required separation from insulation and combustible materials according to listing.
 3. Luminaires Recessed in Fire-Rated Ceilings: Install using accessories and firestopping materials to meet regulatory requirements for fire rating.
- J. Suspended Luminaires:
 1. Unless otherwise indicated, specified mounting heights are to bottom of luminaire.
 2. Install using the suspension method indicated, with support lengths and accessories as required for specified mounting height.
 3. Provide minimum of two supports for each luminaire equal to or exceeding 4 feet nominal length, with no more than 12 feet between supports, as per manufacture recommendations.
 4. Install canopies tight to mounting surface.
 5. Unless otherwise indicated, support pendants from swivel hangers.
- K. Wall-Mounted Luminaires: Unless otherwise indicated, specified mounting heights are to bottom of luminaire.
- L. Install accessories furnished with each luminaire.
- M. Bond products and metal accessories to branch circuit equipment grounding conductor.
- N. Emergency Lighting Units:
 1. Unless otherwise indicated, connect unit to unswitched power from circuit indicated. Bypass local switches, contactors, or other lighting controls.
- O. Exit Signs:
 1. Unless otherwise indicated, connect unit to unswitched power from circuit indicated. Bypass local switches, contactors, or other lighting controls.
- P. Emergency Power Supply Units:
 1. For field-installed units, install inside luminaire unless otherwise indicated. Where installation inside luminaire is not possible, install on top of luminaire.
 2. Unless otherwise indicated, connect unit to unswitched power from same circuit feeding normal ballast(s) in luminaire. Bypass local switches, contactors, or other lighting controls.
 3. Remote Power Supply Units: Install in accessible location as indicated or as required to complete installation, using conductors per manufacturer's recommendations not exceeding manufacturer's recommended maximum conductor length to luminaire.
- Q. Identify luminaires connected to emergency power system in accordance with Section 260553.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect each product for damage and defects.
- C. Operate each luminaire after installation and connection to verify proper operation.
- D. Test self-powered exit signs, emergency lighting units, and emergency power supply units to verify proper operation upon loss of normal power supply.
- E. Correct wiring deficiencies and repair or replace damaged or defective products. Repair or replace excessively noisy generator transfer device as determined by Architect.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



3.05 ADJUSTING

- A. Aim and position adjustable luminaires to achieve desired illumination as indicated or as directed by Architect. Secure locking fittings in place.
- B. Aim and position adjustable emergency lighting unit lamps to achieve optimum illumination of egress path as required or as directed by Architect or authority having jurisdiction.
- C. Exit Signs with Field-Selectable Directional Arrows: Set as indicated or as required to properly designate egress path as directed by Architect or authority having jurisdiction.

3.06 CLEANING

- A. Clean surfaces according to NECA 500 (commercial lighting), NECA 502 (industrial lighting), and manufacturer's instructions to remove dirt, fingerprints, paint, or other foreign material and restore finishes to match original factory finish.

3.07 CLOSEOUT ACTIVITIES

- A. See Section 017800 - Closeout Submittals, for closeout submittals.
- B. See Section 017900 - Demonstration and Training, for additional requirements.
- C. Demonstration: Demonstrate proper operation of luminaires to Architect, and correct deficiencies or make adjustments as directed.
- D. Just prior to Substantial Completion, LED drivers or boards that have failed.

3.08 PROTECTION

- A. Protect installed luminaires from subsequent construction operations.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



SECTION 284050
CONDUCTORS AND CABLES FOR FIRE DETECTION AND ALARM

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. 1. Fire alarm wire and cable.
- B. 2. Single mode optical fiber cabling.
- C. 3. Identification products.

1.02 RELATED REQUIREMENTS

- A. Section 016000 - Product Requirements: Fundamental product requirements, substitutions and product options, delivery, storage, and handling.
- B. Section 260519 - Low-Voltage Electrical Power Conductors and Cables.
- C. Section 260526 - Grounding and Bonding for Electrical Systems.
- D. Section 260533.13 - Conduit for Electrical Systems.
- E. Section 260533.16 - Boxes for Electrical Systems.
- F. Section 260536 - Cable Trays for Electrical Systems.
- G. Section 260533 - Identification for Electrical Systems.
- H. Section 284600 - Fire Detection and Alarm.

1.03 DEFINITIONS

- A. BICSI: Building Industry Consulting Service International.
- B. EMI: Electromagnetic interference.
- C. IDC: Insulation displacement connector.
- D. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control and signaling power-limited circuits.
- E. Open Cabling: Passing telecommunications cabling through open space (e.g., between the studs of a wall cavity).
- F. RCDD: Registered Communications Distribution Designer.

1.04 REFERENCE STANDARDS

- A. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.
- B. FM (AG) - FM Approval Guide; current edition.
- C. ITS (DIR) - Directory of Listed Products; current edition.
- D. NEMA MG 1 - Motors and Generators; 2016.
- E. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Warranty Documentation: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.
- C. Provide allowable pulling tension of cable.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____



- D. Provide cable connectors and terminations information, recommended by the manufacturer.
- E. Project Record Documents: Record actual locations of all fire alarm junction boxes.

1.06 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Independent firm specializing in performing testing and inspections of the type specified in this section.
- B. Copies of Documents at Project Site: Maintain at the project site a copy of each referenced document that prescribes execution requirements.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Do not install conductors and cables that are wet, moisture damaged, or mold damaged.
 - 1. Indications that wire and cables are wet or moisture damaged include, but are not limited to, discoloration and sagging of factory packing materials.
- B. Environmental Limitations: Do not deliver or install optical fiber and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.08 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.
- B. Correct defective Work within a three month period after Date of Substantial Completion.
- C. Fire alarm system shall be completely installed, per contract documents, and operating per manufacture's recommendations, prior to the commencement of the warranty period.
- D. Upon Date of Substantial Completion, the contractor shall provide a document stating the date commencing the system warranty.
- E. Provide five year manufacturer warranty for entire system.

PART 2 PRODUCTS

2.01 PATHWAYS

- A. Pathways for fire alarm cabling and conductors, see Specification Section 260533.16 for additional requirements.

2.02 SOURCE QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. According to BICSI ITSIM, telecommunications cables should be tested upon receipt. Low-voltage wires and cables do not normally require testing before installation.
- C. Test cables upon receipt at Project site.
 - 1. Test optical fiber cable to determine the continuity of the strand end to end. Use optical fiber flashlight or optical loss test set.
 - 2. Test optical fiber cable on reels. Use an optical time domain reflectometer to verify the cable length and locate cable defects, splices, and connector; include the loss value of each. Retain test data and include the record in maintenance data.

2.03 FIRE ALARM CONDUCTORS AND CABLE

- A. Conductor and Cable Manufacturers:
 - 1. Omni
 - 2. Beldon.
 - 3. Genesis.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



4. Windy City Wire; www.smartwire.com, 801-633-0651.
- B. Non-Power-Limited Circuits:
 1. Copper conductors with 600-V rated, 75 deg C, color-coded insulation.
 - a. Low-Voltage Circuits: No. 16 AWG, minimum.
 - b. Line-Voltage Circuits: No. 12 AWG, minimum.
- C. Fire Alarm-Circuit Conductor Identification, 600 V or Less: For conductors in pull boxes, junction boxes and enclosures. Use factory colored cables and conductors to identify the individual circuits.
 1. Fire alarm device constant power (24 VDC):
 - a. Install conductors throughout each trunk line, i.e., water bugs, control modules, etc.
 - b. Conductor colors:
 - 1) Red (+), #12, CU.
 - 2) Black (-), #12, CU.
 2. Fire Alarm Remote (NAC) Horn Strobe Booster Panel Sync Circuit:
 - a. Install conductors from main fire alarm panel to each horn strobe booster panel.
 - b. Conductor colors:
 - 1) Purple (+), #12, CU.
 - 2) Yellow (-), #12, CU.
 3. Color-Coding for fire alarm Signal Line Circuits (SLC) circuits. Use colors listed below. All conductors shall be Red and Black, #16, twisted pair, CU; enclosed in a non-shielded cable.
 - a. SLC Circuit #1. Grey cable with red (+) and black (-) conductors; Cable shall not be stripped.
 - b. SLC Circuit #2. Grey cable with red (+) and black (-) conductors; Provide cable with a black stripe.
 - c. SLC Circuit #3. Grey cable with red (+) and black (-) conductors; Provide cable with a red stripe.
 - d. SLC Circuit #4. Grey cable with red (+) and black (-) conductors; Provide cable with a purple stripe.
 - e. SLC Circuit #5. Grey cable with red (+) and black (-) conductors; Provide cable with a brown stripe.
 - f. SLC Circuit #6. Grey cable with red (+) and black (-) conductors; Provide cable with a yellow stripe.
 - g. SLC Circuit #7. Grey cable with red (+) and black (-) conductors; Provide cable with a white stripe.
 - h. SLC Circuit #8. Grey cable with red (+) and black (-) conductors; Provide cable with a green stripe.
 - i. SLC Circuit #9. Grey cable with red (+) and black (-) conductors; Provide cable with a pink stripe.
 - j. SLC Circuit #10. Grey cable with red (+) and black (-) conductors; Provide cable with a blue stripe.
 4. Color-Coding for fire alarm speaker circuits. Use colors listed below. Cable conductor colors shall be Red and Black, #16, TSP, CU.
 - a. Speaker Circuit #1. Grey PVC jacket with red (+) and black (-) conductors; Provide cable with an orange stripe.
 - b. Speaker Circuit #2. Grey PVC jacket with red (+) and black (-) conductors; Provide cable with orange and black stripes.
 - c. Speaker Circuit #3. Grey PVC jacket with red (+) and black (-) conductors; Provide cable with orange and red stripes.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- d. Speaker Circuit #4. Grey PVC jacket with red (+) and black (-) conductors; Provide cable with orange and purple stripes.
- 5. Color-Coding for fire alarm horn and horn/strobes. Use colors listed below. All conductors shall be Blue and Grey, #12, CU, stranded.
 - a. Strobe Circuit #1. Conductors shall be blue (+) and grey (-), with no stripes.
 - b. Strobe Circuit #2. Conductors shall be blue (+) and grey (-), with a black stripe.
 - c. Strobe Circuit #3. Conductors shall be blue (+) and grey (-), with a red stripe.
 - d. Strobe Circuit #4. Conductors shall be blue (+) and grey (-), with a purple stripe.
 - e. Strobe Circuit #5. Conductors shall be blue (+) and grey (-), with a brown stripe.
 - f. Strobe Circuit #6. Conductors shall be blue (+) and grey (-), with a yellow stripe.
 - g. Strobe Circuit #7. Conductors shall be blue (+) and grey (-), with a white stripe.
 - h. Strobe Circuit #8. Conductors shall be blue (+) and grey (-), with a green stripe.
 - i. Strobe Circuit #9. Conductors shall be blue (+) and grey (-), with a pink stripe.
 - j. Strobe Circuit #10. Conductors shall be blue (+) and grey (-), with a black and red stripe.
 - k. Strobe Circuit #11. Conductors shall be blue (+) and grey (-), with a purple and brown stripe.
 - l. Strobe Circuit #12. Conductors shall be blue (+) and grey (-), with a yellow and white stripe.
 - m. Strobe Circuit #13. Conductors shall be blue (+) and grey (-), with a green and pink stripe.
 - n. Strobe Circuit #14. Conductors shall be blue (+) and grey (-), with a black, red and purple stripe.
- 6. Color-Coding for fire alarm sounder bases. Use colors listed below. Provide two (2) white, #12, CU, (24 VDC power) in each cable.
 - a. Sounder Base Circuit #1. Conductors shall be red (+) stripe conductor and black (-) stripe conductor.
- 7. Door Holding Circuiting: #12, CU
 - a. Brown “-“ door holder power.
 - b. Orange “+“ door holder power.
- 8. The SLC cable and the four (4) #12 conductors (constant power and door holder circuits) are to be installed in every main 3/4" trunk line, for present and/or future use.
- 9. Never install more than eight conductors in a conduit.
- 10. Identification of Fire Alarm Cables on Multiple Building Floors:
 - a. Do not intermix fire alarm cabling between floors. Provide dedicated fire alarm circuiting for each floor.
 - b. For each floor, start with Circuiting #1 conductors/cables.

D. BACKBOARDS

- 1. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches. Comply with requirements for plywood backing panels in Section 061000.

2.04 FIRE ALARM FIBER OPTIC CABLES

A. Fiber Optic Cable:

- 1. Manufacturers:
 - a. Corning Cable Systems.
- 2. Description: Singlemode, 6 fiber, tight buffer, optical fiber cable.
 - a. Comply with ICEA S-83-596 for mechanical properties.
 - b. Comply with TIA/EIA-568-B.3 for performance specifications.
 - c. Flame-retardant and UV-retardant.
 - d. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444, UL 1651, and NFPA 70 for the following types:
 - 1) Riser Rated: Type OFNR, complying with UL 1666.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- e. Maximum Attenuation: 0.65 dB/km at 1310 nm; 0.65 dB/km at 1383 and 0.05 dB/km at 1550 nm.
- f. Model Number: #006E8F-31131-29.
- 3. Cable Colors:
 - a. Tight Buffer Colors: First pair, Blue and Orange; second pair, Green and Brown; third pair (spare), Slate and White.
- 4. Jacket:
 - a. Jacket Color: Black.
 - b. Cable cordage jacket, fiber, unit, and group color shall be according to TIA/EIA-598-B.
 - c. Imprinted with fiber count, fiber type, and aggregate length at regular intervals not to exceed 40 inches (1000 mm).
- B. Fiber Optic Cable Hardware:
 - 1. Manufacturers:
 - a. Corning Cable Systems.
 - 2. Cable Connecting Hardware: Comply with the Fiber Optic Connector Intermateability Standards (FOCIS) specifications of TIA/EIA-604-2, TIA/EIA-604-3-A, and TIA/EIA-604-12. Comply with TIA/EIA-568-B.3.
 - a. Quick-connect, simplex and duplex, Type SC connectors. Insertion loss not more than 0.75 dB.
 - b. Cable Connection Boxes (Coupler Panel):
 - 1) Corning, #SPH-01P.
 - 3. Patch cables:
 - a. For LC Connections, provide patch cables with white/yellow and yellow/white cables.
 - b. For SC Connections, provide patch cables with black/red and red/black cables.

PART 3 EXECUTION

3.01 INSTALLATION OF PATHWAYS

- A. Cable Trays: Comply with NEMA VE 2 and TIA-569-B. Cable tray in non-plenum areas.
- B. Comply with TIA-569-B for pull-box sizing and length of conduit and number of bends between pull points.
- C. Comply with requirements in Sections 260533.13, for installation of conduits and wireways.
- D. Install manufactured conduit sweeps and long-radius elbows whenever possible.

3.02 INSTALLATION OF HANGERS AND SUPPORTS

- A. Comply with requirements in Section 260529, for installation of supports for pathways, conductors and cables.

3.03 INSTALLATION OF CONDUCTORS AND CABLES

- A. Comply with NECA 1.
- B. Conductors: Size according to system manufacturer's written instructions unless otherwise indicated.
- C. General Requirements for Cabling:
 - 1. Comply with TIA/EIA-568-B.1.
 - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
 - 3. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, and cross-connect and patch panels.
 - 4. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



5. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Install lacing bars and distribution spools.
6. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
7. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
8. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
9. Fire-Rated Cables: Use of 2-hour, fire-rated fire alarm cables, NFPA 70, Types MI and CI, shall not be permitted.

3.04 FIRE ALARM WIRING INSTALLATION

- A. Comply with NECA 1 and NFPA 72.
- B. Raceway Method: Install wiring and cabling in metal raceway according to Sections 260519 and 260533.16.
 1. Minimum conduit size shall be 3/4 inch.
 2. Fire alarm circuits and equipment control wiring associated with the fire alarm system shall be installed in a dedicated raceway system. This raceway system shall not be used for any other type of systems.
 3. Install wiring in metal raceways and wireways.
 4. Install fiber optic cable in raceways or cable trays. In cable trays, cable only permitted in non-plenum areas.
 5. Conceal raceway and wiring except in unfinished spaces. Surface raceways shall not be permitted in finished areas, unless finished surface is concrete, block or other hard surface. Coordinate such finished areas with campus electrical engineer.
 6. Control and data transmission wiring shall not share conduit with other building wiring systems.
 7. Cables and raceways used for fire alarm circuits, and equipment control wiring associated with the fire alarm system, may not contain any other wire or cable.
 8. Signaling Line Circuits:
 - a. Power-limited fire alarm cables shall not be installed in the same cable or raceway as signaling line circuits.
 - b. Voice annunciation. Provide a dedicated conduit for voice/speaker cabling.
 - c. Strobe cabling shall be installed with the voice/speaker cabling.
- C. Fiber Optic Cabling Method:
 1. Route fiber cable from nearest campus fire alarm communication gateway, to the fire alarm coupler panel. Do not extend fiber cabling into the fire alarm panel.
 2. Route fiber cable between the fire alarm coupler panel and the annunciator panel.
 3. Final connection between the fire alarm panel and coupler panel shall be by a SC to LC patch cable. Extend patch cable to NCM (Network Control Module) located in main fire alarm panel.
 4. Final connection in annunciator panel shall be by a SC to LC patch cable. No coupler panel required for annunciator panels.
- D. All new power limited cabling shall be installed in EMT conduit. Wire is to be provided by the electrical contractor and closely coordinated so as to insure proper codes and U.L. requirements are met, as well as the BYU color codes.
- E. Box extensions. Provide no more than one box extension for each junction or pull boxes.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



- F. All cable splices at the main panel shall be made in the wire gutter. Only wire to be connected to fire alarm system shall be pulled in the fire alarm control panel. All wire is to be terminated properly, most devices have wire clamps. Use terminal forks when clamps are missing.
- G. All terminations to field devices shall be attached to proper terminal points.
- H. Run a #12 AWG green ground wire to the main service connection, and in all 120 VAC branch circuits.
- I. Wiring color code shall be maintained throughout the installation.
- J. All wiring "passing through" junction boxes shall be un-broken and looped out of each junction box 8"+ (When cut for future use, each resulting wire will be 8" long). Where such installation is especially difficult, the wires may be cut and wire nuts installed. The addressable loop cable will be installed un-broken as much as possible. (Intent: Wires are to be broken only at their points of termination.) Leave minimum of 12" loop or 8" wire slack in all junction & pull boxes where wire is feeding through to provide capability for future connection at that point.
- K. Connection of wire to wire: Use wire nuts on all connections including the speaker drain wire. Drain wire and metal sheathing in speaker cable must be taped with no metal exposed, and drain wire length is to be 2" or longer. When taping the drain, put the wire nut on, fold back on sheathed cable and tape both cables together with folded drain.
- L. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with the fire alarm system to terminal blocks. Mark each terminal according to the system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.
- M. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes, cabinets, or equipment enclosures where circuit connections are made.

3.05 GROUNDING

- A. For communications wiring, comply with ANSI-J-STD-607-A and with BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. For low-voltage wiring and cabling, comply with requirements in Section 260526.

3.06 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.

3.07 SYSTEM STARTUP

- A. Provide manufacturer's field representative to perform systems startup.
- B. Prepare and start equipment and systems in accordance with manufacturers' instructions and recommendations.
- C. Adjust for proper operation within manufacturer's published tolerances.

3.08 CLOSEOUT ACTIVITIES

- A. See Section 017800 - Closeout Submittals, for closeout submittals.
- B. See Section 017900 - Demonstration and Training, for additional requirements.
- C. Demonstrate proper operation of equipment to Owner's designated representative.
- D. Demonstration: Demonstrate operation of system to Owner's personnel.
 - 1. Use operation and maintenance data as reference during demonstration.

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*

Signature & Date: _____



2. Conduct walking tour of project.
 3. Briefly describe function, operation, and maintenance of each component.
- E. Training: Train Owner's personnel on operation and maintenance of system.
1. Use operation and maintenance manual as training reference, supplemented with additional training materials as required.
 2. Provide minimum of two hours of training.
 3. Instructor: Manufacturer's training personnel.
 4. Location: At project site.

END OF SECTION

I _____ the Principal in Charge on this project have reviewed this section and it is in accordance with the Instructions to Architects & Engineers. Print Date: *Monday, July 25, 2022*
Signature & Date: _____